

PURCHASE DESCRIPTION

NAS Pax River POST Hoist Platform FRP

1. INTRODUCTION

Naval Surface Warfare Center Corona (NSWC Corona) is seeking to procure Fiberglass Reinforced Polymer prepared material to assemble a replacement POST and Hoist training platforms at NAS Pax River.

2. BACKGROUND

Naval Surface Warfare Center Corona (NSWC Corona) has been tasked by the Naval Aviation Training Systems to demolish and re-install a retrofitted Helicopter Hoist Trainer (Device 9H1) located within NAS Pax River, MD. These trainers provide hands on training in helicopter rescue hook, rescue basket, and rescue strop procedures. The efforts involve removing the existing metal Hoist and POST platforms, their concrete footings, and replacing them with new platforms made of Fiberglass Reinforced Polymer (FRP) and replaced concrete footings. Redesign of the platform and all requisite parts has been completed and require fabrication out of FRP.

3. REQUIREMENTS

The contractor is required to adhere to all applicable standards and guidelines when applicable. In the absence of named standards, Department of the Navy (DON) standards, applicable Federal Information Processing Standards (FIPS), and broadly accepted professional standards shall prevail as related to the associated industries within the task identified below.

3.1 The contractor shall provide the parts manufactured to the drawings listed in Table 1, in the quantities in Tables 2, and 3.

Table 1. Government provided documentation

Document Type	No./Version	Title	Date
DOD Documentation	1.0	POST FRP 12-3-25 Distro.pdf	December 2025
DOD Documentation	1.0	Hoist FRP 12-3-25 Distro.pdf	December 2025

Table 2. Hoist FRP quantities

PART NUMBER	DESCRIPTION	QTY
H-201	Control Box Column Left	1
H-202	Control Box Column	1
H-203	Control Box Lateral	1
H-204	Control Panel Shelf Long Outer	1
H-205	Control Panel Shelf Long Inside	1
H-206	Control Panel Legs	3
H-207	Control Panel Short	1
H-208	Pulley Mount I-Beam Left	1
H-209	Pulley Mount I-Beam Right	1
H-210	Short Stair Support	2
H-211	Tall Stair Support	2
H-212	Stair Right	1
H-213	Stair Left	1
H-214	Step Grating	12
H-215	Railing Vert Platform	19
H-216	Rail Spacer	56
H-217	Toe Kick	1
H-218	Platform railing	1
H-219	Platform railing	1
H-220	Platform railing	1
H-221	Platform railing	1
H-222	Platform railing	1
H-223	Platform railing	1
H-224	Toe Kick	1
H-226	Railing Vert Stairs	8
H-228	Vert Rail End	2
H-229	Stair Railing	4
H-230	Gate Horizontal	2
H-231	Gate Horizontal	1
H-232	Gate Horizontal	1
H-233	Column Center Right	1
H-234	Column Center Left	1
H-235	Column Front Mid Right	1
H-236	Column Rear Right	1
H-237	Column Front Mid Left	1
H-238	Column Front Left	1
H-239	Column Rear Left	1
H-240	Platform Beam Back	1

H-241	Platform Beam Front	1
H-242	Platform Beam Right	1
H-243	Platform Beam Stair Side	1
H-245	Platform L/R lateral	4
H-246	Platform Beam Ledge Mid	1
H-247	Platform Beam Ledge left	1
H-248	Platform beam Ledge Right	1
H-249	Platform Beam	1
H-250	Ledge Support	2
H-251	Angle Support	13
H-252	Platform Lateral	2
H-253	Long Right Lateral	2
H-255	Ledge Support Mid	1
H-256	Rear Upper Support	2
H-257	Long Rear Upper Support	1
H-258	Cable Housing	1
H-259	Motor Support	1
H-260	Short Front L/R Bottom Support	2
H-261	Front L/R Bottom Support	2
H-262	Bottom Mid Support	1
H-263	Platform Grating	1
H-264	Platform Grating	1
H-265	Platform Grating	1
H-266	Platform Grating	1
H-267	Platform Grating	1
H-268	Platform Grating	1
H-269	Platform Grating	1
H-270	Toe Kick	2
H-271	Toe Kick	2
H-272	Toe Kick	2
H-273	Stringer	4
H-274	Stringer	4
H-275	Stringer	4
H-276	Mid Bottom Ledge Support	1
H-279	Control Box Lower	2
H-281	Column Front Mid Left	1
H-282	Gate Horizontal	2
H-283	Gate Vertical	4
H-284	Stairs Vertical	2
H-285	Railing Vertical Ends	2
H-286	Bottom Rail	1
H-287	Top Rail	1
H-288	Platform Railing	1

H-289	Platform railing	1
H-290	Platform railing	1
H-291	Platform railing	1
H-292	Platform railing	1
H-293	Platform railing	1
H-294	Platform railing	1
H-295	Platform railing	1
H-296	Platform railing	1
H-297	Platform railing	1
H-298	Stair Step	1
H-299	Hand Rail Vertical Reinforcement	28
H-300	Toe Kick Corner	5
H-301	Stair Side Solo	1
H-304	Spacer	16
Bedford ReadyRail Corner Insert	Corner Reinforcement	20

Table 3. POST FRP quantities

PART NUMBER	DESCRIPTION	QTY
Bedford ReadyRail Corner Insert	Internal Reinforcement	10
P-101	Rear Left Vert	1
P-102	Rear Right Vert	1
P-103	Front Left Vert	1
P-104	Front Right Vert	1
P-105	Rear Short Rail	1
P-106	Platform Main	1
P-107	Horizontal Platform	1
P-108	Platform Short Side	1
P-109	Platform Stair Side	1
P-110	Platform	2
P-111	Platform	1
P-112	Mid	1
P-113	Vert Front Mid	1
P-114	Vert Right Mid	1
P-115	Ledge Angle Support	2
P-116	Plat Grating	1
P-117	Plat Grating	1
P-118	Plat Grating	2
P-119	Horizontal Support Brace	3
P-120	Horizontal Support Brace	1
P-121	Step Support Brace	1
P-123	Horizontal Support Brace	1

P-124	Platform	1
P-125	Toe Kick	1
P-126	Toe Kick	2
P-127	Corner Support	7
P-129	Stringer	6
P-130	Stringer	2
P-131	Stringer	2
P-132	Stringer	2
P-133	Front Mid Left	1
P-134	Hand Rail	1
P-135	Toe Kick	1
P-136	Plat Vert Rail	15
P-137	Vert Spacer	28
P-138	Hand Rail	1
P-139	Hand Rail	1
P-140	Hand Rail	1
P-141	Hand Rail	1
P-142	Vert Rail End	4
P-143	Toe Kick	1
P-144	Hand Rail	1
P-145	Hand Rail	1
P-146	Right Stairs	1
P-147	Stair Vert Support	2
P-148	Stair Vert Support	2
P-149	Stairs Left	1
P-150	Ledge Step	3
P-151	Ledge Stairs Right	1
P-152	Ledge Stairs Left	1
P-153	Main Stair Grating	12
P-154	Ledge Hand Rail Vert	4
P-155	Hand Rail	1
P-156	Ledge Rail	2
P-157	Hand Rail	1
P-158	Main Stair Railing	2
P-159	Vert Rail End	2
P-160	Stair Vert	8
P-161	Ledge Railing	2
P-162	Ledge Rail	2
P-164	Platform	1
P-165	Top Stair Vertical Rail	2
P-166	Railing Corner	1
P-167	Railing Corner	1
P-168	Railing Corner	1

P-169	Railing Corner	1
P-170	Hand Rail	1
P-171	Hand Rail	1
P-172	Hand Rail	1
P-173	Spacer	2
P-174	Top Stair Vertical Rail	2
P-176	Toe Kick	1
P-177	Toe Kick	1
P-178	Stair Grating Top	1
P-179	Spacer	24
P-180	Hand Rail Vert Reinforcement	27
P-181	Plat Grating	1
P-182	Main Stair Railing Lower	2
P-300	Toe Kick Corner	5

ADDITIONAL INFORMATION

A. PERIOD OF PERFORMANCE / REQUIRED DELIVERY DATES

RDD Prior to 2nd June 2026

B. PLACE OF PERFORMANCE

N/A

C. SHIPPING ADDRESS

DODAAC: N41171
ASTC Pax River
2165 Fortin Circle
Patuxent River, MD 20670

D. INSPECTION AND ACCEPTANCE

TBD

E. TECHNICAL POINT OF CONTACT

TBD