

BUILDING 299 WELD VENTILATION

GREEN HIGHLIGHT = decision must be made or data filled in.**Error! Bookmark not defined.**

Blue HIGHLIGHT = For Turnkey Projects Only**Error! Bookmark not defined.**

1.	GENERAL SYSTEM DESCRIPTION	2
2.	STANDARDS AND PUBLICATIONS	2
2.1	Clarification	2
2.2	National Standards and Specifications.....	2
3.	DESIGN.....	2
3.1	Ownership.....	2
3.2	General Design Standards.....	2
3.3	Safety, Security and Environmental	5
3.4	Responsibilities.....	8
4.	COMPONENT SPECIFICATION	11
4.1	Dimensions:	Error! Bookmark not defined.
5.	INFORMATION TECHNOLOGY SUPPORT.....	
	Error! Bookmark not defined.	
6.	APPROVAL/SHIPPING	11
6.1	Shipping	11
6.2	Installation.....	12
6.3	Completion.....	13
7.	TRAINING	13
7.1	Schedule.....	13
7.2	Location	14
7.3	Type	14
8.	SERVICE.....	14
8.1	Service/Support Requirements.....	14

BUILDING 299 WELD VENTILATION

1. GENERAL SYSTEM DESCRIPTION

This requirement is for an ambient weld ventilation system to be installed in B299 Zone 8. The ambient system is to include all auxiliary components necessary to provide a safe and functioning system. Currently we are slated to install 12 weld booths in Zone 8. Height clearance, weld volume, and air changeover will all need to be taken into account for the design of this system.

2. STANDARDS AND PUBLICATIONS

2.1 Clarification

Any ambiguities, questions, requests for clarification or discrepancies between sections of this purchase description, drawings, national or industry standards discovered by the contractor in reviewing this purchase description shall be reported by the bidder in writing to the contracting officer BEFORE THE DATE SCHEDULED FOR CLOSE OF BIDDING/receipt of proposal. Submission of a proposal or bid shall be construed as evidence that such examination has been made. Therefore, later claims for labor, material, or equipment required, or for difficulties encountered, which could have been foreseen had such reasonable examination been made, may be denied.

2.2 National Standards and Specifications

The contractor shall conform and provide equipment conforming to all local and federal codes and standards applicable to the equipment they are providing based on location and purpose of equipment in effect on the date of the opening of solicitation. It is not the responsibility of the government to make modifications to ensure compliance.

3. DESIGN

3.1 Ownership

3.1.1 This equipment is a standard product of the manufacturer and shall require either no change or minor design changes to meet requirements of these specifications. Therefore, ownership of the design will remain with the manufacturer.

3.2 General Design Standards

3.2.1 DEVIATION FROM PRODUCT: Modifications to the manufacturer's standard design to achieve requirements as specified in this document are only permissible as dictated by good design practice. For example, mounting a 20-hp motor in a power train designed and normally using a 10-hp motor would not be acceptable.

3.2.2 UNITS OF MEASURE: Dimensions and capacities in this purchase description are given in the English-US (in-lb) system. All dials, gauges, and drawings shall be in the English-US system or both the English-US and the metric systems, unless otherwise specified in this document.

3.2.3 ID DATA PLATE: The equipment shall include a main data plate which will include the following data as a minimum requirement (additional information is acceptable):

BUILDING 299 WELD VENTILATION

Manufacturer Name, Manufacturer's Dunns and Bradstreet Number, Manufacturer's Model Number, Manufacturer's Serial Number, Year of Manufacture, Contract Number, Machine Weight. This information is necessary for compliance with the governments Unique Identification Program (UID).

3.2.4 **DATA PLATES**: All instruction, data, and identification plates and labels attached to this equipment and its controls shall be manufactured of corrosion and oil resistant metal or plastic material. All wording shall be in the English language using plain, bold face lettering. Lettering shall be permanent and have a contrasting background.

3.2.5 **ITEM UNIQUE IDENTIFICATION (IUID) REGISTRATION**: The contractor shall register the equipment in the IUID Registry (as one single system). IUID registration requires the contractor to input Cage Code, Model Number, and Serial Number into a Government Database to allow for asset and inventory tracking. IUID Registry of the equipment shall be performed at <http://dodprocurementtoolbox.com/site/uidregistry/>. Training for IUID is available in <https://wawftraining.eb.mil>. IUID registration of this equipment is required prior to final payment in the Wide Area Work Flow (WAWF). The contractor shall also affix a machine readable 2-dimensional (2-D) matrix representing the IUID registry to the machine. The IUID 2-D matrix may be included on the ID Data Plate outlined in paragraph 3.2.4.

3.2.6 **UTILITY CONNECTION**: Equipment supplied to the Rock Island Arsenal will have single point shut-off for each utility supplied to a system. This means that equipment constituting a single system shall be wired to a single main electrical disconnect point, plumbed to a single pneumatic shut-off valve, etc... This will be referred to as the "point of first connection". Each type of power source may have only one point of first connection. E.g. (1) pneumatic shut-off valve, (1) water supply shut-off valve, (1) electrical disconnect, etc... Each point of first connection shall be clearly labeled on the system and shown in the safety lockout portion of the documentation package. These points must be located on a stationary component and positioned such that they will not create a hazard to personnel during normal operation of the system. The first connection points shall be accessible from the shop floor without the use of ladders, steps, or stools. Access cannot be hampered by operation of the system.

3.2.7 **UTILITY CONNECTION LABOR**: Rock Island Arsenal shall provide only such labor and materials as will be needed to connect facility utilities to each point of first connection of the system. The supplier will be responsible for all connections beyond the point of first connection for each utility.

3.2.8 **UTILITIES AVAILABLE**: Rock Island Arsenal shall be responsible for providing the following:

3.2.8.1 Connection of 460-V, 60-Hz, 3-Ph AC electrical power to the fused or breaker type disconnect switch required in the ELECTRICAL DISCONNECT paragraph of this purchase description. Connection does not include filters, surge protection, or any peripheral equipment necessary to make the equipment functional.

3.2.8.2 Connection of approximately 80-psi compressed air to a single point for each system, if needed. Connection does not include filters, dryers, or any peripheral equipment necessary to make the equipment functional.

BUILDING 299 WELD VENTILATION

3.2.8.3 If, due to contractor caused problems, the equipment or components of the equipment must be moved or removed and replaced, by RIA after initial placement, the contractor shall be billed for such work at current RIA labor and overhead rates.

3.2.9 ELECTRICAL DISCONNECT: The equipment shall be equipped with a manual, fused or breaker type disconnect switch, readily accessible to the operator, which will deactivate the entire equipment. It shall be located no more than 6-ft 7-in from the floor to the highest point the control device. It shall be capable of being locked in the de-energized state (OFF) only.

3.2.10 CONDUIT: Flexible conduit is not permitted in exposed areas. All wires, cables, and hoses will be enclosed by rigid, oil-proof protection, except where flexibility is necessary for operation of the equipment. Flexible wires, cables and hoses shall be arranged to prevent draping or tripping hazards.

3.2.11 SERVICE ACCESS: Components subject to periodic adjustment, replacement, or servicing shall be readily accessible. Meaning that experienced personnel can access the part after no more than 30-min of labor. If any special tools or equipment are necessary to access these components, said equipment will be supplied as part of the system and provided with a proper storage location within the system.

3.2.12 NEW EQUIPMENT: The equipment furnished under this purchase description shall be new and unused.

3.2.13 COMPONENT ENVIRONMENT: Under no circumstances shall a component be used in an application not recommended by the component manufacturer. Components shall not be subjected to conditions of operation beyond the recommendations of the manufacturer, such as excessive heat, lack of lubrication, over-loading.

3.2.14 REPLACEMENT COMPONENTS: All replaceable components shall be manufactured to definite standards for tolerance, clearance, and finish, enabling components to be field installed without further machining.

3.2.15 SURFACE BUILDING AND COATINGS: Welding, brazing, soldering, coating or plating shall be employed only where specified in the original design. These operations may not be employed as a means of reclaiming a defective part.

3.2.16 FASTENING DEVICES: All screws, pins, bolts, and similar parts shall be installed in such a manner as to prevent change in tightness. Those devices subject to removal or adjustment shall not be swaged, peened, staked, or otherwise permanently deformed. They shall not be installed using permanent bonding adhesives.

3.2.17 CLEANING AND DEBURRING: All surfaces of castings, forgings, molded parts, stampings, and welded components shall be cleaned and free from sand, dirt, fins, flash, scale, flux, and other harmful or extraneous materials. All edges shall be either rounded or beveled unless sharpness is required to perform a necessary function. Except as specified herein, the condition and finish of all surfaces shall be commensurate with the manufacturer's commercial practice.

3.2.18 PAINTING: All unfinished surfaces of the equipment shall be painted with a lead free and chromium free commercial grade of metal primer and a minimum of one finish coat. The

BUILDING 299 WELD VENTILATION

color shall be in accordance with the manufacturer's standard commercial practice, or as necessary to maintain compliance with OSHA regulations, as applicable.

3.2.19 MOTORS:

3.2.19.1 All motors shall be rated for continuous duty.

3.2.19.2 Motors shall not operate in an overload condition during normal operation of the equipment and shall be equipped with overload protection.

3.2.19.3 Each motor shall bear an identification plate containing the identity of the manufacturer, model number, serial number, input voltage, amperage, horsepower, phase, frequency, duty cycle, and frame size or mounting identification.

3.2.19.4 Motor starters and controls shall operate at no greater than 120-VAC. It is preferred that they operate at 24-VDC.

3.2.19.5 Motor starters shall provide drop-out protection. This means that, in the event of a loss of power, the equipment shall be re-energized only by the deliberate action of the operator. Manual or mechanical motor starters shall not be deemed acceptable.

3.2.20 **DIALS AND GAUGES:** All scales, dials, and gauges shall be manufactured of corrosion and oil resistant material. All wording shall be in the English language using plain, bold face lettering. Lettering shall be permanent and have a contrasting background.

3.3 Safety, Security and Environmental

3.3.1 **SECURITY:** The RIA-JMTC is an Army installation subject to Department of Defense safeguards, various precautions, and plant protection measures. All of the below requirements will be necessary of contractors visiting RIA to satisfy requirements of this purchase description; Additional requirements will be placed on contractors requiring access to the Army Network, or Common Access Card (CAC), as specifically detailed below. At all times during the execution of this work, contractor personnel will maintain adequate plant protection devices to minimize espionage, sabotage, and other malicious destruction and damage. The contractor shall comply with all security requirements of the Rock Island Arsenal. Rock Island Arsenal island-wide Force Protection levels may be adjusted/changed at any time, which may cause possible delays and will directly affect procedures for accessing the island.

3.3.1.1 Access and General Protection/Security Policy and Procedures: The contractor and any associated subcontractor employees shall provide all information required for background checks to meet installation access requirements to be accomplished by the installation Director of Emergency Services. All contractor employees must comply with all personal identity verification requirements (IAW FAR clause 52.204-9) as directed by Department of Defense (DoD), Headquarters Department of the Army (HQDA), and any local policy. If the Force Protection Condition (FPCON) changes, the Government may require changes in contractor installation access, security matters, or security processes.

3.3.1.1.1 Access to RIA: Contractor and all subcontractor employees performing work at RIA shall comply with adjudication standards and procedures using the National Crime Information Center Interstate Identification Index (NCIC-III) and Terrorist Screening Database (TSDB) and any applicable installation, facility access screening and local security policies and procedures. The JMTC Representative/ COR shall provide

BUILDING 299 WELD VENTILATION

guidance to complete the Access Control Records Check request Form through the Rock Island Arsenal Directorate of Emergency Services.

3.3.1.1.2 Random Antiterrorist Measures Program (RAMP) participation: Contractor personnel are subject to RAMP security program (i.e. vehicle searches, wearing of ID badges, etc.). Contractor shall comply with any, and all instructions issued by the Rock Island Arsenal Police Department. The RAMP is discussed in the RIA-JMTC Anti-Terrorism Training.

3.3.1.1.3 During FPCONs levels of Charlie or Delta, services may be discontinued/postponed due to a higher National or local security threat. Services will resume when FPCON Level is reduced to Bravo, or lower. FPCON levels are described in Anti-Terrorism Level I Training.

3.3.1.1.4 Contractor personnel shall return all Installation Badges and access passes as soon as possible prior to contract completion. RIA-JMTC electronic keys and access passes are accountable items, shall be returned within 24-hours of no longer being needed. Items will be returned to the COR, or placed in a drop box at a RIA-JMTC access point.

3.3.1.2 Security Training: The contractor shall complete the following training:

3.3.1.2.1 Anti-Terrorism, Level I: All contractor employees, including subcontractor employees, requiring access to Army installations, facilities, or controlled access areas shall complete Anti-Terrorism (AT) Level I Awareness training. The COR will be provided a copy of the Rock Island Arsenal –Joint Manufacturing and Technology Center (RIA-JMTC) AT Level I Awareness Training and assure that the training is complete. The contractor shall sign a memorandum of record for each contractor employees and subcontractor employee to the RIA-JMTC Operations Center prior issuing any electronic keys, or access pass being authorized.

3.3.1.2.2 iWatch (See Something, Say Something) Training: The Contractor and all associated subcontractors shall complete iWatch Training. iWatch Training shall be provided during the Anti-Terrorism Training.

3.3.1.3 For Contractors requiring Common Access Card (CAC): Before CAC issuance, the contractor employee requires a favorably adjudicated National Agency Check with Inquiries (NACI) or an equivalent or higher investigation in accordance with Army Directive 2014-05. The contractor employee will be issued a CAC only if duties involve one of the following: (1) Both physical access to a DoD facility and access, via logon, to DoD networks onsite, or remotely or (2) Remote access via logon, to a DoD network using DoD-approved remote access procedures, or (3) Physical access to multiple DoD facilities or multiple Non-DoD Federally controlled facilities on behalf of the DoD on a recurring basis for a period of 6-months, or more. At the discretion of the sponsoring activity, an initial CAC may be issued based on a favorable review of the FBI fingerprint check and a successfully scheduled NACI at the Office of Personnel Management. Contractors needing a NACI or equivalent investigation or higher investigation will coordinate this investigation through their COR. Contractor personnel shall turn in CAC cards upon completion of their contractual obligations, or at the request by the COR, or at the request of the Contracting Officer.

BUILDING 299 WELD VENTILATION

3.3.2 **FEDERAL MARIJUANA LAWS REMAIN UNCHANGED:** Note: Rock Island Arsenal is under the exclusive federal jurisdiction of the United States. Under federal law, marijuana is still defined as a Schedule I drug, and possession and use of marijuana is still illegal. Any person using or in possession of marijuana on Rock Island Arsenal may be criminally prosecuted in federal district court. In addition, such individuals may be permanently barred from entering Rock Island Arsenal.

3.3.3 **REAL ID:** Starting 03-May-2025 all personnel entering Rock Island Arsenal will be required to show a Real ID form of identification.

3.3.4 **FIRE PREVENTION AND PROTECTION:** The contractor shall comply with all fire prevention measures prescribed in the installation Fire Regulations, a copy of which is on file in the office of the Contracting Officer. A written fire permit shall be obtained from the installation Fire Marshall for use of open flame devices, such as torches, portable furnaces, tar kettles, or gas and electric welding and cutting equipment, in, on, or within 15-ft of the building. The contractor shall be liable for any fire loss to the Government properly attributable to negligence on the part of the contractor, including failure to comply with fire prevention measure described by the terms of this purchase description.

3.3.5 **INDUSTRY AND REGULATIONS:** The equipment shall comply with the most current of all local, state, and federal laws and regulations listed in Standards and Publications.

3.3.6 **MATERIAL EXCLUSIONS:** The equipment shall not contain polychlorinated biphenyl (PCB), ozone depleting substances (Class I or Class II), or asbestos materials.

3.3.7 **SAFETY REGULATION COMPLIANCE:** The contractor shall comply with standard OSHA and RIA safety standards, including but not limited to conforming to confined space work requirements when applicable and wearing of Personal Protective Equipment (PPE) where designated.

3.3.8 **SAFETY LOCKOUTS:** Each point of first connection shall be designed and constructed to allow the utility to be completely isolated from the equipment. This isolation shall be insured by application of a standard key locking padlock. The device(s) shall only be lockable in the de-energized (OFF) condition.

3.3.9 **LOSS OF PRESSURE:** Hydraulic and pneumatic circuits shall be designed such that loss of pressure, or pressure surges, shall not cause a hazard. Means shall be provided to prevent operation of the equipment with insufficient pressure, if such operation could cause a hazard.

3.3.10 **TRAPPED ENERGY:** Means shall be provided for the controlled release of stored energy. This energy may be in the form of, but not limited to, air and hydraulic pressure accumulators, capacitors, springs, counter balances and flywheels. When appropriate, a label shall be affixed to the stored energy source to identify the hazard.

3.3.11 **WORKING RANGE:** Hydraulic and pneumatic components shall be selected, which cannot be adjusted outside the safe working range of the circuit and/or equipment.

3.3.12 **EMERGENCY STOP:** The system will incorporate a clearly identified, red, mushroomed, control button with a yellow backing plate at every operator work station. Upon momentary operation, any emergency stop button shall de-energize all machine motions and override all other controls without creating additional hazards. All motion stopped shall be

BUILDING 299 WELD VENTILATION

restarted by the deliberate action of the operator (requiring manual reset). No other red mushroomed buttons shall be allowed on the equipment. It is preferred that there is no other red buttons of any type.

3.3.13 CONTROL GUARDS: Controls shall be guarded against accidental operation.

3.4 Responsibilities

3.4.1 SITE INSPECTION: Any site inspections and/or measurements, which must be taken in order to determine the suitability of the proposed location or to perform the design of the system, are the sole responsibility of the contractor. This may begin prior to completing the bidding process. Rock Island Arsenal will support this function through the POC (point of contact) by guiding personnel, facilitating security registration, and providing general assistance. The contractor will be responsible for providing any and all equipment necessary for this process.

4. CLIN001 – AMBIENT WELD VENTILATION SYSTEM

Equipment: The supplier shall furnish all equipment normally considered by him to be standard for his machine unless identified in this requirement to be of specific manufacture. The following equipment shall be provided in addition to the equipment specified in other sections of this purchase description, which may not be standard. The inclusion of standard equipment in this paragraph is inadvertent and should not be construed to allow duplication.

4.1 Site Dimensions

This system is to be installed in B299 Zone 8 on the easternmost bay. This is to be designated as the weld area. The bay is roughly 80-ft wide by 240-ft long. Roughly 20-ft of the 80-ft width is low-bay with a height of roughly 18-ft. The 60-ft high bay has a peaked roof of roughly 35-ft in height. There is no barrier wall between the high-bay and the next low-bay section. There are rigid structures in place such as a electrical/mechanical room and overhead doors leading into the space. All of these site dimensions are to be taken into account for design of the ambient system.

4.2 Site Operations

This system will be used in service of cleaning/circulating the air in the weld area. There will be up to 14 weld booths operating in this bay. The potential for all 14 booths to be torch on at the same time is there, however with material movement and loading/unloading, a more realistic expectation is for 80 percent of the booths to be welding at any given time. The weld booths will be located in the high bay portion of the space. There will also be a large ultrasonic cleaning system located on the North side of the building. Most of the welding operations will be performed on a weld table or a manipulator. The estimated height of torch would be anywhere from 3-ft to 6-ft.

4.3 Ambient Cleaner Specifications

BUILDING 299 WELD VENTILATION

- 4.3.1 SYSTEM DESIGN: The system shall be designed as such that there are standalone filtering units installed on either side of the specified area. The units shall be placed as such to create an air circulation pattern to allow for air changeover in the area. The system shall be capable of handling 10 air exchanges per hour. Our understanding is that this can be completed with approximately (22) units but it is the responsibility of the contractor to verify the number of units required. Vertical space is a premium in the facility. Our understanding is that the units should be installed with such orientation that it minimizes the vertical footprint.
- 4.3.2 CFM: Each unit shall have a 5,000 CFM capability.
- 4.3.3 MOTOR/BLOWER: The units shall have single 3HP Motor/Blower combination.
- 4.3.4 FILTER: Each unit shall include a self-cleaning filter. The filter shall use a combination of compressed air and a cleaning apparatus such as a rapper tube or equivalent method of knocking media off of the filter. The filters shall be rated to handle weld particulate suspended in the air amongst the other particulates that may be present in the air derived from the welding process.
- 4.3.5 SENSORS: At a minimum, each unit shall include a velocity sensor, differential pressure sensor, filter status indicator, as well as a compressed air sensor. Each unit shall also include a temperature sensor that will shut down the unit in the event of the system overheating. The sensors shall indicate when more hp is needed from the blower in order to maintain appropriate level of air flow from the unit. Each unit shall include a filter pressure sensor.
- 4.3.6 SPARK ARRESTER: The units shall include guarding to protect against sparks entering the system.

4.4 System Cleanout Specifications

- 4.4.1 DUCTING: The air filtering units shall be connected to the dust collector system via a duct system. The duct shall be no larger than 8-in. Any necessary gates or dampers are the responsibility of the contractor to provide.
- 4.4.2 BLOWER: The system shall include a 25hp blower to be used with the cleanout system.
- 4.4.3 DUST COLLECTOR: The system shall be a vertical downflow dust collector with an appropriate number of cartridge filters. The unit shall expel to a 55 gallon drum for sediment removal.
- 4.4.4 SILENCER: The blower for the system cleaning unit shall include a silencer to minimize ambient noise. The unit will be located indoors in a manufacturing environment.
- 4.4.5 SENSORS: The system shall include sensors to identify when the bin is full of particulate.

4.5 Control Specifications

The system shall include an overarching control system responsible for diagnostics, controlling the cleaning cycles of the units etc. The cleaning process initiate by the control shall function as such that when the filter pressure of any given unit is determined to be too high, the control will turn that unit off and initiate the filter cleaning and suck out process. Only one unit shall be

BUILDING 299 WELD VENTILATION

turned off at any given time in order to maintain system functionality. The control interface shall include such information as: Communication Status, Any Faults, Cleaning Status, Filter Status, Filter Pressure, Air Speed, and Unit Set Points at a minimum. It shall be possible to set the cleaning cycles up on a time schedule so that the units are cleaning off shift if necessary.

4.6 Performance Test Requirements

RIA-JMTC shall require a performance test to be able to sign off on the system. The test shall be performed using some form of smoke emitting device OR welding performed in the area to ensure proper air filtering and cycling of air in the space.

5. INFORMATION TECHNOLOGY SYSTEMS AND SUPPORT

5.1 Installation IT Support:

5.1.1 PERSONNEL: RIA-JMTC will not provide the technician credentials to access the workstation. Access to the workstation will be provided by the RIA-JMTC IT Support Staff escort. Removable Media e.g., CD/DVD/USB/SD/External hard drive will be scanned prior to use. Programs and software must be ran from RIA-JMTC approved/provided media or CD/DVD(s). Contractor Devices will not be allowed to connect to the RIA-JMTC network nor will they be allowed to connect to RIA-JMTC equipment other than to scan and transfer media.

5.2 INSPECTION/FINAL ACCEPTANCE:

5.2.1 LICENSING: The software/ hardware license shall not have an internet connection. A license dongle or license file must be provided for offline use.

5.3 Media/ Devices

5.3.1 REMOVABLE MEDIA: Removable media consists of the following: CD, DVD, USB, SD, and External Hard Drives. Removable media shall be scanned prior to use. Programs and software must be ran from RIA-JMTC approved/ provided media or CD/ DVD(s).

5.3.2 CONTRACTOR DEVICES: Contractor Devices will not be allowed to connect to the RIA-JMTC network and they will not be allowed to connect to RIA-JMTC equipment other than to scan and transfer media.

5.3.3 NON-GOVERNMENT OWNED SYSTEMS OR DEVICES: The contractor shall comply with AR 25-1 and AR 25-2. The contractor shall not install or connect non-Government-owned computing systems or devices to Government networks without the COR's coordination and obtaining the proper authorization from the appropriate Information System Security Manager (ISSM), ensuring that all software has a Government Assess Only Authorization. The non-Government-owned computing systems or devices include, but are not limited to, personal or Contractor-owned thumb drives e.g., memory sticks, flash drives, Universal Serial Bus (USB) drives, jump drives, pen drives, removable or external hard drives, Personal Digital Assistants (PDA), PC Cards/Express Cards, MP3 players, cell phones, digital media, floppy disks, compact disc (CD)/digital video disk (DVD) burners, optical recordings, photo flash cards, laptops, or any devices that can store data.

BUILDING 299 WELD VENTILATION

5.3 INFORMATION ASSURANCE AND ACCREDITATION:

5.3.1 Non-Government-Owned computing systems or devices: The Contractor shall comply with AR 25-1 and AR 25-2. The Contractor shall not install or connect non-Government-owned computing systems or devices to Government networks without a government representative coordinating and obtaining proper authorization from the appropriate Information System Security Manager (ISSM), ensuring that all software has a Government Assess Only Authorization. The non-Government-owned computing systems or devices include, but are not limited to, personal or Contractor-owned thumb drives e.g., memory sticks, flash drives, Universal Serial Bus (USB) drives, jump drives, pen drives, removable or external hard drives, Personal Digital Assistants (PDA), PC Cards/Express Cards, MP3 players, cell phones, digital media, floppy disks, compact disc (CD)/digital video disk (DVD) burners, optical recordings, photo flash cards, laptops, or any devices that can store data.

5.3.2 System Accreditation and Re-Accreditation: The Contractor shall assist in providing system accreditation documentation such as required artifacts and shall answer technical questions required for registration for accreditation. All documents shall be IAW Chapter 5, and Appendices D and E, AR 25-2, Information Systems Security (dated 3 August 2007) and DOD Instruction 8510.01, Risk Management Framework (RMF) Program or future DOD regulation that supersedes these regulations. The Contractor shall assist in performing yearly reviews of the accreditation, or whenever changes/additions are made to the system. The Contractor will assist in preparing risk assessments, as required.

6. APPROVAL/SHIPPING

6.1 Shipping

6.1.1 RESPONSIBILITY: The contractor is responsible for delivery of the equipment to the Rock Island Arsenal. Adequate preserving of equipment surfaces, packing, marking, and skidding of materials for shipment shall be the responsibility of the contractor. If special lifting devices, such as hooks or eyes, are required for ease of handling, they shall be supplied with the equipment. Any special devices shall be returned to the contractor upon request only if they will not be required for future movement of the equipment, and at the contractor's expense.

6.1.2 SHIPPING SCHEDULE: Be aware, the Rock Island Arsenal will only off-load equipment arriving between 6:00 am and 12:00 pm (noon), local time on Mondays through Thursdays except holidays. For information concerning holidays, the contractor should consult the contracting officer. There is no place to stage transporting vehicles awaiting the arrival of contractors. All equipment shall be delivered at the same time, meaning the same day (multiple trucks are acceptable) unless pre-authorized to deliver on multiple days by the RIA-JMTC contracting officer.

6.1.3 RECEIVER: All shipments to Rock Island Arsenal including installation tools and/or replacement parts, as well as the original shipment of the equipment, shall be marked "ATTN: Mr. Robert McClure TARA-LGC". Items not correctly marked are subject to being returned at the vendor's expense.

6.1.4 ARRIVAL INSPECTION: Upon receipt of equipment at Rock Island Arsenal, a preliminary inspection shall be performed to determine condition and/or count. This inspection shall be performed by Rock Island Arsenal personnel.

BUILDING 299 WELD VENTILATION

6.2 Installation

6.2.1 SITE PREPARATION REQUIREMENTS: The contractor shall be solely responsible for any necessary site inspections required for determining the specifications of work that must be completed prior to final system installation. The contractor will then provide detailed information of any preparation work that the vendor must perform prior to system installation to Rock Island Arsenal.

6.2.2 SITE PREPARATION EXECUTION: The contractor will be solely responsible for site preparation except as specifically excluded in this document. This includes but is not limited to excavation, foundation work, and surface preparation. This work may be performed through the use of a sub-contractor, but the specification, supervision, and certification of the work remains the responsibility of the primary contractor.

6.2.3 PREPARATION EXECUTION SUPPORT: Rock Island Arsenal will support the preparation portion of the installation by providing utilities to the points of first connection.

6.2.4 LABOR AND MATERIAL: The supplier is solely responsible for providing all labor, materials, hardware, tools, and equipment necessary for complete installation/start-up of this system except as specifically listed in this document as being provided by the Rock Island Arsenal.

6.2.4.1 Any anchoring mechanisms/materials shall be the responsibility of the contractor to provide. If RIA-JMTC is installation the foundation, JMTC will be responsible for the installation of the contractor provided anchoring mechanisms in preparation for machine placement.

6.2.4.2 Any decking, stairs, rail systems, or other specialized operator/machine interfaces shall be provided by the contractor for use at the install location

6.2.5 SUPERVISION: Supervision of the installation process will be the responsibility of the contractor. Rock Island Arsenal shall retain the right to periodic inspection and evaluation of the process, as it deems necessary.

6.2.6 OFF-LOADING/PLACEMENT: Off-loading of the equipment from the delivery vehicle, and placement of the equipment in position for the installation is the responsibility of the contractor. The contractor shall not be allowed to use government equipment to accomplish this work.

6.2.7 LIABILITY: In any case, the equipment remains the property of the contractor, and the contractor shall assume all responsibility and liability for the equipment and the work performed upon it. The government shall be held harmless for any damage done to the equipment at any time up until final acceptance of the equipment by Rock Island Arsenal, except in the case of intentional damage and/or gross negligence on the part of Rock Island Arsenal personnel.

6.2.8 SET-UP: The contractor shall be responsible for set-up and connection of the equipment beyond connections of the utilities to the points of first connection.

6.2.9 SECURITY: The RIA-JMTC is an Army installation subject to Department of Defense safe guards, various precautions, and plant protection measures. At all times during the execution of this SOW, the contractor will maintain adequate plant protection devices to

BUILDING 299 WELD VENTILATION

minimize espionage, sabotage, and other malicious destruction and damage. The contractor shall comply with all security requirements of the Rock Island Arsenal. Rock Island Arsenal Island-wide Force Protection levels may be adjusted/changed at any time, which may cause possible delays and will directly affect procedures for accessing the Island.

6.2.10 Delivery Hours or Service Hours: Service calls, equipment installation, training, and equipment delivery (where the contractor offloads) will only be allowed from 0600 – 1530, Monday through Thursday, except for Government Holidays. Deliveries of items where the contractor has opted for Government “off-loading option”, must be received before 1200 hours. These hours are subject to change, however, the Government will notify the contractor of such changes. The vendor will contact the designated Performance Certifier/ COR to obtain an electronic key for their representative (i.e. delivery driver) in order to have access to the facility. Deliveries and service calls outside the normal hours stated above will be coordinated with the Performance Certifier/ COR to address any emergency situations."

6.3 Completion

6.3.1 Final acceptance of the equipment shall occur after the following:

6.3.1.1 Set-up completion by the contractor.

6.3.1.2 Successful completion of performance testing at Rock Island Arsenal.

6.3.1.3 Final inspection approval by the government representative or inspector. This is to verify full compliance with this description to include amendments and modifications to the final contract. The government representative shall perform any and all tests he deems necessary to insure compliance with this description and industry standards to include, but not limited to ease of control, convenience of operation, safe operation, and adequacy of lubrication devices.

6.3.1.4 All required training is complete.

6.3.1.5 Complete documentation packages are delivered.

7. TRAINING

The contractor shall provide instruction in proper operation and maintenance of the equipment without additional cost to the government. Training shall be of sufficient duration that the recipients are able to demonstrate a reasonable level of competence as determined by the equipment installer and/or the inspector. Acceptance may be delayed as a result of inadequate training.

7.1 Schedule

Training shall training shall be coordinated with the Rock Island Arsenal. Daily training shall begin no later than 6:30 a.m. CST and shall continue until at least 2:15 p.m. CST. This is required to get full coverage of the 1st shift of operation at RIA-JMTC. If training does not begin until after the stated time, RIA-JMTC may at its option require additional training at a different time to compensate for the loss of training caused by the late start. This may include more time than what is represented by the delay (e.g. a 1-hr delay may require 2-hrs later to impart the knowledge lost).

BUILDING 299 WELD VENTILATION

7.2 Location

All training shall be performed at the Rock Island Arsenal. It shall be performed using the equipment purchased in this description.

7.3 Type

Each type of training shall be given independently. Rock Island Arsenal shall coordinate with the contractor to provide the proper personnel for each type of training. The following types of training shall be provided by the contractor.

7.3.1 **OPERATOR**: Training shall be provided by the contractor for (5) operators. This shall include instruction on the safe, efficient operation of the equipment delivered. The trainees supplied by RIA-JMTC shall be familiar with machine operation, but not necessarily with the style or type of controls provided with the equipment. (E.g. for a new CNC lathe, the operator will be familiar with CNC lathe operation, but may have no experience with a Fanuc control system.)

7.3.2 **PROGRAMMING**: If the equipment includes a programmable controller, programmer training shall be provided, separate from the operator training for (2) personnel. If programming is normally performed by the operator only, then this training may be combined with the operator training.

7.3.3 **MAINTENANCE**: Mechanical and electrical control and diagnostic maintenance training shall be provided by the contractor. This shall include information on troubleshooting and preventive maintenance procedures. This shall be provided for (2) personnel.

8. SERVICE

8.1 Service/Support Requirements

The contractor shall have as a minimum, a verifiable service/repair capability which meets or exceeds the following requirements:

8.1.1 **STAFF**: Staffed by qualified, English speaking personnel fully knowledgeable in the service/repair of the equipment offered.

8.1.2 **TELEPHONE ACCESS**: Telephone access to service/repair personnel shall be available for consultation during Rock Island Arsenal normal working hours. Rock Island Arsenal normal working hours are 8:00 am CST to 3:00 pm CST, Monday through Friday, except legal federal holidays.

8.1.3 **ON-SITE RESPONSE**: Physical, on-site response shall be possible within 48-hrs of notification that service/repair of the equipment is necessary.

8.1.4 **MAINTENANCE PARTS**: Parts necessary for periodic replacement such as belts, hoses, filters, and other parts normally considered as spare parts, by the manufacturer, shall be stocked and available for shipment.

8.1.5 **PRIOR HISTORY**: Said service/repair capability shall have been available to the general public prior to the issue date of this purchase description. Adequate proof of prior availability shall be provided upon request.