

**AK USFS Chug1004 9(1), Vagt Lake Trailhead,
Chugach National Forest, Kenai Peninsula Borough, Alaska**

The work consists of excavation, grading (involving placement of Unclassified Borrow and Aggregate), vault toilet installation, concrete placement for ADA parking spaces and walkways, sign installation, and other small items of work.

Project length: 0.133 miles

Tentative Fixed Completion Date: Fall 2025
(Once solicitation is issued, see FAR Clause 52.211-10 for exact date.)

Estimated Price Range: \$700,000 and \$2,000,000

Location: Lower Trail Lake in Crown Point, Kenai Peninsula Borough, AK

**DESCRIPTION OF WORK in US CUSTOMARY UNITS
FP-14**

	One Schedule
DIVISION 150 – Project Requirements	
152 Construction Survey & Staking	Yes
153 Contractor Quality Control and Assurance	Yes
154 Contractor Sampling & Testing	Yes
155 Construction Schedule	Yes
157 Soil Erosion Control, Silt Fence	200 LNFT
157 Soil Erosion Control, Fiber Roll	2,350 LNFT
157 Soil Erosion Control, Stabilized Construction Exit	1 EACH
DIVISION 200 – Earthwork	
201 Clearing & Grubbing	3.0 ACRE
203 Removal of Gate	1 EACH
204 Roadway Excavation	140 CUYD
204 Unclassified Borrow	10,500 CUYD
204 Berms	Yes
211 Roadway Obliteration, Method 2	1,650 SQYD
DIVISION 250 – Slope Reinforcement and Retaining Walls	
251 Boulder	120 EACH
DIVISION 300 – Aggregate and Base Courses	
302 Roadway Aggregate, Method 2 (Alaska DOT Gradation D-1)	3,900 CUYD
DIVISION 500 – Rigid Pavement	
501 Minor Concrete Pavement, Reinforced, 6-inch Depth	280 SQYD

	One Schedule
DIVISION 600 – Incidental Construction	
609 Concrete Gutter	110 LNFT
609 Wheelstop, Rubber	31 EACH
615 Sidewalk, Concrete (4-inch depth)	37 SQYD
615 Detectable Warning Panels	17 SQYD
622 Rental Equipment	Yes
623 Special Labor, Hired Technical Services (Archaeologist)	Yes
624 Placing Conserved Topsoil, 6-inch Depth	2,940 SQYD
625 Turf Establishment (Hydraulic Method)	2,940 SQYD
633 Sign System (Directional Sign)	4 EACH
633 Sign System (MUTCD Standard)	7 EACH
633 Sign System (Site Sign)	1 EACH
633 Remove and Reset Sign	1 EACH
634 Permanent Pavement Markings, Type B, Solid (White Parking Stripe)	420 LNFT
635 Permanent Pavement Markings, Type B, Accessibility Symbol	2 EACH
635 Temporary Traffic Control	LPSM
646 Fixture, Kiosk	1 EACH
646 Fixture, Vault Toilet	1 EACH