

Statement of Work

Preventive Maintenance Services for plumbing

BACKGROUND

Northern Navajo Medical Center (NNMC) current plumbing infrastructure is aging and requires ongoing monitoring and maintenance of its drainage system.

OBJECTIVES

The objective is to provide preventative maintenance drainage system services for NNMC SR0001 and the West Wing Administration Building SR0004. The service is to remove waste matter systematically to maintain healthy conditions in the buildings main drainage system.

PERIOD OF PERFORMANCE

Period of Performance will have a base period of 12 months followed by 4 option periods of 12 months each.

TASK

1. Contractor shall complete Preventative Maintenance work; Drain Line Bi-Annual Cleaning of problem area, Jetting of Drain Lines for (2) 1-week visits, Bio-Clean Treatment for Drain Lines, use high-resolutions Video camera to view drain lines and assess its conditions. These inspections should identify blockage, cracks or pipe deterioration, etc.
2. Work must be coordinated with the Facility Management 120 hours (5 business days) prior notice must to minimize disruption to patient care.
3. Contractor Qualification Requirements: Contractor shall be licensed to perform the Plumbing Drain Lines and other Plumbing Services in the State of New Mexico.
4. Schedule routine inspections and cleaning of sewer lines to prevent debris buildup
5. Ensure waste from faucets, toilets and drains are in good conditions
6. Any build up will require mechanical auger to keep from further build up
7. Contractor shall develop and maintain a comprehensive safety program. All Contractor's personnel onsite must use Personal Protective Equipment (PPE) that meet Occupational Safety Health Administration (OSHA) requirements.
8. Train and provide recommendations to Shiprock Northern Navajo Medical Center Maintenance Staff on the best solutions to continuous maintain Drain Lines in excellent conditions.
9. Provide a completed Service Report for completed preventative maintenance services.
10. Any damages caused during Preventative Maintenance Services must be fixed immediately by the contractor. All work areas shall be maintained in a clean and in orderly condition.

GOVERNMENT-FURNISH (Include - PROPERTY)

No government furnish supplies, equipment, etc. is required.

Contractor shall comply with the Hospital Policy including Pre-construction Risk Assessments (PRCA), which includes Interim Life Safety Measure (ILSM), Infection Control Risk Assessments (ICRA) while performing work on IHS property.

CONTRACT-FURNISH (Include – PROPERTY)

The Contractor shall provide all labor, tools, materials, and necessary supervision.

SECURITY REQUIREMENTS

Contractor shall check in with Facility Maintenance and a Maintenance Staff will escort to security to obtain a contractor's visitor badge.

PLACE OF PERFORMANCE

Northern Navajo Medical Center, U.S. Hwy, 491 North, Shiprock New Mexico, 874120

- Main Hospital
- West Wing