

ELECTRICAL

SOR-26-051

Category "A"

High Voltage Switchboard Circuit Breaker Earthing Solenoid Coils and Switch Replacement

1.0 ABSTRACT

This item describes the requirement to provide the services of High Voltage certified / qualified field service technicians with experience performing maintenance and repair on the High Voltage 6.6 KV Main Switch Board circuit breakers and circuitry for troubleshooting and replacement of Circuit Breaker Earthing Solenoid Coils and Switch's.

2.0 REFERENCES

2.1 Tech Manual T9235-AL-MMC-010, Main Power Switchboard, 6.6KV, 2500A

2.2 Drawing 2876 Point Eight Power High Voltage Switchboard Drawing

3.0 ITEM LOCATION AND DESCRIPTION

3.1 Location:

3.1.1 Location: Engine Room

3.1.2 Quantity: One (5) Switchboard Circuit Breaker earthing switches and associated keys

3.2 Item/Description/Manufacturer's Data: Point Eight Power 6.6 KV, 2500 Amp 3 Phase 3 Wire 41 KA RMS System

3.2.1 Contractor Furnished Material: None

4.0 GOVERNMENT FURNISHED MATERIALS:

Qty	Description
9	Interlocking Coil P/N UEKOZL1/ 110 VAC
2	Key Interlock Mechanism P/N S1059001Y
9	Earthing Switch P/N OJWN12/100A210-OJW-ZB31-UEKO2C

5.0 NOTES: None

6.0 QUALITY ASSURANCE REQUIREMENTS: None Additional

7.0 STATEMENT OF WORK:

7.1 Provide the services of High Voltage certified / qualified field service technicians with a minimum of 5-years' experience performing maintenance and repair on the T-AKE 1 Lewis and Clark Class High Voltage 6.6 KV Main Switch Board circuit breakers and circuitry.

ELECTRICAL

SOR-26-051

Category "A"

High Voltage Switchboard Circuit Breaker Earthing Solenoid Coils and Switch Replacement

- 7.2 Prior to performing maintenance, conduct a meeting with the Chief Engineer and MSCREP to discuss the plan of action and power that is required to be secured and duration of the power outage.
- 7.3 Ship's Crew will secure the required power and perform lockout/tagout of the affected SWBD sections.
- 7.4 Perform initial troubleshooting on the below circuit breaker earthing switches, interlocking coils, and key interlocks:
 - CB22 (1A)
 - CB25 (2B)
 - CB24 (2A)
 - CB27 (Harmonic Filter #2)
 - CB1 (MDG#1)
- 7.5 Replace a total of Nine (9) Earthing Switches, Nine (9) Earthing Switch Interlock coils, and two (2) Key Interlock Switches.
- 7.6 Upon completion of all repairs / replacements Operationally test CKT Breaker Interlocks and Keys for proper operation and earthing.
- 7.7 Provide a Condition found report for any critical repairs required to deliver a fully functional and Safe High Voltage Switchboard System. The Government may issue Contract Change Order (CCO) to repair all critical safety repairs.
- 7.8 Reports:
 - 7.8.1 Provide a final report documenting the as found condition, troubleshooting and repair actions taken, and results of the operational testing.

8.0 GENERAL REQUIREMENTS: None additional