

Statement of Work (SOW) (Draft)
42 SFS Duress Notifier System

1.0 PURPOSE. IAW UFC 4-022-01 Entry Control Facilities Access Control Points, para., 5-7.8 ID Check Island and Guard Booth, “the guard booth must have space allotted for electronic control panels for ECF/ ACP automation equipment, EFO, duress alarm, intercom, workspace incorporating space for computer monitors, and an electrical panel board”.

2.0 DESCRIPTION OF ITEMS/SERVICES. The following minimum requirements are needed as indicated:

2.1 Under this effort, the Contractor will provide a Wireless Duress Notifier System addition in Building 865 at Maxwell (physically Gunter Annex) AFB must be able to seamlessly integrate with the Advantor Systems without any alteration or modification of the existing systems. This system will annunciate at the BDOC to notify Security Forces Squadron personnel of emergency situations within the defined areas of Building 865:

2.2 The Intruder Detection System (IDS) addition on this project fully integrates with the Advantor Suite for Networks (ASN) Head End system.

2.3 This Duress system will consist of one (1) IG2 Panel with fiber modem, one (1) ITK Keypad, one (1) wireless receiver, one (1) hardwire duress button to be mounted under the desk, two (2) wireless duress buttons for use in and around B865.

2.4 The Contractor will establish 120VAC connections from the GFE-provided breaker box to each Infraguard II IDS chassis via GFE-provided junction boxes that incorporate with Advantor systems. The GFE-junction boxes must be within 6 feet of each Advantor IG2 Panel.

2.5. The Contractor will provide all required system cabling for this effort. The Contractor will also provide Design Drawings and a post-installation As Built Package in PDF format.

3.0 DELIVERY/SERVICE ADDRESS: BLDG 865, DALRAIDA GATE

4.0. INSTALLATION GUIDELINES:

4.1. The Contractor only provides Full Turnkey Installations. Installation of any product provided by Advantor by anyone other than an Advantor Certified Installer is prohibited.

4.2 Electrical installations/modifications must be completed by a certified electrician in accordance with NFPA 70. Flexible power cords must not pass through walls, floors, door, or ceilings. Any penetrations in walls and ceilings must be appropriately fire

stopped. Ensure a facility assessment is completed to ensure facility systems can support this request.

4.3 Properly label breaker for emergency shutoff and power isolation

4.4 Any hot work that is required (grinding, torches for heat setting/curing, cutting, brazing, soldering, hot tapping, etc.) requires permits. Contact fire prevention office to obtain permits prior to work beginning.

4.5 Protect all fire alarm system/fire suppression system components from damage during the project. If assistance is required due to proximity to/affecting the systems contact Fire Department/CE Chugach alarm shop prior to work beginning.

4.6 Do not block emergency egress. If this is not avoidable during construction/project a DD Form 2977 Deliberate Risk Assessment Worksheet must be accomplished either in form format or in the Joint Risk Assessment Tool (JRAT) for rerouting of emergency traffic. A map must be provided to occupants displaying the temporary rerouting must be supplied to all occupants. This must be signed by the squadron commander for risk assumption authority prior to project start.

5.0. WARRANTY: The Contractor's system must be able to seamlessly integrate with the Advantior Systems without any alteration or modification of the existing systems will repair or replace, without charge, any merchandise manufactured by it that has been proven defective in material for a period of three (3) years after the date of shipment, upon receipt of defective product to the proper Warranty Depot. Subsystems such as monitors, computers, printers, and other product not classified as Advantior-compatible Systems manufactured product will be warranted for the period of time provided for by the original equipment manufacturer. Advantior-compatible Systems will provide warranty on all replacement parts and repairs for ninety (90) days from the date of shipment. All goods for warranty work shall be sent freight prepaid to our Orlando, Florida facility. The Contractor will provide warranty without charge for any failed installation or service that has been proven the result of the workmanship of the Contractor's technicians for a period of one (1) year from acceptance of the installation. Repairs made necessary by reason of misuse, alteration, normal wear, excessive voltage, or Acts of God are not covered under this warranty. The Contractor is not liable for any incidental or consequential expenses or liability incurred by the customer and any installation, modification, repair, or attempted repair by any non-Contractor certified technician will void the warranty.

The foregoing warranty is in lieu of all other warranties, expressed or implied, including but not limited to, the implied warranties of merchantability and fitness for a particular purpose.

6.0 GENERAL INFORMATION: ALL items provided must be brand new.

Refurbished/remanufactured items or previously used items are not authorized.