

SHIP: YRB-30

COAR: 18KTA

PLANNER: A. PETTY

ITEM NO: YR30-L246

PCN: YR30-L246

1. **SCOPE:**

- 1.1 Title: Lagging; replace
- 1.2 Location of Work:
 - 1.2.1 INTERIOR HULL; YRB-30
- 1.3 Identification:
 - 1.3.1 Quantity 1500 Square feet: Lagging

2. **REFERENCES:**

- 2.1 Standard Items FY26
- 2.2 YRB-30 General Arrangement DWG.

3. **REQUIREMENTS:**

- 3.1 Accomplish the requirements of NAVSEA STANDARD ITEM 009-11 of 2.1
 - 3.1.1 Remove up to 1,500 square feet of existing damaged or deteriorated thermal insulation (lagging) from piping, ducting, and associated systems located in various compartments onboard YRB-30. Specific locations and access requirements shall be identified by the Government during the pre-performance ship check or provided as Government Furnished Information (GFI) prior to the start of work.
 - 3.1.2 Install up to 1,500 square feet of new thermal insulation (lagging) in the areas where removal was performed under 3.1.1. Installation shall conform to the requirements of NAVSEA Standard Item 009-11 and applicable specifications. All materials shall be approved by the Government prior to installation.
- 3.2 The Contractor shall accomplish the requirements of NAVSEA Standard Item 009-32 of reference 2.1 to perform surface preparation and touch-up painting on all new and disturbed surfaces resulting from the work described in 3.1.1 and 3.1.2. Coatings shall be applied in accordance with the applicable paint schedule and environmental controls.

4. **NOTES:**

- 4.1 None.

5. GOVERNMENT FURNISHED MATERIAL (GFM):

- 5.1 LLT M:
 - 1. None
- 5.2 PUSH MATERIAL:
 - 1. None
- 5.3 KITTED MATERIAL:
 - 1. None