

SHIP YRB-30

ITEM NO. YR30-L244

COAR 18KTA

PLANNER A. PETTY

1: SCOPE

1.1 Title Temporary Scaffolding; provide

1.2 Location of Work

- 1.2.1 OFFICE; 1-9-0-Q
- 1.2.2 OFFICE; 1-11-0-Q
- 1.2.3 PASSAGE; 1-11-1-L
- 1.2.4 PASSAGE; 2-12-1-L
- 1.2.5 PASSAGE; 1-14-2-L
- 1.2.6 PASSAGE; 2-14-2-L
- 1.2.7 PASSAGE; 2-14-3-L
- 1.2.8 CREW LOUNGE; 1-14-0-L
- 1.2.9 PASSAGE; 2-14-3-L
- 1.2.10 PASSAGE; 1-17-0-L
- 1.2.11 PASSAGE; 2-17-2-L
- 1.2.12 PASSAGE; 1-20-0-L
- 1.2.13 PASSAGE; 2-20-4-L
- 1.2.14 SEABAG LOCKER; 2-7-4-Q
- 1.2.15 SEABAG LOCKER; 2-7-2-Q

1.3 Identification

1.3.1 Not Applicable

2. REFERENCES

- 2.1 FY26 Standard Items
- 2.2 29 CFR PART 1915, Occupational Safety and Health Standards
- 2.3 YRB-30 GEN DRAWING

3. REQUIREMENTS

3.1 Provide and install a steel tube and clamp type staging in accordance with 2.2 in the location listed in 1.2, with sufficient levels and projections to safely reach and access to all elevated areas identified.

3.1.1 Install the staging within the first 5 days of the availability:

3.1.2 Install staging/scaffolding assembly with platform including safety life rails around platform for maintenance & preservation work overhead.

3.1.3 Staging shall be capable of sustaining a load of 300 pounds at any point or level of the staging:

3.2 Remove staging upon completion of work and when directed by the supervisor

3.3.3 Accomplish the requirements of 009-32 of 231 for new and disturbed surfaces

4. NOTES.

4.1 None.

5. **GOVERNMENT FURNISHED MATERIAL**

5.1 LLTM

1. None

5.2 PUSH MATERIAL

1. None

5.3 KITTED MATERIAL

1. None