

SHIP YRB-30

ITEM NO. YR30-L234

COAR 18KTA

PLANNER A. PETTY

1: **SCOPE**

1.1 Title: 03 LEVEL DECK DRAIN; GRILL ROOM INSTALL

1.2 Location of Work

1.2.1 03 LEVEL GRILL ROOM

2. **REFERENCES**

2.1 FY26 Standard Items

2.2 29 CFR PART 1915, Occupational Safety and Health Standards

2.3 YRB-30 GEN DRAWING (GFI)

2.4 DWG-7642480_C (WEATHER DECK DRAINS PIPING MODS) (GFI)

2.5 DWG-8784675 (GRILL ROOM ARRANGEMENT AND MOD DETAILS) (GFI)

3. **REQUIREMENTS**

3.1 Provide all labor, material, and services necessary to install new vertical drain piping from existing deck drains on the 03-level grill room roof to a designated discharge point on the 02-level deck.

3.2 Submit a Process Control Procedure (PCP) in accordance with 2.1, Standard Item 009-09, for the installation of new drain piping. The PCP shall include detailed steps for routing, structural penetrations, installation of hangers/supports, and restoration of watertight integrity. Work shall not commence until the PCP is reviewed and approved by the Government.

3.3 Install new vertical drain piping from each existing 03-level grill room roof drain to the designated discharge point on the 02-level deck. Installation shall include:

3.3.1 Pipe routing along bulkheads or structural members. Installation of hangers, brackets, and supports in accordance with applicable standards.

3.3.2 Penetration of the 03-level deck (if required), with watertight integrity restored per NAVSEA requirements.

3.3.3 Termination at a Government-approved location for proper drainage.

3.4 Ensure all materials (pipe, fittings, sealants, supports) meet applicable MIL-SPEC or ASTM standards and are suitable for marine service.

3.5 Perform functional testing of the installed drain system to verify proper flow and leak-free operation.

3.6 Accomplish cleaning and touch-up painting of all disturbed or newly installed surfaces in accordance with 2.1, Standard Item 009-32. Coating systems shall match existing adjacent surfaces and comply with the applicable paint schedule.

4. **NOTES.**

4.1 All work shall be accomplished in accordance with 2.1, 009-11.

4.2 Coordinate all penetrations and routing with the Government prior to execution.

4.3 All measurements and routing shall be verified during the pre-performance ship check.

5. **GOVERNMENT FURNISHED MATERIAL**

5.1 LLTM

1. None

5.2 PUSH MATERIAL

1. None

5.3 KITTED MATERIAL

1. None