

TASK GROUP INSTRUCTION
 AIM REV 20.11.4.0 (OCTOBER 2020)

TGI NO.:	COMPONENT NAME: FUEL OIL FILL PP	TYPE: AY	PHASE: A	REPEAT: 0	CHANGE: 0
SHIP/HULL NO.: DDG-113	SHIP/HULL NAME: USS JOHN FINN	SYSTEM:		PROJ/WO NO: BC1	CASREP CAT:
CU PHASE TITLE: F/O - REPLACE FUEL OIL FILL PIPING IN 01-122-0-L					
PREPARING ACTIVITY:					
PREPARED BY: SHINICHI ITO		CODE 234.	PHONE 315-243-4297	DATE 27-JUN-2025	
APPROVED BY: HIDEO HARADA		CODE 234.	PHONE 315-243-5176	DATE 27-JUN-2025	
CONCURRED BY:		CODE	PHONE	DATE	
CONCURRED BY:		CODE	PHONE	DATE	
CONCURRED BY:		CODE	PHONE	DATE	
CONCURRED BY:		CODE	PHONE	DATE	
REASON FOR WORK/NEED FOR CHANGE:					
CHANGE INSTRUCTIONS:					
SPECIAL REQUIREMENTS: CLEANLINESS FOR PIPING SYSTEM/EQUIPMENT LEVEL II AND III. CLASS P-2 PIPING.					

WORK CERTIFICATION SIGNATURES

COMPLETION OF WORK REVIEW:		BADGE NO.:	SHOP/CODE:	PHONE:	DATE:
ACCEPTANCE OF COMPLETED WORK					
PHYSICAL INSPECTION REQUIRED: ☐ YES ☒ NO	PHYSICAL INSPECTION COMPLETED:	BADGE NO.:	SHOP/CODE:	PHONE:	DATE:
RECORDS REVIEW:		BADGE NO.:	SHOP/CODE:	PHONE:	DATE:



LIST OF EFFECTIVE PAGES									
SHT NO.	CHG NO.	SHT NO.	CHG NO.	SHT NO.	CHG NO.	SHT NO.	CHG NO.	SHT NO.	CHG NO.
1-6		QA28 (1)							
J1-2		QA28 (1-2)							
M1-3									
Sketch (1)									

1. SCOPE/PURPOSE

1.1 Title: Fuel Oil Fill Piping; replace

1.2 Location of Work:

1.2.1 Passage (01-122-0-L)

1.2.2 Fan Room Pressure Zone (PZ) No. 2 (01-126-3-Q)

1.2.3 Chief Petty Officer Living Space No. One (1-110-0-L)

1.2.4 Auxiliary Machinery Room No. One (4-126-0-E)

1.2.5 Decontamination Station No. One (Outer Clothing Undressing Area) (01-120-2-L)

1.2.6 02 Level Weather, Frames between 126 and 134, Starboard (Stbd)

1.2.7 02 Level Weather, Frames between 126 and 134, Port

1.2.8 Vacuum Collection Holding Tank Room No. One (4-110-0-E)

1.2.9 Sewage Collection Tank No. One

1.2.10 Power Supply / Conversion Room (3-126-2-Q) (CHW dewater)

1.3 Identification:

1.3.1 Quantity (One EA), Sewage Collection Tank No. One
Capacity: 490 Gallons

1.3.2 Quantity (Approx 5 FT), Sewage Collection Tank No. One Vent Piping
Size: 2 Inch IPS (2.375 Inch OD x 0.083 Inch WT)
Material: Cu-NI 90-10
Specification: MIL-T-16420
Remarks: See Sketch Enclosure-01, Sheet 5B (Zone 2-F) of 2.4, and Sheet 4 (Zone 2-E and -F) of 2.5 for details.

1.3.3 Quantity (Approx 8 FT), Fuel Oil Fill Piping including Valve (FT-V-14) with Tubing, from welding bead on upper side of elbow joint near the ceiling to ahead on first bent portion, and inlet side tailpiece on cutout valve of pressure transducer (FT-PT-3)
Size: 8 Inch IPS, SCH 10S (8.625 Inch OD x 0.148 Inch WT)
1/4 Inch IPS, SCH 40S (0.540 Inch OD x 0.088 Inch WT)
1/4 Inch OD (0.250 Inch OD x 0.065 Inch WT)
Material: CRES 304L
Specification: ASTM A312 / ASTM A269

2 TGI NO.:

SHIP:

FUEL OIL FILL PP	AY	A	0
DDG-113	CHG/VER:		0/0

Remarks: See Sheet 4 (Section 2-F) of 2.11 for detail

1.3.3.1 Quantity (One EA), Fuel Oil Fill Transducer Root Valve (FT-V-14)

Size: 1/4 Inch IPS

Material: CRES 316 / 316L

Specification: 803-2177525 / ASTM A182

Pressure: 900 PSI

Type: Globe In-Line Stop / Socket Weld

1.4 Security Classification: None.

1.5 Initial Condition:

1.5.1 Potential Asbestos Hazard.

1.6 Contractor work start date: 4/20/26

1.7 Contractor work completion date: 6/15/26

2. **REFERENCES:**

REF. NO.	DOCUMENT /DRAWING NUMBER	DOCUMENT/DRAWING TITLE	REV	CHG NO.	COPY REQ'D (Y/N)	SOURCE DOC (Y/N)	PARA	SEC	PG	CHP
1	NSI FY-26	NAVSEA Standard Items	-	1	N					
2	LI FY-26	Local Standard Items	-	ORG	N					
3	DWG 7300007	SEWAGE COLLECTION TANK ASSEMBLY	L		Y				AL L	
4	DWG 529-7060033	DDG-51 CLASS SEWAGE AND PLUMBING DRAIN DISH PP DIAGRAM	D		Y				5B	
5	DWG 528-7062083	PLUMBING DRAINS, ZONE 4210	-		Y				4	
6	PDD 505-ELM-210146	TEST GUIDANCE FOR REQD ELEVATED NDT OF INACCESSIBLE WELDING JOINT ON PIPING SYS	-		Y				AL L	
7	TM S9AA0-AB-GOS-010/GSO	General Specifications for Overhaul of Surface Ships (GSO)	11		N					
8	DWG 803-2177525	1/4"-2" BW & SW 900 LB ASME Valve	AA		N					
9	TM S9086-RK-STM-010/CH-505	Piping Systems	6		N					
10	DWG 541-7059978	FUEL TRANSFER SYSTEM DIAGRAM	C		Y				3A 6,4 A, 8A	
11	DWG 541-7062080	FUEL OIL SYSTEMS, DISTILLED ZONE 4210	-		Y				4	
12	DWG 541-7061793	FUEL OIL SYSTEMS DISTILLED ZONE 1450	-		Y				4	
13	DWG 541-7062090	FUEL OIL SYSTEM, DISTILLED, ZONE 4220	-		Y				4,5	
14	DWG 541-7061807	FUEL OIL SYSTEMS, DISTILLED,ZONE 2120	-		Y				4,5	
15	MIL MIL-STD-1627	BENDING OF PIPE OR TUBE FOR SHIP PIPING SYSTEMS	C		N					

3. **APPENDICES:**

3 TGI NO.:

SHIP:

FUEL OIL FILL PP	AY	A	0
DDG-113	CHG/VER:		0/0

- 3.1. ~~Appendix "J" TGI Job Summary Information Sheet~~
- 3.2. ~~Appendix "M" TGI Material List~~
- 3.3. ~~Appendix "D" Deficiency Form~~

4. GENERAL REQUIREMENTS:

4.1 Not Applicable.

5. PROCEDURE:

5.1 Accomplish the requirements of 099-902YO of 2.2 for each tank listed in 1.3.1.

5.1.1 Install new steel hex head cap screws conforming to Item No. 37 in Parts List of 2.3 and steel nuts conforming to Item No. 38 in Parts List of 2.3 for each tank listed in 1.3.1.

5.2 Remove existing and reinstall each sewage collection tank No. One vent piping listed in 1.3.2 for supporting of fuel oil fill piping replacement, using 2.4, 2.5, and Enclosure-01 for guidance.

5.2.1 Accomplish the requirements of 009-012 of 2.1, including Table One, Column(s) A, Lines One through 10.

5.2.2 Accomplish liquid penetrant test on final layer of each onboard weld joint for Class P-2 sewage collection tank No. One vent piping listed in 1.3.2 in accordance with Paragraph 4.3.a of 2.6. The accept or reject criteria must be in accordance with Paragraph 4.3.a of 2.6.

(I)(G) "ELEVATED NDT INSPECTION"

5.2.2.1 The area of ENDT is shown on Enclosure-01.

5.2.3 Accomplish an unobstructed air flow test for sewage collection tank No. One vent piping listed in 1.3.2 with pressure source at not greater than 100 PSIG to ensure free flow capability and to ensure removal of blanks, using compressed air in accordance with Paragraph 506h of 2.7. Allowable obstruction: None.

(V)(G) "UNOBSTRUCTED AIR FLOW TEST"

5.3 Remove corrosion inhibitor of each new valve listed in 1.3.3.1.

5.3.1 Disassemble each new valve as required for cleaning, using 2.8 for guidance.

5.3.1.1 Accomplish a visual inspection of the groove pin of each valve in accordance with Paragraph 4 of NAVSEALOGCENDET PORTSMOUTH BULLETIN 4855-Ser-6231/B11-2-22Nov2011 of 2.8.

5.3.2 Assemble each new valve with bonnet gasket and gland packing. Bonnet gaskets must conform to MIL-G-24716. Gland packing must conform to MIL-P-24503 and MIL-P-24583.

5.3.3 Thread lubricant must be in accordance with General Note 4.C of 2.8.

5.3.4 Accomplish a shop test of each new valve, using 2.10 for guidance.

5.3.4.1 Shop test equipment must conform to the requirements in Paragraph 505-11.1.3 of 2.9.

5.3.4.2 Tolerance of shop test pressure and rounded off to graduation of test pressure gauge/gage must be in accordance with Paragraph 505-11.1.3.18 of 2.9.

5.3.4.3 Accomplish a strength test of each valve with the valve half open position, using clean fresh water at 270 PSIG (not less than 270 PSIG and not more than 275 PSIG) for a minimum of 30 minutes. Verify there are no signs of external leakage and the permanent deformation.

FUEL OIL FILL PP	AY	A	0
DDG-113	CHG/VER:	0/0	

(V) "STRENGTH TEST"

5.3.4.4 Accomplish a seat tightness test of each valve, test for seat tightness in the direction tending to open the valve, using clean fresh water at 40 PSIG (not less than 40 PSIG and not more than 41 PSIG) for a minimum of 3 minutes. Maximum allowable leakage: 10 cubic centimeters (cc) per hour.

(V) "SEAT TIGHTNESS TEST"

5.3.4.5 Document each shop test results on QA Form 28 Enclosure-02-1.

5.4 Remove existing, fabricate, and install new each fuel oil fill piping including valve with tubing listed in 1.3.3, using 2.10 through 2.14 for guidance.

5.4.1 Bend each new pipe in accordance with 2.15.

5.4.2 Accomplish the requirements of 009-012 of 2.1, including Table One, Column(s) A, Lines One through 10.

5.4.3 Accomplish the requirements of 009-071 of 2.1 for hydrostatic test, using clean, fresh water at 270 PSIG, for each new and disturbed fuel oil fill piping systems.

5.4.3.1 Document shop hydrostatic test results on QA Form 28 Enclosure-03-1.

5.4.4 Accomplish the requirements of 009-071 of 2.1 for air tightness test, using low pressure air at 50 PSIG, for each new and disturbed fuel oil fill piping systems at onboard.

5.4.4.1 Document the test results on QA Form 28 Enclosure-03-2.

5.4.5 Cycle each valve from fully closed to fully open to fully closed 4 times. Allowable sticking, binding, or leaking: None.

(V) "VALVE CYCLING"

5.5 Accomplish the requirements of 009-032 of 2.1 for each new and disturbed surface.

5.6 Notes:

5.6.1 Planner: Code 234 S. Ito, 243-4297
 Planner: Code 231A Y. Kishi, 070-7787-1998
 Planner: Code 231A N. Maruyama, 243-9939
 Planner: Code 231A T. Uematsu, 243-9943
 Planner: Code 232 K. Suzuki, 243-2490
 Planner: Code 233 S. Suzuki, 070-3769-2799

5.6.2 Work Integration Manager (WIM): Code 333 T. Yaginuma, 080-5419-0598

5.6.3 Installation, maintenance, and removal of cofferdam to Item No. 30 at the forward for supporting of sewage collection tank No. One vent piping removal/reinstallation will be accomplished by TGI Nos. 38BC154101R01, M01, and U01 (SRF-JRMC TGI).

5.6.4 SRF-JRMC Code 134 will provide laboratory analysis and test service for disinfectant solution used for CHT tank when requested by WIM, Code 333.

5.6.5 This TGI is issued to clear DFS No. DDG-113-0002-2025.

5.6.6 JCN EB14-0523 is related to this TGI.

FUEL OIL FILL PP	AY	A	0
DDG-113	CHG/VER:		0/0

- 5.7 Government Furnished Material (GFM):
 - 5.7.1 SRF-JRMC will provide GFM listed in the Appendix “M”.
- 5.8 SRF-JRMC will provide the following service work: (TGI No. 38BC154101S02)
 - 5.8.1 [C740] Crane and crane rigging service.
 - 5.8.2 [X99E] Utilities service, electrical.
 - 5.8.3 [X99M] Utility service, including low pressure air supply, water supply, and steam supply.
 - 5.8.4 [C106.1] Safety inspection for SRF-JRMC employees.
 - 5.8.5 [C106.2] Gas free inspection for SRF-JRMC employees.
 - 5.8.6 [C133] QA inspection for (G) Symbol(s).
 - 5.8.7 [C135] QA inspection for (G) Symbol(s).

6	TGI NO.:	FUEL OIL FILL PP	AY	A	0
	SHIP:	DDG-113	CHG/VER:		0/0

APPENDIX "M"

TGI MATERIAL LIST

SYSTEM:	PLANT NO.:	COMPONENT NAME:	TYPE:	PHASE:	REPEAT:	CU PH VERSION:	CASREP CAT:
		FUEL OIL FILL PP	AY	A	0	0	

CU PHASE TITLE:

F/O - REPLACE FUEL OIL FILL PIPING IN 01-122-0-L

MATERIAL REFERENCES

REF NO.	DOCUMENT/DRAWING NUMBER	DOCUMENT/DRAWING TITLE	REV
---------	-------------------------	------------------------	-----

JOB ORDER:

38BC154101

KEY OP:

A01

MATERIAL LIST

ITEM NO.	PC NO.	REF NO.	M / C	DESCRIPTION	STOCK NUMBER	GENERIC MATL TYPE	LVL	QA	HAZ MAT	DOC NO.	QTY REQD/ UNIT	QTY USED/ UNIT
200			M	GASKET, ORIG: C232 K. SUZUKI 243-2490 ORDERED FOR KTR	9B 5330 013294168		NA	4	N	51275175	3/EA	
201			M	GASKET,S, ORIG: C232 K. SUZUKI 243-2490 ORDERED FOR KTR	9B 5330 015386718		NA	4	N	51275177	1/EA	
400			M	PIPE, METAL, PIPE, METAL, 8 INCH IPS (8.625 INCH OD X 0.148 INCH WALL THICKNESS), SCHEDULE 10S, SEAMLESS, ASTM A312 TP 304L *REQUIRED CONTINUOUS LENGTH 10 FT. ORDERED FOR KTR C234 S.ITO 243-4297	9B 4710 LL9004690		NA	4	N	51167465	10/FT	

NOTES:

M-1

TGI NO.:	FUEL OIL FILL PP	AY	A	0
SHIP:	DDG-113	CHG/VER:	0/0	

MATERIAL LIST

ITEM NO.	PC NO.	REF NO.	M / C	DESCRIPTION	STOCK NUMBER	GENERIC MATL TYPE	LVL	QA	HAZ MAT	DOC NO.	QTY REQD/ UNIT	QTY USED/ UNIT
401			M	PIPE, METAL, PIPE, METAL, 8 INCH IPS (8.625 INCH OD X 0.148 INCH WALL THICKNESS), SCHEDULE 10S, SEAMLESS, ASTM A312 TP 304L *REQUIRED CONTINUOUS LENGTH 10 FT. ORDERED FOR KTR C234 S.ITO 243-4297	9B 4710 LL9004690		NA	4	N	51167466	10/FT	
402			M	PIPE, METAL, PIPE, METAL, SIZE: 1/4 INCH IPS X SCHD 40S (0.088 INCH WALL THICKNESS), MATL: CRES 304L, SEAMLESS FOR HIGH TEMP, PLAIN END, ASTM A312 GR TP304L PROVIDE ONE CONTINUOUS LENGTH 5 FT. DO NOT PROVIDE SEPARATELY. ORDERED FOR KTR C234 S.ITO 243-4297	9B 4710 LL4647629		NA	4	N	51167467	5/FT	
403			M	TUBE, METAL, TUBE, METAL, SIZE: 1/4 INCH OD X 0.065 INCH WALL THK, CRES GR-TP304L, ASTM A269, SEAMLESS *REQUIRD ONE CONTINUOUS LENGTH 10 FT. ORDERED FOR KTR C234 S.ITO 243-4297	9B 4710 LL9000995		NA	4	N	51167464	10/FT	
404			M	COUPLING,TUBE, ORDERED FOR KTR C234 S.ITO 243-4297	9B 4730 012498375		NA	4	N	51165188	1/EA	
405			M	UNION,TUBE, ORDERED FOR KTR C234 S.ITO 243-4297	9B 4730 000610412		NA	4	N	51165191	1/EA	
407			M	BUSHING,, ORDERED FOR KTR C234 S.ITO 243-4297	9C 4730 LL4637345		NA	4	N	51167451	1/EA	
408			M	ELBOW 90 DEG, ELBOW 90, SHORT RADIUS, SIZE: 8 INCH IPS, BUTT WELD, CRES 304L, SCH 10S, ASME B16.9, ASTM A403 ORDERED FOR KTR C234 S.ITO 243-4297	9B 4730 LL9100991		NA	4	N	51187408	1/EA	
409			M	BOSS, OUTLET, WELDED BASE X SOCKET WELDING OUTLET, 1/4 INCH IPS OUTLET, CRES 316L, DWG# SP485064 TABLE III FITTING ASSY NO. 0801, ASTM A182 GRADE 316L ORDERED FOR KTR C234 S. ITO 243-4297	9B 4730 LL4647632		NA	4	N	51187409	1/EA	
410			M	COUPLING, ORDERED FOR KTR C234 S.ITO 243-4297	9C 4730 LL9800917		NA	4	N	51167452	2/EA	

M-2

TGI NO.:	FUEL OIL FILL PP	AY	A	0
SHIP:	DDG-113	CHG/VER:	0/0	

MATERIAL LIST

ITEM NO.	PC NO.	REF NO.	M / C	DESCRIPTION	STOCK NUMBER	GENERIC MATL TYPE	LVL	QA	HAZ MAT	DOC NO.	QTY REQD/ UNIT	QTY USED/ UNIT
411			M	BACKING RING, BACKING RING, 8 INCH IPS, RING WIDTH 1 INCH, CRES 304L, TYPE "CCC", SCH 10 ORDERED FOR KTR C234 S.I.T.O 243-4297	9B 4730 LL4569210		NA	4	N	51167461	4/EA	
412			M	O-RING, ORDERED FOR KTR C234 S.I.T.O 243-4297	9B 5331 014461959		NA	4	N	51165194	4/EA	
413			M	SHIELD,SAFETY,PIPE, ORDERED FOR KTR C234 S.I.T.O 243-4297	9B 4730 010101000		NA	4	N	51165195	1/EA	
414			M	SHIELD,SAFETY,PIPE, ORDERED FOR KTR C234 S.I.T.O 243-4297	9B 4730 010101003		NA	4	N	51165197	1/EA	
415			M	COUPLING,TUBE, ORDERED FOR KTR C234 S.I.T.O 243-4297	9B 4730 005423290		NA	4	N	51165199	2/EA	
416			M	BACKING, ORDERED FOR KTR C234 S.I.T.O 243-4297	9C 4730 LL4558779		NA	4	N	51167453	2/EA	
417			M	VALVE,GL, ORDERED FOR KTR C234 S.I.T.O 243-4297	3B 4820 015415287		NA	4	N	51625128	1/EA	
450			M	COUPLING,TUBE, ORDERED FOR KTR C234 S.I.T.O 243-4297	9B 4730 007225473		NA	4	N	51165200	2/PG	
451			M	BACKING,, ORDERED FOR KTR C234 S.I.T.O 243-4297	9C 4730 LL4558783		NA	4	N	51167454	4/EA	
452			M	INSULATI, ORDERED FOR KTR C234 S.I.T.O 243-4297	9B 5640 LL9607846		NA	4	N	51167455	4/EA	
453			M	INSULATI, ORDERED FOR KTR C234 S.I.T.O 243-4297	9B 5640 LL9607849		NA	4	N	51167456	2/EA	
454			M	INSULATI, ORDERED FOR KTR C234 S.I.T.O 243-4297	9B 5640 LL9607854		NA	4	N	51167457	1/SH	
455			M	ADHESIVE, ORDERED FOR KTR C234 S.I.T.O 243-4297	9B 8040 002738708		NA	4	Y	51165202	4/GL	
456			M	ADHESIVE, ORDERED FOR KTR C234 S.I.T.O 243-4297	9B 8040 008419773		NA	4	Y	51165205	6/PT	

M-3

TGI NO.:	FUEL OIL FILL PP	AY	A	0
SHIP:	DDG-113	CHG/VER:	0/0	

☐ NUCLEAR

☐ NON-NUCLEAR

APPENDIX "D"
DEFICIENCY FORM

1. SHIP/HULL NO.:	2a. DL or DR No. (Circle One)	2b. REVISION:	3a. COMPONENT NAME:	3b. TYPE:	3c. PHASE:	3d. REPEAT:
DDG-113			FUEL OIL FILL PP	AY	A	0
4a. ICN:	4b. KEY OP:	5. LOC SPACE/LVL:	FRAME:	P/S/C:	6. CAUSED BY:	
38BC154101	A01					
7. DESCRIPTION:						
8. ORIGINATOR:	NAME:	BADGE:	SHOP/CODE:	DATE:	PHONE NO.:	
9. CORRECTIVE ACTION:						
10. EVALUATOR:	NAME:	BADGE:	SHOP/CODE:	DATE:	PHONE NO.:	
FOR NON-NUCLEAR USE ONLY						
11. RFD/RFW REQ'D ☐		LAR REQ'D ☐		SRD/PLAN REV REQ'D ☐		
ILS MOD REQ'D ☐		DWG NO.:		S/A NO.:		
12. ISOLATION SATISFACTORY:	SIGN:	BADGE:	SHOP/CODE:	DATE:	PHONE NO.:	
13. SUBSAFE OQE RECORD? YES ☐ NO ☐	SIGN:	BADGE:	SHOP/CODE:	DATE:	PHONE NO.	
14. CORRECTIVE ACTION COMPLETE:	SIGN:	BADGE:	SHOP/CODE:	DATE:	PHONE NO.	
15. INSPECTION REQ'D? :YES ☐ NO ☐	INSPECTION COMPLETE/SIGN:	BADGE:	SHOP/CODE:	DATE:	PHONE NO.	
16. RECORDS REVIEW COMPLETE (DR ONLY)	SIGN:	BADGE:	SHOP/CODE:	DATE:	PHONE NO.	
DL's ISSUED (DR ONLY)						

☐ NUCLEAR

Deficiency Form Continuation Sheet

☐ NON-NUCLEAR

1. SHIP/HULL NO.:	2a. DL or DR No. (Circle One)	2b. REVISION:	3a. COMPONENT NAME:	3b. TYPE:	3c. PHASE:	3d. REPEAT:
DDG-113			FUEL OIL FILL PP	AY	A	0

This image shows a single sheet of white paper with horizontal blue or grey ruling lines. The lines are evenly spaced and run across the width of the page. There are no margins, text, or other markings on the paper.

Sewage Collection Tank No. One Vent Piping



Location: Passage (1-122-0-L)

Remarks:

The painted red is area of Elevated NDT

SKETCH

SHOP TEST RECORD

QA FORM 28 Planning must fill in blocks identified by a ♦ prior to issuing

♦1. SHIP USS JONH FINN		HULL NO. DDG-113		♦2. JCN EB14-0523		♦3. LWC/SHOP KTR		♦4. CWP/REC SER NO. N/A		5. SYSTEM/COMPONENT/ROTATABLE POOL SER NO. Fuel Oil Fill Transducer Root Valve FT-V-14					
♦6. REFERENCES: TEST REF (E.G., MS, TECH MAN) & OTHER REFS (E.G., VLV DWG)						7. TEST GAGE RANGE /INSTRUMENT USED		SERIAL NO.		CAL DUE DATE		8. RELIEF VLV SET POINT			
A.		DWG: 541-7059978 Rev. "C"													
B.		TM: S9086-RK-STM-010/CH-505 Rev. "6"													
C.															
D.															
9. TEST REQUIREMENTS & RESULTS															
TEST TYPE KEY		H = STRENGTH AND POROSITY/ELEVATED PRESSURE TEST				J = MECHANICAL JOINT TIGHTNESS		ST = SEAT TIGHTNESS		OP = OPERATIONAL		O = OTHER (SPECIFY):			
♦ TEST TYPE (SEE KEY)	♦ PARAGRAPH DESCRIBING VALVE POSITION AND POINT OF ENTRY	♦ REF LTR	GAGE USED (LTR FROM BLK 7)	♦ REQUIRED MEDIUM	MEDIUM USED	♦ REQUIRED PRESSURE	ACTUAL PRESSURE	♦ MINIMUM DURATION	ACTUAL DURATION	♦ ALLOWED LEAKAGE	ACTUAL LEAKAGE	SAT/UNSAT	SIGNATURE, BADGE NO. & DATE		
H	Para 5.3.4.3 "Strength Test"	A B		Clean Fresh Water		270 PSIG		30 Minutes		None.					
ST	Para 5.3.4.4 "Seat Tightness Test"	A B		Clean Fresh Water		40 PSIG		3 Minutes		10 cc per hour					
10. REMARKS. (CRAFTSMAN/QAI SUBMIT A DF TO RESOLVE UNSAT DATA)															
11. QA INSPECTOR/SHOP SUPERVISOR SIGNATURE/BADGE NO. (RECORD REVIEWED FOR FINAL ACCEPTANCE)							DATE		12. QAS SIGNATURE/BADGE NO. (RECORD HAS BEEN REVIEWED FOR COMPLETENESS)					DATE	

SHOP TEST RECORD

Page 1 of 1

QA FORM 28 Planning must fill in blocks identified by a ♦ prior to issuing

♦1. SHIP USS JOHN FINN		HULL NO. DDG113		♦2. JCN EB14-0523		♦3. LWC/SHOP KTR			♦4. CWP/REC SER NO. N/A		5. SYSTEM/COMPONENT/ROTATABLE POOL SER NO. FUEL OIL FILL SYSTEM PIPING				
♦6. REFERENCES: TEST REF (E.G., MS, TECH MAN) & OTHER REFS (E.G., VLV DWG)						7. TEST GAGE RANGE /INSTRUMENT USED			SERIAL NO.		CAL DUE DATE		8. RELIEF VLV SET POINT		
A.	S9086-RK-STM-010/CH-505 Rev. 6														
B.	DWG 541-7059978 Rev. C														
C.															
D.															
9. TEST REQUIREMENTS & RESULTS															
TEST TYPE KEY		H = STRENGTH AND POROSITY/ELEVATED PRESSURE TEST				J = MECHANICAL JOINT TIGHTNESS			ST = SEAT TIGHTNESS		OP = OPERATIONAL		O = OTHER (SPECIFY): _____		
♦ TEST TYPE (SEE KEY)	♦ PARAGRAPH DESCRIBING VALVE POSITION AND POINT OF ENTRY	♦ REF LTR	GAGE USED (LTR FROM BLK 7)	♦ REQUIRED MEDIUM	MEDIUM USED	♦ REQUIRED PRESSURE	ACTUAL PRESSURE	♦ MINIMUM DURATION	ACTUAL DURATION	♦ ALLOWED LEAKAGE	ACTUAL LEAKAGE	SAT/UNSAT	SIGNATURE, BADGE NO. & DATE		
H	5.4.3	A,B		Clean Fresh Water		270 PSIG		30 minutes		None					
10. REMARKS. (CRAFTSMAN/QAI SUBMIT A DF TO RESOLVE UNSAT DATA)															
11. QA INSPECTOR/SHOP SUPERVISOR SIGNATURE/BADGE NO. (RECORD REVIEWED FOR FINAL ACCEPTANCE)							DATE		12. QAS SIGNATURE/BADGE NO. (RECORD HAS BEEN REVIEWED FOR COMPLETENESS)					DATE	

SHOP TEST RECORD

QA FORM 28 Planning must fill in blocks identified by a ♦ prior to issuing

♦1. SHIP USS JOHN FINN		HULL NO. DDG113		♦2. JCN EB14-0523		♦3. LWC/SHOP KTR		♦4. CWP/REC SER NO. N/A		5. SYSTEM/COMPONENT/ROTATABLE POOL SER NO. FUEL OIL FILL SYSTEM PIPING					
♦6. REFERENCES: TEST REF (E.G., MS, TECH MAN) & OTHER REFS (E.G., VLV DWG)						7. TEST GAGE RANGE /INSTRUMENT USED		SERIAL NO.		CAL DUE DATE		8. RELIEF VLV SET POINT			
A.		S9086-RK-STM-010/CH-505 Rev. 6													
B.															
C.															
D.															
9. TEST REQUIREMENTS & RESULTS															
TEST TYPE KEY		H = STRENGTH AND POROSITY/ELEVATED PRESSURE TEST				J = MECHANICAL JOINT TIGHTNESS		ST = SEAT TIGHTNESS		OP = OPERATIONAL		O = OTHER (SPECIFY):			
♦ TEST TYPE (SEE KEY)	♦ PARAGRAPH DESCRIBING VALVE POSITION AND POINT OF ENTRY	♦ REF LTR	GAGE USED (LTR FROM BLK 7)	♦ REQUIRED MEDIUM	MEDIUM USED	♦ REQUIRED PRESSURE	ACTUAL PRESSURE	♦ MINIMUM DURATION	ACTUAL DURATION	♦ ALLOWED LEAKAGE	ACTUAL LEAKAGE	SAT/UNSAT	SIGNATURE, BADGE NO. & DATE		
H	5.4.4	A		Low Pressure Air		50 PSIG		30 minutes		None					
10. REMARKS. (CRAFTSMAN/QAI SUBMIT A DF TO RESOLVE UNSAT DATA)															
11. QA INSPECTOR/SHOP SUPERVISOR SIGNATURE/BADGE NO. (RECORD REVIEWED FOR FINAL ACCEPTANCE)							DATE		12. QAS SIGNATURE/BADGE NO. (RECORD HAS BEEN REVIEWED FOR COMPLETENESS)					DATE	