

SHIP YRB-30

ITEM NO. YR30-L245

COAR 18KTA

PLANNER A. PETTY

1: SCOPE

- 1.1 Title: REPLACEMENT OF LIFERAIL & STANCHION ON MAIN DECK
- 1.2 Location of Work
 - 1.2.1 MAIN DECK; WEATHER DECK, STARBOARD
 - 1.2.2 The Government will identify the exact stanchion to be removed and the installation location for the new removable life rail stanchion during the pre-performance ship check. Reference 2.4, 2.5 and 2.6 shall be used by the Contractor as technical guidance for configuration and installation intent.

2. REFERENCES

- 2.1 FY26 Standard Items
- 2.2 29 CFR PART 1915, Occupational Safety and Health Standards
- 2.3 YRB-30 GEN DRAWING (GFI)
- 2.4 ELM-081775 REPLACEMENT OF LIFERAIL & STANCHION ON MAIN DECK_A (GFI)
- 2.5 ELM-230018 FAB-INSTL OF LIFERAIL STAN ASSY ON MN DK (WEATHER STBD) (GFI)
- 2.6 PHOTO REFERENCE OF FWD WEATHERDECK - Weather Deck Stanchion Location, STBD Side (GFI)

3. REQUIREMENTS

- 3.1 Submit a Process Control Procedure (PCP) in accordance with 2.1, Standard Item 009-09, for the removal of the existing stanchion and installation of the new removable life rail stanchion. The PCP shall include detailed steps for hot work, structural modifications, fastener installation, and restoration of watertight integrity. Work shall not commence until the PCP is reviewed and approved by the Government.
- 3.2 Remove the existing fixed life stanchion from the weather deck at the location identified in 1.3. Removal shall include all associated hardware, base plates, and securing components. Preserve surrounding structure and coatings to the maximum extent practicable.
- 3.3 Install a new removable life rail stanchion assembly in the location identified in 1.3. Installation shall be guided by the configuration and intent described in 2.5 and 2.6, and shall include:
 - 3.3.1 Fabrication or installation of a deck-mounted socket or base to receive the removable stanchion.
 - 3.3.2 Installation of the removable stanchion and associated hardware, ensuring secure fit and ease of removal.
 - 3.3.3 Alignment and height of the stanchion shall comply with applicable safety standards for personnel protection and gangway operations.
- 3.4 Ensure all materials and components meet applicable MIL-SPEC or ASTM standards and are suitable for marine and weather deck service.
- 3.5 Accomplish cleaning and touch-up painting of all disturbed or newly installed surfaces in accordance with 2.1, Standard Item 009-32. Coating system shall match adjacent surfaces and comply with the applicable paint schedule.

4. NOTES.

- 4.1 All work shall be accomplished in accordance with 2.1, 009-11.
- 4.2 Coordinate all penetrations and routing with the Government prior to execution.
- 4.3 All measurements and routing shall be verified during the pre-performance ship check.

5.

GOVERNMENT FURNISHED MATERIAL

5.1 The Government will furnish the following material for use in this work item:

5.1.1. Removable life rail stanchion chains, quantity and specifications as identified in 2.4 & 2.5.

5.1.2. The Contractor shall receive, inspect, and verify the condition and quantity of all GFM prior to installation. Any discrepancies shall be reported to the Government immediately.

5.1.3. The Contractor shall install the GFM chains in accordance with the configuration and intent described in 2.4, 2.5 and 2.6, and as directed by the Government during the pre-performance ship check.

5.2 PUSH MATERIAL

1. None

5.3 KITTED MATERIAL

1. None