

WebAIM Short Form TASK GROUP INSTRUCTION

08-AUG-2025 0806

20.15.6.0.9333 (July 2025)

ICN: 38BC112201 KeyOp: A01

TGI NO:	COMPONENT NAME: 03 - 05 LVL WEATHER	TYPE: AY	PHASE: A	REPEAT: 0	CHG/VER: 0/0
SHIP/HULL NO: DDG-113	SHIP/HULL NAME: USS JOHN FINN	PROJECT: BC1	SYSTEM:	PLANT ID:	CASREP CAT:
CU PHASE TITLE: F/O – ACCOMPLISH PSVTN OF SUPERSTR AND PLTF AND REPLT OF NONSKID DECK COVERING					
PREPARING ACTIVITY:		STATUS: APP		WORKING STATUS:	
PREPARED BY: TAKANASHI, TATSUNORI		CODE: 231A	PHONE: 3152436238	DATE: 28-JUL-2025	
APPROVED BY: NAKAMURA, YUUJI		CODE: 231A	PHONE: 3152436041	DATE: 28-JUL-2025	
CONCURRED BY:		CODE:	PHONE:	DATE:	
REASON FOR WORK/NEED FOR CHANGE: ES01L024					
JCN: ES01-L024					
SPECIAL REQUIREMENTS: TGI Short Form					
CU PHASE DESCRIPTION: 1 SCOPE/PURPOSE: 1.1 Title: Preservation of Superstructure and Platform and Replacement of Nonskid Deck Covering; accomplish 1.2 Location of Work: 1.2.1 03 Level Weather, Frames between 175 and 215, Port 1.2.2 04 Level Weather, Frames between 175 and 190, Port and Starboard (Stbd) 1.2.3 05 Level Weather, Frames between 180 and 192, Port and Stbd 1.3 Identification: 1.3.1 Quantity (650 SF), Exterior Surface of Platform 76 Feet – 5 Inches Above Base Line (ABL) and Platform 65 Feet – 8 Inches ABL, including stanchion and support Remarks: The area except where nonskid deck covering system is installed					
ZONE MANAGER: YAGINUMA, TAKEHIDE		ZONE:	COMPARTMENT:	LEVEL:	FRAME: SIDE:
JOB SUMMARY ID: 122A2101	TOT MAN HR.:	TOT DUR:	TOT JML COST:	PLANNING ACCEPTANCE:	

WORK CERTIFICATION SIGNATURES:	DLs												
COMPLETION OF WORK REVIEW:				BADGE NO:	SHOP/CODE:	PHONE:	DATE:						
RECORDS REVIEW:				BADGE NO:	SHOP/CODE:	PHONE:	DATE:						



WebAIM Short Form TASK GROUP INSTRUCTION

08-AUG-2025 0806

20.15.6.0.9333 (July 2025)

(Continued)

ICN: 38BC112201

KeyOp: A01

TGI NO:	COMPONENT NAME: 03 - 05 LVL WEATHER	TYPE: AY	PHASE: A	REPEAT: 0	CHG/VER: 0/0
SHIP/HULL NO: DDG-113	SHIP/HULL NAME: USS JOHN FINN	PROJECT: BC1	SYSTEM:	PLANT ID:	CASREP CAT:
CU PHASE TITLE: F/O – ACCOMPLISH PSVTN OF SUPERSTR AND PLTF AND REPLT OF NONSKID DECK COVERING					

CU PHASE DESCRIPTION (Cont.)

1.3.2 Quantity (175 SF), Deck Plating of Platform 76 Feet – 5 Inches ABL and Platform 65 Feet – 8 Inches ABL, including vertical surface up to height of 4 inches from deck in and around peel and stick nonskid deck area

1.3.3 Quantity (One Lot), Composite Panel for Platform 76' – 5" ABL and Platform 65 Feet – 8 Inches ABL

1.3.4 Quantity (5 SF in Total), Deteriorated Coating of Longitudinal Bulkhead, 03 Level, Frames between 193 and 213, Port
Remarks: The area is surface where underside of louver

1.3.5 Quantity (9 SF in Total), Deteriorated Coating of Transvers Bulkhead, 03 Level to 05 Level, Frames between 186 and 189, Port and Starboard

1.3.6 Quantity (4 SF in Total), Deteriorated Coating of Foundation for Antenna 3-10B

1.4 Security Classification: None.

1.5 Initial Condition: None.

1.6 Contractor work start date: 4/20/26

1.7 Contractor work completion date: 6/15/26

2 PROCEDURE:

2.1 Accomplish the requirements of 009-032 of Ref. No. One, including Table 2, Line(s) One, for each area listed in 1.3.1.

2.2 Accomplish the requirements of 009-032 of Ref. No. One, including Table 2, Line(s) 23, for each area listed in 1.3.2.

2.2.1 Accomplish the requirements of 009-026 of Ref No. One, including Attachment G, for installation of new peel and stick nonskid deck covering. Application of peel and stick nonskid deck covering must conform to MIL-PRF-24667, Type XI, Composition PS.

2.3 Accomplish the requirements of 009-032 of Ref. No. One, including Table 2, Line(s) 83, for each area listed in 1.3.3.

2.4 Accomplish the requirements of 009-032 of Ref. No. One, including Table 2, Line(s) One, for each area listed in 1.3.4 through 1.3.6.

2.4.1 The preservation area must not exceed 10 square feet per one area.

2.5 Notes:

2.5.1 Planner: Code 231A T. Takanashi, 243-6238

2.5.2 Work Integration Manager (WIM): Code 333 T. Yaginuma, 080-6522-9560

2.5.3 JCN ES01-L024 is related to this TGI.

2.6 Government Furnished Material (GFM): None.

WebAIM Short Form TASK GROUP INSTRUCTION

08-AUG-2025 0806

20.15.6.0.9333 (July 2025) (Continued) ICN: 38BC112201 KeyOp: A01

TGI NO:	COMPONENT NAME: 03 - 05 LVL WEATHER	TYPE: AY	PHASE: A	REPEAT: 0	CHG/VER: 0/0
SHIP/HULL NO: DDG-113	SHIP/HULL NAME: USS JOHN FINN	PROJECT: BC1	SYSTEM:	PLANT ID:	CASREP CAT:
CU PHASE TITLE: F/O – ACCOMPLISH PSVTN OF SUPERSTR AND PLTF AND REPLT OF NONSKID DECK COVERING					

CU PHASE DESCRIPTION (Cont.) 2.7 SRF-JRMC will provide the following service work: (TGI No. 38BC112201S02) 2.7.1 [C740] Crane and crane rigging service. 2.7.2 [X99E] Utility service, electrical. 2.7.3 [X99M] Utility service, including water supply, steam supply and low pressure air supply except on-board blasting work. 2.7.4 [C106.1] Safety inspection for SRF-JRMC employees. 2.7.5 [C106.2] Gas free inspection for SRF-JRMC employees. 2.7.6 [C133] QA inspection for (G) symbol(s).					
--	--	--	--	--	--

Ref. No.	Document/Drawing Number	DOCUMENT/DRAWING TITLE	REV	CHG NO.	CPY REQ	PARAGRAPH	SECT	PG	CHPT
----------	-------------------------	------------------------	-----	---------	---------	-----------	------	----	------

WebAIM Short Form TASK GROUP INSTRUCTION

08-AUG-2025 0806

20.15.6.0.9333 (July 2025)

(Continued)

ICN: 38BC112201

KeyOp: A01

TGI NO:	COMPONENT NAME: 03 - 05 LVL WEATHER	TYPE: AY	PHASE: A	REPEAT: 0	CHG/VER: 0/0
SHIP/HULL NO: DDG-113	SHIP/HULL NAME: USS JOHN FINN	PROJECT: BC1	SYSTEM:	PLANT ID:	CASREP CAT:
CU PHASE TITLE: F/O – ACCOMPLISH PSVTN OF SUPERSTR AND PLTF AND REPLT OF NONSKID DECK COVERING					

Ref. No.	Document/Drawing Number	DOCUMENT/DRAWING TITLE	REV	CHG NO.	CPY REQ	PARAGRAPH	SECT	PG	CHPT
1	NSI FY-26	NAVSEA Standard Items	-	1	N				
2	LI FY-26	Local Standard Items	-		N			OR G	

TASK NAME / TASK DESCRIPTION	SHOP/ TSD	TS	SF WC	CREW #	MHRS	RWRK
2.1 PNTR , RGRS , CARP , QA	22/KE	PC				N
2.2 PNTR , CARP , QA	22/KE	PC				N
2.3 PNTR QA	22/KE	PC				N
2.4 PNTR , QA	22/KE	PC				N
Preservation Work CFM: all paints, grits, thinner, compressor and fuel oil, dryer for compressor, air conditioner, and misc such as consumable parts and covering material.	22/MQ	CS				N
Process Funding Document	10/CT	OM				N

MATERIAL REFERENCES			
REF NO.	DOCUMENT/DRAWING NUMBER	DOCUMENT/DRAWING TITLE	REV

ICN: 38BC112201	KEY OP: A01
-----------------	-------------

MATERIAL LIST												
ITEM NO.	PC NO.	REF NO.	M / C	DESCRIPTION	STOCK NUMBER	GENERIC MATL TYPE	LVL	QA	HAZ MAT	DOC NO.	QTY REQD/ UNIT	QTY USED/ UNIT