

WebAIM Short Form TASK GROUP INSTRUCTION

08-AUG-2025 0806

20.15.6.0.9333 (July 2025)

ICN: 38BC186502 KeyOp: A01

TGI NO:	COMPONENT NAME: TEMPORARY STAGING SF	TYPE: TST	PHASE: A	REPEAT: 0	CHG/VER: 0/0
SHIP/HULL NO: DDG-113	SHIP/HULL NAME: USS JOHN FINN	PROJECT: BC1	SYSTEM: 86512	PLANT ID:	CASREP CAT:
CU PHASE TITLE: *F/O - INSTALL AND REMOVE SCAFFOLDING TO/FROM VARIOUS LOCATION FOR S/F WORK					
PREPARING ACTIVITY:		STATUS: APP		WORKING STATUS:	
PREPARED BY: TAMURA, DAISUKE		CODE: 231A	PHONE: 3152439526	DATE: 18-JUL-2025	
APPROVED BY: KOMATSU, SHUUHEI		CODE: 231A	PHONE: 3152436786	DATE: 19-JUL-2025	
CONCURRED BY:		CODE:	PHONE:	DATE:	
REASON FOR WORK/NEED FOR CHANGE: ES01L025					
JCN: ES01-L025					
SPECIAL REQUIREMENTS: TGI Short Form					
CU PHASE DESCRIPTION: 1. SCOPE/PURPOSE: 1.1 Title: Scaffolding for Ship's Force Work; install and remove 1.2 Location of Work: 1.2.1 Between 03 Level and 04 Level Weather, Frames between 128 and 140, Port and Starboard (Stbd) 1.2.2 Between 03 Level and 05 Level Weather, Frames between 159 and 171, Port and Stbd 1.2.3 Between 02 Level and 04 Level Weather, Frame 185, Port and Stbd 1.2.4 Between 02 Level and 05 Level Weather, Frame 240, Port and Stbd 1.2.5 Access Trunk (3-322-1-T) 1.2.6 Escape Trunk (4-220-2-T)					
ZONE MANAGER: YAGINUMA, TAKEHIDE		ZONE:	COMPARTMENT: VARIOUS	LEVEL:	FRAME: SIDE: U
JOB SUMMARY ID: 865A1202	TOT MAN HR.:	TOT DUR:	TOT JML COST:	PLANNING ACCEPTANCE:	

WORK CERTIFICATION SIGNATURES:	DLs												
COMPLETION OF WORK REVIEW:				BADGE NO:	SHOP/CODE:	PHONE:	DATE:						
RECORDS REVIEW:				BADGE NO:	SHOP/CODE:	PHONE:	DATE:						



WebAIM Short Form TASK GROUP INSTRUCTION

08-AUG-2025 0806

20.15.6.0.9333 (July 2025)

(Continued)

ICN: 38BC186502

KeyOp: A01

TGI NO:	COMPONENT NAME: TEMPORARY STAGING SF	TYPE: TST	PHASE: A	REPEAT: 0	CHG/VER: 0/0
SHIP/HULL NO: DDG-113	SHIP/HULL NAME: USS JOHN FINN	PROJECT: BC1	SYSTEM: 86512	PLANT ID:	CASREP CAT:
CU PHASE TITLE: *F/O - INSTALL AND REMOVE SCAFFOLDING TO/FROM VARIOUS LOCATION FOR S/F WORK					

CU PHASE DESCRIPTION (Cont.)

1.3 Identification:

1.3.1 Quantity (2 Lot), Scaffolding Assembly

Location: 1.2.1

Remarks: Preservation work of antenna numbers 5-3A and 5-3B will be accomplished by Ship's Force.

1.3.2 Quantity (2 Lot), Scaffolding Assembly

Location: 1.2.2

Remarks: Preservation work of antenna numbers 5-3C and 5-3D will be accomplished by Ship's Force.

1.3.3 Quantity (One Lot), Scaffolding Assembly

Location: 1.2.3

Remarks: Preservation work of forward side of forward stack, including platforms for antenna numbers 3-10B and 3-31 will be accomplished by Ship's Force.

1.3.4 Quantity (One Lot), Scaffolding Assembly

Location: 1.2.4

Remarks: Preservation work of forward side of aft stack, including platform for antenna number 2-4 will be accomplished by Ship's Force.

1.3.5 Quantity (One Lot), Scaffolding Assembly

Location: 1.2.5

Remarks: Preservation work of entire interior surface of access trunk will be accomplished by Ship's Force.

1.3.6 Quantity (One Lot), Scaffolding Assembly

Location: 1.2.6

Remarks: Preservation work of entire interior surface of escape trunk will be accomplished by Ship's Force.

1.3.7 Quantity (2 Lot), Temporary Containment Enclosure

Location: 1.2.1

Remarks: Preservation work of antenna numbers 5-3A and 5-3B will be accomplished by Ship's Force.

1.3.8 Quantity (2 Lot), Temporary Containment Enclosure

Location: 1.2.2

Remarks: Preservation work of antenna numbers 5-3C and 5-3D will be accomplished by Ship's Force.

1.3.9 Quantity (One Lot), Temporary Containment Enclosure

Location: 1.2.3

Remarks: Preservation work of forward side of forward stack, including platforms for antenna numbers 3-10B and 3-31 will

WebAIM Short Form TASK GROUP INSTRUCTION

08-AUG-2025 0806

20.15.6.0.9333 (July 2025)

(Continued)

ICN: 38BC186502

KeyOp: A01

TGI NO:	COMPONENT NAME: TEMPORARY STAGING SF	TYPE: TST	PHASE: A	REPEAT: 0	CHG/VER: 0/0
SHIP/HULL NO: DDG-113	SHIP/HULL NAME: USS JOHN FINN	PROJECT: BC1	SYSTEM: 86512	PLANT ID:	CASREP CAT:
CU PHASE TITLE: *F/O - INSTALL AND REMOVE SCAFFOLDING TO/FROM VARIOUS LOCATION FOR S/F WORK					

CU PHASE DESCRIPTION (Cont.)

be accomplished by Ship's Force.

1.3.10 Quantity (One Lot), Temporary Containment Enclosure

Location: 1.2.4

Remarks: Preservation work of forward side of aft stack, including platform for antenna number 2-4 will be accomplished by Ship's Force.

1.4 Security Classification: None.

1.5 Initial Condition: None.

1.6 Contractor work start date: 4/20/26

1.7 Contractor work completion date: 6/15/26

2. PROCEDURE:

2.1 Erect/hang scaffolding listed in 1.3.1 through 1.3.6 in accordance with Ref. No. 3 and Ref. No. 4.

2.2 Install each temporary containment enclosure listed in 1.3.7 through 1.3.10 to each scaffolding listed in 1.3.1 through 1.3.4.

2.3 Remove each temporary containment enclosure listed in 1.3.7 through 1.3.10 upon completion of the work from each scaffolding listed in 1.3.1 through 1.3.4 when requested by Ship's Force via Code 333.

2.4 Remove scaffolding listed in 1.3.1 through 1.3.6 upon completion of the work in accordance with Ref. No. 3 and Ref. No. 4 when requested by Ship's Force via Code 333.

2.5 Notes:

2.5.1 Planner: Code 231A D. Tamura, 243-9526

2.5.2 Work Integration Manager (WIM): Code 333 T. Yaginuma, 080-5149-0598

2.5.3 JCN ES01-L025 is related to this TGI.

2.6 Government Furnished Material (GFM): None.

2.7 SRF-JRMC will provide the following service work: (TGI No. 38BC186502S02)

2.7.1 [C740] Crane and crane rigging service.

2.7.2 [C106.1] Safety inspection for SRF-JRMC employees.

2.7.3 [C133] QA inspection for (G) symbol(s).

WebAIM Short Form TASK GROUP INSTRUCTION

08-AUG-2025 0806

20.15.6.0.9333 (July 2025) (Continued) ICN: 38BC186502 KeyOp: A01

TGI NO:	COMPONENT NAME: TEMPORARY STAGING SF	TYPE: TST	PHASE: A	REPEAT: 0	CHG/VER: 0/0
SHIP/HULL NO: DDG-113	SHIP/HULL NAME: USS JOHN FINN	PROJECT: BC1	SYSTEM: 86512	PLANT ID:	CASREP CAT:
CU PHASE TITLE: *F/O - INSTALL AND REMOVE SCAFFOLDING TO/FROM VARIOUS LOCATION FOR S/F WORK					

CU PHASE DESCRIPTION (Cont.)

Ref. No.	Document/Drawing Number	DOCUMENT/DRAWING TITLE	REV	CHG NO.	CPY REQ	PARAGRAPH	SECT	PG	CHPT
----------	-------------------------	------------------------	-----	---------	---------	-----------	------	----	------

WebAIM Short Form TASK GROUP INSTRUCTION

08-AUG-2025 0806

20.15.6.0.9333 (July 2025)

(Continued)

ICN: 38BC186502

KeyOp: A01

TGI NO:	COMPONENT NAME: TEMPORARY STAGING SF	TYPE: TST	PHASE: A	REPEAT: 0	CHG/VER: 0/0
SHIP/HULL NO: DDG-113	SHIP/HULL NAME: USS JOHN FINN	PROJECT: BC1	SYSTEM: 86512	PLANT ID:	CASREP CAT:
CU PHASE TITLE: *F/O - INSTALL AND REMOVE SCAFFOLDING TO/FROM VARIOUS LOCATION FOR S/F WORK					

Ref. No.	Document/Drawing Number	DOCUMENT/DRAWING TITLE	REV	CHG NO.	CPY REQ	PARAGRAPH	SECT	PG	CHPT
1	NSI FY-26	NAVSEA Standard Items	-	1	N				
2	LI FY-26	Local Standard Items	-	ORG	N				
3	TM 29 CFR PART 1915.71	Scaffolding or Staging	-		N				
4	MP PM240-0049, SURF	AEGIS RADAR SPY ANTENNA ARRAY SCAFFOLDING	A		Y			ALL	

TASK NAME / TASK DESCRIPTION	SHOP/ TSD	TS	SF WC	CREW #	MHRS	RWRK
2.1 RGRS	22/KE	PC				
2.2 CARP	22/KE	PC				
2.3 CARP	22/KE	PC				
2.2 RGRS	22/KE	PC				
CFM: for mobile crane cost, shrink wrap tape, spray adhesive, propane gas, firewatch cost, consumable parts, and MISC such as covering material.	22/MQ	CS				
Process Funding Document.	10/CT	OM				

MATERIAL REFERENCES			
REF NO.	DOCUMENT/DRAWING NUMBER	DOCUMENT/DRAWING TITLE	REV

ICN: 38BC186502	KEY OP: A01
-----------------	-------------

MATERIAL LIST												
ITEM NO.	PC NO.	REF NO.	M / C	DESCRIPTION	STOCK NUMBER	GENERIC MATL TYPE	LVL	QA	HAZ MAT	DOC NO.	QTY REQD/ UNIT	QTY USED/ UNIT