

AMENDMENT 0003

RFP NO: N62470-26-R-0011
P1360 Joint Maritime Facility, Newfoundland, Canada

Date Issued: April 09, 2026

The purpose of this amendment is to:

1. The proposal due date is extended to 20 April 2026.
2. Revise solicitation
3. Respond to pre-proposal inquiries (PPIs)
4. Provide Revised Drawings and Specification Attachments
5. Provide Site Visit Log

2. Revise the Solicitation

CURRENT:

13. ADDITIONAL SOLICITATION REQUIREMENTS

- a. Sealed offers in original and 2 copies to perform the work required are due at the place specified in Item 8 by 02:00 PM local time 19 MAR 2026.

REVISED TO:

13. ADDITIONAL SOLICITATION REQUIREMENTS

- a. Sealed offers in original and **1** copy to perform the work required are due at the place specified in Item 8 by 02:00 PM local time **20 APR 2026**.

CURRENT:

ALL SUBMITTALS MUST BE RECEIVED AS SPECIFIED ABOVE PRIOR TO 2:00PM Norfolk, VA local time, THURSDAY, 16 APRIL 2026. LATE SUBMITTALS WILL NOT BE CONSIDERED.

REVISED TO:

ALL SUBMITTALS MUST BE RECEIVED AS SPECIFIED ABOVE PRIOR TO 2:00PM, NORFOLK, VA LOCAL TIME, **MONDAY, 20 APRIL 2026. LATE SUBMITTALS WILL NOT BE CONSIDERED.**

3. Respond to Pre-Proposal Inquiries (PPIs) 1-215

PPI #	Inquiry	Response
1	The solicitation requires pre-proposal inquiries to be submitted no less than 15 business days before the closing date. However, the site visit is scheduled for March 4, leaving no time to submit questions based on information gathered during the visit. Can the Government adjust the Q&A deadline?	Proposals were extended to 20 April 2026.
2	Understanding this is an OCONUS project and it is assumed that the project site is under a lease agreement between US and Canadian governments, please advise if there are any Status of Forces Agreements (SOFA) that need to be flowed down to the Prime and subtrades?	There are no Status of Forces Agreements.
3	Understanding this is an OCONUS project, please advise if there are any Canadian tax requirements that need to be flowed down to the Prime and subtrades?	There are no specific Canadian tax requirements.
4	Please confirm if this project is to be constructed on Canadian soil. IF the answer is YES, please provide any Canadian business license requirements for the Prime and relevant subtrades.	Yes, Refer to FAR Clause 52.236-7 Permits and Responsibilities
5	Please advise if specialty CEQ requirements are to be included in a planned contract modification for this contract?	There are no Specialty CEQ requirements in this contract.
6	Please advise if there is a planned contract modification for AV that will include a CTSD subtrade requirement to develop the final AV package with the NAVFAC CTSD?	There are no AV requirements in this contract.
7	Please advise if there is a planned contract modification for AV that will include BAA and TAA requirements?	There are no AV requirements in this contract.
8	Please advise if there is a planned contract modification for ESS that will include BAA and TAA requirements?	Option Item 2 (CLIN 0003) covers the Electronic Security System (ESS)
9	Understanding that the planned modification for FF&E will need to go through the standard BVD process, please advise on the budgetary value for this CLIN and confirm if HAR is applicable.	Refer to Attachment D - Schedule B Price Proposal Form, Option Item 3.
10	Understanding that the planned modification for AV will need to go through the standard BVD process, please advise on the budgetary value for this CLIN.	There are no AV requirements in this contract.
11	Per Factor 1 (Construction Experience) the solicitation requires the Prime to submit a maximum of five (5) relevant projects of equal or exceeding \$30M USD over the past 10 years. Can the Prime submit two (2) classified projects that exceed the size, scope and complexity and submit three (3) classified projects	The solicitation under Factor 1 provides the definition of a relevant project, which includes "A new administrative, industrial, or commercial facility that is a minimum of 1,000-Square Meters (10,764-Square Feet) or greater and has a

	that exceed complexity but are below the \$30M threshold?	construction value equal to or exceeding \$30,000,000 USD at the time of project completion. RENOVATION, REPAIR, OR ALTERATION of existing facilities shall not be submitted and will NOT be considered relevant. Submitted projects that include expansion of an existing facility footprint must clearly demonstrate a \$30,000,000 USD construction value of the expansion and an area of at least 1,000-Square Meters (10,764- Square Feet). Failure to provide the value in US dollars will result in the project being deemed irrelevant and ineligible for consideration.” “
12	Understanding the location of the project, did the government take into consideration weather delays in the region where the work is being performed?	Yes, the contract completion time included consideration of the region where the work will be performed.
13	Would it be acceptable to utilize a Stego Wrap system for the Vapor Barrier & Radon Mitigation plan in place of the underground PVC piping and above ceiling-mounted exhaust fans as the Radon mitigation plan? If Stego Industries’ product is approved as an alternative, it would provide overall cost savings and eliminate the ongoing maintenance and long-term reliability concerns associated with the exhaust fan system to mitigate the Radon. This product is used largely in North America with confirmation of availability in Canada.	Propose in accordance with the solicitation per design.
14	Will this project be exempt from Harmonized Sales Tax (HST)?	There are not any specific tax exemptions associated with this project.
15	Given the project’s location and the extended periods of sub-zero temperatures, heavy snowfall, high winds, and freezing rain during winter (typically December through March), would it be acceptable to fully encapsulate the building with a temporary weatherproof enclosure (such as a fabric structure, scaffolding with reinforced tarps, or modular system) combined with climate control measures like heating, ventilation, and dehumidification? The goal would be to create a controlled environment that allows construction work to continue safely and productively through the winter months	This is considered to be means and methods per the Request for Proposal.
16	What are the seismic requirements for HVAC on this project? It mentions in the spec to see section 23 05 48.19, which is not included in the spec. Also, there	Buildings are in seismic design category B which is low seismic, however the contractor is responsible

	are drawings M-503 & M-504 that show the seismic bracing for Mechanical equipment but are not specific to anything with HVAC. Please advise as to what requirements should be followed for HVAC, if any.	for ensuring all seismic bracing for HVAC is required per applicable code.
17	On drawing M-101 it shows Motorized Dampers for louvers L-3 & L-1 but not for louvers L-4 & L-2, will these louvers also require motorized dampers?	Per Drawing M-704 EF-3 EF-4 Room Control Diagram L-4 will be provided with a motorized damper. L-2 requires a motorized damper and interlocks with L-1 and generators.
18	Can ASP Icon HD 3000 be considered as an approved alternative to the specified raised access floor?	Drawing IN601 Note 1 states "the use of manufacturer's names and product numbers is not intended to be proprietary. Other manufacturer's products will be considered, provided they closely approximate color, finish, texture, pattern and quality."
19	Spec 09 69 13-page 6 line item 2.1.1.a calls for a Concentrated load of 11120 N or 2500lb. However, Drawing IN601 Finish Legend is using CONCORE 3000, which is a 3000lb concentrated load. There is a 500lb difference. Please clarify which is to be used.	3000lb concentrated load.
20	Is the contractor to provide the government with an on-site office trailer?	Yes, provide an on-site office trailer per Specification 01 50 00.
21	For the Cybersecurity Assessment Plans that are managed by the Contractors (KTR) Information System Security Engineer (ISSE) detailed in 25 08 11.00 20, to include SAP, STIG, eMASS, POAM, ISSE Check List, ISSM, ISSO, etc. Please provide the specific DDC systems (JCI, Siemens, etc.) that are required for this project, program, organization, or enclave.	DDC vendor is not specified. DDC system requires cyber security per drawings and specifications but outside connection is currently unknown.
22	Paragraph 1.5 "Security Classification" references OCA, SCG requirements, paragraph 1.5.1 references CUI marking requirements and paragraph 1.6.2; Table 1 "Project Documentation Types" references Site Security Manger (SSM) requirements for As-builts, BIM, shop drawings, OMSI and eOMSI. Please provide a Construction Security Plan (CSP) that defines the SSM duties, certifications and responsibilities for this project.	Project does not warrant a requirement for a Site Security Manager nor a Construction Security Plan (CSP).
23	Paragraph 1.6.2; Table 1 "Project Documentation Types" references Site Security Manger (SSM) requirements for As-builts, BIM, shop drawings, OMSI and eOMSI. Understanding that the SSM is assigned to manage a Site Security Area (SSA), please provide a Construction Security Plan (CSP) that defines the SSA requirements and the SSM duties, certifications and responsibilities for this project.	Project does not warrant a requirement for a Site Security Manager, Construction Security Plan (CSP), nor Secure Storage Area (SSA).
24	Paragraph 1.6.2; Table 1 "Project Documentation Types" references Site Security Manger (SSM)	See revised Specification 01 31 23.13 20.

	requirements for BIM, etc. In FF&E Spec 12 00 00 1; paragraph 3.1.1.1, BIM is referenced. Please provide a BIM specification and clarify BIM requirements and application.	
25	Based on the assumption that the project site is under existing SOFA and lease agreements between US and Canadian governments, please clarify is there is an US Accrediting Official (AO) that will provide final accreditation for P1360.	There are no Status of Forces Agreements.
26	We would like to request a two-week extension to the closing date to allow us time to complete the SAM.GOV registration process.	Proposals were extended to 20 April 2026.
27	Drawing B-101 - SUBSURFACE EXPLORATION LOCATION PLAN shows 5 Boreholes MB-1 to MB-5. The Record on B-601 to B-607 shows Additional boreholes at MB-1A, MB-2A, MB-3A. These appear to be at different locations based on the Latitude /Longitude Coordinates but are not shown on the drawing.	Letter designations are offsets of the original borings and were drilled in the relative vicinity of the original boring. Relative locations of borings are shown on the drawings, not exact locations, as such offsets are not shown.
28	Drawing B-601 provides info on Borehole MB-1 but it is not described therefore is not useable.	MB-1A is an offset boring that was drilled after no recovery from boring MB-1. MB-1A provides adequate data.
29	Drawing B-201 shows limit of Earth Removal to get to suitable soil under the foundations. There is no other Geotechnical Recommendations for the remaining Slab on Grade or Exterior Items such as Asphalt. Are there any requirements to take any other areas down to the appropriate level and remove any Marsh Deposit if encountered?	Marsh Deposit was encountered in limited borings. If the Marsh Deposit is encountered during construction in areas outside of the undercut plan, an Request for Information should be filed.
30	Civil Drawings refer to a Demolition Package prepared by Alliance for Demolition; can the demolition package be provided please?	Please refer to revised drawings for demolition package.
31	Drawing CS101. Item 12 on the Construction Keynotes says to replace the Barbed Wire at top of Fence only refers to the 2 sections on the West Side of the Plan and wants to confirm that the note is not meant to be the complete perimeter of both the exterior and interior lines of fencing	Replace the barbed wire with the complete perimeter of both the exterior and interior lines of fencing.
32	Division 9 references Section 09 67 23.15 Fuel Resistive Resinous Flooring; there are no finishes for this product shown on the finish schedule, please confirm if this is required and if so where is it located?	Not required.
33	Demolition drawings are listed but were not provided as part of the drawing set (items 3 to 33), can these please be provided?	Please refer to revised drawings for demolition package.
34	Please provide the number of kilometers away from site, where salvaged material will be stored.	Salvaged items will be stored within the construction site, location determined by the construction manager.

35	What is the U.S. Standard type form? Are these government bond forms, including SF 24 (Bid Bond), SF 25 (Performance Bond), and SF 25A (Payment Bond), which are available for PDF download via the GSA Forms Library? If not, please advise what forms are acceptable.	Standard Forms are approved forms by the Administrator of General Services. Please refer to www.gsa.gov for complete forms library.
36	The RFP document indicates that if the offeror is registering a new entity in SAM the offeror must follow new procedures which include providing an original, signed notarized letter indicating authorized entity Administrator for the entity before a new SAM gov entity registration will be activated. Please clarify what this letter entails and how it is to be submitted.	Please consult the SAM.GOV helpdesk directly to ensure that all requirements for timely registration are met.
37	Drawing VF101 General Notes item 8 and CU101 Construction Keynotes item 32 refers to EXWC Shoreline Improvement Plans prepared by ROICC-Maine. Will these plans be issued? Will they be issued as "Background Information" only or as drawings to be added to the Index of Drawings?	The EXWC Shoreline Improvement design plans by ROICC-Maine are not finalized to date and will not be added to the Index of Drawings for this project. The EXWC project is anticipated to be constructed before P1360. The locations for the 100 drainpipe and Vault are shown for information and are approximate. Contractor to field verify exact locations.
38	Drawing VF101 on the north side has 5 UGCX's originating from the ocean and terminating into their individual communication manholes before they the discharge and enter the large "VA" (Vault). ES101 Sheet Keynotes labels this "VA" as "Existing Underground Manhole". ES102 Sheet Keynote #26 indicates we must "break into this manhole" with 5 horizontal rows of 100mm conduit with each row containing 3 for a total of 15 - 100mm conduits. If the EXWC Shoreline Improvement Plans do not have specific information on this existing Vault / Manhole can as-built drawings be issued for understanding what this "break into this manhole" means for a work scope. For example, VF101 does not show a connection from this existing Vault / Manhole to the existing building so is this south face of the existing "VA" should be available for coring holes in a configuration matching the UCIC new Manhole that is shown on ES501 detail A3 in the folded down wall profile on both the right and on the bottom of this core holes layout detail.	As-built drawings are unavailable. Break into manhole means to connect new 15-way duct bank into existing manhole as shown on site plan.
39	Drawing G-007 Code Compliance Summary contains USA code references. The proceeding design drawings have references to the National Building Code (NBC) 2020, Canadian Standards Association (CSA), Canadian Electrical Code (CEC), etc. We also	The project must use the Code with the more stringent requirements for each project item. If U.S. Code has more stringent requirements, then use U.S. Code for an item. If Canadian code is

	have ULC MEP fixtures in Canada. a) Are the construction services being requested to meet Canadian Codes and Standards or USA Codes and Standards? b) Are references to USA Codes and standards to be ignored. For example, S-001 references DOD Codes and Criteria and the same drawing references Canadian Codes and Criteria. c) Can a narrative be provided should a mix of Canadian and USA Codes and Standards be required? Local trade contractors in Newfoundland will not be familiar with USA Codes and Standards which oppose our goal of achieving SCQC.	more stringent, then use Canadian Code for the item.
40	Drawing G-008 Sheet Keynotes item 9 indicates the location of the Fire Department Connection. Drawing P-401 shows a P-7 Wall Hydrant at this approximate location. FX 101 shows the 2-inlet fire department connection and the 3-outlet fire pump test header location. M-401 shows the HVAC connection to the wall louver. A-206 shows the louver elevation with the bottom being at or near the header of the double entrance door. A-306 sections show a corrugated finish on the exterior face of the precast. S-001 Precast Concrete Walls note 1 requests the concrete members and connections be designed in accordance with CSA-A23.1 and CSA-A23.4. Are these wall hydrants and 2 inlet / 3 outlet fire department connections round pipe sleeves through the structural precast wall for wall mounted fixture attachment or are these fixtures expected to be recessed flush with the outer corrugated texture surface into the precast requiring larger block outs in the precast concrete?	No, they are not expected to be recessed flush.
41	Drawing G-101 shows a smoke partition labeled using the legend of “-S-“ between room 110 and rooms 108 & 107. A-105 labels this wall as a “S150-2” which is a 2 hour rated wall. Please clarify which is correct.	Refer to revised Drawing G-101.
42	Drawing G-101 shows a 2-hour partition using the legend of “-uu-“ between room 110 and 109. A-105 labels this wall as a “S150-1” which is a 1 hour rated wall. Please clarify which is correct.	Refer to revised Drawing G-101
43	Drawing G-101 shows a smoke partition using the legend of “-S-“ around room 112, except at the adjoining wall of room 113. A-105 labels these wall without a “S” smoke rating. Please clarify which is correct.	Refer to revised Drawing G-101
44	Drawing G-101 shows a smoke partition around door 109B (door number shown on A-105). A-105 labels these wall without a “S” smoke rating. Please clarify which is correct.	Refer to revised Drawing G-101

45	Drawing G-101 shows the location of ten fire extinguisher hooks. There are four clean agent and six dry chemical fire extinguishers being requested. The drawings for Fire Protection, Architectural, and Mechanical drawings do not show these fire extinguishers. Please confirm the mounting locations have been coordinated with the other design disciplines scope.	Refer to revised Drawing G-007 for fire extinguisher quantity. There are 10 ABC type extinguishers and 2 -Clean agent type extinguishers. Please refer to revised Drawing G-101 for location: there are two types of fire extinguisher, RFEC and FEH.
46	Drawing B-101 shows the location of the five MB bore hole locations. B-607 indicates the presence of some hydrocarbon impacted soils and high levels of chloride and sulfate content in the soil and water samples. The excavations of the much lower SOG elevation for the OPS Equipment room, three large communication manholes with 15 100mm conduits c/w associated concrete ductbanks, 10,000 litre holding tank, etc. which will result in a surplus of soil having to be removed from site. Does DOD own land outside the limits of construction where this soil can be spread out and retained on the DOD lands or is the soil to be remediated off site?	All soils must be disposed of off site in accordance with specification 31 00 00 Earthwork and 01 57 19 Temporary Environmental Controls
47	Drawing B-201 shows the extent of the excavation Undercut Detail. The New building's upper SOG elevation (FFE) is 4.500 per CE102. The Undercut Details wants the underside of the undercut to be at 0.73m or 3.77m below the 4.5 m elevation. The higher WF900 wall footings have an underside of footing of 1m to top of footing plus 300mm footing depth equals 1.3 m below the exterior grade. The depth D (underside of footing to the 0.73m elevation) is roughly 2.5 meters for the WF900's so D/2 is roughly 1.25 m. This means the bottom width of the undercut trench for these WF900 strip footings is roughly 3.4 m wide before sloping up. The precast walls are designed to sit on a consistent footing elevation. Structural drawings do not advise on fills or fill types, but they do provide 10 MPa lean concrete below footings on S-501 detail A1. Can we get a specification for the fill below these footings at the undercut locations (i.e. – structural fill or lean concrete).	Backfill material and compaction requirements are provided in Specification 31 00 00 Earthwork.
48	Drawing B-601 provides a borehole MB-1 profile labelled MB-1A that encounters a reinforced concrete slab at a depth of 10 feet below grade. Is there a record of what this might be for size and location?	Boring identifies concrete and rebar and makes no inference as to what the debris could be from. It is understood to be concrete debris located within the FILL. We have no documentation of anything in this location.
49	Drawing C-002 Utility Note #1 requires a dig permit before excavation. Note # 2 wants the underground utilities to be positively identified by third party,	a) A dig permit is not required. The Contract Officer will not be issuing a dig permit. Locates for active utility

	independent, private utility companies. Note # 4 requests a scan of the site with electromagnetic and sonic equipment. C-501 Phase 1 note # 1 wants a pre-construction meeting prior to any land disturbance. The C-501 detail C1 construction entrance must be installed prior to the remaining erosion and sediment controls being installed. The Contracting Officer will inspect and approve the erosion and sediment control prior to starting the clearing and grubbing: a) Is the Contract Officer the AHJ that is issuing the dig permit? b) Can the demolition work start without a dig permit? c) Can the demolition start with only the C-501 detail C1 construction entrance being installed? d) Is there a location outside the site perimeter where demolition debris can be staged for removal or excavated topsoil can be piled for reuse such as the entrance parking lot?	and electrical service lines must be completed by the contractor prior to commencing digging operations. b) A dig permit is not required. Locates for active utility and electrical service lines must be completed by the contractor prior to commencing digging operations. c) Land disturbance and demolition work is not permitted to start until Phase 1 erosion and sediment control measures are installed and in place. d) The adjacent parking lot can be used for staging and stockpile locations. There is an old quarry site located adjacent to the property that may be available and could also be used for temporary storage. Coordinate exact locations that are available with the contracting officer prior to commencing work.
50	Drawing C-002 Note #6 and # 14 want the existing elevations of all connections to existing utilities to be field verified prior to ordering materials or prior to constructing upstream portions of the new utilities. Can these investigation pits be dug prior to the sediment and erosion controls and the dig permit being in place?	Yes, temporary investigation test pits are acceptable to field verify existing utilities before the sediment and erosion control measures are installed.
51	Drawing C-002 Note #5 wants any damage to the utilities to be immediately repaired at the contractor's expense. VF101 indicates many existing utilities. CU101 indicates far less of these existing utilities remaining. CU101 still includes utilities that are being abandoned. If an abandoned utility on CU101 is damaged, does it need to be repaired? For example, the three communication lines originating from the ocean and connecting to the west side of the existing building on VF101 are shown on CU101 not extending to the new building (i.e. – abandoned). When installing the perimeter fence power and communications u/g conduits, and one of these 3 abandoned communication lines is damaged, is the contractor required to immediately repair it?	Abandoned utility does not need to be repaired. Refer to Drawing CD101 for the extent of site demolition and refer to Drawing ES101 for partial electrical site demolition.
52	Drawing VF101 indicates electrical manholes around the perimeter fence. The manholes do not show any electrical u/g connection between them. ES101 indicates existing 6m tall wood poles around the perimeter fence that do not show up on VF101	The location of the u/g lines between the electrical manholes was not picked up on the survey and there are no as-built record drawings available that show the u/g lines. Contractor to field

	drawings. ES101 does not show electrical manholes around the perimeter of the fence. a) are there electrical manholes? b) Is there an u/g electrical and communications feed around the perimeter fence?	verify location of existing the u/g lines. a) Yes, there are existing electrical manholes. Drawing VF101 indicates the location of existing electrical manholes in front of several existing light poles around the perimeter fence. These existing light poles on Drawing VF101 are the existing 6m tall wood poles shown indicated to be removed on Drawing ES101. Contractor to remove existing electrical manholes, the existing u/g lines between the manholes, and the existing light poles around the perimeter fence. b) Yes, contractor to provide new light poles and new u/g electrical and communication lines around the perimeter fence as shown on Drawings CU101 and ES102.
53	Drawing CS101 Note 12 is to replace the barbed wire at the top of the existing fence. C-510 & C-511, Chain Link Fence Notes describe a new fence installation. Is the scope for the existing fence only a barbed wire top replacement while these notes can be used for the new fence man gates and fence sliding gates?	Yes, replace the barbed wire on the existing fence for both the interior and exterior perimeter lines of fencing. The notes on Drawings C-510 and C-511 pertain to the new pedestrian security swing gates and new sliding security gates.
54	Drawing CS101 Note 10 indicates to see the Structural drawings for the mechanical yard concrete for the chiller. S-101 shows the footings for the chiller screen walls but provided no information on the mechanical yard concrete. S-301 detail B4 indicates "mechanical yard, see Civil". On S-501 there is a detail B4 called Exterior Equipment Pad. Can this exterior equipment pad detail be used for the mechanical yard concrete work scope?	Yes, per joint legend on Drawing CS401, use detail B4 on Drawing S-501 for the mechanical yard concrete pad.
55	Drawing CS101 Construction Keynotes number 15 indicates to see the Landscape Plans for the Mechanical Yard Enclosure (precast screen wall). LS501 detail C2 shows the screen wall with note 10 at the footing / wall connection indicating "connection by manufacture". Should the S-001 Precast Concrete Wall notes apply to the design of this landscape screen wall or will landscaping provide the screen wall reinforcing?	Drawing S-001 Precast Concrete Wall notes should apply to the design of the landscape screen wall.
56	Drawing CS101 Construction Keynotes item 11 and LS101 identifies a "Security Clear Zone". What does this mean for the purpose of constructing the facility?	The security clear zone is an established area around the perimeter that provides unobstructed views. For the purpose of constructing the facility,

		the security clear zone is inconsequential.
57	Drawing CS401 has designing the R (Reinforced) slabs at the recessed doors 100A, 102, 111B, 112A, 113A, 114A and 114B (all recessed locations). The detail has an expansion joint where these exterior civil slabs contact the building perimeter. S-101 is designing these same slabs but they are structural in nature and have no expansion joints. These exterior slab locations are labeled with note #1 on S-101 which indicates 150mm SOG reinforced. S-301 detail A1 shows the break line with Civil for the design limits. S-502 detail A3 indicates reinforcing steel between the interior SOG and exterior SOG with this steel passing below the door opening locations. a) Which design prevails? b) There is a thermal bridge occurring on the structural drawing that may not be avoidable unless a structural thermo-break material is installed below the door sill. Will a structural thermo-break design be provided? c) If structural prevails will the CS401 EJ (Expansion Joint) be moved to the face of the exterior structural SOG?	a) Structural design prevails. b) For typical doors including recessed slab follow detail C2 on Drawing S-301 and with insulation provided per detail C1 on Drawing A-607. Reinforcement on detail A3 on Drawing S-502 does not cross the doorway as indicated by the door sections and joint locations shown on the plan. c) Yes, refer to Drawing CS401 for revised EJ locations at the face of the exterior structural SOG at recessed doors 100A, 109A, 112A, 113A, 114A and 114B. Delete EJ at 111B.
58	Drawing CS401 Joint Legend has an "R" Reinforced Slab referencing A4 on C-504. A4 on C-504 is an exterior slab with welded wire fabric for reinforcing. The depth of the slab is (T) Pavement Thickness. Drawing C-504 detail A1 Thickened Edge (TE) does include a slab thickness of 200 mm. No other slab thickness was found. Is there a location where a table of (T) thickness are provided or do we use 200 mm for all the "R" labeled locations?	Refer to Drawing C-504 for table added to detail A4.
59	Drawing CS401 shows an equipment pad for the drawing ES102 generator load bank and quick disconnect enclosure for a portable generator. CS 401 note 3 indicates to "reinforce slabs with electrical and communication structure". Civil does not provide a detailed reference for this note 3. Drawing S-501 has detail B4 Exterior Equipment Pad. Should the structural detail be used or will civil provide a reference detail assuming this electrical equipment is being referred to as electrical structure?	Use detail B4 on Drawing S-501 for the generator and load bank pad.
60	Drawing CS401 detail B2 shows a pad labeled TR. ES102 indicates this is a note 2 Transformer. ES501 provides a Pad-Mounted Transformer Detail showing electrical elements within the pad: a) Please provide a transformer reinforced concrete	a) Use detail B4 on Drawing S-501 for the transformer pad. b) Bollards and/or fencing are not needed.

	pad design. b) Are bollards and/or fenced needed to protect this transformer from moving vehicles or from being tampered with? c) Who is supplying the transformer on drawing ES102 Sheet Keynotes item 2? (This could be supplied by NL Power, DOD, or the Contractor)	c) It is part of the contract, so the contractor is responsible for providing, in conjunction with NL Power.
61	Drawings CS101, CS401, and TN401 detail A1. The large communication manhole (+/-4m x 3m x 2m deep) is located strategically on TN401 to allow the TN401 detail C1 commercial telcon services duct bank to enter room 110 while the 15 100mm conduits from manhole UC1A enter partially under the loading dock double doors to terminate into the five NEMA 4X cable enclosures mounted o the room 116's wall. In this design the Electrical appears to be a priority for the manhole location due to the cable sizes being pulled into the building and coordination with other duct bank. CS101 shows the manhole in a different location that would conflict with the commercial telcon service duct bank and not align with the room 116 five NEMA enclosures. a) Does the electrical location prevail over civil? b) Does UC1A need to be engineered for vehicle traffic loading, or will the loading dock doors be moved further to the west? c) Will civil reflect the electrical manhole location on CS401 with perhaps a modified loading dock entry exterior slab design?	a) Yes. b) There is no vehicular traffic above the manhole. c) No.
62	Drawing CS401 shows the mechanical yard concrete paving and precast screen wall for the chillers. LS101 shows the precast screen wall design and requests an expansion joint between the wall and the mechanical yard slab. CS401 does not show this expansion joint. Will an EJ expansion joint be added to the civil drawing or will the expansion joint note be deleted from the landscape drawing?	Refer to revised Drawing CS401 which indicates an EJ expansion joint between the precast screen wall and mechanical yard slab to align with Drawing LS101.
63	Drawing CG101 shows the topography elevation around the chiller screen wall that is shown on CS401. The slope moves from the open side of the screen wall to the middle of the screen wall at the back side. LS501 Work Keynotes note number 2 describes a 100mm x 200mm opening in the precast screen wall at this low point for drainage. M-102 shows the chillers sitting on a 150 thick concrete pad that blocks this drainage pathway. Please clarify how this drainage works at the chiller screen wall.	Chillers will sit on housekeeping pads on top of the mechanical yard concrete pad (B4 on S-501). Refer to revised Drawing LS501 which adds another 100mm x 200mm opening in the precast screen wall. The screen wall now has two openings/low points on the mechanical yard slab for runoff to pass through the wall. Runoff sheet flows from the building between the housekeeping equipment pads and toward the back side of screen wall.

		Runoff ultimately flows to the two low points on the back side of the screen wall.
64	Drawing CS401 indicates the many Control Joints (CJ). Drawing C-503 detail 4 indicates these are a double saw cut control joint with a 6.35 mm (+/- 1.6 mm) recessed silicone sealant being installed. The normal CJ in St. John's (SJ) is a single saw cut with no sealant. Is the double saw cut CJ with rebated silicone a mandatory requirement or can a normal SJ control joint be installed?	The customary control joint (single saw cut with no sealant) used in SJ is acceptable.
65	Drawing CU101 does not show the electrical power feed from the west face of the building to the perimeter fence lighting as shown on ES102. a) Is this electrical feed a buried conduit or is concrete encasement needed? b) ES102 appears to show power entering into the VSS communication fiberglass hand hole before exiting the hand hole and heading towards the building. Is this correct? c) The power connection to the light appears to be using the light pole as a junction box for feeding power north and south from this pole. Is this correct?	a) The drawings do not note that concrete encasement is needed. b) As depicted on the site plan, the VSS conduit is not connected to the electrical handhole in question. c) The contractor is at liberty to use whatever approved method is warranted to route the circuit.
66	Drawing CU101 does not show u/g power for the three chillers. ES102 does not show u/g power feed to the chillers. Please clarify? (Overhead?)	The civil utility drawings may not show every single circuit for electrical. The circuits required are shown on the electrical plan and are underground, not overhead.
67	Drawing CU101 shows a short u/g power line for the wastewater holding tank. ES102 shows alarm power and a fiberglass hand hole pull box. C-509 shows a holding tank with float alarms for notification to when to empty the tank. a) Are both communication and power conduits needed from the building to the tank so the time to empty alarm can be monitored by the facility staff in the building? b) Are these conduit(s) concrete encased or direct bury?	a) No. The alarm will be local at the tank site, not in the building. b) There is no indication on the drawings for this conduit to be concrete encased.
68	Drawing CU101 shows existing UGC entering from outside the south fence and traveling north. VF101 shows the feed for these conduits originating from a manhole # 21 that is not being retained. Are these abandoned conduits?	No, the contractor is to remove existing feed and conduits per CD101.
69	Drawing CU101 shows that the existing OHE feed from the primary power pole to the guard shack is	Drawing ES101 is correct.

	being retained. ES101 shows the existing guard shack OH electrical and communication service being removed including the power pole being removed near the shack. Please clarify which is correct.	
70	Drawing CU101 shows an existing UGE line near the east interior fence line being retained. VF101 shows this UGE line be fed from manhole # 22 which is not being retained. Are these abandoned conduits?	No, the contractor is to remove existing feed and conduits per Drawing CD101.
71	Drawing CU101 shows an existing UGE line running parallel to the eastern fence and passing by the guard shack. VF101 shows this UGE line being fed from manhole # 22 to a structure / chamber which is not being retained. Are these abandoned conduits?	No, the contractor is to remove existing feed and conduits per Drawing CD101.
72	Drawing CU101 shows an existing UGC line running though the north fencing. VF101 shows this UGC line being fed from the existing building which is not being retained. Are these abandoned conduits?	No, the contractor is to remove existing feed and conduits per Drawing CD101.
73	Drawing CU101 shows an existing UGC and HWS line running though the east fencing. VF101 shows this UGC and HWS line being fed from the existing building which is not being retained. Are these abandoned conduits?	No, the contractor is to remove existing feed and conduits per Drawing CD101.
74	Drawing CU101 shows an existing 2" watermain running under the north fencing. CU202 detail A2 tags this water line as "ABND Wx". To avoid working around this 2" water line can the service be capped at the 200 mm water main with this 2" watermain then being abandoned?	Contractor to field verify location and remove 2" abandoned water line per CD101.
75	Drawing VF101 shows sliding gates with a box mounted to each of the gates. ES101 identifies these two boxes with note #5 that indicates to remove the gate controller connections for power and control back to the guard shack. Underground conduits are not shown from these boxes to the guard shack on either of these drawings. ES102 note # 7 has a weatherproof exterior pull box mounted on the guard shack wall to facilitate routing of panel board feeders and gate controller circuits into the gate house. a) Are there buried u/g conduits between the gate house and the sliding gates that are being abandoned? b) Why do the gates have gate controller connections if no new gate controller connections are being made to the new gates?	a) The location of the u/g lines between the gate controller and guard shack were not picked up on the survey and there are no as-built record drawings available that show the u/g lines. Contractor to field verify location of existing the u/g lines and remove. b) The old gates had gate controller connections. The new sliding gates do not have gate controller connections.
76	Drawing CU101 shows at keynote #9, the 10,000-litre waste holding tank and provides an elevation for the riser cover of 4.15m and the top of the tank at 3.10m with a pipe invert at 3.00m. Plumbing drawings indicate that this invert is much lower in elevation. P-102 shows the facility plumbing lines with the four	a) Refer to revised Drawing CU101. FFE is 4.5m, so 100mm sewer pipe invert is 3.49 out the building (FFE 4.5 - 1.01=3.49). 100mm pipe ties to SMH-1 at 3.13, then flows to holding tank. Surface ground elevation at

	OPS Equipment cooling units requiring drains for the condensate lines in the slab located at FFE 3.3m (4.5m main level less the 1.2m deep raised floor depression). This lower slab is 200 mm thick with the discharge drainage pipe requiring a depth below this u/s of slab. The furthest floor drain must have a pipe that slopes to the building discharge inverted location. The Sheet Keynote 1 indicates the DN100 sewer pipe invert is 1010mm below the finished floor elevation. The finish floor being referenced is the lower raised access floor, so the exterior building inverts are 3.3m less 1.010m or 2.290m. Assuming the civil inverts were assuming a 4.5m FFE verses a 3.3m FFE then the holding tank inverts are likely 1.2m too high on civil. The holding tank top of tank would possibly be 1.90m with pipe inverted at 1.80m. Note: CU101 note 19 has an invert at the building of 3.35m which is above the raised access floor SOG elevation. a) Please confirm the top and pipe invert elevations. b) At a depth of approximately 1.90m to the top of the tank, along with the water elevations noted in the geotechnical bore holes, this tank could float when emptied. If this is a design concern a design solution be provided.	holding tank is approximately 4.15. The holding tank is a delegated design which must follow the latest edition of Standard CA/CSA-B66-21 for design, material and manufacturing requirements. The contractor must have the design completed by a certified and approved designer registered with the Government Service Centre. b) The holding tank is a delegated design. Contractors will provide permanent, integral protection from frost uplifting and buoyancy due to ground or surface waters. Refer to Drawing C-509.
77	Drawing VF 101 and CU101 do not specifically reference the ES101 Electrical Demolition Site Plan or the ES102 Electrical Site Plan which would be beneficial for coordinating the entire scope of removals and new work. Can these specific drawing references be added to the civil drawings? (Note: The electrical demolition drawings is for the removal of the transformer, electrical & communication power pole modifications, existing 6m tall wood poles, and for the sliding gate connection removals)	Refer to Drawing CU101. Revised General Note #7.
78	Drawing C-503 detail A2 indicates the depth of the aggregate base below the sidewalks. Drawing C-504 detail A2 indicates the depth of the aggregate below the asphalt paving. Structural drawings do not provide aggregate depths for items like S-501 detail B4 Exterior Equipment Pad or for SOG Radon piping system. A-302 Note 31 indicates structural and plumbing drawings will be addressing passive below slab Radon mitigation systems. P-103 shows below slab radon pipe collection system that is connected to a riser pipe. There are no structural chambers that we normally would see in WSP Golders radon design for this region of NL. The below slab structural chambers are used to equalize the suction in the radon collection piping. A Radon gravel depth and type of gravels are not provided. a) What is the depth of gravel below the exterior equipment	a) Provide per slab-on-grade note 2 on Drawing S-001. b) Provide per slab-on-grade note 2 on Drawing S-001. c) No d) Provide per slab-on-grade note 2 on Drawing S-001. e) Updated to ASTM C33 no 57 stone.

	pads? b) What is the depth of gravel below the transformer pad? c) Are under slab structural chambers, for equalizing suction pressure between collection piping, required? d) What is the depth of the Radon gravel below the SOG. e) Please provide a specification for Radon gravel.	
79	Drawing C-506 includes a number of removable covers. C-509 has a holding tank with a “cover with lock to prevent unauthorized access”. P-602 detail C4 has a lockable hinged cover on the generator automatic fill port control panel. a) Are the grates for the catch basins to be tack welded to the frames or are these to be left removable? b) Are the circular closed or open covers for maintenance to be lockable covers or are these to be left removable at all times?	The holding tank cover and generator automatic fill port control panel are to be lockable covers for security purposes. These should be integral to the equipment itself. a) The grates for the storm sewer catch basins that are located within the inner perimeter fence are to be left accessible for maintenance purposes. In addition, there are two outfall pipes which discharge towards the Bay. One is on the north side, and one is on the south side. These pipes extend beyond the outer perimeter security fence and will need to be protected by securely fastened grills or equivalent means to prevent entry or provide forced entry penetration resistance equal that of the fence. Refer to revised sheets CU101 and C-509. b) Per Drawing CG101 Construction Keynote #5, use Type A Closed Cover. Leave accessible or removable for maintenance purposes.
80	Drawing C-509 Note 1 indicates this contractor is responsible for the delegated design of the holding tank. Note 2 indicates no work should occur until a “Certificate of Approval” has been issued. Who is issuing this certificate as the AHJ?	The Certificate of Approval for the holding tank design will be issued by Newfoundland Labrador Government Services. The contractor must have the design completed by a certified and approved designer registered with the Government Service Centre.
81	Drawing C-509 Note 3 is wanting leak testing which will require 10,000 litres from a water delivery truck unless DOD can advise where water might be available on their property. Is there water available for this leak testing?	Water is available to the site. The existing fire hydrant on the north side of site is currently served by an existing 8" water main. There was a second fire hydrant on the south side of the site but it was removed in January 2025 due to an emergency repair. It was also served by an existing 8" water main. This project will extend the fire line to the loop

		road and a new fire hydrant will be installed.
82	Drawing C-510 detail # C4 has a ¾" - 10-foot-long grounding rod being connected to a 50mm (2 inch) copper cable. Detail # B4 labels the cable as being "#8 AWG Solid Copper Wire". The cable is then connected to the fence with an exothermic weld. a) Please advise if the #8 AWG Solid Copper Wire is the correct cable size. b) Is there only one fence post being grounded?	a) No, the correct cable size is #4 AWG solid copper wire. See revised Drawing C-510. b) No
83	Drawing LS101 at the chiller screen wall calls for Note # 15 which is hydroseeded grass mix. LS501 at the chiller screen wall calls for Note # 11 which is Turf. Which is correct?	The "turf" is a hydro-seeded grass mix, see specification 32 92 19 Seeding. Notes revised for clarification.
84	Drawing LS101 does not show the P-104 automatic fill port. The fill port is shown on detail C4 on drawing P-602 and consists of a lockable control panel and an equipment stand mounted on a 150mm equipment pad. a) Can Landscape locate this assembly on the Precast screen wall. b) Can an equipment pad size be provided with this pad shown on the landscape and civil drawings. c) Can detail B4 on S-501 be used for the exterior equipment pad (200mm not 150mm thick reinforced pad) or will another design detail be provided? d) Will the Pad be sized for the fuel pump operator to comfortably pump the fuel with a fuel hose from the truck likely perpendicular to the filling port?	a) The assembly will be located near the wall, parallel to the road, but not attached to the wall. b) Yes, the equipment pad will be shown on the landscape and Drawing CS101. c) Yes, please use detail B4 on Drawing S-501. d) The pad will be sized appropriately. See Drawing CS101.
85	Drawing LS501 detail C2 has a note 7 indicating structural will provide the aggregate base design. S-101 shows the screen wall footing with section B4/S-301 provided. S-101 does not show an exterior mechanical equipment slab / pad design. S-301 detail B4 has an exterior equipment pad but does not have an aggregate design. Can an aggregate design be provided?	Provide porous fill per slab-on-grade note 2 on Drawing S-001.
86	Drawing S-001 General Note #10 has the Ground Floor Elevation at 4.375m. This is the existing building ground floor elevation. CE102, CG101, etc. have the new building elevation at 4.500m. Please confirm 4.500m is correct.	Drawings CE102 and CG101 are correct. The FFE is 4.5m.
87	Drawing S-001 Foundations Note #4 wants all foundations to be inspected by the Contractor's Special Inspector prior to concrete placement. Foundations are designed for bearing pressures of 143kPa and must be founded on approved subgrade or	See Specification 01 45 35 1.5.7 for special inspector requirements, license in NL is acceptable. Soil must be tested and confirmed prior to concrete placement.

	structural fill. Is this Contractor Specialty Inspector a licensed geotechnical engineering firm registered in NL and are the subgrade or structural fill bearing pressures to be tested and confirmed prior to placing foundation concrete?	
88	Drawing S-001 Slab on Grade Note #2 request 200mm of porous fill. S-001 Slab on Grade Note 4 request a 15 mills (.381mm OR 0.015 inch thick) vapor retarder under the SOG which is typical for Radon designs. P-103 shows a Radon piping system while P-102 shows a under slab drainage system. These two plumbing systems cross each other. The Radon pipe can be installed without a slope so we would expect this to be the top layer of piping (where the gas is present) while the drainage piping is lower. The west side drainage piping must slope towards the exterior wall discharge location. Is the 200mm porous fill depth from the Radon engineer and if not, what should this depth of porous fill be when considering the drainage piping being installed below?	200 mm is the minimum depth and must be provided in all locations.
89	Drawing S-001 Slab on Grade Note 3 is asking for 50mm (2" thick) premoulded joints as isolation joints. Note 6 requests any penetration in the slab to be surrounded by 50mm (2" thick) pre-molded joint filler. S-301 has detail C1 showing that the main floor level has a premoulded joint filler at 12mm (1/2" thick) while the lower slab on detail C3 is not a joint filler but rather a hydrophilic water stop. B1/S-501 has joint filler around the steel column in fills. This joint filler is 15mm thick and is not hydrophilic water stop. a) What is the thickness of premoulded joint fillers to be used? b) Are the joints in the lower raised access floor slab depression to be premoulded joint fillers or hydrophilic water stop?	a) Notes and details have been updated to 12mm joint. b) Water stop at slab edge has been removed.
90	Drawing S-001 Slab on Grade Note 4 has 15 mills thick vapor retarder. On Radon designs this vapor retarder is sealed with mastic at the perimeter edges, vapour retarder lapping joints, column penetration, and any pipe sleeving locations. The intent is to stop Radon gas from entering the space above. Is this sealing of the Radon vapor retarder required for this project?	Yes. Provide sealant per Specification 31 21 13 Radon Mitigation. Seal new and existing floor slab penetrations in accordance with EPA 402-R-93-078 and as specified herein. Prevent entry of soil gas into the building and exhausting of conditioned air via the radon mitigation system. Seal cracks and openings around floor slab penetrations with polyurethane sealant.
91	Drawing S-001 Slab on Grade Note 7 indicates to see Architectural drawings for the location of drains and slopes. Architectural drawings have located room 103 shower pan that is rebated into the SOG, room 106 mop sink, and the room 104 toilet which connect to	Yes, provide drain slab penetrations in locations shown on plumbing, note has been updated.

	drainage but there are no floor drains or sloping floors on the Architectural drawings. P-102 shows floor drains and clean-out locations. Can the plumbing drawings be used for the locations of drainage slab penetration when the architectural drawing has provided no locations or will drains and slopes be added to the Architectural drawings?	
92	Drawing S-001 Concrete Note 1 requests 35 MPa and 32 MPa strengths. S-002 has an Embedment and Lap Splice Lengths table with only two options, 30 MPa and 35 MPa. Does this mean that only 35 MPa splice lengths are being used?	Use table for 30 MPa lap splices for 32MPa concrete.
93	Drawing S-001 Concrete Note 6 asks for water tops in all construction joints at or below grade. A) Is the main floor level control joints premoulded joint fill or waterstop? B) Is the lower RAF floor level waterstop the reference the same as the hydrophobic water stop on the drawing details?	A) Main level is pre-molded joint fill. B) Waterstop has been removed from SOG.
94	Drawing S-001 Special Inspections Note 2 requests the Contractor to retain qualified Special Inspection & Testing agencies to perform the necessary inspections of International Building Code (IBC) section 01 45 35. These inspections apply to structural steel, concrete, masonry, wood framing, sprayed fireproofing, smoke control, etc. Newfoundland does not have any IBC qualified agencies, but we do have the equivalent Canadian Code and Standards inspection and testing agencies. Can these inspections and testing requirements be applied to meeting Canadian codes and standards or are agencies from the US to be retained for this project?	Canadian engineers or inspectors can be used as indicated per Specification 01 45 35.
95	Drawing S-001 Precast Concrete Walls Note # 8 list other design disciplines to coordinate with. Can this list be expanded to include Landscaping (Precast chiller screen walls), Plumbing, and Fire Protection?	Refer to revised Drawing S-001, Note #8 has been updated.
96	Drawing S-001 Precast Concrete Walls Note # 9 asks for “Goal Tar Epoxy” to be applied to all below slab precast fasteners. Should this read Coal Tar Epoxy?	Refer to revised Drawing S-001, Note #9 has been updated.
97	Drawing S-001 Cold Formed Metal Framing indicates the structural stud and soffit framing shown on the tender drawings S-504 Detail A3 has not been engineered and it is the Contractor’s responsibility to hire a manufacture who can perform this engineering with design calculations submitted as part of the shop drawing package. What Code and Standards are being applied to this design as DOD and Canadian Codes are both noted on this S-001 drawing?	Design must meet CSA codes for cold formed as indicated, loading for DoD codes is provided in loading diagrams and Note #7, Note 2 has been updated.
98	Drawing S-101 shows the stepped footings to the lower footing stepping from TOF = -1000 to TOF = -1800. The raised access floor is -1200 from the main	The piping layouts are diagrammatic in nature (Drawing P-001 Gen Note #21.) The piping can be routed and installed

	floor zero elevation and has a 250mm thick slab. The underside of the lower SOG sits 350mm above the top of footing. With the Radon piping pushing down the invert elevations of the drainage piping of the lower-level floor drains (see P-103 and P-102) can we get confirmation from the Plumbing and Radon engineers that 350mm clearance is sufficient?	in a manner which avoids any conflict with the structural footings, meets the design intent, and is code compliant.
99	Drawing S-101 Note 10 is identifying the approximate location of utility penetrations. Many penetrations from Civil, Fire Suppression, Plumbing, and Electrical / Communications are not shown on S101. The 5 penetrations at grid 1 & B-C and grid 2 B-C require further clarification. At grid 1 the five penetrations are sets of vertically stacked 100mm conduits but at grid 2 these same conduits must be shown as 15 horizontal 100mm conduits that rise up into the 15 holes (3 per five NEMA enclosures) shown on TN401. The transition from vertical stacked to horizontal occurs between grid lines 1 and 2. If the design team agrees this is an correct interpretation of how the 100mm conduits are being run then structural should show the 15 penetration on grid line 2 to inform the precast manufacturers engineers of this complexity before price, cost, and quality certainty is provided to the GC. Is the grid 2 penetration five vertical stacks of three 100mm conduits or is these 15 horizontal penetrations that align with the NEMA cabinets above?	As indicated in drawing S-101, keynote 11, locations are approximate and must be coordinated with electrical. Note has been updated to indicate location is of (3) conduits.
100	Drawing S-101 section C4/S-301 is taken at grid 2 & A-B. This is a double door opening. a) Does this cast-in-place foundation wall also occur at the single door locations at this recessed RAF slab area? b) Can the Contractor provide a precast wall engineered solution in lieu of the CIP wall design?	A) Section is applicable to all doors. B) Yes, a precast solution would be acceptable. Sections have been updated.
101	Drawing S-101 has three 560 mm wide precast walls at grid D & 3-5. At grid D and 1-2 detail A3/S-502 is marked "Typ" (typical). A3 on S-502 shows the interior SOG and exterior SOG as monolithic pour with added reinforcing passing through the door openings. Is the exterior SOG poured tight against the 560mm wide precast walls and exterior envelope precast sandwich panels walls or is there any isolation joints required? (I.e. – does the SOG brace the 560 mm fin walls structurally)	Detail A3 on Drawing S-502 is the typical detail for slab re-entrant corner reinforcing but does not show the exterior slab. Section C2/S-301 shows the typical slab detail at door openings with a joint in the middle of the doorway as shown.
102	Drawing S-101 shows the price proposal CLIN 0002 second generator oil tank supports and the second generator equipment pad. Which portion of this scope forms part of the CLIN 0002? (Likely just the	CLIN 0002 is for the purchase of the second generator. Pad for second generator is in CLIN 0001.

	equipment pad due to the A4 on S-301 reinforcing detail)	
103	Foundation Keynotes Note # 2 has a 250mm SOG with two layers of reinforcing steel. EG101 has requested a copper-clad steel 100mm x 100mm mesh to be installed within the entire RAF SOG and the main floor commercial telcon room SOG. The mesh has 22 ground connector posts installed (see C1 on EG502) that sit flush with the top of the SOG. The height of these ground connect post assemblies is not provided on the drawings. Does the mesh sit above the top layer of structural reinforcing steel or is it sandwiched between the 2 layers of structural reinforcing steel? (Note: above maybe easier to install but the post depth may lower the elevation of the top structural reinforcing mat)	Yes, the intent was that the signal reference ground mesh sits above the top layer of reinforcing rebar.
104	Please confirm note references 2 and 3 are also needed for the roof located at grid 5-7 & A-C.	Confirmed.
105	Detail C1 has hydrophilic waterstop shown continuously under the precast wall panels on the main floor level. A-306 has Detail A3 with note 25 indicating dampproofing on these upper perimeter walls. A-306 has Details A1 and A2 for the lower RAF areas with note 18 indicating waterproofing. a) Is the RAF lower depressed area perimeter being tanked with waterproofing products while the upper main floor area perimeter is being treated with only dampproofing products? b) Is the dampproofing on A-306 A# to be applied to the top and side of the footing? (Note: A2 on A-307) indicates this dampproofing is wrapped onto the footing? c) A-305 Detail A1 at grid 7 references A2/A-306. This is a RAF wall assembly that has waterproofing being requested. Should this reference be A3/A-306 which is requesting dampproofing? d) If the upper level perimeter walls are dampproofing then does A1 and C1 on S-301 need hydrophilic waterstop on the bottom of the sandwich panels? e) C3 on S-301 RAF perimeter wall does not show hydrophilic waterstop below the precast wall panel. Is hydrophilic waterstop required in this detail? f) Does C4 on drawing S-301 get a "strip" of hydrophilic waterstop in the pour break between the wall and the footing and perhaps a strip of hydrophilic waterstop between the perimeter CIP walls and the precast walls? (i.e. - similar to S-504 Details C2) g) S-504 Detail D2 has no hydrophilic waterstop while S-504 Detail C2 has hydrophilic waterstop. Is the hydrophilic waterstop only installed in the precast walls that frame the RAF depression?	A) Correct, only the recessed floor area in Ops Equipment 116 is to be treated with waterproofing products. B) Correct. C) Correct, should read detail A3 on Drawing A-306 D) Yes E) Yes, it is shown but not indicated. Detail C1 has been updated to say typ. F) Yes G) Yes, install below grade only. H) This is not needed.

	h) Drawing S-502 Details C1 shows a SOG construction joint. Should this joint include a s "strip" of hydrophilic waterstop in the pour break if used in the RAF SOG?	
106	Detail C1 and C2 show a precast coping. A-306 Detail A3, A-307 detail A2, and A-505 Details C1 / C2 / C3 show precast copings. A-107 roofing drawing references these precast coping locations with Note # 3 (top left side) which is described as Prefinished Aluminum Coping on A-101. Please clarify which is correct.	Precast coping is correct. Refer to updated keynote on revised Drawing A-101.
107	Detail B1 and B2 references B3/S-504 which does not exist. Should this be A3/S-504? Is S302 Detail B4 a A3 /S-504 reference as well?	Yes, it has been updated to A3 on revised Drawing S-504.
108	Drawing S-401 shows a precast slab ceiling for the fuel tank room. This is a 3-hour fire rated room. Is the precast manufacture to engineer the slab panel sizes or is this to be manufactured as a single panel approximately 9.6m x 6.08m in size? If there are joints with these joints require sprayed fireproofing or just the A-509 Detail B4 fire caulking?	Manufacturer can provide multiple slab panels and sizes as needed. Joints should have caulking per Drawing A-509 detail B4 since this is a precast ceiling.
109	Drawing S-501 Detail B1 shows the footing assembly for the four structural steel columns. A-105 shows these columns enclosed by metal stud assemblies with A-405 Details B3 and B4 detailing the enclosures. A-306 Detail A1 shows the perimeter room metal stud assembly starting at the lower SOG and terminating above the ceiling. A-305 Detail C1 appears to show these column enclosures terminating at the U/S of the roof structure. Do the column enclosures terminate at the U/S of the roof structure or just above the ceiling?	Wall furring around columns to terminate just above the ceiling at same height as perimeter wall furring.
110	Does the RAF footings need a "strip" of hydrophilic waterstop in the footing pour breaks?	Yes, provide hydrophilic waterstop within joints, note has been added to detail.
111	Drawing S-501 Detail A4 shows a long radius bend in the 15 - 100mm conduits rising up into the NEMA cable boxes shown on TN401 Detail A1. The elevation of the conduit entry through the precast is the top of the 1200 mm recessed SOG elevation with the bottom conduit's elevation sitting roughly +/- 400mm in elevation lower. S-101 shows the grid # 1 wall at -1000 with the 5 rows of 3 - 100mm vertically stacked conduits penetrating the wall. The vertical stacking is dictated by the electrical manhole sleeving on ES501 Detail A3 for UC1A and the manholes proximity to the grid 1 foundation wall. a) Are the conduits entering vertically stacked in the grid 1 precast wall and then rolling over to a horizontal distribution dropping down +/-1m in elevation before rising up into the grid 2 wall or does the grid 1 wall need to be dropped in elevation to	A) They are depicted penetrating the precast wall horizontally, not vertically. There should be no concern by the contractor as he is not required to install any cabling in this conduit. B) Opening is sized based on only part of the bend being within the wall as shown on the drawings, the full bend would not fit within the opening. Contractor is responsible for coordinating opening size required for final conduit location. C) Yes, the structural openings should be considered into the precast design for pricing. D) The drawings do not show this

	reduce the +/-1m elevation change?) The concern is too much friction on the conduits for pulling the data wires into the NEMA cable boxes) b) The opening in A4 on S-501 is indicated to be smaller than the long radius conduit bend which requires a much larger opening height. Please confirm the larger opening height is required. c) Can the layout of the NEMA cable boxes on TN401 be dimensioned so that the structural openings on A4 S-501 can be engineered by the precast manufacture for inclusion in the GC pricing? d) Do the 15-100mm conduits under the SOG need to be concrete encased in a ductbank? e) Is there a design detail for waterproofing these 15-conduit block-out penetrations?	requirement. E) Block outs will be filled with grout.
112	Typical Equipment Pad Detail is engineered for a 150mm housekeeping pad. a) Can this same detail be used for MEP equipment housekeeping pads with MEP specified thicknesses of 100mm, 200mm, etc.? b) P-501 Detail B1 has backflow preventor supports that references A-1/P-502. This detail is another engineered housekeeping pad with no roughing or doweling to the slab. Should detail C4 S-502 be used in lieu of this plumbing designed pad and should this be a dowel connection to the SOG this backflow preventor? (Is movement a concern) c)M-102 shows a 150mm concrete pad for the chillers. Please confirm C4/S-502 can be used for this pad. d)M-402 shows housekeeping pads for BT-1 and the CHWP – 1&2. M-505 Detail B-4 shows the BT-1 pad to be 100mm thick. Please confirm C4/S-502 can be used for these pads. e)M-402 does not show a housing keeping pad for DOAS-1. Is this correct? f)M-502 detail A1 has a housekeeping pad that is connected with dowels to the SOG. This has seismic anchorage needs so there is no structural pad option for roughing up the slab. Is this correct and please confirm C4/S-502 can be used for this pad using the dowel option? g) EP201 and EP202 Detail A1 show 100 mm housekeeping pads for GS1 and ES1. Please confirm C4/S-502 can be used for these pads. h) EP202 Detail C1 shows 100mm housekeeping pads for UPS A & B and Battery Racks. Please confirm C4/S-502 can be used for these pads. i)TN401 Detail C1 shows two data cabinets with no housekeeping pad requirement. Is this correct? j) Are there other MEP housekeeping pads required that are not identified above?	a) Yes b) Yes c) Yes d) Yes e) Provide housekeeping pad for DOAS. f) Yes g) Yes h) Yes i) Yes j) All mechanical equipment on floor must have a housekeeping pad.

113	Drawing S-503 Detail B2 shows the steel framing for the roof hatch. S-504 Detail B4 shows the roof framing for the roof hatch ladder connection (also for two door jambs). A-506 shows the roof hatch and roof hatch ladder details. a) Please confirm the steel framing on S-503 Detail B2 is being installed for the roof opening. This is not the same framing as what is indicated on the Architectural drawings. b) Please confirm the steel framing on S-503 Detail B4 will be installed for the ladder but adjusted to be lower in elevation than the roof framing. This is not the same framing as what is indicated on the Architectural drawings. c) How does the ladder on A-506 Detail A1 and A2 connect to the S-503 Detail B ladder steel framing? d) Intrusion by air (parachute) is possible on military bases. Should this roof hatch be pad locked from the interior side of the hatch? e) TY101 has no perimeter detection for this roof hatch. Is detection required (BMS) and is a VSS exterior camera needed for surveillance of the building perimeter which would include this roof entry point?	a) Yes b) Drawing S-504 detail B4 is to support the ladder. c) The ladder connects to the steel framing via the steel angles (Note 63), that extend from the ladder to the drywall and are fastened, through the drywall, into the steel tubes (detail B4 on Drawing S-504) located within the wall. d) Provide interior padlock able roof hatch. e) BMS will be required on the exterior roof hatch. Provide VSS Exterior camera pointed toward roof hatch from upper exterior wall of room 116.
114	Document P1360_Pre-Solicitation.pdf (1).pdf states this is Design build? Is there any part of this project that is a Design Build?	No, this is a Design Bid Build project.
115	There is a discrepancy in the price proposal form. a. Attachment _D - _Schedule_B_Price_Proposal_Form.pdf.pdf is different than Solicitation - N6247026r0011.pdf.pdf	Refer to Attachment D – Schedule B Price Proposal Form.
116	The specifications refer to demolition drawings. Please provide demolition drawings and/or as-builts.	Demolition Drawings are in revised drawings.
117	There is a spec section for 09 67 23.15 Fuel Resistive Resinous Flooring, 3-Coat System but it is not called out in the room finish schedule. Please clarify if this the same as the SC-1 on the room finish schedule.	Not required.
118	Fireproofing details B2 & B3 / A509 which show spray fireproofing but there is no clear detail as to where this actually occurs. nor is there a specification provided. Please provide locations of spray fireproofing and a spec section for spray applied fireproofing.	Only the beams in Generator Fuel Room 114 need to be fire proofed. Refer to section A5 on Drawing A-307 through this space and subsequent details B2/B3 on Drawing A509. Refer to revised Specification 07 81 00.
119	Factor 1 – Construction Experience states: “A project that was completed within the past ten (10) years of the date of issuance of this RFP.” Will the Government accept projects that are currently ongoing? Several recent Navy RFPs have allowed the	The solicitation requires "Projects submitted for the Offeror shall be completed within the past ten (10) years of the date of issuance of this RFP". The Government will not waive this requirement.

	submission of ongoing projects. We respectfully request that the Government consider allowing projects that are at least 60% complete (based on the remaining amount left to invoice), as these projects can still demonstrate relevant and recent experience performing similar work.	
120	Please confirm metric or imperial size equivalent will be allowed.	Utilize metric to the greatest extent possible. Imperial sizes must be approved by the construction manager prior to use.
121	SF1442 shows bid bond is not required, where solicitation page 30 of 46, includes FAR 52.228-1 Bid Guarantee. Please confirm a bid bond is not required	Refer to Solicitation Section 2.2.2 Performance Guarantee.
122	Box 13 required 2 copies, please confirm there is no hard copy proposal requirement, and the only requirement is the electronic copy.	Refer to revised solicitation box 13.
123	The electrical one-line riser diagram shows panelboard LR109 twice, please confirm this is in error and only (1) panelboard LR109 is to be furnished and installed in room #109.	Correct. LR109 was incorrectly shown twice on power riser.
124	The electrical one-line riser diagram shows existing panelboard at Gate House as 600A, please confirm this is in error and panelboard amperage should be 60A.	The riser is correct.
125	Please confirm the new underground primary conduits should be 100mm in lieu of 150mm as referenced on detail A1/ES502	There isn't any reference to 150 mm conduits on the detail you referenced (Detail A1 on Drawing ES502).
126	The primary electrical service voltage is 12.47kV however the exterior conduit and cable schedule note #1 on drawing ES102 states to provide (8kV), as well as the one-line diagram feeder schedule "F16", is this correct or should this cable be rated for 15kV?	The cable voltage rating shown is correct.
127	As this project is not a US Territory and remote, please remove the carpet reclamation requirement as there is no locally available facility.	Propose in accordance with solicitation.
128	As this project is not a US Territory, please confirm there is no prevailing wage decision.	There are not any prevailing wage decisions associated with this project.
129	Please confirm/clarify if there are any exemptions/waivers for tariffs, duties, taxes available for this project.	There are not any specific tax exemptions associated with this project.
130	Quality Control (QC) Specialist Experience Matrix, Civil, Mechanical, Electrical, Structural and Architectural positions, please confirm the related experience satisfies both the 2-1 Qualification and 2-2 Experience requirements. For Example of intent: Graduate Civil Engineer or Construction Manager with	Confirmed.

	a professional engineer registration in Newfoundland Canada, and 2 years' experience in the type of work being performed on this project or technician with 5 years related experience	
131	Abatement specification references a Appendix A-AECOM/Baker report, but it was not provided. Please provide.	Will provide after contract construction award
132	Please confirm there is no workforce labor nationality restriction requirements.	Refer to FAR clause 252.222-7002
133	QC Specialist: As there is no relatable specifications/scope on this project please remove the Roofing Manufacturer's Technical Representative, & the Mechanical Inspector International Code Council (ICC) Certified positions.	Refer to revised Specification 01 45 00.
134	Do to the timing of the site visit and volume of files to review, please consider providing a two-week extension to the pre-Proposal Inquiry due date.	Proposal due date extended to 20 April 2026.
135	Please confirm that UL certification is acceptable for electrical equipment and is equivalent to the CSA certification if the material is imported from USA?	The contractor is responsible for ensuring that the materials provided are acceptable to the requirements set forth in the specifications.
136	Details on the Mechanical/Electrical demo scope of work is very limited in the tender package. Please provide more information on the extent of demo with drawings of existing to be removed, equipment that will be handed over to the owner and equipment we are to dispose of.	Refer to revised Drawings - Demolition Details.
137	Drawing P-102, note #7 states to install GD-1, please provide information/specifications regarding GD-1 for bidding purposes.	GD-1 is a standard residential-type garbage disposal (120V/60Hz) with cord and plug. It will be connected to an outlet beneath the sink as indicated on the Electrical drawings.
138	Specification section 26 51 00, 2.2 states "provide luminaires as provided on the luminaire schedule" however there is no information provided pertaining to model numbers or manufacturers, please provide brand/ model numbers for the lighting that are acceptable for use.	Manufacturers and model numbers are not typically provided on US Navy projects. Luminaire requirements and details are shown in the drawings and specifications.
139	Drawing P-602 shows a panel schedule for TCP-1 "Tank Control Panel" that is a lead/lag fuel storage tank control however there is no reference in the specifications 33 09 52 for this panel. The specification section 33 09 52 is for Fuel Pump Control and Annunciation System (Non-Hydrant) however this doesn't seem to be in line with what the drawings show, for example there are references to (3) transfer pumps in the specification that do not appear on the drawings. Please confirm for bidding purposes,	The drawings indicate the correct configuration of fuel system equipment and the system should employ automatic changeover between tanks while the generator is operating and shall employ selectable changeover between tanks during refilling from the automatic fill port. The Specification 33 09 52 is incorrect in listing the three pump configuration in paragraph 3.5.4;

	contractors should price what is shown on the drawings.	however, the remainder of the subsection should be applied to the equipment configuration as indicated on the drawings.
140	What type of valves are represented on Detail C1 of drawing P-704, the plumbing legend on drawing P-001 list them as "VALVE: GLSE" however there is no reference to this in the associated specification.	The design intent for these valves was to be ball valves in conformance with Specification 33 52 10.
141	The "VALVE: GLSE" is shown as NO (Normally Open), NC (Normally Closed) and LO, please confirm "LO" is Locked Open and if so, please provide a specification on the LO listed valves for bidding purposes.	Correct. The design intent for these locked-open valves was to be lockable ball valves in conformance with Specification 33 52 10.
142	Please provide a specification for the Chemical Shot Feeder shown on drawing M-402/A2 for bidding purposes.	Refer to Specification 23 64 26 paragraph 2.9.4 for information on the chemical shot feeder.
143	What are the temporary power and utility requirements once utilities/poles are removed as per demolition scope, for example does the Guard Shack need to remain active during construction or refed once the new electrical service is in place?	The contract drawings clearly show that the power to the existing building and guard shack are to be removed during demolition. There is no indication of a temporary power requirement to the guard shack.
144	Who owns the existing utility poles on the property?	The electrical utility, Newfoundland Power.
145	Please confirm the contractor is responsible to furnish and install the new 750kVA pad-mounted service transformer in lieu of the Utility provider.	The electrical utility Newfoundland Power will provide the service transformer.
146	There are two existing overhead poles being used for main incoming power, what if any, are the pole requirements for supply and installation in reference to details shown on ES503, and ES504?	The work included for overhead electrical utility is indicated on Drawing ES102. The details provided on Drawings ES503 and ES504 are provided for describing the work indicated on Drawing ES102.
147	Newfoundland is not a known seismic zone, is it expected that we will have to supply seismic rated equipment and/or a seismic engineer's signoff?	There are no seismic requirements. Rated equipment and seismic engineer are not required.
148	Are DB-2 conduits acceptable in duct banks or is Schedule 40 required for the full lengths?	The specification for underground electrical work clarifies acceptable material for underground ducts.
149	Specification section 01 14 00, 1.2 states government approval is required for submittals with a "G" or "S" classification prior to acceptance. Please clarify.	Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submittals not having a "G" or "S" classification are for information only.
150	Specification section 01 35 29.13 section 3.3.1 states general HTRW training is required, is this only for	HTRW training is required for all abatement personnel.

	abatement companies or all site contractors participating in demolition?	
151	Specification section 26 36 23, 3.3 Please clarify “provide the services of a qualified factory-trained manufacturer’s representative” does that mean local authorized representatives are not accepted?	Specification section has been removed.
153	Drawing EP601 Electrical One-Line Diagram has the generators sized at 800kW however sheet keynotes #6 & #7 on drawing EP101 have them sized at 750kW. Please clarify the required sizing for the generator sets.	750 kW is the correct value.
154	Please confirm the outdoor Load bank is required to be NEMA 3R construction.	The load bank is located exterior to the building, so the appropriate rating is expected.
155	Is the Load bank a horizontal discharge design?	The product used as the basis of design was a horizontal discharge type.
156	Does the Load bank have auto load controls?	Refer to revised Specifications EP601.
157	Does the Load bank require a remote control panel?	Refer to revised Specifications EP601
159	Does the Load bank control need interface with the building automation controls (TCP/IP)?	Refer to revised Specifications EP601
160	Could the CAD files for the project be provided to assist in bid preparation?	CAD files will not be provided.
161	Please confirm Balance of Payment Clause is applicable to this project.	Refer to solicitation DFARS Clause 252.225-7035.
162	There appears to be no mention of the Portable Generator Quick Connect Enclosure in the electrical specifications. Please provide more information such as desired NEMA rating, enclosure material, etc.	Ratings provided on drawings. Generator is shown exterior to the building, installed on a concrete pad, thus materials must be rated per the drawings.
163	With regards to the various material and installation details indicated on Overhead Electrical Site Detail drawings ES503 & ES503; please clarify in detail what new utility pole work or existing poles are required to be dressed or redressed by the Electrical Contractor to accommodate the new service.	The work included for overhead electrical utility is indicated on Drawing ES102. The details provided on Drawings ES503 and ES504 are provided for describing the work indicated on Drawing ES102.
164	The project data management and validation requirement is an unusual specification, and we have not seen this on international projects of this size and nature. Please clarify if this requirement applies to this project.	Project Data Management and Validation Specification section has been removed.
165	Specification section 01 30 00, paragraph 1.6.1 indicates the Superintendent is permitted to also serve as the Quality Control Manager as established in section 01 45 00. However, section 01 45 00 indicates the QC Manager can also perform the Level 2 Site Safety and Health Officer (SSHO). Please clarify if the Site Superintendent can also serve as the Quality Control (QC) Manager.	Superintendent can also serve as the Quality Control (QC) Manager, provided they meet the qualifications outlined in Specification 01 45 00.
166	Specification section 01 45 00, paragraph 1.6.1.1 indicates the QC Manager is permitted to also serve as	Specification 01 45 00, paragraph 1.6.1.1 states that the QC Manager's

	the Level two Site Safety and Health Officer (SSHO). Please confirm the QC Manager can also serve as the Level two SSHO.	duties include "to serve as the Level two Site Safety and Health Officer (SSHO) as detailed in Section 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS." See Level Two SSHO definition in Specification 01 35 26 paragraph 1.3.1.2. Additionally, per Specification 01 35 26, paragraph 1.9.2 and 1.9.3, provide a minimum of one Level One SSHO that meets the requirements of EM 385-1-1.
167	035326 Safety requires a SSHO level one safety, whereas 01 45 00 requires level two SSHO safety. Please clarify require level.	When requirements differ, the most stringent one governs. Specification 01 35 26, paragraph 1.8 of the specification's states, "Where the requirements of this specification, applicable laws, criteria, ordinances, regulations, and referenced documents vary, the most stringent requirements govern. Level one SSHO is the more stringent requirement.
168	Safety and Health Manager must be an Industrial Hygienist. Please confirm individual can be provide by and independent third party	The specifications provided do not contain the term "Safety and Health Manager".
169	Please confirm the Safety and Health Manager is only required for the contaminated work and not required during other non-contaminated activities.	The specifications provided do not mention a "Safety and Health Manager". However, various sections discuss safety personnel required for specific hazardous tasks. For instance, Specification 01 35 26, paragraph 1.10.3.3 references a "Site Safety and Health Plan" for contaminated sites. It is likely that specialized safety personnel are only required for the phases of work involving their area of expertise, such as contaminated work.
171	Additional Certified Health and Safety Support Personnel appears to be a duplicate certification to the Safety and Health Manager as they are both required to be an Industrial Hygienist. Please confirm this individual is only required, if needed, to support Safety and Health Manager.	The specifications provided do not mention "Additional Certified Health and Safety Support Personnel" or require an Industrial Hygienist for the SSHO or QC Manager roles.
172	Specification section 01 35 26 states the Safety personnel are required to meet/follow requirements for both NL OH&S and EM 385-1-1. As EM 385-1-1 (USACE standards for federal military/construction contracts) requirements are significantly more stringent than the local NL requirements, please confirm that EM 385-1-1 requirements are to be followed.	Specification 01 35 26, paragraph 1.8 states, "Where the requirements of this specification, applicable laws, criteria, ordinances, regulations, and referenced documents vary, the most stringent requirements govern." Therefore, since EM 385-1-1 is more stringent, its requirements must be followed.

173	Please confirm if the SSHO needs to be a direct employee of the prime contractor, or can the SSHO be an employee of the subcontractor or consultant.	Specification 01 35 26, paragraph 1.3.1 defines the SSHO as "A Contractor Employee". It does not specify that this must be a direct employee of the prime contractor. This implies the SSHO can be an employee of a subcontractor or consultant, as long as they are a dedicated member of the contractor's team for the project.
174	Please confirm the Safety and Health Technicians are required one each per work crew in the exclusion zone.	The specifications provided do not contain the term "Safety and Health Technicians" or mention a requirement for one per work crew in an exclusion zone.
175	Specification section 01 45 35 Special Inspections, paragraph 1.2, indicates that the statement of special inspections and schedule of special inspections are included as an attachment to the specification. However, it appears this document is not included in the solicitation. Please provide the statement of special inspections and schedule of special inspections.	Refer to revised Specification.
176	Specification section 01 50 00, paragraph 3.2.2.b indicates the Government will make available reasonable amounts of utilities at prevailing rates. However, no additional information is provide. Please identify the utilities available and the prevailing rates for each utility to be charged to the Contractor in performance of the work.	Refer to revised Specification.
177	Specification section 01 57 19, paragraph 3.4.1 indicates existing archaeological resources within the work area are shown on the drawings. We have not been able to locate this information. Please clarify if known areas of archaeological resources are located within the work area.	Refer to revised Specification. No archeological/historical resources expected.
178	Reference specification section 01 57 19, paragraph 1.11Please confirm the Government will remain the Generator associated for all contaminated material and Hazardous Waste for materials currently within the project site.	Refer to revised Specification.
179	Building Commissioning Specification para 1.2 & 1.12, identifies the commissioning provider and specialist to be hired by the government , whereas para 11.11 identifies them as a first tier subcontractor. Please clarify if the commissioning firm and specialist will be provided by the government.	The Government will provide Third-Party commissioning services.
180	Specification section 01 91 19 paragraph 1.3.7 Building Enclosure Commissioning (BECx) states "Technical service provided on behalf of the Government to provide quality-focused process for	The Government will provide Third-Party commissioning services.

	enhancing the performance of the building enclosure by validating the design phase and verifying during the construction phase that the performance of the building enclosure materials components, assemblies, and systems are designed and installed to meet the Owner's Project Requirements (OPR)." Please confirm if BECx will be provided by the Government under a separate contract.	
181	Specification section 01 91 19 paragraph 3.10 lists Appendix A, B and C. However, we are unable to locate these documents in the solicitation. Please advise.	Refer to revised Specifications - Appendix A, B, and C.
182	Specification Section 02 51 19 Solidification and Stabilization Decontamination, paragraph 1.3.3 Performance Requirements includes Table 1 - Post Treatment Test Criteria. The test values for the chemical and physical criteria have not been specified. Please provide the requirements of the chemical and physical criteria.	Refer to revised Specifications.
183	Specification Section 02 51 19 Solidification and Stabilization Decontamination, paragraph 3.1.a and 3.1.c identifies the stockpile geomembrane liner and cover with minimum thickness but does not actually provide the thickness value. Please provide the minimum thicknesses.	Refer to revised Specifications.
184	Specification Section 02 51 19 Solidification and Stabilization Decontamination, paragraph 3.1.d identifies the stockpile berm minimum height but does not actually provide the height value. Please provide the minimum heights.	Refer to revised Specifications.
185	Specification Section 02 51 19 Solidification and Stabilization Decontamination, paragraph 3.3 Field Demonstration indicates to perform field demonstration on at least 500 Cubic Meters (CM) of contaminated material. However, Schedule B Price Proposal Form, Line Item 1C only includes a quantity of 250 CM. Please advise.	Refer to revised Specifications.
186	Specification Section 02 61 13 Excavation and Handling of Contaminated Material, paragraph 1.3 indicates excavation and temporary storage of 3.1 cubic meters of contaminated soil. The quantity of 3.1 cubic meters does not seem accurate. Please clarify.	Contaminated soils are considered unlikely to be encountered outside of a localized area. Previous investigation identified diesel related impacts in one of five borings, limited to the vicinity of a former fuel tank where releases occurred, suggesting impacts are isolated rather than widespread. This specification will be updated to have a more reasonable quantity in case contaminated soil is encountered.
187	Specification Section 02 61 13 Excavation and Handling of Contaminated Material, paragraph 1.3	Yes, groundwater contamination is anticipated based on historical (2012)

	indicates groundwater is approximately 0.6-1.22 meters below pre-excavation ground surface. However, the Boring Logs included on the drawings indicate groundwater at 10 to 19 Feet below existing grade. If there is an expectation to encounter groundwater during excavation activities; Please clarify the following: - Is groundwater anticipated to be contaminated? - What is the expected contaminant? - Will a unit price Line Item be added to the Schedule B for Contaminated Groundwater?	sampling that slightly exceeded applicable limits; however groundwater is not expected to be encountered during the planned excavation.
188	Specification Section 02 61 13 Excavation and Handling of Contaminated Material, paragraph 2.2 identifies requirements for sampling backfill from off-site sources. However, required sampling parameters are not provided. Please provide both physical and chemical required.	Refer to revised Specifications. Provide backfill in accordance with Specification 31 00 00.
189	Specification Section 02 61 13 Excavation and Handling of Contaminated Material, paragraph 3.4.1 indicates to excavate areas of contamination to the depth and extent shown on the drawings and not more than 60 mm beyond the depth and extent shown on the drawings unless directed by the Contracting Officer. However, the drawings do not provide any information as to the extent or depth of excavations related to contaminated materials. Please advise.	Extent of contaminated material is expected to be small as contaminants were confirmed in only one boring.
190	Reference Specification Section 02 61 13 Excavation and Handling of Contaminated Material, paragraph 3.5 Confirmation Sampling and Analysis. This paragraph appears to be related to an expectation that the project involves removal of a known area of contamination which is not representative of this project. Please confirm this requirement does not apply to this project.	Refer to revised Specifications.
191	Reference Specification Section 02 61 13 Excavation and Handling of Contaminated Material, paragraph 3.7 Sampling Beneath Storage Units. This paragraph appears to be related to another project. Please confirm this requirement does not apply to this project.	If contaminated material is encountered and stockpiled, testing is required to ensure that containment for the stockpile is not breached.
192	Reference Specification Section 02 61 13 Excavation and Handling of Contaminated Material, paragraph 3.11 Closure Report. This paragraph appears to be related to an expectation that the project involves removal of a known area of contamination which is not representative of this project. Please confirm this requirement does not apply to this project.	Modified to require a closure letter that contaminated materials, if encountered, were handled and disposed of in accordance with host nation's regulatory requirements.
193	Reference Specification Section 02 61 23 Removal and Disposal of PCB Contaminated Soil, paragraph	Refer to revised Specifications, section has been deleted.

	1.4 Method of Payment. This section indicates unit of measure as TON, however the Price Proposal Form Line Item 1C is Cubic Yard. Please change the Price Proposal Form unit of measure to TON.	
194	Reference Specification Section 02 61 23 Removal and Disposal of PCB Contaminated Soil, paragraph 1.4 Method of Payment. This section indicates the requirements of Contract Clause entitled "Variation in Estimated Quantity" do not apply to payment for removal of PCB contaminated soil. We respectfully request that the Government reconsider and remove this limitation. Allowing the Variation in Estimated Quantity clause to apply will help ensure a fair and equitable contract structure for both the Government and the Contractor, particularly given the inherent uncertainty associated with subsurface contaminated soil quantities.	Refer to revised Specifications, section has been deleted.
195	Multiple specification sections address different types of contaminated soils—including metals, PCBs (<50 ppm and >50 ppm), and petroleum-impacted materials—yet the current Price Proposal Form provides only one unit-price line item for contaminated soil removal and disposal. Given the distinct handling, disposal requirements, and cost impacts associated with each contaminant type, the Government should consider adding separate unit-price line items for each major contaminant category? This approach would allow offerors to provide more accurate pricing and would support a fair and transparent evaluation of the varied contaminated soil conditions anticipated in the project.	Refer to revised Specifications, section has been deleted. The nature and extent of the contaminated material is limited to hydrocarbons, PAHs, and BTEX contaminants related to diesel fuel spills only, located around the former fuel tank at the Generator building
196	Due to the critical importance of Appendix A – the AECOM/Baker report associated with the contaminated and hazardous materials scope of work, we respectfully request an extension to the question deadline to a minimum of one week after receipt of Appendix A. This extension will allow offerors sufficient time to review the report in detail and submit informed questions specifically related to the contaminated and hazardous materials scope.	Contaminated soils are considered unlikely to be encountered outside of a localized area. Previous investigation identified diesel fuel related contaminants in one of five borings (MB-1), limited to the vicinity of a former fuel tank where releases occurred, suggesting impacts are isolated rather than widespread. The nature and extent of the contaminated material is limited to hydrocarbons, PAHs, and BTEX contaminants related to diesel fuel spills around the former fuel tank at the Generator building

197	Is there a preferred/standard Electronic Security System (ESS) integration system or is it open to any integration compliant with SECNAV M-5510.36?	The contractor is not providing the ESS equipment.
199	Specification Section 02 61 23 Removal and Disposal of PCB Contaminated Soils references CCME (Canadian Council of Ministers of the Environment) guidelines and United States CFR (Code of Regulations) related to PCB contaminated materials classification, removal, transportation and disposal. In consideration of the project location please confirm only following the CCME guidelines is acceptable for the classification, handling, and disposal of PCB contaminates.	Refer to revised Specifications, this section has been removed.
200	Specification Section 02 65 00 Underground Storage Tank Removal references CEPA (Canadian Environmental Protection Agency) guidelines and United States CFR (Code of Regulations) regulations related to tank closures, contaminated soils and pumpable liquids materials removal, transportation and disposal. In consideration of the project location please confirm only following the CEPA guidelines is acceptable for the closure, handling, and disposal.	Confirmed.
201	Specification Section 02 81 00 Transportation and Disposal of Hazardous Material references Canadian TDGA (Transportation of Dangerous Goods Act) guidelines and United States CFR (Code of Regulations). In consideration of the project location please confirm only following the TDGA guidelines is acceptable for the handling and disposal of hazardous materials.	Confirmed.
202	Specification Section 02 82 00 Asbestos Remediation references United States CFR (Code of Regulations) related to asbestos remediation. In consideration of the project location please confirm if following the Newfoundland and Labrador's Asbestos Abatement Regulations, 1998 (NLR 111/98) is acceptable for the remediation, handling, landfill approval, and disposal of asbestos.	Confirmed.
203	Specification Section 02 83 00 Lead Remediation references CCME (Canadian Council of Ministers of the Environment) guidelines and United States CFR (Code of Regulations) related to Lead Remediation. In consideration of the project location please confirm following the CCME guidelines is acceptable for the remediation, handling, and disposal.	Confirmed.
204	Specification Section 02 84 16 Handling of Lighting Ballasts and Lamps Containing PCBs and Mercury references CCME (Canadian Council of Ministers of the Environment) guidelines and United States CFR (Code of Regulations) related to handling, storage,	Confirmed.

	and disposal. In consideration of the project location please confirm only following the CCME guidelines is acceptable for the handling, storage, and disposal of PCBs.	
205	Price 1A and 1B are for a 1.5m line outside the facility These are a subtotal of the base price so included in price 1?	All SUBCLINS within CLIN 0001 are included in the base price
206	Price 1C is a subtotal for 250 m3 of contaminated soil not identified (1 bore hole identifies hydrocarbons so I'll assume this does not count. Is this part of the base price?	All SUBCLINS within CLIN 0001 are included in the base price
207	Price 1D is 250 m3 of structural fill for unsuitable subgrade soils. Is this the Geotechnical "Under Cut" or in addition to that? I suspect the quantity on the drawings will be higher so do we include say 400 m3 in the base price and only breakout 250 m3?	The amount of structural fill identified in Line Item 1D is in addition to any required undercut soil requirement for the base bid.
208	Price 1E is a subtotal of the base price and wants us to include 30,000 l of oily water and sludge inside tanks What tanks and what oily water?	Propose in accordance with the solicitation.
209	Price 2 needs a better scope of work for which my drawing questions have asked. Electrical Generator, Plumbing Fuel Tank and Piping, and Structural housekeeping pad?	CLIN 0002 should include price for purchase of second generator.
210	Price 3 ESS does not mention cabling like the drawings do so I asked a question on this. It does expand the scope into PCU's, central processing units, field panels, workstations, etc. Not sure if there are specifications for all this stuff?	Contractor will not provide ESS equipment
211	Price 4 FF&E includes transportation From where?	From the manufacturing location.
212	There is a reference to LEED and advanced commissioning for this project, can you please confirm if this project is a LEED project as there are no LEED specifications. If this is confirmed not to be a LEED project would the notes regarding advanced commissioning still be applicable.	This should not be a LEED project. We are GBI certified only. Any LEED verbiage should be disregarded.
213	There is a reference to LEED in the specifications, can you please confirm if this project is a LEED project as there are no LEED specifications. If this is confirmed not to be a LEED project would the specification still be applicable.	This should not be a LEED project. We are GBI certified only. Any LEED verbiage should be disregarded.
214	We are requesting a two week extension to closing date.	Proposal deadline were extended to 20 April 2026.
215	Current design has the Automatic Transfer Switch installed within the lineup. Would it be acceptable if the ATS were externally mounted and cable connected to the switchboard?	The PPI process should not be used as a platform to offer variations to the design. Bid the design as it is shown on the specs and drawings.

4. Provide Attachments

Amendment 0003 Revised P1360 DEMO Drawings

Amendment 0003 Revised P1360 Drawings

Amendment 0003 Revised P1360 Specifications

5. Provide P1360 Site Visit Attendance Log