

**Statement of Work (SOW)**  
**326 TRS**  
**JBSA-Lackland AFB**

**1.0 General Information.**

**1.1 Scope** The contractor shall provide all labor, equipment, and materials to remove/dispose of existing carpeting and install new flooring in two (2) separate buildings ATC5 and ATC6. Each room is identical layout in section 5, each measuring approximately 21 x 27 feet (approx. 1,134 sq. ft. total), at JBSA-Lackland.

**1.2 Background** This requirement is a complete turnkey solution for flooring modernization. The project includes the removal and off-site disposal of current flooring, subfloor preparation, and the installation of new flooring. All work shall be performed to commercial standards with no structural modifications required to the facility.

**1.3 Applicable Documents** Diagram of room layout (Section 5.0).

**1.4 Restrictions** No unauthorized photography on base, any photos must be approved by a Government POC prior to taking them.

**2.0 Schedule & Coordination.** **INSTALL MUST BE COORDINATED WITH INSTALL POC NLT TWO WEEKS PRIOR TO ON BASE WORK START TO ASSURE ACCESS AND WORK AREA IS CLEAR.**

**2.1 Contract Management.** 502 Contracting Squadron, Contracting Officer/Specialist POC information listed on solicitation/contract. Install/Base access POC: Capt Derek Guedes, derek.guedes.3@us.af.mil, 210-612-0153

**2.2 Work Hours and Special Conditions.** Monday - Friday 0700-1600 not to include federal holidays and weekends.

**2.3 Place of Performance**

ATC6 - JBSA Lackland 326 TRS, Section 1, 1135 Luke St, Building 9239, JBSA Lackland, Texas 78236.

ATC5 - JBSA Lackland, TX 78236. 322 TRS. 1231 Luke St. Building 9231.



The Contractor shall maintain sole responsibility for the supervision and direct control of all personnel. Personnel shall adhere to the Joint Ethics Regulation 5500.7.R and maintain a professional appearance with visible company identification (clothing or badges). All inquiries or issues arising from performance shall be directed to the Government PM and Contracting Officer (CO).

## 2.4 Site Surveys

May be requested by the awardee through the Project Manager to verify final measurements and floor conditions.

## 2.5 Start-Up Meeting.

Post-award, a meeting (virtual or in-person) will be held between the Contractor, PM, and customer to finalize the work schedule and timelines.

**3.0 Requirement** Installation requires professional, trained personnel to ensure a seamless fit, proper adhesion/stretching, and commencement of the manufacturer's warranty. This includes all materials, equipment, shipping, and full turnkey installation services.

- Demolition: Complete removal and off-site disposal of existing carpet, padding, and debris.
- Preparation: Subfloor must be cleaned and prepped for the new installation.
- All one piece Smooth, solid-grip, seamless. 13mm thickness. Blue, speckled appearance doorway to not have tripping hazard. Warranty in line with industry standards (about 5-15 years)
- Installation: New flooring shall be installed as specified in the design layout, including transitions and wall base.
- Site Cleanliness: No trash, scraps, or discarded materials shall be left on-site.
- Validation: The Government PM will inspect the finished flooring to ensure it is free of defects (e.g., bubbles, fraying, or visible seams).

**4.0 Contractor Requirements.** The Contractor shall provide all materials tools transportation required for design, install, and install.

The contractor shall be familiar with and capable in the field of work that is being executed and certified as to not void any warranty on equipment or items provided to the Air Force.

## 4.1 Security Requirements

Installers must be able to pass a security check and provide valid state license to gain entry to base. All work performed under this contract is Unclassified.

## 5.0 Attachments



