

Minimum Requirement for the Naval Construction Group 2 (NCG-2), Gulfport, MS

- 1) Be available for a minimum of 15 days.
- 2) Be able to transit along the Gulf Coast or meet us at pre-determined locations
 - a) Embark locations
 - i) Port of Gulfport, MS
 - ii) NAS Pensacola, FL
 - iii) Panama City Beach, FL
- 3) Have a minimum total usable deck space of 1,320 square feet (e.g., 55' x 24') to accommodate the following equipment:
 - a) 4 TRICONS (6'x8'x8' container) (SSDS, SSDS support, SCUBA, dive gear, and survey equipment)
 - b) Bauer air compressor
 - c) Inflatable wing boat (during transit)
 - d) Transportable Recompression Chamber System (TRCS) with 2 Air racks and multiple O2 K-Bottles for chamber treatments, SURDO2 procedures, and in-water Air/O2 decompression procedures
 - e) Accommodate 25-30 PAX (can be adjusted) (excluding VOO crew) with enough room to perform daily dive side operations and recompression treatments (as needed)
 - f) Possess the ability to maintain a 2-point moor (minimum) over a diving location
 - g. If a DP2/3 vessel, have adequate room to place and operate a Diver Launch and Recovery System and Stage
- 4) The following items are referenced from the US Navy Diving Manual Rev 7 CH-A, Para. 6-2.2.2.6:
 - a) Provide ample space for divers to dress.
 - b) Include USCC-required lifesaving and other safety gear
 - c) Have a reliable engine.
 - d) Be able to carry all diving safety equipment for the operation
 - e) Have a well-trained crew.
 - f) Carry other safety equipage as required by the unit SOP (binoculars, fresh water, charts, etc.).
- 5) Possess head facilities for topside personnel.
- 6) Be able to carry all diving safety equipment required for the operation.
- 7) Possess an area where UCT can attach a ladder in order to extract divers.

Additional/Optional

1. Crane availability for loading and unloading gear and equipment.
2. Berthing.
3. Mess support.
4. If a LARSS is utilized, a crew to operate the LARSS is needed.

Location/Timelines for execution:

- Pensacola, FL: November - December 2026, two week window for execution.

Prior vessel examples:

- The below photos show previous vessels utilized and typical deck layout for UCT.





