

Statement of Work (SOW)

Project Number: GHLN 26-7001

Project Title: Repair Storm Damage Historic Star Vents MULTI Bldgs

19 Feb 2026

1. GENERAL REQUIREMENTS:

- 1.1. Conduct all work in accordance with the SOW and Specifications herein, all applicable codes, manufacturer's recommendations, and the construction drawings and details. The Contractor shall pay special attention to the FE Warren AFB Installation Facilities Standards (IFS).
- 1.2. The Contractor shall follow all Green Procurement mandates and submittal requirements. The government requires the use of recycled and recovered materials, bio-based products, energy and water saving products, and environmentally preferable products. Energy Star, FEMP-designated, or EPA Water Sense labeled equipment, appliances, and fixtures are mandated in all cases unless specifically directed otherwise.
- 1.3. Dispose of all waste generated by this project according to all applicable regulations.
- 1.4. The Contractor is responsible to verify site conditions, measurements, quantities, and materials needed to complete this project prior to submitting a proposal, ordering materials, and starting work activities. All materials including those concealed or covered shall be new and of the most suitable and highest grade and type for the intended use unless otherwise indicated.
- 1.5. Install all materials in strict accordance with the manufacturer's printed instructions and details: rigid, secure, plumb, level, aligned, square and straight with suitable fastening devices.
- 1.6. The term "provides" means provide (or furnish) and install.
- 1.7. The term "replace" means remove existing material or items and furnish and install a similar new material as required to match existing adjacent material or items. All Historic Buildings will utilize 'replacement-in-kind' (matches design/materials/texture and detailing).
- 1.8. Any change in conditions or modification with this project must be presented to the Contracting Office and approved by the Project Manager prior to changes. After the changes have been agreed upon, the contractors shall complete a REQUEST FOR INFORMATION (RFI), processed through the contracting office. It will reflect

whether additional costs will be incurred by the Government. It will also have all agreeing party's signatures.

- 1.9. Assume that all buildings are occupied. Include how work will proceed in safety plan.
- 1.10. See AF Form 66 for required submittals. This may not be an all-inclusive list. All materials brought onto the base shall be on an approved submittal. It is advisable to have approved submittals on materials prior to purchase. Other submittals required by the specifications may apply.
- 1.11. All facility work must comply with the latest edition of the International Building Code (IBC).
- 1.12. If any excavation or ground penetration is necessary, request and obtain 100% approval on a Dig Permit (AF Form 103) prior to any digging, trenching, or below grade construction work. The Contractor must maintain all utility markings throughout the project. The Contractor is responsible for extending/updating all dig permits until digging, trenching, or below grade construction work is completed.
- 1.13. If any welding, cutting, grinding, brazing, torching, open flame, or spark generating equipment is utilized, the contractor shall obtain a "hot work" permit from the 90 CES/CEF Fire Department prior to commencing any such work. Contractor is responsible for extending/updating all "hot work" permits until such work is completed.
- 1.14. Coordinate material storage, laydown, and staging areas with the 90 CES Construction Management Inspector (CMI). Coordinate road closures and traffic restrictions with 90 CES two weeks prior to construction activities.
- 1.15. Review of Technical Submittals by the Government will not be construed as a complete check but indicates only that the submittals are in general conformance with the design concept and with the information given in the Contract Documents. This approval shall not relieve the Contractor from responsibility for errors and omissions. The Contractor is responsible for field measurements, dimensions, design of adequate connections, details, fabrication processes, and the means, methods, techniques, and procedures for satisfactory installation.
- 1.16. Any alternative methods aside from those specified in the plans and specifications submitted by the Contractor require CRM approval through the CO and additional SHPO consultation if the alternative is not included within the scope of the SHPO concurrence. This is accomplished via RFI process with a submittal for review and approval to follow.

2. PROJECT SCOPE:

The contractor shall provide all labor, materials, equipment, transportation, and supervision necessary to remove/dispose of old vents, manufacture, deliver and install new vents as

specified storm damaged 'Star Vents' at F.E. Warren AFB in accordance with this Statement of Work for buildings 232, 250 and 366. The replacement work includes but is not limited to the following features: Remove roofing as necessary, remove vent and boot, fabricate new vent of the same design, fabricate new boot to match vent, install new boot and vent, replace roofing of the same make/model according to manufacture specifications. The drawings and field sketches provided with this package shall be used to assure correct gauges of metals and attachments. Contractor to field verify measurements to assure identical size.

Historic buildings and repair or replacement work required are listed below:

- Bldg. 232 (synthetic slate roof)
 - Four Large Star Vents (deck mounted).
- Bldg. 250 (synthetic slate roof)
 - Four Medium and Six Large Star Vents (deck mounted).
- Bldg. 366 (clay tile roof)
 - Three Small Star Vents (deck mounted).

Mounting shall be as show in drawings and as originally mounted, Roof slopes vary as shown in Drawings.

2.0.1 Additional Scope Requirements:

The Government needs several historic "Star Vents" replaced on multiple buildings. The following statements describe how work shall be completed as required by Cultural Resource Manager (CRM) in compliance with the State Historic Preservation Office (SHPO), the National Park Service (NPS), as well as the Unified Facilities Code (UFC) as follows.

1. Contractor shall complete and submit, after award, Attachment 1 Historic Evaluation form for each building, detailing condition, vent locations and other information. A Sample completed form is included as Attachment 2. If it is determined that repairs can be accomplished on a particular vent, notify 90 CONS and CE Inspector.
2. Remove existing ridge cap and roofing down to the lower edge of the baseplate area of the new Star Vent, approximately 50 square feet per unit. Then remove the old 'Star Vent' and its boot. The amount of roofing to remove will be less if it is mounted on the ridge.
3. Repair attic framing and decking as necessary with similar materials (replacement-in-kind). Allowance is made in this plan for replacement of up to thirty-two (32) square feet of decking and twenty (20) linear feet of 2x8 wood per vent. Contractor shall track usage and notify 90CONS and CE inspector should additional materials be required.
4. Replacement 'Star Vents', boots, mounting straps shall be manufactured exactly as specified in drawings, Contractor to field verify correct size. It is acceptable to

remove one vent of each size, weather in the area to create a watertight condition, and use that vent as a model for manufacturing a new 'Star Vent'. If an active vent is removed, accommodation shall be made when weathering in for the activity to remain fully functional. Contractor may not seal the hole while waiting for vents to be fabricated. If the vent is just venting the attic space, the weathering in should use a method that allows ventilation of the attic to continue. If the vent removed is tied into the HVAC system, the function must remain.

- a. The new vents must meet the exact specifications as the old vents. The manufacturer shall use the original press, located at Advanced Metal Solutions, LLC in Fort Collins, CO or approved equal. Contractor may use a different press and different manufacturer if the new vents will meet CRM/SHPO approval and can exactly replicate the original vents. Contractor shall place a maker's mark on the new vents stating the vents are not original and indicates Fabricator's company name and city of fabrication. Star tops may be re-cast by a vendor of Contractor's choice. Maker's mark shall face the ground below.
 - b. Drawings provided are for two common sizes, the vents on Bldg #366 are smaller in size than vents on the balance of buildings. Provide a sample vent for review and approval prior to installation. Once approved, this sample may be used on the roof.
5. 'Star Vents' were originally used for facility boiler or heating system ventilation. There are three current/modernized configurations on the interior/attics of the facilities:
- a. Passive attic ventilation (most common).
 - b. Connection to a drum which captures exterior blown in moisture which is then piped through 1" copper to interior drains. (second most common).
 - c. For use as a flue for modern HVAC venting. (extremely rare).

Roof mounted boots and 'Star Vents' shall be replaced and reconnected to the facility as the above configurations dictate, to match build prior to demolition.

6. If the existing roof is asphalt shingles and the vent is mounted on the ridge, use existing boot height. If the vent is mounted on the pitched deck with asphalt shingles, the new boot shall be 6" taller than the existing boot. The mounting flange on original boots is only about 3" wide and is round, following the contour of the boot. New boots shall be made with a square mounting flange extending beyond the circular throat of the boot as shown in drawings.
7. Repair wood framing and deck as necessary to assure solid mounting strap connection between the mounting ring element of the 'Star Vent' and the framing beneath the deck. New mounting straps are required and shall be the same type and gauge metal as currently exists.

8. There are multiple gauges of galvanized steel in the construction of new boots and vents. Use gauges identified in the attached drawings and field sketch.
9. The Stars on top of the vents shall be re-cast in aluminum and made smooth prior to coating. The Stars shall be coated with “satin bronze” metallic exterior paint. Star sizes are unique to each of the typical sizes of vents. Stars shall be oriented parallel to adjacent ridgelines when work is completed as shown in drawings. Old Stars from existing vents shall be salvaged and delivered to the Government Inspector for Cultural Preservation. One Star of each size which may be sacrificed for the new castings.
10. Submit color samples for review and approval prior to coating the stars.
11. Upon re-installation of the new ‘Star Vents’ and boots, Contractor shall install roofing of the same type (as appropriate) by a Certified Roof installer for the material used. Roof installation shall be in compliance with Manufacturer’s recommendations and installation instructions. As there are future plans to replace roofs, this project’s roof installation is a repair. The Government has a supply of synthetic slate shingles as well as clay tiles which Contractor may use. Coordinate quantities needed with CE Inspector.
12. Provide adequate personnel and safety equipment (including temporary barriers on the ground in the area where work is being performed) to ensure building occupants will not be at risk. Assure site is clean and free of debris during operations and after hours. Coordinate staging areas with Government Inspector and Facility Managers.
13. Provide a permanent Makers Mark affixed to the vent to include manufacturer’s name and City/State of production, as shown in drawings. The mark shall be 4” wide by 2” tall as indicated in attached drawings.
14. Provide 2 year No Dollar Limit Warranty on materials and labor for all aspects of work described above and in compliance with all requirements. A Sample Warranty shall be submitted for review and approval prior to work, with an executed warranty submitted prior to final billing.
15. If any inadvertent damage impacts historic structures, Contractor must provide photographs of inadvertent damage on the exterior of historic buildings to the CRM through the CO for historic documentation.
16. Substitute materials not listed in specifications will require additional CRM review and SHPO Concurrence before implementing. Use the RFI process to provide documentation of the issue encountered.

2.1. Environmental Requirements:

2.1.1 See attached Environmental Specification section 01 57 19.05 32.

2.1.2 Asbestos: If potentially hazardous materials such as asbestos are encountered, submit sampling and laboratory test results to Project Manager for approval. Samples shall be taken by a trained and accredited asbestos professional (inspector). If asbestos materials are discovered, the government will seek additional funding for abatement. An advance 10-day Notification to WY DEQ/AQD will be required prior to any abatement work being accomplished. Any asbestos waste generated must be disposed of properly and be manifested through 90 CES/CEI at building 321.

2.1.3 Lead: Some surfaces and materials may contain lead. If materials containing lead are disturbed or removed, the Contractor must comply with all applicable RPA, OSHA, State and Federal laws and regulations.

2.1.4 Mold Remediation: Some surfaces may contain mold. If surfaces containing mold are present, the effective way to clean mold is to use detergent solutions which physically and completely remove the mold. This requires the use of a commercially available detergent marketed for mold cleanup that includes an EPA-approved antifungal agent.

2.1.5 The use of hazardous materials shall be approved by the Contracting Officer prior to use. Follow Environmental specification section 01 57 19.05 32 and Hazardous Materials Authorization form provided. Please note there are three areas covered: Authorization, Storage, and Use.

2.2. Security Requirements:

2.2.1 Real ID

- a) IAW DoDM 5200.08V3 _DAFMAN 31-101V3 _DAFGM 2024-01, *Installation Perimeter Access Control*. Base access and Common Access Cards (CAC) requests will require REAL ID-Compliant identification for Base access and CAC creation. Failure of the vendor to ensure personnel have REAL ID-compliant identification will result in denial of Base access and CAC requests.

2.2.2 Operational Security (OPSEC)

The contractor shall adhere to the following minimum requirements in support of this requirement:

- a) All contractors, subcontractors, their employees, associates, and consultants who have access to critical information and indicators must comply with the Air Force-sponsored Operations Security (OPSEC) program.
- b) OPSEC is an information-related capability that preserves friendly essential secrecy by using a process to identify, control, and protect critical information and indicators. If critical information and indicators are disclosed, it could allow adversaries or potential adversaries to identify and exploit friendly vulnerabilities leading to increased risk to mission failure or the loss of life. The desired effect of

OPSEC is to influence the adversary's behavior and actions by reducing the adversary's ability to collect and exploit critical information and indicators about friendly activities.

c) RESPONSIBILITIES:

1. Contractors must ensure employees receive OPSEC education that includes an overview of the OPSEC process, the definition of OPSEC, its purpose, what is critical information, the individual's role in protecting critical information, and the general adversary threat to the AF's critical information. Additionally, OPSEC education must include updated threat information, changes to critical information and indicators, new procedures and/or OPSEC measures implemented, altered, or deleted by the organization.
 2. DoD Contractors with OPSEC requirements, or that have access to critical information and indicators, shall complete initial and annually recurring refresher training. Accomplishment of initial OPSEC training must not exceed 90 days from initial assignment to a contract with OPSEC requirements. Access to mission-critical information will not be allowed until OPSEC education has been completed and documented.
 3. OPSEC education is a continuous requirement. The host unit OPSEC coordinator must track OPSEC training statistics to include the personnel working on the contract, when each individual received the required initial OPSEC training, and when refresher training is due and/or completed.
- d) Contractor personnel shall not discuss government operations in public or over unprotected or unencrypted communications. Controlled unclassified information (CUI) may only be transmitted as directed in this SOW.
- e) The Contractor shall not post to company websites, publications, newsletters, or other media any images, data, or information that reveal sensitive government operations, personnel, equipment, and/or classified or controlled unclassified information. When in doubt, company press releases related to this contract should be coordinated through the Requiring Activity POC or CO, as applicable.
- f) Prior to seeking approval through the F. E. Warren AFB Public Affairs, any information to be released outside of official U.S. Government channels, via any media (to include electronic communications), must be approved through an OPSEC review. All personnel must promptly report OPSEC-related incidents, issues, and concerns to the host-unit OPSEC coordinator.
- g) Contractor shall restrict access to those individuals with valid need-to-know who are providing services under the contract. Further dissemination to other

contractors, subcontractors, or other government agencies and private individuals or organizations is prohibited unless authorized in writing.

- h) Because observation of events, operations, physical changes, etc., may reveal National Security information, specific restrictions are needed to preclude unintentional release of this information to unauthorized parties. Unauthorized disclosure and transfer of National Security Information is punishable under 18 USC § 793. Therefore, contractor personnel shall not disclose to unauthorized third parties, post to unofficial sites (including Social Networking sites) any images, data/information, or observed events that reveal sensitive government operations, personnel, equipment, including, but not limited to:
1. Tactics, techniques, and procedures, production, or work schedules, any visible or concealed modifications, upgrades, additions to vessels, aircraft, or weapons or equipment; increases, change, or decreases in work/deployment frequency or government personnel, vehicle, vessel, or aircraft movements; specialized equipment orders, deliveries, shipments, etc. Contractor shall report all unauthorized disclosures and attempts to solicit this type of information by unauthorized third parties or others not affiliated with this contract to the Requiring Activity POC or CO, as applicable.
 2. Contractor shall remove and/or conceal from plain sight, all government issued badges and identification when off base. Government badges and identification shall not be left in vehicles or unprotected areas. Badges and passes may not be duplicated, copied, or loaned to others. Lost or stolen identification badges, vehicle passes, etc., will be immediately reported to the Requiring Activity POC, CO, and/or Installation Security Office.

2.2.3 ANTI-TERRORISM

3. Notification: If the Contractor (contract employees/subcontractors) identify any suspicious activity, they shall contact the Base Defense Operations Center (BDOC) at 307-773-3501 (On-installation)/Missile Security Control (MSC) at 307-773-2701 (Off-installation) and notify the CO and the Requiring Activity POC that they contacted the BDOC and/or MSC.
4. **Training**
Contractor employees that require routine physical access to a Federally controlled facility or military installation shall complete Level I antiterrorism awareness training within 30 days of requiring access and annually thereafter send a copy of their employees' training certificate(s)

to the CO or Requiring Activity POC. Training is located at Joint Knowledge Online (JKO) website:

5. Contractor must comply with all requirements of attached memorandum *Department of the Air Force Guidance Memorandum, Civil Engineer Control Systems Cybersecurity.*

2.3. SAFETY REQUIREMENTS:

The safety requirements will be the same throughout. Follow the Accident Prevention Plan (APP) and Activity Hazard Analysis (AHA) the Contractor has created and submitted for the entirety of the project.

2.4. Licenses and Permits:

Follow Local, State, and Federal rules and regulations relating to licenses and permits required throughout the entirety of the project.

3. WORK SCHEDULE:

Site work hours shall be from 7:00 AM to 4:30 PM. Workdays are Monday through Friday except for federal holidays. Base Closures may occur without notice as Security requirements are met. Coordinate with the Project Manager and the onsite facility manager on specific building hours.

4. PERFORMANCE PERIOD:

Contractor shall coordinate work start date with the CE inspector and Contracting Office. The Period of Performance (PoP) for this project will be 300 Calendar days.

4.1 Winter Suspension:

In the case of the winter season that has direct impact on performing the work outlined in this SOW, the Contractor will notify the Government they can no longer perform work. 90 CES will validate that the weather no longer allows work to be performed within the specifications. If the reason for stopping work is due to materials and/or supplies being delayed in poor weather conditions, a letter from the manufacturer will need to be provided to support the winter suspension. The project will be placed into suspension upon approval from CES and CONs and the remaining number of PoP days will be documented. When weather is no longer a cause for delay and allows for work to begin again, 90 CONS will start conversations with the contractor regarding when they can come back to work. When the suspension is lifted, a new completion date will be established based on the remaining PoP days.

5. WORK AREA ACCESS:

Access to the building will need to be coordinated with the CE Construction Inspector and building facility manager. Access to Building #250 interior and attic will require coordination with the CE Inspector for each day access is needed.

6. SITE MAINTENANCE AND CLEAN-UP:

All work areas will be cleaned of debris daily. Contractor and employees must leave the facility and work areas in a clean condition ready for use. All work and surrounding areas shall be left free of blemishes and defects. Construction marks are not acceptable on any exposed finished surfaces. Pre-drilled holes are approved as necessary to facilitate connections. Protect the existing facility, sidewalks, and landscaping from damage due to equipment or personnel. Promptly remedy all damage or loss thereto. Contractor to notify CE Inspector and 90 CONS at the time damage occurs. Communication shall be made in writing, though verbal communications may assist resolving immediate issues.

7. SPECIFICATIONS OF WORK:

Principle features of work: Refer to drawings and attachments/schedules. The project includes but is not limited to the following items of work. This scope is a general overview of intended work. The project will include, but not be limited to the following items of work:

GENERAL REQUIREMENTS

1. Asbestos or lead paint testing required for this project shall be accomplished by the contractor. CES has not conducted testing for this project. See section 2.2 Environmental Requirements if any suspicious materials are discovered.
2. Contractor shall supply any lifts required to access high finishes.
3. Contractor shall supply any restroom facilities needed for this project.

EXISTING CONDITIONS

1. Remove and dispose of existing roofing around Star Vents. Carefully remove existing Star Vent from building. Weather in area on roof to watertight condition. Consult with CRM during and after removal for where to store historic star vents.
2. Make sure that passive attic ventilation, moisture drains, or flues are kept in working order during removal and installation of vents.

METALS

1. Depending upon location of star vent, new boots will meet the following:

- a. If the existing roof is asphalt shingles and the vent is mounted on the ridge, use existing boot height.
 - b. If the vent is mounted on the pitched deck, the new boot shall be 6” taller than the existing boot.
 - c. All new boots shall be made with a square mounting flange extending beyond the circular throat of the boot as shown in drawings.
2. Existing star vents shall be carefully measured and dimensions checked with supplied drawings and field sketches prior to manufacture of new star vents. Star vents shall be manufactured using the original press found in Fort Collins or approved equal.
3. The Stars on top of the vents shall be re-cast in aluminum. Stars shall be oriented parallel to adjacent ridgelines when work is completed as shown in drawings. Old Stars from existing vents shall be salvaged and delivered to the Government inspector. One Star of each size may be sacrificed for the new castings, coordinate with CRM and government inspector.
4. The Stars shall be coated with “satin bronze” metallic exterior paint. Submit color samples for review and approval prior to coating the stars.
5. Fabricate new mounting straps from the same type and gauge metal used on existing star vent mounting straps.

WOOD, PLASTICS, AND COMPOSITES

1. Repair wood framing as necessary underneath the deck to assure solid mounting strap connection between the mounting ring element of the ‘Star Vent’ and the framing beneath the deck. Repair wood deck as necessary.

THERMAL AND MOISTURE PROTECTION

1. Upon re-installation of the new ‘Star Vents’ and boots, Contractor shall install roofing of the same type (as appropriate) by a Certified Roof installer for the material used. Roof installation shall follow Manufacturer’s recommendations and installation instructions.

ATTACHMENTS:

Attachment 1 Historic Evaluation Form

Attachment 2 Sample Completed Historic Evaluation Form

ENVIRONMENTAL SPECIFICATION SECTION 01 57 19.05 32

UFC 1-200-01	https://wbdg.org/FFC/DOD/UFC/ufc_1_200_01_2019_c1.pdf
UFC 3-110-03	https://www.wbdg.org/FFC/DOD/UFC/ufc_3_110_03_2012_c5.pdf
FE Warren AFB IFS	https://www.wbdg.org/ffc/af-afcec/installation-facilities-standards-ifs/fe-warren-afb-ifs
NPS Preservation Brief 4 – Roofing for Historic Buildings	https://www.nps.gov/orgs/1739/upload/preservation-brief-04-roofing.pdf

Secretary of Interior Standards for the Treatment of Historic Properties:

<https://www.nps.gov/orgs/1739/secretary-standards-treatment-historic-properties.htm>

END OF REQUIREMENTS