

GROUNDS MAINTENANCE
PERFORMANCE WORK STATEMENT (PWS)
2 Mar 2026

DRAFT

Prepared by
EGLIN AFB< FLORIDA

[LEFT CLICK ON THE TABLE THEN SELECT “UPDATE TABLE” TO REFLECT PAGE NUMBERS]

TABLE OF CONTENTS

1	DESCRIPTION OF SERVICES	5
1.1	Mintain Improved Grounds	5
1.1.1	Mow	5
1.1.2	Edge.....	5
1.1.3	Trim	5
1.1.4	Weed Control	6
1.1.5	Munition Storage Area (RESERVED)	6
1.1.6	Irrigation (RESERVED).....	6
1.1.7	Remove Debris/Police Grounds	6
1.1.8	Leaf Removals	6
1.1.9	Lawn Conditioning.....	6
1.1.10	Pest control (RESERVED).....	7
1.1.11	Lawn Repair	7
1.1.12	Prune Shrub, Hedges and other Plants.....	7
1.1.13	Cemeteries (RESERVED).....	7
1.1.14	Artificial Turf (RESERVED)	7
1.2	Maintain Semi-Improved Grounds	7
1.2.1	Mow	7
1.2.2	Trim	7
1.2.3	Base Perimeter Fence Line (RESERVED).....	8
1.3	Maintain Bird Area Strike Hazard (BASH) (RESERVED)	8
1.3.1	Mow (RESERVED)	8
1.3.2	Airfield Light Fixtures (RESERVED)	8
1.3.3	Herbicides and Insecticides (RESERVED).....	8
1.3.4	Airfield Coordination (RESERVED).....	8
1.3.5	Flight-Line Drivers (RESERVED).....	8
1.3.6	Airfield Tower Communications (RESERVED).....	8
1.4	Un-Improved Grounds.....	8
1.5	Maintain Vegetative Beds, Inert Beds, Rock Beds and Related Areas	9
1.6	Maintain Surface Drainage Ditches	9

1.7	Perform Snow/Ice Removal (RESERVED).....	9
1.8	Special Requirements	9
1.8.1	Trees.....	9
1.8.2	Emergency and Special Events Services	10
1.8.3	Xeriscaping and Urban Forest Services. (RESERVED)	11
1.8.4	Special Cuts. (RESERVED)	11
1.8.5	Planting Trees, Shrubs, and Vegetative Beds.....	11
2	SERVICE SUMMARY.....	11
2.1	QUALITY CONTROL	12
2.2	QUALITY ASSURANCE.	12
3	GOVERNMENT FURNISHED PROPERTY AND SERVICES.....	12
3.1	FACILITIES	13
3.2	UTILITIES	13
3.3	MATERIALS	13
3.4	SECURITY, FIRE, AND MEDICAL SERVICES.....	13
3.5	TELEPHONE	13
3.6	SOLID WASTE COLLECTION AND DISPOSAL.....	13
4	GENERAL INFORMATION	13
4.1	MISSION.....	13
4.2	RESERVED	13
4.3	DAMAGES TO GOVERNMENT BUILDINGS, EQUIPMENT, OR VEGETATION.....	14
4.4	ENVIRONMENTAL REQUIREMENTS.	14
4.4.1	Hazardous Materials	14
4.4.2	Spill Controls	14
4.4.3	Pesticides.....	14
4.4.4	Hazardous Materials Inventory.....	15
4.4.5	Hazardous Materials Management.....	15
4.4.6	Final Report	15
4.5	PERMITS, LICENSES AND CERTIFICATIONS	15
4.6	HOURS OF OPERATION.....	15
4.7	RECOGNIZED HOLIDAYS.....	15
4.7.1	Base Closures	16
4.8	SECURITY REQUIREMENTS	16

4.9	PERFORMANCE OF SERVICE DURING CRISIS OR HEIGHTENED SECURITY	16
4.10	SPECIAL QUALIFICATIONS.....	16
4.11	INTERFACES	16
4.12	CONTRACTING OFFICER AND CONTRACTING OFFICER REPRESENTATIVE (QUALITY ASSURANCE PERSONNEL).....	16
4.13	WORK CLEARANCE REQUESTS.....	16
4.14	SAFETY REQUIREMENTS AND REPORTS	17
4.15	SCHEDULES	17
4.15.1	SCHEDULE CHANGES.....	17
5	APPENDIXES	17

1 DESCRIPTION OF SERVICES

The Contractor shall provide non-personal services, to include all personnel, equipment, tools, supervision, and other items and services necessary to ensure that grounds maintenance is performed at Eglin Air Force Base (AFB) in a manner that will promote the growth of healthy grass, trees, shrubs, and plants and present a clean, neat, and professional appearance. ***Areas maps and workloads depicting the service described in this PWS are identified in the Appendices.*** The Contractor's performance will be based on the Contracting Officer's Representative (COR), and Contracting Officer's (CO) evaluation of the results required by the Service Summary (SS) and not the method of performance. The evaluation of results will be based on COR surveillance, tenant satisfaction, and customer complaints. Final results of the evaluations will be the determining factor for the success or failure of this contract. The Contractor shall comply with applicable federal, regional, state, and local laws and commercial standards.

The growing season at Eglin AFB is considered to be 15 March through 15 December. All damage caused by the Contractor or its employees to government property and personal property (to include facilities, fences, equipment, trees and shrubs, etc.) due to Contractor operations shall be repaired or replaced by the Contractor within 15 days after identification/notification at no additional cost to the Government. If a plant should die or become unhealthy due to damage, the Contractor will be responsible for replacing the damaged plant with a plant of same size and type. Plant replacement shall occur within 15 days after identification or notification or as otherwise agreed to by the parties.

1.1 MAINTAIN IMPROVED GROUNDS

Improved grounds are identified in Appendix A. These areas are Buildings 1,11,13,349,350,351 and 1315.

1.1.1 MOW

The contractor shall mow all improved grounds to look well-manicured, with a neat and professional appearance. Maintain grass height between 2- and 4-inches uniform in appearance, free of skips, gaps, rutting, or scalping. The contractor shall be required to pick up debris, natural and manmade, prior to mowing any area. The contractor shall remove or mulch grass clippings when visible after mowing, before leaving work area. Removed debris shall be disposed of in accordance with the base's solid waste management plan.

1.1.2 EDGE

The contractor shall edge sidewalks, driveways, street edges, curbs, and other hard surfaced areas located within the improved grounds so that grass height matches surrounding area grasses. Grass, vegetation and weeds shall be cut back no more than ½-inch from the surface edged, maintaining an even contour with the edged surface, uniform in appearance and free of scalping, rutting, and uneven or rough cutting.

1.1.3 TRIM

The contractor shall trim grass and weeds around trees, shrubs, buildings, fences, poles, fire hydrants, parking lots bumper blocks, boulders, and other fixed obstacles and temporary obstacles/objects on improved grounds. Trimming height shall match surrounding area grass

height. All areas shall be trimmed concurrently with mowing. The contractor shall remove or mulch grass clippings when visible after trimming, before leaving work area.

1.1.4 WEED CONTROL

Control weeds in identify improved grounds through execution of a weed control program appropriate for the area to maintain a professional appearance. Restore grounds made barren where weeds are removed to the level of care of the surrounding area (i.e. semi-improved, improved, etc.). The Contractor shall use only approved pesticides as stated in DoD Instruction 4150.07, DoD Pest Management Program, Encl 4 para 4.2.2 and AFI 32-1053, Pest Management Program, para 4.7.4 and 4.7.6. All pesticides, herbicides, and rodenticides are defined in DoD and Air Force documents. The Contractor shall comply with current federal, state, local, DoD, and Air Force regulations, plans, and policies. The contractor shall comply with all applicable parts of 29 Code of Federal Regulations (CFR) 1910, Labor, Occupational Safety and Health Standards, 29 CFR 1925, Labor, Safety and Health Standards for Federal Service Contracts, 40 CFR 150-189, Protection of Environment, Pesticide Program, and 49 CFR 171, Transportation, General Information, Regulations, and Definitions. The Contractor shall ensure that all workers have current state certification for the pest control services being performed. Civil Engineer Asset Management Flight must approve all herbicides prior to use. All herbicides and pesticides used must be on the installation-approved inventory list and applied by certified personnel.

1.1.5 MUNITION STORAGE AREA (RESERVED)

1.1.6 IRRIGATION (RESERVED)

1.1.7 REMOVE DEBRIS/POLICE GROUNDS

The contractor shall perform general litter patrol in areas of improved grounds identified in Appendix A and B. Remove and dispose of natural debris, (tree limbs, dry brush, etc.), and man-made debris. Police areas to maintain a neat and professional appearance. Seasonal leaves are not part of this debris removal.

1.1.7.1 DEAD ANIMALS

The contractor shall notify the COR as soon as possible to report a dead animal. Specify type of animal and its location. The COR will notify Pest Management to accomplish removal of the carcass.

1.1.8 LEAF REMOVALS

The contractor shall mulch in place leaves in areas of improved grounds to maintain a neat and professional appearance. Leaf removal to be included natural debris (i.e. Tree limbs, dry brush, rodent habitats), and man-made debris. Tree limbs shall be collected and disposed of in the wood recycling yard, off Tustenuggee Loop.

1.1.9 LAWN CONDITIONING

1.1.9.1 FERTILIZATION

The contractor shall have a pH adjustment and fertilizer application program. The contractor shall perform a laboratory test of the soil in improved grounds and apply fertilizer and other soil amendments to bring soil condition to that suitable for the vegetation being treated. This work will be issued as a work order by the CO or COR.

1.1.9.2 AERATION (RESERVED)

1.1.10 PEST CONTROL (RESERVED)

1.1.11 LAWN REPAIR

The contractor shall renovate lawns in improved grounds as identified by the CO or COR. This work will be issued via a separate work order. Renovate deteriorated lawn area to match surrounding areas.

1.1.12 PRUNE SHRUB, HEDGES AND OTHER PLANTS

The contractor shall prune/trim shrubs and other plants to maintain their natural growth characteristics to enhance the beauty and health of the plant. Hedges shall be maintained to their natural mature height and shape. Shrubs, plants, hedges, and ground cover/vines shall be pruned/trimmed 3 inches away from buildings, fences, curbing, sidewalks, and other fixed obstacles. All ground cover and plants shall be kept within the bed borders. All plants around landscape and ground lights shall be pruned/trimmed to allow light usage for its intended purpose. Shrubs and hedges located on street corners, curb easements, etc. shall be pruned/trimmed to keep from obstructing view of oncoming traffic. Areas beneath shrubs and hedges shall be kept free (clean) of all grass, weeds, vegetation, and debris.

1.1.13 CEMETERIES (RESERVED)

1.1.14 ARTIFICIAL TURF (RESERVED)

1.2 MAINTAIN SEMI-IMPROVED GROUNDS

Semi-improved grounds are identified in [Appendix A and B](#).

1.2.1 MOW

The contractor shall maintain semi improved grounds at a grass height between 4 and 10 inches in all semi-improved grounds areas. Maintain a uniform appearance in all areas. Where possible, maintain adjacent areas at or near the same grass heights.

1.2.2 TRIM

The contractor shall trim grass and weeds around trees, shrubs, buildings, fences, poles, fire hydrants, parking lots bumper blocks, boulders, and other fixed obstacles and temporary obstacles/objects on semi - improved grounds. Trimming height shall match surrounding area grass height. All areas shall be trimmed concurrent with mowing.

1.2.3 BASE PERIMETER FENCE LINE (RESERVED)

1.3 MAINTAIN BIRD AREA STRIKE HAZARD (BASH) (RESERVED)

1.3.1 Mow (RESERVED)

1.3.2 AIRFIELD LIGHT FIXTURES (RESERVED)

1.3.3 HERBICIDES AND INSECTICIDES (RESERVED)

1.3.4 AIRFIELD COORDINATION (RESERVED)

The contractor shall coordinate all activities on the airfield by contacting Airfield Management. Work will be accomplished only after Airfield Management has approved scheduled times.

1.3.5 FLIGHT-LINE DRIVERS (RESERVED)

Training must be completed prior to operating vehicles or mowers on the flight line. All employees working on airfield grounds shall be required to have an AF Form 483, Certificate of Competency (flight-line driver's license) with them at all times. Vehicles must have a valid POV pass issued by Airfield Management prior to operating on the flight line. No equipment will be left unattended while working in these areas. The contractor shall be responsible for insuring that all foreign objects and debris produced by grounds maintenance is cleared off of all taxiways, runways, and aircraft parking aprons before leaving the work area.

1.3.6 AIRFIELD TOWER COMMUNICATIONS (RESERVED)

[NOTE TO THE COR: VERIFY WITH BASE-OPS TO MAKE SURE IF RADIOS ARE AVAILABLE TO PURCHASE AND BE ABLE TO PROGRAM TO THE RIGHT FREQUENCIES. IT MIGHT BE NECESSARY TO HAVE BASE-OPS PROVIDE THE RADIOS FOR CONTRACTOR TO USE]

The contractor shall be radio-equipped to maintain constant two-way radio contact with the control tower and Airfield Management when operating near runways, overruns, and taxiways. The contractor shall maintain contact with the control tower when operating on or within 150 feet of the runway. The contractor shall provide all communication equipment required for this contract. The government shall provide the transceiver frequency to the contractor. All equipment shall be VHF type with a minimum five-mile range and shall have private line capability. The contractor shall be responsible for any changes to radio types that the base makes in the course of this contract, i.e. frequency changes. The contractor shall respond immediately to the directions of the Air Traffic Control tower personnel.

1.4 UN-IMPROVED GROUNDS

Un-improved grounds are identified in Appendix A and B. The contractor to mow grass and vegetation in un-improved grounds to prevent woody encroachment. The contractor shall mow un-improved grounds once per year to a height between 10"- 14".

1.5 MAINTAIN VEGETATIVE BEDS, INERT BEDS, ROCK BEDS AND RELATED AREAS

The contractor shall maintain vegetative beds, inert beds, rock beds, and related areas as identified in Appendix A and B to present a neat and professional appearance. Maintenance activities may include but are not limited to fertilizing, watering, weeding, mulching, and repairing or replacing of damaged plants and shrubs. When replacing plants, shrubs, and performing repairs, conform to good Xeriscaping practices for the area.

1.6 MAINTAIN SURFACE DRAINAGE DITCHES

The contractor shall maintain surface drainage ditches to be free of shrubs, trees, and trash to prevent erosion and ensure continuous flow of water. Drainage ditches to be maintained are identified in Appendix B.

1.7 PERFORM SNOW/ICE REMOVAL (RESERVED)

1.8 SPECIAL REQUIREMENTS

All work under this section shall be executed via a work order by the CO or COR (except for whereas, referring to, “the contractor shall identify”). The contractor shall be responsible for removing all debris generated from all tree related operations. All non-emergency work order shall be completed within five (5) workdays from the work order date unless noted otherwise within subsections.

1.8.1 TREES

The contractor shall identify trees that pose public safety hazards or threats to structures/buildings. These hazards include minimum safety clearances, which are: 14 feet over streets, 12 feet over driveways, 8 feet over walk areas, 4 feet over buildings, and 1 foot from buildings.

Topping and de-horning are not permitted. Trimming or pruning of trees that touch or hang over energized utility poles or power lines is the responsibility of the contractor. Minimum clearance from primary lines (over 600 volts) shall be 8 feet. Minimum clearance from secondary lines (under 600 volts, i.e. electric service drops, telephone, and cable TV) shall be 4 feet.

1.8.1.1 TREE CARE

The contractor shall brace, cable, guy (to keep tree vertical), and deep water all damaged trees after identification. The contractor shall remove all guy wires, cables, straps, and stakes when the trees remain vertical (normally, after one growing season). The contractor shall adjust wires, cables, and straps as required, to prevent girdling.

1.8.1.2 TREE STANDARDS

The contractor shall perform all tree work in accordance with contract specifications and the following tree care standards, latest addition, unless otherwise directed by the CO.

- ANSI A300 - Standard Practices for Tree Care Operations including referenced Combined Federal Regulations (Utility Pruning and Emergency Service Restoration)
- ANSI A300 (Part 1) – Tree Pruning
- ANSI A300 (Part 3) – Tree Support Systems (Cabling, Bracing, and Guying)

- ANSI Z60.1 – American Standards for Nursery Stock
- ANSI Z133.1 – Safety Requirements for Tree Care Operations

1.8.1.3 EMERGENCY SPOT PRUNING/TRIMMING

The contractor shall complete an emergency spot pruning/trimming within one (1) workday from the work order date. Typically, emergency spot pruning/trimming includes removal of dead and/or broken limbs or removal of limbs for required clearances.

1.8.1.4 TREE AND STUMP REMOVAL

The contractor shall perform stump and perimeter roots removal by completely removing, by cutting and grinding all growth to a minimum of 8 inches below grade. Stumps shall be ground within 5 days after approval of dig permit) workday of the work order. Stump-grinding debris shall be removed the same day grinding is performed. The Contractor shall backfill with topsoil, and lay sod to match the existing ground grade and the type of grass. The Contractor shall maintain the patch area IWA manufacturer's recommendation until the grass has become established.

Trees identified for removal shall be considered within the following categories, Large, Medium, Small and Sapling, as based on their diameter. The diameter of the tree shall be determined by measuring 4.5 feet above the ground. Trees with multiple trunks shall be measured as follows: All trunk diameters shall be measured. The largest trunk diameter shall be recorded. Each remaining trunk diameter shall be halved. All values will then be added together to obtain the final tree diameter.

- Large Trees: Diameter 36" and above, remove within 10 workdays from the work order date. [Due to the complexity and difficulty of removing large trees, the bid schedule should have large trees on a proposal basis and not a firm fixed cost]
- Medium Trees: Diameter 24" to less than 36", remove within 10 workdays from the work order date.
- Small Trees: Diameter 3" to less than 24", remove within 5 work days from the work order date.
- Extra Small Trees: Diameter 3" and smaller, remove within 2 workdays from the work order date.

1.8.1.5 EMERGENCY TREE AND STUMP REMOVAL.

The following timeframe shall be apply for emergency tree and stump removal by the contractor:

- Large Trees: Remove within 2 workdays from the work order date
- Medium Trees: Remove within 2 workdays from the work order date
- Small Trees: Remove within 1 working day from the work order date

1.8.2 EMERGENCY AND SPECIAL EVENTS SERVICES

Upon notification of an emergency, the contract manager shall respond within one (1) hour to meet with the CO and government evaluator and initiate emergency services. Upon receiving direction by the contracting officer, contractor personnel shall begin emergency work within two hours. Oral work orders for emergency services to minimize damages or mitigate hazardous conditions will be confirmed with written work orders.

1.8.3 XERISCAPING AND URBAN FOREST SERVICES. (RESERVED)

1.8.4 SPECIAL CUTS. (RESERVED)

1.8.5 PLANTING TREES, SHRUBS, AND VEGETATIVE BEDS.

The contractor shall upon notification by the CO or COR through the issuance of a work order, perform planting of trees, shrubs, and vegetative beds to include but not limited to: removal and disposal of trees, shrubs, or vegetative beds being replaced; and performance of maintenance after planting to include watering, pruning, and insect and disease prevention to promote survivability. Provide estimate specifying unit pricing for planting trees, shrubs, and vegetative beds upon request.

2 SERVICE SUMMARY

The contract service requirements are summarized in performance objectives that relate directly to mission essential items. The performance threshold briefly describes the minimally acceptable levels of service required for each requirement. The Services Summary (SS) and the contractor's Quality Control Plan provide information on contract requirements, the expected level of contractor performance and the expected method of government validation and confirmation of services provided. These thresholds are critical to mission success. Procedures as set forth in the FAR 52.212-4 (a), Contract Terms and Conditions - Commercial Items, Inspection/Acceptance, will be used to remedy all deficiencies. During the first initial 30 days of the contract, two additional errors on each work shall be allowed in an effort to identify normal phase-in problems.

Performance Objective (PO)	PWS Section	Performance Threshold	Method of Surveillance
PO-1 - Maintain Improved Grounds	1.1	Excellent: 0 defects	Customer Complaint; 100% Inspection; Periodic Validation
		Very Good: 1 defect	
		Satisfactory : 4 defects	
		Marginal: 5 defects	
		Unsatisfactory: More than 5 defects	
PO-2 - Maintain Semi-Improved Grounds	1.2	Excellent: 0 defects	Customer Complaint; 100% Inspection; Periodic Validation
		Very Good: 1 defect	
		Satisfactory : 4 defects	
		Marginal: 5 defects	
		Unsatisfactory: More than 5 defects	
PO-3 - Maintain BASH	1.3	Excellent: 0 defects	RESERVED
		Very Good: 1 defect	
		Satisfactory : 4 defects	

		Marginal: 5 defects	
		Unsatisfactory: More than 5 defects	
PO - 4 Maintain Unimproved Grounds	1.4	Satisfactory : 1 defect	100% Inspection
PO-5 - Maintain Vegetative Beds, Inert Beds and related Areas	1.5	Excellent: 0 defects	100% Inspection
		Very Good: 1 defect	
		Satisfactory : 4 defects	
		Marginal: 5 defects	
		Unsatisfactory: More than 5 defects	

2.1 QUALITY CONTROL

The contractor shall provide a written description of the quality control system to include identification of the commercial practices and procedures to be used, such as those of the Professional Grounds Management Society (PGMS), Tree Care Industry Association, American Society of Landscape Architects, the American National Standards Institute (ANSI), and local Extension Offices of the Federal Cooperative Extension Service. Include the inspection system requirements of FAR 52.246-4 in this document. The contractor shall develop and implement procedures to identify, prevent, and ensure non-performance and continual repeat of defective service does not occur. A written Quality Control Plan shall be submitted to the contracting officer for review and feedback. The plan shall be submitted no later than the pre-performance conference. The plan shall specifically address the contractor's strategy to provide quality workmanship, continual process improvement and for correcting deficiencies as required.

2.2 QUALITY ASSURANCE.

The government shall inspect and evaluate the contractor's performance to ensure services are received in accordance with requirements set forth in this contract. The CO or COR shall inspect by validating actual work performance, physically checking an attribute of the completed task, checking a management information report, investigating customer complaints, conferring with facility managers, or otherwise inspecting the task or its results to determine whether or not performance meets the standards contained in this PWS. The CO or COR will use the contractor's work schedule or modified version thereof, to record validation results. Results of the validation then become the official Air Force record of the Contractor's performance. When a performance threshold has not been met or contractor performance has not been accomplished, the COR will initiate and provide the Contracting Officer a Contract Discrepancy Report (CDR) DD Form 2772 for issuance to the contractor. The contractor shall respond to the CDR IAW instructions provided and return it to the Contracting Officer within 1 calendar days of receipt.

3 GOVERNMENT FURNISHED PROPERTY AND SERVICES

3.1 FACILITIES

The Government will provide the facilities identified below for contractor use in support of the requirements of this contract. The facilities are provided “as is.” Obtain CO approval in advance of making any changes to the facilities. Such changes will be at no cost to the Government unless otherwise approved by the CO. The contractor shall ensure facilities are maintained in a neat, clean and professional manner. The CO reserves the right to reallocate and relocate assigned facilities during the term of the Contract. Upon completion or termination of this Contract, or upon such reallocations or relocations, return facilities to the government in the same condition as received, fair wear and tear and approved modifications.

3.2 UTILITIES

The Government will furnish electricity, water, and sewage as necessary for accomplishment of work in accordance with this contract. All facilities do not receive the same utility services. The Contractor shall not change or modify any utility system or component; or connect any Contractor property, equipment or system without prior CO review and approval. The contractor shall practice energy conservation in the Government provided facilities.

3.3 MATERIALS

"None"

3.4 SECURITY, FIRE, AND MEDICAL SERVICES

The Government will provide police and fire protection. In the event of a medical emergency, base ambulance service for transporting an injured employee to a local hospital is available on a cost reimbursement basis.

3.5 TELEPHONE

The Government will provide one telephone line in the Government provided facility for contractor use in making local commercial calls and on base calls in support of contract requirements. Long distance calls and toll calls are not authorized on government phones.

3.6 SOLID WASTE COLLECTION AND DISPOSAL

The Contractor shall use existing bulk containers to dispose of trash or solid waste generated from accomplishment of services detailed in this PWS (except for the work describes in section 1.8 Special Requirements). The contractor shall adhere to all base level recycling programs to include disposal of yard/tree waste as specified at the recycling collection center on base as identified in 1.1.8 above. .

4 GENERAL INFORMATION

4.1 MISSION

The overall Civil Engineer mission at Eglin AFB is to plan, maintain, operate, and protect the infrastructure, facilities, and environment for assigned airmen, families, and civilian employees.

4.2 RESERVED

4.3 DAMAGES TO GOVERNMENT BUILDINGS, EQUIPMENT, OR VEGETATION

Damages to Government buildings, equipment, or vegetation are addressed in clause 52.237-2 – “Protection of Government Buildings, Equipment, and Vegetation.”

4.4 ENVIRONMENTAL REQUIREMENTS.

In addition to all applicable Federal, State and local environmental codes and regulations, the following specific guidance is provided:

4.4.1 HAZARDOUS MATERIALS

The CO shall approve all hazardous materials brought on-site by the contractor prior to use. The contractor shall obtain approval using the application requirements of the AF Form 3952. Once the process is implemented and contractor is trained, the contractor may submit the AF Form 3952 electronically. The CO has the right to prohibit the use of hazardous materials it deems to be especially hazardous to human health and environment. In the event the CO does not approve a hazardous material for use, the CO may provide the contractor a list of suitable substitutes; however, the contractor shall retain responsibility for finding an acceptable substitute. The contractor shall take appropriate actions to comply with waste minimization and pollution prevention practices and policies.

4.4.2 SPILL CONTROLS

The contractor shall maintain spill control material on hand at all times sufficient to contain a worse case spill, both volume and hazard level.

4.4.3 PESTICIDES

All pesticides must be approved prior to use by the Command Entomologist if not on base approved list (Submit list with intended uses via the CO). The contractor shall provide an inventory of hazardous materials with the applicable Material Safety Data Sheet (MSDS) that will be used to perform the required services. In addition, use reasonable care to avoid releasing hazardous material or hazardous waste, which may cause environmental damage to government structures, public land, water, or other natural resources. If the Contractor's failure to use reasonable care causes damage to any of this property, the Contractor shall replace or repair the damage at no expense to the Government as the CO directs. If the Contractor fails or refuses to make such repair or replacement, the Contractor shall be liable for the cost, which may be deducted from the contract price.

4.4.3.1 PESTICIDE STORAGE AND MIXING

Perform pesticide storage and mixing operations off base.

4.4.3.2 MONTHLY REPORTS

The Contractor shall submit a report to the CO within 10 working days following each month listing all pesticide applications made. Include pesticide name, use concentration, amount applied, date, and detailed location of use. A DD Fm 1532 will be provided on request to facilitate record keeping.

The Contractor is subject to inspection by DOD certified applicators/inspectors as well as State Department of Agriculture Pesticides Division or equivalent agency.

4.4.4 HAZARDOUS MATERIALS INVENTORY

The contractor shall maintain an up-to-date hazardous material inventory with copies of MSDS(s) for all materials used on the job site. The contractor shall maintain a complete copy of all approved MSDS and AF Form 3952s.

4.4.5 HAZARDOUS MATERIALS MANAGEMENT

The contractor shall remove all hazardous materials by the end of each workday. Contractor shall not conduct process treatments (e.g. paint thinner solvent recycling) on base.

4.4.6 FINAL REPORT

The contractor shall submit a final inventory, not later than ten working days following termination/completion of this contract, of all hazardous materials used since the last hazardous usage report to the CO or COR. The final inventory will list all hazardous materials used, total amount of each used, and a description of the disposition of any remaining hazardous material.

4.5 PERMITS, LICENSES AND CERTIFICATIONS

Unless otherwise specified in this contract, obtain necessary permits, licenses, and certifications; give all required notices; and comply with applicable Federal, State, County, and local laws, codes, and regulations in performance of the requirements of this contract. Maintain records of such requirements and make the documentation available to the Government for review. All pesticide application will be made by State or Host Nation certified applicator as prescribed in DoDI 4150.07.

4.6 HOURS OF OPERATION

Perform grounds maintenance services during normal duty hours which are 0600 – 1630, Mondays through Fridays, excluding federal holidays, unless otherwise required in the contract or approved by the CO. There may be situations that require the contractor to work at times other than normal working hours. When the contractor's work schedule conflicts with an Air Force mission requirement, advise the CO and reschedule the work to minimize disruption.

4.7 RECOGNIZED HOLIDAYS.

The following federal holidays will be observed by the contractor except where Service Contract Act specifies differently:

- New Year's Day - 1 January
- Martin Luther King Day - 3rd Monday in January
- Washington's Birthday - 3rd Monday in February
- Memorial Day - last Monday in May
- Juneteenth – 19 June
- Independence Day - 4 July
- Labor Day - 1st Monday in September
- Columbus Day - 2nd Monday in October
- Veteran's Day - 11 November
- Thanksgiving Day - 4th Thursday in November
- Christmas Day - 25 December

If these holidays fall on Saturday, the preceding Friday will be observed. If these holidays fall on Sunday, the following Monday will be observed. If a holiday falls on a scheduled service day, the Contractor will be responsible for rescheduling services for the first day post the holiday observance.

4.7.1 BASE CLOSURES

Work scheduled but not accomplished because of base closure due to weather, exercises, or actual alert, will be accomplished as soon as possible after reopening the base.

4.8 SECURITY REQUIREMENTS

These regulations are available for review in the Contracting Office. Security and base access requirements are contained in clause 5352.242-9000 "Contractor Access to Air Force Installations." Contractor employees will be required to obtain and display identification badges. Anticipate delays in getting commercial vehicles on base and allow time for commercial vehicles to reach their destination by driving designated routes at posted speed limits throughout the base. Procedures for commercial vehicle access to the base are subject to change without prior notice.

4.9 PERFORMANCE OF SERVICE DURING CRISIS OR HEIGHTENED SECURITY

This service is not determined to be essential for performance during crisis according to DODI 3020.37.

4.10 SPECIAL QUALIFICATIONS

The contractor shall provide the name and telephone number of the Contractor's on-site contract manager and alternate responsible for all requirements in the PWS. The contractor's on-site manager must be able to speak and write in the English language. Provide telephone numbers of contractor manager and alternate(s) for after duty hours. The contract manager and alternate(s) must be able to read, write, speak and understand English.

4.11 INTERFACES

Do not unduly interfere with regularly scheduled Government operational activities in the performance of contract requirements. In the event a Government supervisor so requests, temporarily cease work in the area and report the instructions, to include name of the Government person involved, to the CO immediately by the most expedient means. Notify the CO verbally of disputes with customers or other base contractors and follow-up in writing.

4.12 CONTRACTING OFFICER AND CONTRACTING OFFICER REPRESENTATIVE (QUALITY ASSURANCE PERSONNEL)

The Contracting Officer will appoint a primary and alternate representative for management of the day to day activities of the contract. The identity, title, and authority of this representative will be provided in writing to the contractor after contract award.

4.13 WORK CLEARANCE REQUESTS

The contractor shall obtain an approved Work Clearance Request for all work which involves excavation including minor digging. Digging permits are available at Building 690, Civil Engineering Customer Service.

4.14 SAFETY REQUIREMENTS AND REPORTS

The contractor shall perform work in a safe manner as required by OSHA Safety and Health Requirements. Provide a verbal report to the CO as soon as possible of each occurrence of damage to Government property or an accident resulting in death, injury, occupational disease, or adverse environmental impact. Provide a completed copy of required Accident Investigation Reports to the CO within five calendar days of each occurrence.

4.15 SCHEDULES

The contractor shall submit a schedule for all services described in this PWS and Appendices to the CO for review at the post-award conference and at each option year. The schedule shall identify plots, acreages, or base areas and days of the week service will occur. The schedule may be submitted electronically using a file format compatible with Government software programs such as "Microsoft Office", PDF or Google Docs software.

4.15.1 SCHEDULE CHANGES

Occurrence based (non-permanent and no more than once a month) schedule changes due to customer requests or base exercises shall be support by the contractor. The COR will request the changes to the contractor 10 days before the schedule change take place for improved grounds mowing only at no additional cost to the government.

5 APPENDIXES

APPENDIX A – GROUNDS DESCRIPTION/WORKLOAD ESTIMATES

APPENDIX B - AREA MAPS OR SITE PLANS

APPENDIX C – DATA REQUIREMENTS

APPENDIX D – DEFINITIONS

APPENDIX E - RESERVED

**APPENDIX F - IRRIGATION SYSTEM DESCRIPTION AND SYSTEM
MAINTENANCE PROJECTED WORKLOAD DATA**

APPENDIX G – [ADD OTHER APPENDICES AS NEEDED]

APPENDIX A – GROUNDS DESCRIPTION/WORKLOAD ESTIMATES

Estimated Workload Data (Annually)				
		ESTIMATED QUANTITIES		
ITEM	DESCRIPTION	QTY	UNIT	FREQUENCY
1	Improved Grounds	5	Acres	N/A
2	Improved Grounds Weed Control (Hard surfaces - Sidewalks, Parking lot, Driveway, etc.)		SF or Acres	N/A
3	Improved Grounds Edging		LF	N/A
4	Irrigation Maintenance/Operation		Heads and Zones	N/A
5	Debris Removal and Grounds Policing	5	Acres	
6	Pest Control		Acres	
7	Leaf Removal		Acres	0 - 6 times
8	Prune Shrubs and other Plants		EA or LF	N/A
9	Semi- Improved Grounds	3234	Acres	N/A
10	Perimeter Fence Line		LF	N/A
11	BASH		Acres	N/A
12	Unimproved Grounds		Acres	1 time
13	Surface Drainage Ditch Maintenance		LF	N/A
14	Tree Pruning		EA	N/A
15	Emergency Tree Pruning		EA	N/A
16	Tree and Stump Removal		EA	N/A
17	Emergency Tree and Stump Removal		EA	N/A
18	Shrub Removal/Replacement		EA	N/A
19	Snow and Ice Removal (Roads)		Lane Miles	N/A

20	Snow and Ice Removal (Parking Lots)		SY	N/A
21	Snow and Ice Removal (Sidewalks, Walkways, and Entryways)		SY	N/A
22	Snow and Ice Removal (Pedestrian Bridge)		SY	N/A
23	Special Cuts		EA	N/A
24	Plants Trees, Shrubs, Vegetative Beds		EA	N/A

APPENDIX B –AREA MAPS OR SITE PLANS

IMPROVED GROUNDS:

Main Base Buildings 1, 11, 13, 349 – 351, 1315 (5 Acres Total)

SEMI-IMPROVED GROUNDS;

Main Base Eglin: 1230 Acres

Off Base:

C-52 (C2, C3, C4, E1, E2, E3) 1362 Acres

Duke Field 197 Acres

Camp Rudder 117 Acres

C-3 – C-86 136 Acres

C-6 45 Acres

Camp Pinchot 14 Acres

Armament Museum 14 Acres

Jackson Guard 43 Acres

B-88 (Camp Bull Simons) 69 Acres

NAVSCOLEOD C-52 N&W 7 Acres

[INSERT MARKED UP MAPS OR SITE PLANS TO IDENTIFY IMPROVED GROUNDS, SEMI-IMPROVED GROUNDS, UNIMPROVED GROUNDS, AIRFIELD BASH AREAS, AND OTHER AREAS AS NECESSARY. THE MARKED UP AREAS SHOULD BE THE BASIS FOR THE AREAS CONTAINED IN THE WORKLOAD ESTIMATES.]

Improved, Semi-improved and Un-Improved Grounds (____ sheets)

Edging & Trimming (____ Sheets)

Areas Requiring Leaf Removal (____ Sheets)

Vegetative Beds, Inert Beds, and Related Areas (____ Sheets)

Surface Drainage Ditches (____ Sheets)

APPENDIX C – DATA REQUIREMENTS

Provide the data as indicated below to the CO. All reports, submittals, logs, and information provided to the Government shall be electronic and compatible with Microsoft Office, such as Excel, Word, and others. “Compatible” means the document can be opened using the appropriate Microsoft Office component without any discernible effect on the text (e.g., loss of data) or the formatting of the document:

DRAFT

APPENDIX D – DEFINITIONS

1. Scalping – areas where the grass is mowed too close to the ground because of uneven ground underneath. When grass is mowed too close to the ground it frequently appears as an unsightly yellow scar. Typically scalping occurs when mowing on hill sides and around obstacles on uneven terrain.
2. Xeriscaping - a landscaping method that employs drought-resistant plants in an effort to conserve resources, especially water, and reduce yard trimmings. Xeriscaping uses decorative brick, lava rock, mulch and low water vegetation such as bougainvillea, hibiscus, cactus, and evergreen ground covering plants to eliminate the high costs of maintaining 2”-4” grass fields and reduce the cost of watering.
3. Pocket Urban Forests – a landscaping technique of planting indigenous local trees and shrubs in clusters to cut down on large open areas of grass that are regularly maintained. This method would be practical on-bases that receive a large amount of rainfall, and as a result do not irrigate.
4. Seed Head Inhibitor – an agent or combination of agents applied to grass areas prone to the production of seed heads to suppress the seed heads and reduce the frequency of mowing required.
5. Rutting – visible marks left on the grounds from the wheels of mowing and edging equipment.
6. Topping – The reduction of a tree’s size using heading cuts that shorten limbs or branches back to a predetermined crown limit. Topping is not an acceptable pruning practice.
7. Lion’s Tailing – The removal of an excessive number of inner, lateral branches from parent branches. Lion’s tailing is not an acceptable pruning practice.
8. Types of Pruning:
 - a. Cleaning – Selective pruning to remove one or more of the following parts: dead, diseased, and/or broken branches.
 - b. Thinning – Selective pruning to reduce density of live branches.
 - c. Raising – Selective pruning to provide vertical clearance.
 - d. Reduction – Selective pruning to decrease the height and/or spread.
9. Branch Bark Ridge – The raised area of bark in the branch crotch that marks where the branch and parent meet.
10. Caliper – The diameter of a tree measured at a point 6 inches above the ground line if the resulting measurement is no more than 4 inches. If the resulting measurement is more than 4 inches, the measurement is made at a point 12 inches above the ground line.
11. Diameter Breast Height (dbh) – The diameter of a tree measured at a point 4.5 feet above the ground line.

12. Trimming – Cutting of grass and other vegetation around grounds obstacles that prevent mowing.

13. Distinguished Visitor (DV) / Special Cut - Grass cutting in high profile areas of the base such as ceremonial areas, ornamental areas, distinguished visitor routes, quarters, and entrances. A DV cut is generally performed more frequently than other cuttings and the height range specified is usually smaller. Grass clippings are removed from the area and the end result is uniform in appearance, well-manicured, and complete.

DRAFT