

Performance Work Statement (PWS) Maintenance Services for Dülmen Tower Barracks, Germany

10 March 2026

Table of Contents

1.0 INTRODUCTION	1
1.1 Background	1
1.2 Objectives	1
1.3 Climatic Conditions.....	2
1.4 Facility Access.....	2
1.5 Traffic Flow.....	3
1.6 Drainage.....	3
1.7 Restoration of Landscape Damage	3
1.8 Dust Suppression	3
1.9 Utility Location	3
1.10 Excavation Permits.....	3
1.11 Work Clearance.....	3
2.0 REQUIREMENTS.....	3
2.1 Description of Services.....	3
2.1.2 General Information.....	4
2.1.3 Place of Performance and Hours of Operation.	5
2.1.4 Federal Holidays	5
2.1.5 Travel/Temporary Duty.....	7
2.1.6 Emergency Services	7
2.1.7 Contract Administration and Management.....	10
2.1.8 COR/ACOR Functions	11
2.1.9 Quality Control (QC).....	11
2.1.10 Subcontract Management.	12
2.1.11 Contractor Employees.....	12

2.1.12 Business Relations.....	14
2.2 Work Management	14
2.2.1 Coordination.....	14
2.3 As-Builts and Geospatial Information System (GIS).....	Error! Bookmark not defined.
2.3.1 Maintain As-Builts.....	Error! Bookmark not defined.
2.3.2 Real Property Records Updates	Error! Bookmark not defined.
2.3.3 GIS.....	Error! Bookmark not defined.
2.3.4 GIS Support Services	Error! Bookmark not defined.
2.3.5 GIS Files	Error! Bookmark not defined.
2.3.6 Other Documents	Error! Bookmark not defined.
2.4 Historic Property or Archaeological Site.....	Error! Bookmark not defined.
2.4.1 Repair and Replacement.....	Error! Bookmark not defined.
2.5 Special Requirements	21
2.5.1 Security.....	21
2.5.2 Security Training.....	23
2.5.3 Safety.....	24
2.5.4 Training, Physical Requirements, or other Expertise Required.	25
2.5.5 Environmental Requirements.....	25
2.5.6 Contingency Plans.....	26
3.0 PERFORMANCE REQUIREMENTS AND STANDARDS	26
3.1 Performance Task Requirements, Standards and Acceptable Quality Levels (AQLs).....	27
3.2 Quality Assurance	27
4.0 PERFORMANCE REQUIREMENTS SUMMARY (PRS) MATRIX.....	28
5.0 TASKS.....	32
6.0 DELIVERABLES.....	52
7.0 RELATED DOCUMENTS.....	52
7.1 Definitions and Acronyms	52
7.1.1 Definitions	52
7.1.2 Acronyms	62
7.2 Applicable Directives, Publications.	Error! Bookmark not defined.
7.3 Technical Exhibits (TE) and Attachments	Error! Bookmark not defined.
7.4 Government-Furnished Material (GFM)/Property (GFP)/Equipment (GFE).	62
7.4.1 Utilities	Error! Bookmark not defined.
7.5 Contractor-Furnished Material (CFM)/Property (CFP)/Equipment (CFE)	Error! Bookmark not defined.

7.5.1 Contractor-Furnished Material and Responsibilities	Error! Bookmark not defined.
7.5.2 Contractor-Furnished Items	73
7.5.3. Contractor Facilities.....	73
7.6 U.S. Department of Labor (DOL) Wage Determination (WD).....	74

DRAFT

1.0 Introduction. This is a non-personal services contract to provide Preventative and On Demand Facility Maintenance and Repairs. The Government will not exercise any supervision or control over the contract service providers. The Contractor shall perform to the standards specified in this Performance Work Statement (PWS). Contract service providers shall be accountable solely to the Contractor who, in turn is responsible to the Government. (Insert local requirements.) The Contractor shall provide all personnel, equipment, supplies, facilities, transportation, tools, materials, supervision, and other items and non-personal services necessary as defined in this PWS. The Contractor is responsible for providing all parts required for Preventive Maintenance Orders (PMOs) and all repair parts required for Demand Maintenance Orders (DMOs).

1.1 Background. The subject matter services are currently being operated on the Dülmen Tower barracks service contracts, as well as in house labor. The site consists of approximately 428,212 m² or 106 acres (on post: 422,425.55 m² (4,546,950.80 ft²) and rail extension: 5,786.93 m² (62,289.98 ft²) and 20 buildings. The population base consists of approximately 390 military, Government civilians, and Contractor personnel.

1.2 Objectives. The Contractor shall ensure all work accomplished in the performance of this PWS meets all applicable Federal, State, and Local Laws, Regulations, and Directives to include, but not limited to, the publications in Section 7, Related Documents The Contractor shall provide scheduled preventative maintenance and repairs on facilities, systems, and equipment listed in this PWS on a recurring basis. In addition, the Contractor shall perform unscheduled maintenance and repairs, to include purchasing and replacing equipment & systems parts as necessary. The Contractor shall provide and maintain all certification in accordance with (IAW) 2.5.4 and shall be required to perform all tasks as described in this PWS. The Contractor shall compile historical data, prepare required reports, and submit all information as specified by the Deliverables presented in the contract. The Contractor shall ensure all work in support of mission requirements tendered to the Government for acceptance conform to the measurable performance standards of quality, timeliness and quantity specified in the PWS of this contract. The intent is to establish work requirements that are performance-based and results-oriented. The Contractor shall determine the best and most cost-effective ways to fulfill facilities, systems, equipment maintenance and repairs and their component needs, emphasizing innovation and commercial best practices.

1.2.1 The Contractor shall compile historical data, prepare required reports, and submit all information as specified by the Deliverables presented in the contract. The Contractor shall ensure all work in support of mission requirements tendered to the Government for acceptance conform to the measurable performance standards of quality, timeliness, and quantity specified in the PWS of this contract.

The intent is to establish work requirements that are performance-based and results-oriented. The Contractor shall determine the best and most cost-effective ways to fulfill preventative and on demand maintenance services and their component needs, emphasizing innovation and commercial best practices.

The Contractor shall assume total responsibility for all requirements stated herein on the commencement date of the performance period. The Contractor shall perform as specified in this PWS and under monitoring of the COR. The Contractor shall perform all work and assume responsibility for planning, programming, administering, managing, and executing all functions necessary to provide the services specified in this PWS. The Contractor shall have adequate personnel for maintenance of facilities, systems, and equipment and allow for repairs to be carried out on several items of equipment at varying locations simultaneously. The Contractor shall comply with existing applicable laws and regulations including but not limited to DIN (Deutsches Institut fuer Normung), VDE (Verband der Elektrotechnik Elektronik Informationstechnik), VDMA (Verband deutscher Maschinen und Anlagenbau), (EN) 54, DIN VDE 0833, all VDS regulations, environmental laws, and accepted commercial standards and practices. The Contractor shall conduct work in accordance with this PWS and all applicable United States (U.S.), German, and local laws, regulations, standards, provisions, and directives to include applicable publications in Part 6. The Contractor shall ensure that all work meets the level of service, performance standards, or tolerances specified in the PWS or in applicable referenced documents. The Contractor shall perform all related administrative actions required to provide services or perform work such as material requisitioning, quality control (QC), financial control meetings, and correspondence. The Contractor shall maintain accurate and complete records, files, and libraries of documents to include all U.S. German, and local regulations, standards, provisions, codes, laws, technical manuals, and manufacturers' instructions and recommendations that are necessary and related to the functions being performed. The Contractor shall compile historical data, prepare required reports, and submit information as specified by the Deliverable Schedules presented in this PWS. The Contractor's key management shall perform continual management of the functional areas contained in this PWS and shall be the central point of contact (POC) with the Government for performance of all work under the PWS. All reports, inspections and correspondence shall be submitted in the English language.

1.3 Climatic Conditions. The average annual rainfall is 75 cm ; with the wettest months being May through August . The average annual snowfall is 2.6 cm, with snowfall expected during the period of November through March . The average frost-free period (growing season) during the year is about 180 days. The first killing frost may be expected about October , and the last killing frost generally occurs in March. The average annual maximum and minimum temperatures are approximately 19°C and 12°C , respectively. Monthly normal temperatures ranged from a low of 1°C (XX) in the month of January to a high of 22°C degrees in the month of August . Summer temperatures often reach 22°C degrees, while sub-freezing weather is common during the winter months.

1.4 Facility Access. The Contractor shall ensure access to all fire detection and suppression systems in case of emergencies or for other Fire Department purposes. The Contractor shall inform the Fire Department point-of-contact (POC), prior to outages that will impact the function of the system, special problems or circumstances, which require Fire Department inspection. The Fire Department will reset alarm systems to operational status.

1.5 Traffic Flow. The Contractor shall maintain the free flow of traffic during surfaced area maintenance. The Contractor shall notify the Contracting Officer (KO), in writing, a minimum of fourteen (14) calendar days in advance of any scheduled closure of streets. Emergency road closures shall be coordinated with the Contracting Officer Representative (COR) or Alternate Contracting Officer Representative (ACOR).

1.6 Drainage. Maintenance work performed under this contract shall not impede drainage. This includes work done on storm water, plumbing. Freshwater or other system affecting drainage.

1.7 Restoration of Landscape Damage. Trees or other landscape features damaged by the Contractor's operations shall be restored to the original state at no additional cost to the Government.

1.8 Dust Suppression. The Contractor shall perform dust suppression when necessary, during maintenance and repair activities or as directed by the Contracting Officer or COR.

1.9 Utility Location. The Contractor shall perform utility cuts in pavements as required to repair existing utilities after obtaining a digging permit to do so. The Contractor shall locate and stake out underground utility pipes/cables prior to digging operations required by any contract on Garrison property. The Contractor shall be responsible for having the proper equipment to locate all underground utilities. Mechanical digging shall not be permitted within ten (10) feet of identified underground utilities.

1.10 Excavation Permits. All excavation permits shall be initiated through the USAG Benelux DPW and Contracting Officer Representative office in this Contract. The Government requires up to five (5) business days to review and approve excavation permits and provide this approval to the Contractor so the permit can be finalized and returned to the requestor. The Contractor shall keep record of every permit, assign a unique number, provide locator and marking service, coordinate marking with the communications Contractor, etc. and provide status to the Government. The Contractor shall notify the requestor within twenty-four (24) hours of receiving a processed excavation permit package.

1.11 Work Clearance. For work involving digging/excavation operations, the Contractor shall obtain a properly approved digging permit before ground disturbance.

2.0 Requirements.

2.1 Description of Services. The Contractor shall provide scheduled preventative maintenance and repairs on facilities, systems, and equipment listed in this PWS on a recurring basis. In addition, the Contractor shall perform unscheduled maintenance and repairs, to include purchasing and replacing equipment & systems parts as necessary. The Contractor shall provide and maintain all certification in accordance with (IAW) 2.5.4 and shall be required to perform all tasks as described in this PWS. The Contractor shall compile historical data, prepare required reports, and submit all information as specified by the Deliverables presented in the contract. The Contractor shall ensure all work in

support of mission requirements tendered to the Government for acceptance conform to the measurable performance standards of quality, timeliness and quantity specified in the PWS of this contract. The intent is to establish work requirements that are performance-based and results-oriented. The Contractor shall determine the best and most cost-effective ways to fulfill facilities, systems, equipment maintenance and repairs and their component needs, emphasizing innovation and commercial best practices

2.1.1 Non-Personal Services. The personnel rendering the services are not subject; either by the contract's terms or by the manner of its administration, to the supervision and control usually prevailing in relationships between the Government and its employees. Non-personal service contracts are authorized by the Government in accordance with (IAW) Federal Acquisition Regulation (FAR) Subpart 37.104, under general contracting authority, and do not require specific statutory authorization.

2.1.2 General Information.

2.1.2.1 Transition (Phase In/Phase Out). The Contractor shall prepare and submit a transition plan within ten (10) business days after contract award. The transition plan will have a sixty (60) business day transition period that will be implemented by the Contractor and shall state Contractor key personnel on board, to include IT/Network accounts and access with the appropriate Government organizations. The Contractor shall provide sufficient experienced personnel during the phase-in and phase-out period to ensure that the services are maintained at the required level of proficiency. During the phase-in, the Contractor shall observe all operations pertinent to the requirements of the PWS, to include office functions, procedures, operations, repair/maintenance operations, and any other operations as deemed necessary by the Contractor that will enable Contractor personnel to become both knowledgeable in, and familiar with, their assigned areas of responsibility. The Contractor shall commence all operations required by this PWS as of the first day of the contract period. Therefore, on the initial day of performance, the Contractor shall provide a work force which is fully qualified and capable of performing all work required under this contract.

2.1.2.1.1 Phase In/Phase Out for Incumbent Contractor.

If the Contractor is the incumbent Contractor, the phase out/phase in period shall be no more than thirty (30) calendar days and will primarily consist of administrative transition under the new contract number. All documents shall be updated with the new contract number and new dates and submitted for approval. All previous approvals under the old contract are invalid. All documents shall be updated and re-approved.

2.1.2.2 Transition (Phase-Out). Sixty (60) business days prior to contract expiration will constitute the phase-out period. The Contractor shall develop and implement a plan to affect a smooth and orderly transfer of performance responsibility to a potential successor. The initial phase-out plan shall be submitted to the COR for approval no later than six (6) months after the start of the base contract year. The plan shall contain details that include but are not limited to; timelines for events, key personnel involved and interface with the Government and follow-on Contractor. The plan shall fully describe how the Con-

tractor shall approach the following issues: Employee notification; Retention of key personnel; Turn-over of work-in-progress, inventories and transfer of Government furnished property; Removal of Contractor property; Data and information transfer; deletion of password access to Government systems, installation clearance actions including turn-in of windshield decals and controlled access cards (CAC) and any other actions required to ensure continuity of operations. The plan shall also include a joint inventory among the incumbent, the Government, and the successor Contractor; reconciliation of all property accounts and requisitions, turn-in of excess property and cleanup of Contractor work areas.

The Contractor shall correct any damage to Government-Owned Property caused by employee negligence or mistake, intentional or otherwise. During the thirty (30) business day transition period immediately prior to the end of the previous contract, the Contractor shall permit the successor Contractor (and the successor Contractor's employees) to observe and become familiar with any and all operations under the contract. The Contractor shall not defer any needed repairs or maintenance for the purpose of transferring responsibility to the successor Contractor. The Contractor shall fully cooperate with the successor Contractor and the Government so as not to interfere with their work or duties. The Contractor shall provide reasonable assistance to the Government's contract solicitation process such as verifying workload data and other factual information to be included in a new solicitation and providing access to the workplace for site visit(s) of prospective offerors.

2.1.3 Place of Performance and Hours of Operation.

2.1.3.1 Place of Performance. The work to be performed under this contract will be performed at Dülmen Tower Barracks, Germany. A map of (Location) is located at **Attachment 3**.

2.1.3.2 Hours of Operation. The Government's regular (normal) hours are from 0700 – 1600 hours, excluding Federal holidays, Host nation holidays, or when the Government facility is closed due to local or national emergencies, administrative closings, or similar Government directed facility closings. The Contractor shall maintain an adequate workforce for the uninterrupted performance of all tasks defined within this PWS when the Government facility is not closed for the above reasons.

2.1.4 Federal Holidays and Host Nation Holidays

The Contractor's performance shall not be required on the Federal public holidays listed below, unless there is a requirement to respond to a Priority 1, Emergency. Holidays occurring on weekends will be observed as directed by the Federal calendar (5 United States Code (U.S.C) § 6103, Government Organization and Employees, Holidays).

NAME OF AMERICAN HOLIDAY	DATE
New Year Day	January 1st

Martin Luther King Memorial Day	3rd Monday in January
President Day	3rd Monday in February
Juneteenth	June 19th
Memorial Day	Last Monday in May
Independence Day	July 4th
Labor Day	1st Monday in September
Columbus Day	2nd Monday in October
Veteran's Day	November 11th
Thanksgiving Day	4th Thursday in November
Christmas Day	December 25th

NOTE: When a holiday falls on a Sunday, the following Monday will be observed as a holiday, and, when a holiday falls on a Friday or Saturday, the preceding Thursday is observed as a holiday by U.S. Government Agencies. Federal holidays also include any Presidential or Congressionally designated days off other than the holidays listed above.

NAME OF GERMAN HOLIDAY	DATE
New Year Day	January 1st
Good Friday	Varies Annually
Easter Monday	Varies Annually
Labor Day	May 1 st
Ascension Day	Varies Annually
Whit Monday	Varies Annually
Day of German Unity	October 3rd
All Saints Day	November 1st
1 st Christmas Day	December 25th
Boxing Day	December 26th

2.1.4.1 The Contractor shall provide personnel support within 2 hours of notification outside the normal hours of operation as required, including holidays, to support the Directorate of Public Works (DPW) mission. Prior to performance of services outside the locally established hours of operation, the Contractor shall request and obtain, in writing, approval from the KO. The Project Manager shall be available after normal hours to serve as the central point of contact for Contractor operations. Contractor personnel shall not be scheduled for overtime work.

2.1.4.2 Installation Closures.

When an unforeseen Installation closure occurs on a regularly scheduled day of work, the Contractor shall reschedule the work to be performed the next business day following the closure unless the following day is a Saturday, Sunday, a recognized Federal Holiday, and when routine work is not scheduled for that day.

2.1.4.3 Inclement Weather Delay. If the Contractor determines unsafe weather conditions for continued operations, then the Contractor shall notify the KO if inclement weather suspends operations within 2 hours. The Contractor shall resume operations with KO/COR approval.

2.1.4.4 Curtailment of Operations. When operations are curtailed due to manmade or natural conditions on a working day, it may be necessary for the KO/COR to interrupt that day's work under this contract. The Contractor shall reschedule the work on any day acceptable to the Government. If the KO agrees, the Contractor may continue the work as scheduled. The KO will provide verbal announcements of immediate curtailment of operations to the Contractor.

2.1.4.5 Days of No Scheduled Activities (DONSA). The Installation has historically granted Military personnel (Enlisted and Officers) DONSA, for example, the Friday after Thanksgiving, in addition to the listed Federal Holidays above.

- DONSA are not considered a day of excused absence for the Government civilian work force or Contractor employees.
- If a DONSA affects scheduled contract work or access to facilities, the work in affected facilities may be rescheduled to compensate for the DONSA.
- However, announced DONSA or exodus of Military personnel may provide the Contractor with an opportunity for unrestricted access to facilities and areas or uninterrupted performance of work (i.e., training facility and area maintenance and supply inventories).

The Contractor shall vary work schedules to take full advantage of such opportunities by planning maintenance that is better accomplished when personnel are not using facilities during those times.

2.1.5 Travel/Temporary Duty. N/A

2.1.6 Emergency Services.

2.1.6.1 Emergency Medical Treatment. The Contractor or their employees shall immediately notify their supervisor of any accident requiring emergency medical treatment. The Contractor shall notify the KO or COR/ACOR immediately, not later than (NLT) two (2) hours of the incident. The Contractor shall be responsible for the emergency medical treatment services for Contractor personnel. The Government has no capability to render care on an emergency basis, medical services for injuries incurred while an employee is performing under the contract. The nearest emergency facility to this site is located at: Franz-Hospital Dülmen (Christophorus-Kliniken GmbH) Vollenstraße 10, 48249 Dülmen.

2.1.6.2 Accident Reporting. The Contractor shall comply with FAR 52.236-13, Accident Prevention (November 1991), the references contained therein (e.g. U.S. Army

Corps of Engineers Safety and Health Requirements Manual (EM 385-1-1)), and applicable Host Nation Safety Laws and Regulations. The requirements under FAR 52.236-13 and specifically of the EM 385-1-1 include, but are not limited to the following:

(a) Before initiation of work at the job site, an Accident Prevention Plan, shall be written by the Contractor for the specific work and hazards of the contract and implementing in detail the pertinent requirements of EM 385-1-1; will be reviewed for acceptance by designated Government personnel (**Deliverable #6**). Specific requirements for development of the Accident Prevention Plan are found in 01.A and Appendix A of EM 385-1-1. EM 385-1-1 is available online at www.usace.army.mil.

(b) Before beginning each activity involving a type of work presenting hazards not experienced in previous project operations or where a new work crew or subcontractor is to perform work, activity hazard analysis (AHA) shall be prepared by the Contractor performing the work activity (See paragraph 01.a.09 of EM 385-1-1).

(c) The Contractor shall require subcontractors to submit their plan of operations showing methods they propose to use in accomplishing major phases of work.

(d) The Contractor shall discuss the plans in conferences convened by the Contracting Officer prior to starting work on each major phase of operation. Plans shall include all pertinent information such as layout of haul roads, access roads, storage areas, electrical distribution lines, methods of providing minimum exposure to overhead loads, and methods of access to work areas. The plan for accomplishing the initial work phase shall be submitted within fifteen (15) calendar days after award of the contract. Plans for subsequent major phases of work shall be submitted no later than fifteen (15) calendar days prior to initiation of work on each major phase.

(e) In all areas where operation, demolition, alteration, building, or similar related activities take place, the Contractor shall have the following minimum personal protective clothing and equipment requirements in place for any person working on or visiting the site:

- (i) Short sleeve shirt.
- (ii) Long trousers.
- (iii) Steel-toed safety boots.
- (iv) Hard hat.

2.1.6.2.1 In addition to other requirements for accident prevention specified in this contract, the Contractor shall comply with all Federal and State requirements governing safety and health protection on operation sites and other applicable occupational safety codes. In particular, within the requirements of the German Safety and Health Protection Regulation for operation sites, Baustellenverordnung (BaustellV) (current version in effect), the Contractor shall coordinate all work at the site, including development of plans and providing advance notices. The Contractor shall indicate its plan for compliance considering conditions of the work described by the design, technical

proposal, operational activities of the Government or others in the area of the work, identification of the coordinator, and implementation of all other accident prevention provisions of this contract. For the compliance with host nation laws and regulations, the Contractor shall comply with the non-exclusive list of duties described in this paragraph. If the Contractor determines that additional activities are required to fully comply, the Contractor shall ensure that compliance with the laws is complete. The duties include:

(a) Conditions of operational activities to be considered include but are not limited to:

(i) For all operation activities meeting the following criteria: the work is scheduled to last longer than 30 working days and more than 20 workers are occupied simultaneously, or the volume of work is scheduled to exceed 500 person days, or the work presents particular tasks, e.g. excavations deeper than 5 meters, falls from a height of greater than 7 meters, exposures to hazardous chemical or biological substances, work at less than 5 meters from high voltage lines, underground earth works or tunnels, danger of drowning, diving, use of compressed air, work with ionizing radiation, explosives, or work involving assembly or dismantling of heavy prefabricated components (10 tons or greater).

(b) If the Contractor determines that the BaustellV, dated 10 June 1998, applies, the Contractor shall prepare a Safety and Health Protection Plan (SIGE) as required under that regulation. The SIGE shall be submitted two weeks prior to mobilization. In addition, the Contractor shall appoint a qualified Safety Coordinator who will ensure that safety measures are implemented during operation. The Safety Coordinator must meet minimum training and experience requirements required under Host Nation laws.

(c) The SIGE will be written in a comprehensive form and explained in language the workers understand and shall contain the following minimum information:

(i) Maintenance of tools and equipment.

(ii) Provisions for the storage and disposal of materials and waste, particular hazardous materials and substances.

(iii) Modifying performance periods for such work, taking into consideration the site conditions.

(iv) Organizing cooperation between different employers and Contractors without employees.

(v) Interaction between work at the site and other operational activities in the area, on which or near which the first identified work will be performed, and taking into consideration the instructions and advice of the coordinator as well as safety and health plans.

2.1.6.2.1 A mishap is any unplanned, undesired event that occurs during the course of work being performed. The term “mishap” includes accidents, incidents and near misses. The Contractor shall notify the COR of any mishap via verbal communications, text or email immediately. The Contractor shall complete and provide mishap notifications required by host nation authorities and will provide completed ENG Form 3394 to the Contracting Officer via the COR within 24 hours (**Deliverable #7**) after notification from the affected employee. ENG Form 3394 is available at the following website:

https://www.swf.usace.army.mil/Portals/47/docs/Safety/Eng_Form_3394_2021Aug_1.pdf?ver=SwGJnG_w6HYlcXNTuS2U5Q%3D%3D

2.1.7 Contract Administration and Management.

2.1.7.1 Post Award Conference/Performance Evaluation Meetings. The Contractor shall attend the post award conference convened by the contracting activity or contract administration office IAW FAR Subpart 42.5, Post-award Orientation. The KO and COR/ACOR will meet quarterly with the Contractor to review the Contractor's performance. Written minutes of meetings will be recorded by the Government/Contractor and signed by both the Project Manager and the KO. The written minutes will be distributed within five (5) calendar days after the meeting. If the Contractor does not concur with any portion of the minutes, recorded by the Government, the non-concurrence shall be provided in writing to the KO within two (2) calendar days following receipt of the minutes (**Deliverable #18**).

2.1.7.2 Notwithstanding the Contractor's responsibility for total management during the performance of this contract, the administration of the contract requires maximum coordination and cooperation between the Government and the Contractor.

2.1.7.3 The following provides the roles and their respective authority during the performance of the contract:

2.1.7.3.1 Contracting Officer (KO). The KO is the only person authorized to direct changes in any of the requirements under this contract, and, notwithstanding any provisions contained elsewhere in this contract, said authority remains solely with the KO. In the event the Contractor makes any change at the direction of any person other than the KO, the change shall be considered to have been made without authority and solely at the risk of the Contractor. All contract administration will be affected by the KO. Communications pertaining to contractual administrative matters shall be addressed to the KO. No changes in or deviation from the terms and conditions shall be affected, without a written modification to the contract, executed by the KO authorizing such changes. The KO will approve all submittals and plans required in this PWS.

2.1.7.3.2 Contracting Officer's Representative (COR). The KO will appoint a COR during the performance of this contract. Additional Government personnel may be assigned to assist in contract oversight IAW AR 70-13, *Management and Oversight of Service Acquisitions*. Other surveillance personnel may be designated as COR or Alternate Contracting Officer's Representative (ACOR), and shall be trained and appointed IAW DoDI 5000.72, *DoD Standard for Contracting Officer's Representative (COR) Certification* and DFARS 201.602-2. The Alternate Contracting Officer Representative (ACOR) will serve as on-site representatives of the COR in performance of actual contract surveillance, if they meet all COR training, experience requirements, and are appointed by the KO as an ACOR. The COR/ACOR will provide assistance in identification and resolution of prob-

lems, conflicts in priority, subtask requirement definitions, and other operations type problems. The COR/ACOR will perform IAW the responsibilities and duties identified in the appointment letter.

2.1.7.3.2.1 COR Authority. A letter of designation will be issued to the COR/ACOR by the KO. A copy of the letter will be sent to the Contractor. The letter of designation states the responsibilities and limitations of the COR/ACOR, especially with regard to changes in cost, price estimates, or changes in delivery dates. The COR/ACOR is not authorized to change any of the terms and conditions with regard to cost, quantity, or schedule of the resulting order.

2.1.7.3.3. The Contractor shall not in any way represent the United States (U.S.) Government, or that it has the authority to contract or procure supplies for the account of the United States of America (USA).

2.1.8 COR/ACOR Functions. The COR/ACOR monitors all technical aspects of the contract and assists in contract administration. The COR/ACOR is authorized to perform the following functions: assure the Contractor performs the technical requirements of the contract; perform inspections necessary in connection with contract performance; maintain written and oral communications with the Contractor concerning technical aspects of the contract; issue written interpretations of technical requirements; monitor, document, and report Contractor's performance and notify both the KO and Contractor of any deficiencies; coordinate availability of Government-Furnished Property, and coordinate site entry of Contractor personnel.

2.1.9 Quality Control (QC). . The Contractor shall develop and maintain a QCP to ensure services are performed IAW this PWS. The Contractor shall develop and implement procedures to identify, prevent, and ensure non-recurrence of defective services. The Contractor's QCP is the means by which it assures that the work provided complies with the requirements of the contract.

The Contractor's Proposed QCP shall be submitted to the Contracting Officer (KO) through the Contracting Officer's Representative (COR) for review within *ten (10) days* after date of contract award (**Deliverable #1**)

The Government will review and either notify the Contractor in writing of acceptance of the plan or return their comments to the Contractor within *ten days*. If the Government has provided comments, the Contractor shall then have *three (3) days* to submit a Final QCP. After receipt of the Final QCP, the Contractor may receive the Contracting Officer's acceptance in writing. Any proposed changes to the accepted QCP are required to be resubmitted for acceptance by the Contracting Officer no later than *thirty 30 days* prior to the anticipated change and before implementation by the Contractor. The timeline noted above will apply for review and acceptance for proposed changes. At a minimum, the QCP must include and answer the following to be acceptable:

- a. A chart showing the organizational structure and lines of authority, the names, qualifications, duties, responsibilities, and classification of each member of the Contractor's Quality Control Team.
- b. How will the Contractor monitor work to ensure that performance complies with all deliverables (etc. timelines, deadlines, and goals)?
- c. How will the Contractor monitor work to ensure that performance complies with all specifications and requirements of the contract, including clauses?
- d. How will the Contractor monitor and ensure staff qualifications remain current and valid including DOCPER processes/approvals throughout contract performance?
- e. How will the Contractor ensure all keys issued will remain controlled items (Paragraph 1.7 Key Control)?
- f. How will the Contractor inventory and track maintenance of all Government Provided Equipment / Materials?
- g. How will the Contractor identify, investigate, and correct any non-conforming performance and prevent similar deficiencies in the future?
- h. How will the Contractor file and save all Quality Control related documents for the life of the contract plus 5 years?

2.1.9.1 The Contractor shall inform the COR of issues or potential issues that might affect the performance within *four (4) hours* of identifying those issues. Verbal reports shall be followed up by written reports within *one (1) day*. **(Deliverable # 2)**

2.1.10 Subcontract Management. N/A

2.1.11 Contractor Employees.

2.1.11.1 Key Personnel. The following personnel are considered key personnel by the Government: Contract Manager/Alternate Contract Manager. The Contractor shall provide a Contract Manager who shall be responsible for the performance of the work. The name of this person and an Alternate Contract Manager, who shall act for the Contractor when the Contract Manager is absent, along with a Curriculum Vitae (CV) for each of these individuals, shall be provided in writing to the Contracting Officer no later than no later than five (5) days after contract award **(Deliverable #7)**. The Contract Manager and Alternate Contract Manager shall have full authority to act for the Contractor on all contract matters relating to daily operation of this contract. The Contract Manager or Alternate Contract Manager shall be available between 0700-1600 (Monday through Friday in accordance with paragraph 1.5.4.3, and shall provide an after-hours contact number for emergency responses identified in paragraph 5.2.2. Qualifications for all key personnel are listed below:

2.1.11.1.1 Contract Manager and Alternate Contract Manager: The Contract Manager and Alternate Contract Manager shall be able to read, write, and speak, the English language. In addition, they shall have within the past ten (10) years, three (3) years' experience working as a Contract / Project manager consisting of a minimum of two (2) years manager and/or supervisory experience in managing facility/equipment maintenance and repair contracts The Contract Manager position shall at no time be vacant. The Contract

Manager shall be available between 0700 - 1600 hours, Monday through Friday except Federal holidays or when the Government facility is closed for administrative reasons. The Contract Manager and any individuals designated as key personnel shall be able to understand, speak, read, and write the English language.

2.1.11.1.2 Special Certifications (Contractor/Subcontractor firm and employees): The Contractor/subcontractor firm and employees shall be fully certified, trained and meet all German standards pertaining to facilities, equipment, maintenance and repairs. The Contract Manager shall ensure all technicians are certified in their respective areas of responsibilities i.e. (electricians, plumbers, roofers, carpentry, mechanical, painters, masonry, structural, etc.) IAW all applicable German laws and regulations. All contractor/subcontractor personnel performing the required services shall possess at least the below listed valid certifications, or equivalent valid certifications approved by the designated German Authority (as applicable).

2.1.11.1.2.1 For contractor and/or subcontractor employees: Master (Meister) in the category of the applicable "Tradesman" certification field. The certifications required for each specific task of this contract identified in the Part 5 of the PWS are required prior to work start. The Technicians shall possess working knowledge of the English language or the primary contractor shall provide a translator.

2.1.11.1.2.2 The Contract Manager/Alternate shall validate contractors/subcontractors are registered within the Head Quarters (HQ) Chamber of Crafts to meet the applicable "Meister" certifications requirements IAW the German legislation – The Trade and Crafts Code (Handwerksordnung) and maintain all required certificates required to perform tasks outlined in this PWS, and provide them to the Contracting Officer upon request.

2.1.11.1.3 GFEBS Certification. N/A

2.1.11.1.4 Common Access Card (CAC). N/A

2.1.11.1.5 U.S. Residency. N/A

2.1.11.1.6 Qualification Standards. The Contractor shall inspect, repair, and maintain systems and components associated with facilities listed in real property records as required throughout this contract utilizing properly trained, skilled, and qualified employees or Sub-contractor personnel.

2.1.11.1.7 Contractor Identification. The Contractor shall ensure all personnel be identified as a Contractor to distinguish themselves (e.g., badge, company logo, or uniform) from Government employees. The Contractor shall ensure all correspondence and reports produced are marked as Contractor products or that Contractor participation is disclosed.

2.1.11.1.8 Standards of Conduct. Contractor personnel's conduct shall not reflect discredit upon the Government. The Contractor shall ensure all personnel present a professional appearance while working on the Government Installation. The Contractor's employees shall observe and comply with all local policies and procedures concerning fire, safety, environmental protection, sanitation, security, and possession of firearms or other lethal or illegal weapons or substance. The Contractor shall ensure all Contractor employees, providing services under this contract, conduct themselves and perform services in a professional, safe, and responsible manner. The Contractor shall remove, from the job site, any employee for reasons of misconduct or security. The Contractor shall ensure employee conduct complies with 41 USC 423, *Procurement Integrity*. The Contractor shall also ensure that no Contractor employees conduct political related activities or events on the Installation. The removal of such a person shall not relieve the Contractor of the requirement to provide personnel to perform adequate and timely service.

2.1.11.1.9 Contractor Hiring Restrictions. The Contractor shall not hire or sub-contract with off duty or former Government employees whose employment would result in a conflict with Joint Ethics Regulation (JER) DoD 5500.07-R.

2.1.12 Business Relations. The Contractor shall successfully integrate and coordinate all activity needed to execute the requirement of this PWS. The Contractor shall manage the timeliness, completeness, and quality of problem identification to a degree acceptable to the Government. The Contractor shall provide to the COR/ACOR corrective action plans, timely identification of issues, and effective management of Subcontractors within 5 days or at a mutually agreed upon date. The Contractor shall ensure customer satisfaction and professional and ethical behavior of all Contractor personnel.

2.1.13 Manual Operations. N/A

2.2 Work Management.

2.2.1 Coordination. The Contractor shall schedule and coordinate with the COR/ACOR to minimize disruptions to the facility mission. All correspondence shall be submitted within the established suspense dates. All extensions, releases, or other relief of suspense requirements shall be obtained from the originating office by the Contractor.

2.2.2 General Fund Enterprise Business System (GFEBS): N/A

2.2.2.1 Army Maintenance Application (ArMA): N/A

2.2.2.1.1 Contingency Plan: N/A

2.2.2.1.2 Transition (Phase-in) Plan: The Contractor shall include in the Transition (Phase-in) Plan in the transition of the operations.

2.2.2.1.3 ArMA and GFEBS: N/A

2.2.2.1.4 Duplicate Orders. N/A

2.2.3 Demand Maintenance Orders (DMOs). Demand Maintenance Order (DMO): Non-recurring maintenance or unscheduled repair. Work required to preserve and sustain a real property facility or its components due to unforeseen occurrences. The work is corrective in nature and not generally used for recurring tasks. Unscheduled maintenance is performed through the issuance of DMO. The purpose of a DMO is to provide the Government with a means of remedying unplanned / unscheduled work occurring outside of the normal recurring work. The Contractor and Government shall utilize DMOs to accomplish all unplanned / unscheduled work at the discretion of the COR. The Government shall combine multiple repair requirements received for the same trade in the same building or structure at the same time into one DMO, as long as the hourly threshold is not exceeded. A DMO may involve multiple crafts such as both electrical and carpentry work and more than one related task at a common work site.

2.2.3.1 Upon receipt of a DMO, the Contractor shall provide an informal estimate of labor work-hours and materials cost of the repair prior to starting work. If the estimated labor is expected to exceed 32 onsite work-hours, completion of the repair must be approved, in writing, by DPW. If a DMO is expected to exceed 32 hours of labor the contractor shall notify the COR/KO and not proceed until further guidance is given.

2.2.3.2 Prior to replacing any part the Contractor, provide a full estimate of repair/replacement for consideration prior beginning any work. Individual parts costing over €2,400 to repair/replace must be completed by obtaining at least three (3) quotes. These quotes will be provided to the Contracting Officer via the COR, commencement of work is subject to approval by the Contracting Officer prior to beginning work. **(Deliverable #13).**

2.2.3.1 DMO Performance Requirements. There are 3 priorities for DMOs. They are classified in AR 420-1 as Emergency, Urgent, or Routine. The Government will determine DMO types and priorities according to set criteria and reserves the right to reclassify DMO priorities as it deems necessary. When notified by the COR, the contractor shall respond to DMOs and complete maintenance repairs in accordance with the categorized DMO:

CATEGORY	DEFINITION	EXAMPLE	TIMELINE REQUIREMENT
Routine / Priority 3	For work that does not meet the criteria of emergency/critical or urgent priority. They are utilized to correct situations that are productivity inhibitors that, if left uncorrected, will cause measurable discomfort or inconvenience to the customer or	Examples include, but are not limited to: dripping faucets, cracked window glass, repairs to door and window hardware and screening, replacement of broken or missing tiles, minor roof leaks, minor repairs to	These DMOs are to be completed within thirty (30) calendar days of receipt.

	waste resources or create the need for additional minor repairs.	mechanical equipment, air conditioning, etc.	
Urgent / Priority 2	Failure in service does not immediately endanger personnel or property, but would soon inconvenience or affect the security, health, or well-being of personnel.	Examples include, but are not limited to: unstopping a sink drain where there are backup sinks, replacing overhead office lighting that significantly inhibits productivity, and unscheduled fuel deliveries, etc.	These DMOs are to be completed within seven (7) calendar days from receipt, unless reduced to a Priority 3.
Emergency/Critical / Priority 1	Immediate action is required to eliminate life threatening or serious injury hazards to personnel	Examples include, but are not limited to: Gas, oil, and steam leaks, water or sewage line breaks, Building floods, Safe and Secure Alarms/Doors, Sewage backing up into building, Total power outage in a building, Downed high voltage power line, Loss of heat during periods of cold weather, Locksmithing, damages from Natural Disasters.	Responded to as soon as possible and NLT one (1) hour after the request. Emergency/Critical DMOs are completed within twenty-four (24) hours of the request, unless the urgency of the work has been reduced to a Priority 2 or 3.

2.2.3.1 DMO Desk. N/A

2.2.3.2 DMO Call Receipt and Entry. N/A

2.2.3.3 GFEBS and/or ArMA Case Number. N/A

2.2.3.4 Completed Work. N/A.

2.2.4 Preventive Maintenance Orders (PMOs). Routine, recurring sustainment work performed on all real property facilities (RPF). PM is systematic inspection, testing, cleaning, adjusting, realignment, lubrication/greasing of all parts, calibration, tightening screws and bolts, refilling of all refrigerants and lubricants, replacing parts such as bearings, belts,

gauges, bulbs, servicing of equipment, utility plants and systems, buildings, structures, and grounds facilities performed to detect and correct incipient failures and accomplishing minor maintenance in accordance with manufacturer's instructions, accepted industry standards and the PWS. Preventative maintenance (PM) is executed by a Preventive Maintenance Order (PMO) in support of a preventive maintenance plan intended to keep affected systems, facilities and equipment in good working order.

2.2.4.1 PM Plan: The Contractor, in coordination with the Government, shall develop a comprehensive PM plan for facilities, property, installed equipment, infrastructure and utilities identified in this PWS, IAW AR 420-1 and U.S. Army Corps of Engineers, Technical Manual (TM) 5-610, Preventive Maintenance, Facilities Engineering Buildings and Structures (1979). The contractor shall submit a PM Plan electronically to the COR with a proposed plan for equipment covered under the contract for the entire performance period no later than twenty (20) days after contract performance date. Within ten (10) days after submission of the proposed schedule, the COR shall approve or disapprove the proposed schedule. If disapproved, the Contractor shall submit the corrected schedule to the COR within five (5) days. **(Deliverable #10)**.

When applicable, the Contractor shall update the schedule to reflect additions, deletions and other changes. The Contractor shall not deviate from the approved maintenance schedule without prior coordination with the COR. The COR shall coordinate maintenance deadlines with the end user. Additionally, the Contractor shall provide the COR with an updated PM schedule, including actual work performed, within the first five (5) days of each month. The updated schedule shall be subject to COR approval in the same manner as the original schedule **(Deliverable #10)**.

Equipment requiring preventive maintenance is listed in **Attachment 1**.

Preventive maintenance includes all cost elements (e.g., labor, materials and disposal of materials, etc.). Preventive maintenance shall include the cost for individual parts which do not exceed €150.00 each. Each individual part or individual piece of equipment installed under this maintenance contract (which are reasonably expected to be replaced or consumed during Preventative Maintenance cycles) with a cost less than € 150.00 shall be the responsibility of the contractor. Parts that are discovered damaged and/or defective that are not reasonably expected to be part of the normal Preventative Maintenance replacement schedule will be invoiced directly via DMO upon approval from the COR. The established cost of parts shall be at actual cost invoiced to the contractor including cash, trade discounts, or rebates. The contractor shall stop work immediately and notify the COR if a part or piece of equipment costing exceeding € 150.00 requires replacement or if further repair is required to avoid more serious and costly problems. The contractor shall then provide a scope of work, a list of part(s) to be replaced, and the estimated cost, upon approval, a DMO can be issued and performed.

If PM cannot be performed because equipment is not accessible or has been removed the Contractor shall notify the COR immediately in writing prior to but not later than the day of the scheduled services. **(Deliverable #11)**

2.2.4.2 PM Documentation: If the Contractor detects a deficiency or malfunction of the equipment during PM and repairs are required, the Contractor shall document the finding on the PM work certificate and notify the COR immediately. The COR will determine whether a Demand Maintenance Order (DMO) will be initiated. **(Deliverable #12).**

At a minimum, the work certificate shall contain the following information:

- a. Date, time, and printed and signed name of the individual who performed the PM work on item (Equipment Number, Name, Location according to Inventory List).
- b. A list of all materials and spare parts used for the required repairs.
- c. Cost estimates for any required materials and spare parts for repairs.
- d. Applicable certificates of inspection (example TÜV - Technischer Überwachungsverein certificates) **(Deliverable #16)**

2.2.4.3 Approved PM Schedule. The Contractor shall strictly adhere to the scheduled PM dates to facilitate verification of work by the COR/ACOR. If the Contractor finds it necessary to reschedule a PM, a written request shall be made to the COR/ACOR detailing the reasons for the proposed change at least five (5) working days prior to the originally scheduled PM date. No scheduled PM dates shall be changed without the prior written approval of the COR/ACOR.

2.2.4.4 PMO Stickers/Log. Upon completion of the PM inspection, the Contractor shall attach a sticker to the equipment item (or in the immediate vicinity thereof) indicating the equipment MCD number, the date of maintenance, and the initials and identification number of the Contractor employee who performed the work. PM will not be considered performed unless the sticker is current and affixed. In instances where a PMO sticker is not practicable, then the Contractor may elect to maintain a current PMO log in lieu of a sticker.

2.2.4.5 Warranty Program. The Contractor shall establish and maintain a Warranty Program to warrant all equipment, parts, components, where the manufacturers provide a warranty and shall be exercised for the duration of this contract. The Contractor shall provide the COR/ACOR & PM Coordinator with a copy of the warranty and manual for all equipment in an excel sheet format. The warranty excel sheet should be updated as warranty information changes for the equipment. The warranty information in the excel sheet should match exactly what is in GFEBs. The Contractor shall provide a plan for managing warranties with the technical proposal. All warranty data shall be returned to the Government at contract completion. When Contractor personnel determine that a warranted item not installed by the Contractor requires service, the Contractor shall notify the COR in writing no later than 0900 the next working day or give telephone notification within fifteen (15) minutes of detection if the deficiency threatens damage to personnel or property. The COR/ACOR will direct the Contractor to: (1) repair the deficiency if potential damage may

result from deferring repairs; or (2) clean the work area and stop work. The Contractor shall not receive payment for work not authorized by the COR/ACOR which is performed on warranted equipment, unless the COR/ACOR concurs that such work was a legitimate response to a true emergency condition.

2.2.4.6 Operation and Maintenance (O&M) Manual Digital Library. N/A

2.2.5 Operations Work Orders (OWOs). N/A

2.2.6 Project Work Orders (PWOs). N/A

2.2.7 Warranty Program. The contractor will provide the COR all warranty records to identify the item, the nature and expiration date of the warranty, and the name and location of the firm to contact about entitlement under the warranty. The Contractor shall update ~~within GFEBS~~ warranty records on any items of equipment or repair items to which the Government will take title, or which shall be installed on Government property.

2.2.7.1 Warranty Enforcement Manager. N/A

2.2.7.2 Warranty Management. N/A

2.2.7.3 Routing of Warranty DMOs. N/A

2.2.7.4 Warranty Records. The Contractor shall comply with standard Army execution and warranty claim action reporting programs as defined in AR 700-139.

2.2.7.5 Exceptions. The existence of a warranty does not alleviate the Contractor of his responsibility to perform work needed to prevent potential damage to personnel and property or to prevent unnecessary shutdown of facilities and functions.

2.2.7.6 Technical Document Library Operation. The Contractor shall store, maintain, and make technical documents available to all Government personnel and others approved by DPW upon request. If electronic versions are available, the Contractor shall provide these via e-mail or other electronic media. If no electronic copy is available, the hardcopies will be scanned and sent to the Government personnel and others approved by DPW. Contractor shall obtain and record adequate contact information from the borrower, and the documents will be checked out for no longer than five (5) days. In the case where only one hardcopy exists, and the document cannot be scanned; the documents shall be made available for reference or for copies. The Contractor shall maintain all warranty documents in an electronic data base.

2.2.8. Maintenance/Repair Reports and Invoicing: Contractor shall manage all assigned projects from initial receipt until project completion. The Contractor shall ensure all projects are completed IAW the PWS and Contractor's approved schedule. The Contractor shall keep records and prepare reports for all services performed under this contract.

2.2.8.1 The Contractor shall submit all invoices (electronically via WAWF) within 30 days from completion of work (**Deliverable #14**). At minimum all invoices will contain the following information:

1. Contract Number/Task Order.
2. Call/Job Number.
3. Type of system, Manufacturing Number, Inventory Number, Serial Number.
4. Location.
5. Description of Malfunction.
6. Date, start time, and completion time of services.
7. Name(s) of individual(s) performing the services.
8. Type and amount of required material and replacement parts.
9. Information or recommendations pertaining to the condition or function of the system.
10. Amount of labor hours (signed time sheets).
11. Detailed receipts for expenses and/or invoices from subcontractor reflecting above requirements (As Applicable)

2.2.8.2 When requested by the COR or KO, the contractor shall prepare and provide reports to include but not limited to: Parts Consumption, Labor Hours, Invoice Costs, Waste Removal, Technical Data, Maintenance Schedules etc. When requested reports will be provided to the COR/KO within five (5) days. (**Deliverable #15**).

2.3 As-Builts.

2.3.1 Maintain As-Builts. The Contractor shall maintain as-built drawings. The Contractor shall be provided one (1) hard copy for the detailed Installation maps in **Attachment 4**. The maps to be provided are the following: Heating & Cooling System, Installation Grounds, and Nature Trails System. Utility repairs, component replacements, modifications, alterations, and additions to all systems and components shall be electronically redlined as well as on the hard copy maps upon completion of work. The Contractor shall redline annotate all components replaced during the period of the contract and annotate all items removed from service.

2.3.1.1 Support. Hard copy markups and electronic redlines shall be delivered to the COR/ACOR at the completion of each major project as identified by the COR/ACOR or, at a minimum, at the end of each contract-year quarterly cycle. The Contractor shall validate all maps for accuracy and content.

2.3.2 Real Property Records Updates. When the Contractor is provided plans or drawings as part of a DMO or PWO, the Contractor shall be responsible for providing two (2) copies of marked up red lines drawings reflecting the changes, to the COR/ACOR. The Contractor shall submit these drawings prior to closing out the DMO or PWO. All electronic data and hard copy maps remain the property of the DPW and shall be turned over to the COR/ACOR upon completion of the contract.

2.4 Historic Property or Archaeological Site. Historic properties and archaeological sites

are subject to the provisions of the *National Historic Preservation Act* (NHPA). The Contractor shall maintain the historic properties on the Installation IAW the NHPA, 54 United States Code (U.S.C) § 300101, *National Preservation*; 36 Code of Federal Regulations (CFR) Part 800, *Advisory Council on Historic Preservation*; and United Facilities Guide Specifications (UFGS). The Contractor shall comply with all applicable Federal Historical Structure and Archeological Laws. Location maps can be found at the local DPW.

2.4.1 Repair and Replacement. The Contractor shall report damages to the COR/ACOR within one (1) hour. The Contractor shall repair or replace parts with products similar in appearance to the original. Repairs, renovation, or replacement to historic buildings must be approved by the KO. The Contractor shall coordinate work through the Cultural Resources Manager. Location maps are available at the DPW.

2.5 Special Requirements.

2.5.1 Security.

2.5.1.1 Access and General Protection/Security Policy and Procedures. The contractor and all associated subcontractor employees shall comply with applicable installation, facility, and area commander installation/facility access and local security policy and procedures (provided by Government representative). Contractor personnel performing work under the contract shall have a recent "Standards of Good Conduct" certificate and valid ID Card within three (3) days after the contract award date (see par. 1.6.3.1), and shall maintain the level of security required for the life of the contract.

2.5.1.1.1 The contractor shall also provide all information required for background checks to meet installation-access requirements to be accomplished by the installation provost marshal office, director of emergency services, or security office. The contractor workforce must comply with all personal identity verification requirements as directed by DOD, HQDA, and local policy. In addition to the changes otherwise authorized by the changes clause of the contract, should the force protection condition (FPCON) at any individual facility or installation change, the Government may require changes in contractor security matters or processes.

2.5.1.1.2 Access to U.S. installations and controlled areas is limited to personnel who meet security criteria and are authorized by Host Nation law to work in that country. Failure to submit required information/data and obtain required documentation or clearances in accordance with Army in Europe (AE) Regulation 190-16 (AE Reg 190-16) Installation Access Control or (AE) Regulation 604-1 for Germany specific contracts, will be grounds for denying access to U.S. installations and controlled areas. The Contractor shall ensure that any subcontractors used in performance of the contract complies with these requirements and that all employees, of both the Contractor and any subcontractor utilized by the Contractor, are made aware of and comply with these requirements.

2.5.1.1.3 The Contractor shall be aware of and comply with the requirements associated with Installation Access Control. The Government is not liable for any costs associated

with performance delays due solely to a firm's failure to comply with Installation Access Control System (IACS) processing requirements.

2.5.1.1.4 The Contractor shall return installation passes to the issuing IACS office when the contract is completed or when a Contractor employee no longer requires access. AE Reg 190-16 (and AE 190-16-G German translation) can be found on the following web-site: <https://media.defense.gov/2017/Apr/27/2001921547/-1/-1/0/AER190-16-G.pdf>

2.5.1.1.5 In addition, the Contractor shall provide the Contracting Officer, via the COR, an Initial Installation Pass Log within three (3) days after contract award date. The log shall be updated as employees are added or removed. The Updated Installation Pass Log shall be current and available at any time upon request by the Government and submitted to the COR within three (3) days after any changes to the log. The log must at a minimum contain the following information employees full name, home address, personal ID number, passport/ID card, date of birth, country of citizenship **(Deliverable #3)**. A copy of a "Standards of Good Conduct" certificate (Fuhrmgszeugnis) must be submitted for each employee added to the Initial Installation Pass log and for all updates after contract award within three (3) days. **(Deliverable #4)**.

2.5.1.1.6 The Contractor shall collect the installation access passes the same day employment of an individual has expired or has been terminated and shall return them to the issuing office within five (5) workdays e

2.5.1.1.7 Upon termination or cancellation of the contract, the Contractor shall collect all outstanding installation access passes and return them to the issuing office within five (5) workdays **(Deliverable #5)**.

2.5.1.1.8 The contractor shall bear the primary responsibility to provide authorized personnel to escort sub-contractors who cannot attain installation access permission in a timely manner. For Emergency/Priority1 DMOs, the installation shall assist in providing a short-term escort of sub-contractors to reduce impact of the emergency responses, this must be coordinated with the COR/installation personnel prior. The Contractor shall be authorized escort privileges for two (2) personnel identified on the Installation Access Log to perform this requirement. **(Deliverable #16)**

2.5.1.2 Motor Vehicle Operators. Contractor's personnel, whose tasks involve require operation of any vehicles, shall possess a valid driver's license, certificates, and permits applicable for the type and class of vehicle being operated.

2.5.1.3 Contractor Vehicle Registration. Currently there is no requirement to register Contractor owned vehicles with the Provost Marshal or DES. However, all vehicles must be registered IAW current state requirements. In addition, all vehicles must be registered IAW current state requirements. In addition, the Contractor shall maintain a list of all Contractor-owned or operated vehicles and trailers operating on the Installation at all times. The list may be used in case of emergency and/or another contingency. Evidence of vehicle ownership and vehicle liability insurance must be presented upon request.

2.5.1.3.1 Contractor and Vendor Access. All privately-owned vehicles or motorcycles or Contractor or vendor-furnished vehicles and equipment must enter the Installation through the designated secure access control points (ACP). Under the present Installation FPCON, vehicle and equipment operators and passengers must possess identification documents to access the Installation. Vehicle and equipment operators must also possess and be ready to show a valid state and/or commercial driver's license, current vehicle registration, **show valid applicable Host Nation driver's license** . As determined by the Installation FPCON, an elevated FPCON may require additional security screening and/or limited Installation access.

2.5.1.3.2 All Contractor personnel, not possessing a Common Access Card (CAC), requesting access will enter through the designated Visitor Control Center (VCC). All Contractor personnel will be required to present a United States National or State issued identification that is capable of being scanned for valid entry. Contractor personnel will receive a visitor's badge at the VCC with the length of access allowed. The maximum access length for visitor badging is one year. Once issued a valid visitor's badge Contractor personnel may enter any Manned Access Control Point/Gate. All Contractor personnel and their vehicles, equipment, and packages are subject to inspection or examination (search) at entry/exit .

2.5.1.4 Physical Security. **N/A**

2.5.1.5 Secure Area Access. **N/A**

2.5.1.6 Employee Terminations. **N/A**

2.5.1.7 Departing Employees. **N/A**.

2.5.1.8 Key Control. **N/A**

2.5.2 Security Training.

2.5.2.1 iWATCH Training. The Contractor shall brief the local iWATCH program (training standards provided by the RA's Anti-Terrorism Officer (ATO)) to all of the Contractor's employees and associated Subcontractors. This training is used to inform employees of the types of behavior to watch for and instruct employees to report suspicious activity to the COR/ACOR. The Contractor shall complete the training within thirty (30) calendar days of contract award and within five (5) calendar days of new employees commencing performance with the results reported to the COR/ACOR NLT thirty (30) calendar days after contract award. **(Deliverable #9)**

2.5.2.2 Anti-Terrorism (AT) Level 1 Awareness Training. All Contractor employees, to include Subcontractor employees who possess a CAC Card or Unescorted Access Pass, requiring access to Dülmen Tower Barracks facilities and controlled access areas shall complete AT Level I awareness training within thirty (30) calendar days of contract start date and within five (5) calendar days of new employees commencing performance and

send to the COR via both electronic and paper copy. The Contractor shall complete the training within thirty (30) calendar days of contract award AT level I awareness training is available at the following website: <http://jko.jten.mil>. **(Deliverable #9)**

2.5.2.3 Operational Security (OPSEC) Awareness Training. IAW AR 530-1, Operations Security, Contractor employees to include Subcontractor employees who possess a CAC Card or Unescorted Access Pass, requiring access to Dülmen Tower Barracks shall complete Level I OPSEC Awareness training within thirty (30) calendar days of contract award and send to the COR via both electronic and paper copies. All Contractor personnel shall complete Level I OPSEC Awareness training annually. Level I OPSEC training is available at the following website: <https://securityawareness.usalearning.gov/opsec/index.html>. **(Deliverable #9)**

2.5.3 Safety. The Contractor shall safeguard and maintain all Government and Contractor property, as well as provide for the safety and well-being of personnel employed under this contract. The Contractor shall comply with AR 385-10, *The Army Safety Program*. All Contractor employees shall wear a reflective vest or suitable substitute while working during darkness hours. Contractor shall be responsible for any injury to any Contractor's representative, or others, as well as for any damage to any personal or public property that occurs during the performance of this contract that is caused by the Contractor's fault or negligence.

2.5.3.1 Safety Plan. The Contractor shall develop and implement a safety program for its employees. The Contractor shall submit the Safety Plan to the KO for review and acceptance within ten (10) days of commencement of work. Revisions shall be submitted five (5) calendar days prior to the effective date of change. **Deliverable #17**

2.5.3.2 Occupational Safety and Health Administration (OSHA). The Contractor shall comply with the OSHA standards and/or Host Nation Equivalent. The Contractor shall comply with all applicable Federal, State, Local Laws, and Host Nation Laws Regulations, and Directives. If the Contractor fails or refuses to comply promptly with safety requirements, the Government may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to any such order shall be made the subject of claim for extension of time or for excess costs or damages to/by the Contractor. The Contractor shall be responsible for enforcement of all safety requirements by the Contractor and his Subcontractors/teaming partners and/or joint venture partners.

2.5.3.3 Hot Work Permit. A Hot Work Permit is required any time heat producing devices are used and shall be issued by the USAG Benelux DES/Fire Department prior to ANY work being started.

- Example, welding, grinding, cutting, brazing, etc.
- Hot Work Permits will be closed by the Fire Department, after hot-work is completed, and before personnel responsible for the work clears the job site.

2.5.4 Training, Physical Requirements, or other Expertise Required.

2.5.4.1 Certification and Licensure. The Contractor/subcontractor firm and employees shall be fully certified, trained and meet all German standards pertaining to facilities, equipment, maintenance and repairs. The Contract Manager shall ensure all technicians are certified in their respective areas of responsibilities i.e. (electricians, plumbers, roofers, carpentry, mechanical, painters, masonry, structural, etc.) IAW all applicable German laws and regulations. All contractor/subcontractor personnel performing the required services shall possess at least the below listed valid certifications, or equivalent valid certifications approved by the designated German Authority (as applicable) The Contractor shall ensure all Contractor's employees and associated Subcontractors are certified or licensed in the specific areas required by the State of North-Rhine Westfalen, Germany this includes but not limited to

(1) The Contractor shall ensure employees are certified or licensed in the appropriate Environmental Protection Agency (EPA) areas required.

(2) For contractor and/or subcontractor employees: Master (Meister) in the category of the applicable "Tradesman" certification field. The certifications required for each specific task of this contract identified in the Part 5 of the PWS are required prior to work start. The Technicians shall possess working knowledge of the English language or the primary contractor shall provide a translator.

(3) 2 The Contract Manger/Alternate shall validate contractors/subcontractors are registered within the Head Quarters (HQ) Chamber of Crafts to meet the applicable "Meister" certifications requirements IAW the German legislation – The Trade and Crafts Code (Handwerksordnung) and maintain all required certificates required to perform tasks outlined in this PWS, and provide them to the Contracting Officer upon request.

(4) When applicable, employees and associated Subcontractors are certified according to DGUV Rule 113-004 (formerly BGR 117-1) for Confined Space "*enge Räume*" prior to entry into a confined space

2.5.4.2 The Contractor shall ensure all required documentation of certification or licensure for Contractor personnel are filed with the COR/ACOR within twenty-four (24) hours prior to employees commencing performance.

2.5.5 Environmental Requirements.

2.5.5.1 Green Procurement. N/A

2.5.5.2 N/A

2.5.5.3 Environmental Compliance. The Contractor shall ensure that all of its operations and activities conform to the USAG Benelux environmental policy requirements. The Contractor shall ensure that all contract personnel have received appropriate levels of training in the handling, use, storage, and disposal of hazardous material. In addition, the Contractor shall ensure that all Contractor controlled activities on USAG Benelux installations are conducted in accordance with the USAG Benelux Spill Prevention and Response

Plan, Solid Waste Policy, Final Governing Standards-Germany, and applicable German environmental laws/standards.

2.5.5.3.1 If contract requires the use of hazardous materials/substances, the Contractor shall, prior to mobilization, inform the Contracting Officer (KO)/Contracting Officer Representative (COR) of the types and amount of hazardous materials needed to be brought onto the Garrison in order to fulfill their contractual requirements (Deliverable #8). Contractor shall also provide the Safety Data Sheets, storage requirements and proposed storage locations for the hazardous material (Deliverable #8).

2.5.5.3.2 Prior to contract completion, the Contractor shall remove all hazardous materials and dispose of all hazardous waste (HW) generated in accordance with Final Governing Standards Germany and applicable German environmental laws/standards. A copy of the HW disposal documents must be forwarded to the HW program manager at the DPW Environmental Division.

2.5.5.3.3 The Contractor shall clean up at its own expense any contamination, including soil and ground water contamination caused by hazardous materials/substances brought onto the garrison, or by his activities. The Contractor must immediately report any hazardous substance spills to the USAG Benelux Directorate of Public Works-Environmental Division (DPW-ED) at CIV 09641-70-524-8966.

2.5.5.3.4 The Contractor shall contact DPW-ED, CIV 09641-70-524-8966, Bldg. 40014, APS Dülmen for a copy of the Spill Prevention and Response Red Plan and German Final Governing Standards.

2.5.5.4 Spill Plan. The Contractor shall notify the COR/ACOR within one (1) hour, if the Contractor spills or releases any hazardous substances, *i.e.*, substances listed in 40 CFR 302, *Designation, Reportable Quantities, and Notification*. The Contractor shall submit a Spill Plan to the KO for approval within thirty (30) days of contract award IAW Spill Prevention Control and Countermeasure Plan.

2.5.6 Contingency Plans.

2.5.6.1 General. N/A.

2.5.6.2 Mobilization Contingency Plan. N/A

2.5.6.3 Disaster Contingency Plan. N/A

2.5.6.4 Labor Dispute Contingency Plan. N/A

2.5.6.5 Plan Updates. N/A

3.0 Performance Requirements and Standards.

3.1 Performance Task Requirements, Standards and Acceptable Quality Levels (AQLs).

3.2 Quality Assurance (QA). The Government will evaluate the Contractor's performance under the contract IAW the Government's Quality Assurance Surveillance Plan (QASP) (TE 3). QASPs are considered to be "living documents," dynamic, adaptable, and subject to modification based on Contractor performance surveillance results. The QASP is not part of the PWS and will not be issued with the solicitation. The QASP focuses on the procedures and processes the Government will implement to assure the Contractor is performing IAW the performance standards within the PWS. The Government plan defines the criteria of how the Contractor's performance will be evaluated, the frequency of surveillance, and the items to be inspected. Although the Government will develop a QASP, Government surveillance of Contractor performance is not limited to the QASP, or the performance objectives, outlined in the Performance Requirements Summary (PRS) (TE 1). The Government retains the right to evaluate all services required by the contract. The Government will perform inspections and tests in a manner that will not unduly delay the work. If any of the services performed do not conform to contract requirements, the Contractor shall perform the services again at no additional cost to the Government.

3.3 Quality Control Plan (QCP). Quality control is the responsibility of the Contractor. The Contractor shall develop, implement, and maintain an effective quality control program which shall be documented in a QCP to ensure services are performed IAW this PWS. The Contractor shall develop and implement procedures to identify and prevent the recurrence of defective services. The Contractor's QCP is the means by which they assure themselves that the work conforms to contract requirements. The basic principle of the plan is that the Contractor is responsible for quality control. The QCP shall be constructed in such a manner that each SERVICE can be extracted and used for that function only and not contain extraneous information. The Contractor's QCP shall include a separate section, which addresses the Contractor's method of managing quality of work. The QCP shall include a description of the inspection system to address services listed in this PWS, and a description of the methods to be used for identifying and preventing defects in the quality of services performed. The plan shall include a description of the Contractor's inspection system to include specifics as to areas to be inspected on a scheduled and unscheduled basis, frequency of inspections, and the title and organizational placement of the Contractor's inspectors. No lead person or first line supervisor shall be considered a Quality Control Inspector. The Contractor shall develop, maintain, and submit a QCP to the KO for acceptance within thirty (30) calendar days after the contract is awarded. The Contractor shall submit any proposed changes in the QCP to the KO for written approval five (5) working days prior to implementation. (Deliverable #1)

3.4 Quality Control Files. The Contractor shall maintain files of all inspections or tests conducted by the Contractor, to include any corrective actions taken. These files shall be subject to Government review at the COR's discretion during the contract term, to include any extensions of contract term. The Quality Control Files will be the property of

the Government and shall be turned over to the Government upon completion or termination of the contract.

4.0 Technical Exhibit 1 -Performance Requirements Summary (PRS) Matrix.

PERFORMANCE OBJECTIVE	STANDARD	PERFORMANCE THRESHOLD ACCEPTABLE QUALITY LEVELS (AQLs)	METHOD OF SURVEILLANCE
<u>PRS#1 - General Information</u> Contractor shall comply Installation Access requirements.	Contractor shall comply with installation access procedures. Maintain current documentation throughout duration of contract and provide initial installation access log within three days after contract award date. IAW PWS Paragraph 2.5.1.1	No more than four (4) non-compliance findings per month (COR, Customer, Security Office complaints)	100% Inspection, Periodic Inspection, Random Sampling or Customer Feedback
<u>PRS#2 - General Information</u> Security Passes	Contractor shall ensure security passes are collected and returned to the issuing office within 5 days of termination or expiration IAW PWS Paragraph 2.5.1.1	100% Compliance	100% Inspection, Periodic Inspection, Random Sampling or Customer Feedback
<u>PRS#3 - Accident Prevention Plan</u>	The Contractor shall comply with FAR 52.236-13, Accident Prevention (November 1991), the references contained therein (e.g. U.S. Army Corps of Engineers Safety and Health Requirements Manual (EM 385-1-1), and applicable Host Nation Safety Laws and Regulations IAW paragraph 2.1.6.2	100% Compliance	100% Inspection, Periodic Inspection, Random Sampling or Customer Feedback
<u>PRS#4 - General Information</u> Environmental Compliance	The Contractor shall ensure that all of its operations and activities conform to the USAG Benelux environmental policy requirements IAW paragraph 2.5.5.3	100% Compliance	100% Inspection, Periodic Inspection, Random Sampling or Customer Feedback

<u>PRS#5 - General Information</u> Required Training	Contractor shall ensure employees complete required training outlined in PWS paragraph 2.5.2 within 30 days and provide documented proof to COR within 3 days after completion date for refresher training each year.	>90% Percent Total Overall PRS Inspection Checklist Compliant Rate.	100% Inspection, Periodic Inspection, Random Sampling or Customer Feedback
<u>PRS#6 - Government Property and Services</u> Government Furnished Item and Services	Contractor shall ensure employees operate under conditions that preclude waste of utilities. IAW PWS Paragraph 7.4	100% Compliance	100% Inspection, Periodic Inspection, Random Sampling or Customer Feedback
<u>PRS#7 - Contractor Furnished Items and Services</u> Contractor Furnished Items and Services	Contractor shall furnish all personnel, equipment, supplies, facilities, transportation, tools, materials, supervision, and other items necessary in the performance of this contract. IAW PWS Paragraph 7.4	100% Compliance	100% Inspection, Periodic Inspection, Random Sampling, or Customer feedback
<u>PRS#8 - Specific Tasks</u> PM Plan	The Contractor, in coordination with the Government, shall provide a comprehensive PM plan and PM schedule IAW PWS Paragraph 2.2.4.1	No more than one (1) non-compliance finding per month	100% Inspection, Periodic Inspection, Random Sampling, or Customer feedback
<u>PRS#9 - Specific Tasks Services</u> Demand Maintenance Orders	When notified by the COR, the contractor shall respond to DMOs and complete maintenance repairs IAW paragraph 2.2.3	No more than two (2) non-compliance findings per month (DMOs not meeting response requirements without prior COR coordination/ approval)	100% Inspection, Periodic Inspection, Random Sampling, or Customer feedback
<u>PRS#10 - Specific Tasks Services</u> Equipment Replacement Parts	The contractor shall provide three quotes for parts exceeding € 2400 These quotes will be provided to the contracting Officer via the COR for decision prior to beginning work. IAW Paragraph 2.2.3.2	100% Compliance	100% Inspection, Periodic Inspection, Random Sampling, or Customer feedback
<u>PRS#11 - Specific Tasks</u> Invoices	The Contractor shall submit all invoices (electronically via WAWF) within 30 days from completion of work IAW paragraph 2.2.8	No more than two (2) invoice non-compliance findings per month	100% Inspection, Periodic Inspection, Random Sampling, or Customer feedback

<u>PRS#12 Specific Tasks</u> Air Conditioning	The Contractor shall perform all inspections, and maintenance in accordance with manufacturer's instructions, accepted industry standards and the PWS and provide a report of PM completion results and any deficiencies IAW paragraph 5.2.1.1	>95 Percent Total Overall PRS Inspection Checklist Compliant Rate	100% Inspection, Periodic Inspection, Random Sampling, or Customer feedback
<u>PRS#13 - Specific Tasks</u> Vehicle Exhaust Extraction System	The Contractor shall, annually, inspect, test, provide maintenance, TUV certification to the Ex-haust Extraction system and report to the COR IAW paragraph 5.2.1.5	>95 Percent Total Overall PRS Inspection Checklist Compliant Rate	100% Inspection, Periodic Inspection, Random Sampling, or Customer feedback
<u>PRS#14 - Specific Tasks</u> Fire Alarm System (including permanent, mobile, and local systems/ Smoke Extraction System	The contractor shall inspect, test, perform preventative maintenance, and maintain fire alarm system / smoke extraction system. IAW Paragraph 5.2.3	>95 Percent Total Overall PRS Inspection Checklist Compliant Rate	100% Inspection, Periodic Inspection, Random Sampling, or Customer feedback
<u>PRS#15 - Specific Tasks</u> Lightning Protection and Grounding Systems	A complete inspection of the Lightning Protection System and its components covered under this service agreement shall occur within 11 months from date of last inspection. IAW Paragraph 5.2.3.10.	>95 Percent Total Overall PRS Inspection Checklist Compliant Rate	100% Inspection, Periodic Inspection, Random Sampling, or Customer feedback
<u>PRS#16 - Specific Tasks</u> Chimney Emissions Test	The contractor shall perform an emissions test of the chimney located at building 22, annually and provide a complete inspection and testing of the Chimney Emissions. IAW Paragraph 5.2.7	100% compliance	100% Inspection, Periodic Inspection, Random Sampling, or Customer feedback
<u>PRS#16 - Specific Tasks</u> Chimney and Radio Tower Inspections	The Contractor shall visually inspect the radio and chimney tower structures in accordance with Army regulations and Host Nation requirements, but at a minimum, annual inspections are required. IAW Paragraph 5.2.8.- 5.2.9	100% compliance	100% Inspection, Periodic Inspection, Random Sampling, or Customer feedback

<u>PRS#16 - Specific Tasks</u> Elevator System	The contractor shall provide annual preventative maintenance, TUV inspections, ZUS examination annual (intermediate examination) and Secondment of a specialist assembler for the ZUS examination every two (2) years (main examination). IAW Paragraph 5.2.6	100% compliance	100% Inspection, Periodic Inspection, Random Sampling, or Customer feedback
<u>PRS#16 - Specific Tasks</u> POL Point	The Contractor shall inspect, test, maintain, and certify the entire POL point, to include the pumps, sealed surface, leakage detection system, underground tank and provide required TUV certificates, to include but not limited to the 3, 5 and 10 year TUV for tank IAW Paragraph 5.2.11.	100% compliance	100% Inspection, Periodic Inspection, Random Sampling, or Customer feedback
<u>PRS#16 - Specific Tasks</u> HVAC Systems	The Contractor shall inspect, test, and maintain smoke extraction, Dehumidification, Air Conditioning, Boiler, Heat Pump and all other HVAC Systems identified in the PWS in accordance with Army regulations, Host Nation requirements and manufacturer's instructions, but at a minimum, annual inspections are required. PWS 5.2.1.	100% compliance	100% Inspection, Periodic Inspection, Random Sampling, or Customer feedback
<u>PRS#17 Backflow Prevention Devices.</u>	The contractor shall, annually, visually inspect, test and perform preventative maintenance on Backflow prevention Devices. All maintenance performed shall be accordance with manufacturer's instructions, accepted industry standards, and the PWS. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 5.2.17	100% compliance	100% Inspection, Periodic Inspection, Random Sampling, or Customer feedback

5.0 Tasks.

5.1 Basic Services: The Contractor shall provide inspections, testing, preventative maintenance, maintenance and repair services on all systems listed in section 5.3 (para. 5.3.1 through para. 5.3.17) in a safe and habitable condition and ensure systems are fully functional for the sustainment of the facilities as required in this PWS. The contractor shall have experienced, trained, professional and certified electricians and craftsmen to perform maintenance and repairs of associated property and equipment. The contractor shall coordinate all work with the COR and government representative (DPW). All work shall be performed by trained and qualified personnel in accordance with U.S. Army regulations, manufacturer's instructions, Host Nation Standards, PWS and accepted industry standards. In addition, the contractor is required to have required certificates identified in paragraph 2.5.4.

Note: For all activities that requiring digging on the Dülmen Barracks, a proper dig permit must be obtained through USAG Benelux Dülmen DPW and the German Government as applicable.

5.2. Tasks:

5.2.1. Heating Ventilation and Air Conditioning:

5.2.1.1 Air Conditioning: The Contractor shall, annually, inspect, test, provide maintenance and maintain equipment parts for necessary adjustments, proper internal air temperature, and pressure differential across filters, and detect units for leaks. The Contractor shall perform all inspections, and maintenance in accordance with manufacturer's instructions, accepted industry standards and the PWS. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2. A complete inspection of the Air Conditioning system and equipment covered under this System includes, but are not limited to the following:

- (1) Check and Service Air Filters;
- (2) Check and Service Compressor and/or condenser units; Replace filters as appropriate
- (3) Check and Service Fans—intake and exhaust;
- (4) Check and Service Air handling units;
- (5) Check and Service cooling coils;
- (6) Check and Service belts and valves;
- (7) Check and Service vacuum pumps.
- (8) For retrofitting, the refrigerant gas shall be removed and disposed of by a certified company and replaced by non-Ozone depleting gas when possible.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: VDMA 24186, VDMA 24191, Weishaupt WWP S75 IR, 30 U.S. Code Chapter 23, VDI 6022, VDE (VDE 105) or host nation equivalents

5.2.1.2 Heating System / Heating Pump: The Contractor shall, annually, inspect, test, and provide maintenance to ensure proper operation of the Heating System /Heating Pump, Ancillary Electric system and distribution system to efficiently and safely produce quality hot water to meet all installation-heating requirements, twenty four (24) hours per day, seven (7) days per week, throughout the contract period. A plan for required repairs and maintenance after the inspection shall be addressed within the PMP. The Contractor shall operate and maintain heating systems and related auxiliary equipment, including, but not limited to fans, motors, pumps, shut-off valves, heat exchangers, distribution lines, blower units, heat control, circulating pumps, and individual room radiators. All equipment shall be maintained to meet operational requirements except when offline for maintenance or secured for energy conservation. All scheduled maintenance shall include a visual inspection of all components to ensure proper operation and to check for leaks or other deficiencies. The Contractor shall also ensure control systems operate and function in a manner that maintains the specified output of the mechanical system it controls. The Contractor shall perform all inspections and maintenance in accordance with manufacturer's instructions, accepted industry standards and the PWS. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.1.3. Boilers: The Contractor shall, annually, inspect, test, and provide maintenance and repairs of the boilers to ensure proper operation of the boilers and all components. The Contractor shall perform all inspection and maintenance in accordance with manufacturer's instructions, accepted industry standards and the PWS. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2. Service on the boilers includes, but are not limited to the following:

- (1) Hot water heating systems
- (2) Heat exchangers
- (3) Shut-off valves

- (4) Pumps; Heater boilers, heater furnace
- (5) Ancillary electric systems
- (6) Distribution lines
- (7) Heat controls
- (8) Individual room radiators
- (9) Chimney Emissions testing and burner adjustment.
- (10) Under Sink Water Heaters

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: DIN 4720-8, DIN EN 12828.

5.2.1.4. Heat Oil Storage and Delivery System: The Contractor shall perform inspection and maintenance to ensure proper operation of the Heat Oil Storage and Delivery System. The Contractor shall perform all inspections and maintenance in accordance with manufactures instructions, accepted industry standards and the PWS. The Contractor shall provide TÜV inspection and certification to include annual, 5 and 10 year TUVs for tanks and convey report to local authorities when required. A complete inspection of the Heat Oil Storage and Delivery System and its components covered under this PWS includes, but are not limited to the following: tanks, filling station, oil pump, associated piping. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2. The Contractor shall provide on-call service (not included in the PM schedule), to include inspections, maintenance and repairs of the heat oil storage and delivery system.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: TÜV certified specialist company according to § 62 WhG, DIN 6608 D.

5.2.1.5. Vehicle Exhaust Extraction System: The Contractor shall, annually, inspect, test, provide maintenance, TÜV certification to the Exhaust Extraction system and report IAW 5.2.38. The inspection shall be in accordance with German and US building & electrical codes, safety codes, regulations, manufacturer's instructions, accepted industry standards and the PWS. A complete inspection of the system and its components covered under this service agreement includes, but are not limited to the following: checking for damage actuators, clean parts such as surfaces, fans, hoses, controls, extraction flue, and other disposable parts at recommended intervals, and check control features to ensure that they are calibrated correctly. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.1.6. Dehumidification System: The Contractor shall, annually, inspect, test, provide maintenance and provide certification to the dehumidification system. The inspection shall be in accordance with German and US building & electrical codes, safety codes, regulations, manufacturer's instructions, accepted industry standards and the PWS. A complete inspection of the system and its components covered under this service agreement includes, but are not limited to the following: checking for damage to actuators, clean parts such as surfaces, fans, hoses, controls, extraction flue and other disposable parts at recommended intervals and check control features to ensure that they are calibrated correctly. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.2 Building Automation: *(NOTE: Building Automation is not currently installed but projected within the timeline of this contract. Prices will be requested upon clarification of scope of building automation systems to be installed)* The Contractor shall inspect, test, provide maintenance and maintain electrical components of buildings in accordance annually with applicable standards (e.g., VDMA 24186), The Contractor shall check function of central control software, hardware and upgrade as appropriate. Check function of communication links, inspect remote control unit software, inspect and check remote equipment, check accuracy/calibration of sensors check serviceability of actuators, and check suitability of system settings and provide a report of any problems and recommendations to the COR. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.3 Fire Protection and Emergency Systems:

5.2.3.1. Fire Alarm Systems: The Contractor shall conduct quarterly inspections and maintenance on fire alarm systems and fire detection systems IAW the Verband Deutscher Schadenversicherer (VdS) and Verband Deutscher Elektrotechniker (VDE). Maintenance shall be conducted from the sensor (smoke detector, laser, etc.) up to and including the remote alarm station, including relocation of existing units as required. The Contractor shall perform a complete functional check including electrical functions, visual inspections, sirens test, smoke detectors test, cleaning, and maintenance, technical and mechanical, of all component parts for manual and automatic fire protection systems in accordance with Army Regulations and Host Nation Requirements. The Contractor shall inspect the entire system; however, inspections of components may be accomplished in increments. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2. A complete test and inspection of the system and its components covered under this service agreement includes, but are not limited to the following:

- (1). Check DPW logbook for false alarms. (located in bldg. # 14)
- (2). Inspect operation of automatic fire detection sensors in each protected zone. (Selected sensors shall be scheduled so all are tested within one year).
- (3). Inspect and test control panel functions. (All fault indicators and circuits should be tested, checked and repaired).
- (4). Inspect and test batteries, push buttons, pull stations.
- (5). Simulate mains and check that system reacts properly.
- (6). Check operation of audible warning devices.
- (7). Check that external connections to warning posts (e.g. guardrooms fire stations) are in working order.
- (8). Inspect all accessible cables.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: VDE 0800, VDE 0833, DIN 14675, VDMA 24186-7; VdS 2098, BGG 920, DIN 18232, VDMA 24186-7.

5.2.3.2. Mobile Fire Detection System: The Contractor shall, annually, conduct inspections and maintenance on Mobile Fire Detection systems and IAW the Verband Deutscher Schadenversicherer (VdS) and Verband Deutscher Elektrotechniker (VDE). Maintenance shall be conducted from the sensor up to and including the remote alarm station, including relocation of existing units as required. The Contractor shall perform a complete functional check including electrical functions, visual inspections, sirens test, smoke detectors test, cleaning, and maintenance, technical and mechanical, of all component parts for manual

and automatic fire detection systems in accordance with Army Regulations and Host Nation Requirements. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: VDE 0800, VDE 0833, DIN 14675, VDMA 24186-7; VdS 2098, BGG 920, DIN 18232, VDMA 24186-7.

5.2.3.3. Sprinkler Systems: *(NOTE: Existing and future sprinklers are installed as “Wet Pipe” with pressurized pipes, which rely on external water supply for activation, pending future installation of Pump House and Fire Water Storage Tanks.)* The contractor shall, at minimum annually, inspect, test, perform preventative maintenance, and maintain the sprinkler system, in accordance with Host Nation requirements and Army regulations. Preventative Maintenance of the system and its components covered under this service agreement includes, but are not limited to the following: check positions of all valve, check the performance of the automatic conveyor systems, check water supply level and refill as necessary, check reservoirs, tube system, water pressure and seals, drain and inspect water storage tanks/reservoirs and treat with appropriate materials to prevent algae/fungal growth. Instrumentation and control technology/drive elements. Check sprinkler panel on permissible room temperature, check the operation of the compressed air station, check pressure gauge on displays for correct operation, check sprinklers for obstruction of water distribution, Check mains pressure before main control valve of direct system and pressure in pressurized tank. The contractor shall perform all inspection, and maintenance in accordance with manufactures instructions, accepted industry standards Additionally, When applicable the following will be accomplished by a VdS approved company.

- (1). Every 2 years: Internal inspection of piping and tanks (where applicable). This often involves draining sections of the system.
- (2). Every 3 years: Comprehensive inspection of the entire system, including all components.
- (3). Every 10-30 years: Depending on the type of pipe material, a pressure test may be required.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: DIN EN 12845-2, VDMA 24200-1, VDMA 24186-7, NFPA 13, VdS 2831 "Maintenance of Sprinkler Systems" or host nation equivalent.

5.2.3.4. Liquid Barrier Systems: The Contractor shall, annually, inspect, test, and maintain liquid barrier systems in accordance with Army regulations, Host Nation requirements and manufacturer's instructions. Inspection and maintenance shall include but not limited to inspection of all components, testing, and functional check of liquid barrier system. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4

Applicable publications: VdS / DIN 14675 Certification, US Army Standards or local equivalent

5.2.3.5. Pump House: *(NOTE: A pump house is currently being construction near building 22. This facility is projected to be completed prior to the end of this contract. Prices will be requested upon clarification of scope of Pump House and internal systems to be installed)* A pump house capable of providing sufficient water to sitewide sprinkler systems with two generators, above ground fuel tank to supply generators, a 16-million-liter water reservoir and pump house structure is projected to be installed and completed in year 2027-2028. Projected preventative maintenance tasks will include but not limited to:

- (1). Annual Flow Test: This is a performance test conducted under minimum, rated, and peak flow conditions to verify that the pump's performance is within 95% of the manufacturer's specifications.
- (2). Component Maintenance: This includes lubricating pump bearings, checking pump shaft end play, and checking the accuracy of pressure gauges. For diesel engines, this involves changing the oil and oil filter, inspecting the cooling system, and cleaning the fuel tank.
- (3). Valve and Connection Inspections: All valves should be operated through their full range, and hose connections should be inspected for damage.
- (4). Controller and Electrical System: A qualified professional should inspect and test the fire pump controller and all electrical components, tightening connections as necessary.
- (5). All requires TÜV and ZÜS certifications to include 5-year inspection/certification of water storage tank.
- (5). Documentation of all inspections and maintenance in the logbook (Betriebsbuch)

Required certificates to perform this task: IAW Paragraph 2.5.4

Applicable publications: VdS CEA 4001, DIN EN 12845 US Army Standards or local equivalent

5.2.3.6. Smoke Extraction Window System: *(NOTE: There is an ongoing project projected to be completed during the timeline of this contract. Current pricing will reflect only building 6. Prices will be requested upon completion of additional facilities as they occur.)*

The Contractor shall, annually, inspect, test, and maintain smoke extraction systems in accordance with Army regulations, Host Nation requirements and manufacturer's instructions. Inspection and maintenance shall include but not limited to inspection of all components, testing, and functional check of automatic windows system. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4

Applicable publications: VdS / DIN 14675 Certification

5.2.3.7. Fire Extinguishers: The Contractor shall, annually, inspect, test, and provide maintenance to fire extinguishers and ensure they are in compliance with current fire codes in accordance with Army and German regulations. In addition, the Contractor shall refill the extinguishers as needed, and replace extinguishers when approved by the COR when they are no longer operational. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4

Applicable publications: ASR A2.2. DIN 14406 Part 4, § 16 of the Ordinance on Industrial Safety and Health (BetrSichV), NFPA 10, or host nation equivalent

5.2.3.8. Fire Protection Doors: The contractor shall, annually, inspect, test, perform preventative maintenance, and maintain fire rated doors in accordance with Army regulations, Host Nation requirements, and manufacturer's instructions. Inspection and maintenance shall include but not limited to controllers, seals, magnet devices, and panic hardware, when applicable. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: TÜV zertifizierter Fachbetrieb nach § 62 WhG, BetrSichV; TÜV certified specialist company according to § 62 WhG, DIN 6608 D.

5.2.3.9. Emergency Ladder: The Contractor shall conduct annual inspections and maintenance of Emergency ladder. The Contractor shall perform a complete check of

emergency ladder, to include, but not limited to structural, technical and mechanical, components for systems in accordance with Army Regulations and Host Nation Requirements. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.3.10. Lightning Protection and Grounding Systems: The Contractor shall, annually, perform inspections and provide maintenance of the Lightning Protection Systems (LPS) in accordance with Host Nation requirements (most recent VDI) and Army regulations. A complete inspection of the Lightning Protection System and its components covered under this service agreement shall occur within 11 months of most recent inspection after contract award. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2. A plan for required repairs and maintenance after the inspection shall be addressed within the PMP. Inspection and maintenance tasks include, but are not limited to the following:

- (1) Inspect the general condition of lightning current arrester and surge diverter as well as all connection and resistance components.
- (2) Inspect the earth termination system and the earth resistance including transitions and connections.
- (3) Inspect the internal lightning protection including lightning arrester and fuses.
- (4) General condition of the corrosion category.
- (5) Inspect the secureness of the mounting of all LPS (Lightning Protection System) conductors and its components.
- (6) Documentation regarding any modifications and extensions of the LPS as well as all modifications to the construction.
- (7) Inspect to ensure system is properly grounded.

Required certificates to perform this task: IAW Paragraph 2.5.4

Applicable publications: VDMA 24186-5, DIN 62305-3, VDE 0185, NFPA 780, or host nation equivalent.

5.2.3.11. Safety Emergency Lightning / Exit Lighting: The Contractor shall, annually, inspect, provide full rated duration test, and maintain emergency lighting in accordance with Verband Deutscher Elektrotechniker (VDE) 0510-2 Safety requirements for batteries

and battery installation, but at a minimum, annual inspections are required. In addition, the work shall be in accordance to Army regulations, Host Nation requirements and manufacturer's instructions. During the inspection, the Contractor shall perform minor maintenance as required including but not limited to the replacement of bulbs, light covers, and other accessories to ensure lights are functioning and installed IAW the performance standards. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications (Electrical System/ RCD Circuit Breakers, High Voltage Transformers and Switch Gears): VDE 105-100, VDE 0100-600, NFPA 70E DGUV 3

5.2.4. Roll-Up Doors (Steel, Rubber, Segmented with Key Pads or entry control systems) and Battery Back-up Systems: The Contractor shall, annually, inspect, test, provide maintenance and maintain roll-up doors and battery back up power supply systems in accordance with Army regulations, Host Nation requirements, and manufacturer's instructions. Inspection and maintenance shall include but not limited to keypads, controller, seals, magnet devices, belts, panic hardware, back up battery life, etc. The Contractor shall inspect electric motors and gears for proper operation and check mounts to ensure the motor is secure. The contractor shall inspect the battery system to ensure the doors function as designed in the event of an emergency or power interruption and clean battery system components if required. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: BGG 950, BG3, VDE.

5.2.5. Oil Water Separators (OWS) The Contractor shall, semi-annually, inspect, test, provide maintenance and maintain oil water separator systems in accordance with Army regulations, Host Nation requirements, and manufacturer's instructions. These results shall be documented in the Operator's log located with DPW. Inspection and maintenance shall include but not limited to any structural damage to the vault, baffles, and pipes or mechanical components. The contractor shall perform required 5-year inspection/certifications by a certified company and provide written reports. OWS 5-year inspection/certification completion will be coordinated with the COR and billed via DMO when it is due/performed. OWS systems will be emptied and cleaned through USAG Benelux Environmental Division and not through this contract. The Contractors shall provide a report

of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: DGUV Rule 113-004 (formerly BGR 117-1) for Confined Space “*enge Räume*” entry, DIN EN 858/DIN 1999-100, German Water Resources Act, DIN EN 858-1/2 and DIN 4040-100

5.2.6 Elevator System: The contractor shall provide annual preventative maintenance, Technischer Überwachungsverein (TUV) inspections, ZÜS - Zugelassene Überwachungsstelle examination annual (intermediate examination) and Secondment of a specialist assembler examination every two (2) years (main examination) or as indicated by authorized bodies (ZÜS - Zugelassene Überwachungsstelle). The contractor shall be responsible for all inspection fees. The contractor shall be responsible for all emergency service connections and fees. The contractor shall perform all inspections and maintenance in accordance with the manufacturer’s instructions, accepted industry standards and the PWS. A complete inspection and PM of the Elevator system and equipment components covered under this System includes, but are not limited to the following: visual inspections, check safety-relevant components, lifting systems, electrical equipment, adjust components, check and oil cables as required, check drive unit, tightening screws and bolts, cleaning, realignment, lubrication, calibration, check and replace all mechanical and non-mechanical parts as required, and ensure they are functioning IAW the performance standards. Contractor or subcontracts will provide required inspection interval according to ZÜS (Zugelassene Überwachungsstelle)

Applicable publications: TRBS 3121, TRBS 1201-1, EN 81, Betriebssicherheitsverordnung (BetrSichV), 54, DIN VDE 0833 and all VDS/VDMA regulations which are applicable.

Applicable publications: VOB (Vergabe- und Vertragsordnung fuer Bauleistungen), applicable VDMA, DIN standards, or local equivalent.

5.2.7. Chimney Emissions Test: The Contractor shall perform an emissions test of the chimney located at building 22, annually and provide a complete inspection and testing of the Chimney Emissions. The inspection shall be in accordance with local regulations, manufacturer’s instructions, German and US building codes, accepted industry standards and the PWS. Inspection and maintenance shall include but is not limited to emissions checks/testing, recommendation of any corrections or adjustments, etc. The Contractors

shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: German Local Federal Emission Control Act

5.2.8. Chimney Structure: The Contractor shall, annually, inspect the Chimney structure and provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2. the contractor shall provide maintenance and repairs when approved by the COR, the work shall include, but not limited to regrouting bricks, repair of spalling bricks, ladder repair, bulb replacement. Repairs to the chimney structure will occur through DMO.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.9. Radio Tower Structure: The Contractor shall visually inspect the radio tower structure in accordance with Army regulations and Host Nation requirements, but at a minimum, bi-annual inspections are required. The Contractor shall provide a report to the COR listing any problem areas and recommendations IAW para 2.2.4.2. In addition, the Contractor shall provide maintenance and repairs when approved by the COR, the work shall include, but not limited to regrouting bricks, repair of spalling bricks, ladder repair, bulb replacement. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2. Repairs to the radio tower structure will occur through DMO.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.10. Generators: *(NOTE: There is currently one generator located at building 40006. There are two additional generators planned for the new pump house facility located near building 40022. Pricing will reflect existing generators and new pricing requested upon clarification of new generators, planned for completion 2027-2028)* The Contractor shall, annually, inspect, test, and maintain generators in accordance with Army regulations, Host Nation requirements and manufacturer's instructions. Inspection and maintenance

shall include but not limited to motor oil, coolant and filter changes, motor and generator functional check. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: VDMA 24186-5, DIN, VDE, BGVA3.

5.2.11. Petroleum Oil Lubricants (POL) Point: The Contractor shall inspect, test, maintain, and certify the entire POL point, to include the cathodic protection systems, pumps, sealed surface, leakage detection system, underground tank and provide required TUV certificates, to include the annual, 3, 5 and 10 year TUV for tanks, in accordance with Army regulations, Host Nation requirements, and manufacturer's instructions. Inspection and maintenance shall include leak detector, fill pipes, alarm, sensors, service station pumps, overfill cutoff hoses, receiver nozzle, pavement surface sealing tans, and any other components related to the POL point. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: Applicable VDA, VDMA, DIN, US Army standards, TUV certified specialist company according to § 62 WhG, DIN 6608 D.

5.2.12. Above Ground Fuel Storage Tanks: *(NOTE: Currently there is one existing above ground tank located at building 40006. There is one additional planned at the pending Pump House Facility near building 40022. Pricing will reflect existing tank only and new pricing requested upon installation of new tanks, planned for completion 2027-2028)* The Contractor shall inspect, test, maintain, and certify the entire POL point, to include the pumps, sealed surface, leakage detection system, underground tank and provide required TUV certificates, to include the annual, 3, 5 and 10 year TUV for tanks, in accordance with Army regulations, Host Nation requirements, and manufacturer's instructions. Inspection and maintenance shall include leak detector, fill pipes, alarm, sensors, service station pumps, overfill cutoff hoses, receiver nozzle, pavement surface sealing tans, and any other components related to the POL point. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: Applicable VDA, VDMA, DIN, US Army standards, TUV certified specialist company according to Federal Water Act (Wasserhaushaltsgesetz - WHG) § 62 WhG, DIN 6608 D.

5.2.13. Transformer High-Voltage and Switch Stations: The Contractor shall, annually, inspect, provide maintenance and maintain transformers and switch gear and facility housing and other equipment components in accordance with Army regulations, Host Nation requirements, and manufacturer's instructions. Inspection and maintenance shall include but not limited to, service to cable, (incoming/outgoing), switch gears, check facility structure, doors, cleanliness, grounding, fasteners/hardware, oil level check/leaks, etc. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications (Electrical System/ RCD Circuit Breakers, High Voltage Transformers and Switch Gears): VDE 105-100, VDE 0100-600, NFPA 70E DGUV 3

5.2.14. Dock Levelers and Safety Gates: The Contractor shall, annually, inspect, test and maintain dock levelers and safety gates in accordance with Army regulations, Host Nation requirements, and manufacturer's instructions. Inspection and maintenance, shall include but not limited to controller, springs, hydraulics, proper operation, hardware, mounts or motors and structural components. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.15. Roof, Gutters, Drains, and Downspouts. The Contractor shall annually, inspect and clean all roofs, gutters, drains, and downspouts IAW manufacturer's recommendations or host nation. Cleaning shall include removal of bird nests, cobwebs, beehives, wasp nests, vegetation, leaves, debris, and all other obstructions that restrict flow to and through roof gutters, drains, and downspouts. The Contractor shall replace loose, displaced, broken, or missing strainers. The Contractor shall re-secure and fasten all loose gutters and downspouts in conjunction with inspection and cleaning. The Contractor shall maintain a log and have it available upon request. The Contractor shall provide on-call service and repairs (not included in the PM schedule) of the roof to include removing of

debris/repairing of the roof gutters /spouts, vents and drains in Accordance with para. 5.2.2. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4

Applicable publications: VOB (Vergabe- und Vertragsordnung fuer Bauleistungen), TM 5-822, AR 420-1, or local equivalents.

5.2.16. Electrically Activated Doors: The contractor shall, annually, visually inspect, test and perform preventative maintenance on automatic sliding doors to ensure proper operation. All maintenance performed shall be accordance with manufacturer's instructions, accepted industry standards, and the PWS. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.17. Sliding Doors: The contractor shall, annually, visually inspect, test and perform preventative maintenance on sliding warehouse doors to ensure proper operation. All maintenance performed shall be accordance with manufacturer's instructions, accepted industry standards, and the PWS. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.17. Backflow Prevention Devices: The contractor shall, annually, visually inspect, test and perform preventative maintenance on Backflow prevention Devices. When required due to defect of end of service life, replace backflow devices via DMO. All maintenance performed shall be accordance with manufacturer's instructions, accepted industry standards, and the PWS. The Contractors shall provide a report of PM completion results and any deficiencies and recommendations to the COR IAW para. 2.2.4.2.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: DIN EN 1717, DIN 1988-100, DVGW worksheet W 570-1 – Requirements for the operation and maintenance of drinking water installations. DIN EN 806-5. US Army Standards or local equivalent

5.2.18. Electric Distribution System: PM and repair of the interior and exterior electric distribution system and associated components, e.g., poles, lines, wire, substations, switching stations, and transformers. The Contractor shall maintain and repair all overhead and underground high voltage electrical devices or the low side of the transformer and the transformers and transfer switches associated with generators. The scope of work may include, but are not limited to the following: operation of Residual-Current Devices (RCD) “circuit breakers” and Earth-leakage Circuit Breaker (ELCB) are in proper working condition, electrical equipment and apparatus insulation, test appliances, check protective conductors, test earth loop impedance, test polarity of installed equipment, check main disconnect devices; cables; overload protection devices; electrical distribution panels; wall switches; receptacles; emergency lighting systems; installed lighting fixtures; intercom systems; public address systems; Energy Management Control Systems; Access Control Systems; and all parts and accessories required to distribute electricity for the use of equipment. The Contractor shall contact the DPW for coordination with the utility provider. The contractor shall determine the electrical capacity for a building upon request by the COR and maintain a records of all inspection findings IAW paragraph 2.2.4.2. The contractor shall inspect electrical components In accordance with approved German standards. In addition, the contractor is required to have required certificates identified in paragraph 2.5.4. Electrical distribution system and components work shall be performed through a DMO.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: VDMA 24186, DIN EN 50491-4-1 VDE 0105, or host nation equivalents

5.2.19. On –Demand Water Heaters: The Contractor shall perform inspection and maintenance or replacement to ensure proper operation of the On-Demand Electric Water Heaters. The Contractor shall perform all inspections and maintenance in accordance with manufacturer’s instructions, accepted industry standards and the PWS. On-Demand Water heaters and components work shall be performed through a DMO.

Required certificates to perform this task: IAW Paragraph 2.5.4

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.20. Windows and Doors: The contractor shall perform required maintenance of all windows and doors. The contractor shall determine if, hinges, locking and closure mechanisms and electronic keypad access devices are in satisfactory physical and working condition. Windows and Doors work shall be performed through a DMO.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.21. Interior / Exterior Plumbing and Ventilation: Plumbing includes potable water systems consisting of hot and cold-water piping, components inside the facility, and out from the facility to the point of demarcation (fence line). Waste, vent, and drain systems consist of piping and components inside the facility and out from the building to the point of demarcation. Potable water systems include domestic water heaters. Water heater types may be electric or fueled by natural gas, oil, or gas/oil combination with either atmospheric or forced draft burners. Heating Pipes consisting of all piping and connections from boiler to each facility across site. The Contractor shall repair, replace, and maintain potable water and waste, vent, and drain systems and components from the isolation valve. Plumbing work shall be performed through a DMO.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.22. Storm Water Collection System: The storm water collection system collects and discharges storm sewer runoff to storm sewer outfalls and drainage. The Contractor shall clean, maintain, inspect, 10% of storm sewer lines annually. In addition repair the storm water collection system that including, but not limited to: pipes, manholes, manhole frames, culverts, grates, catch basin inlets, manholes, outlets, swales, gutters, channels, terraces, underground pipe and conduits, inlets, junction structures, drop structures, chutes, energy dissipaters, and storm sewers. Storm water collection system work (beyond 10% annual cleaning/inspection) shall be performed through a DMO.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.23. Wastewater Collection System: The Contractor shall ensure the Wastewater Collection System is uninterrupted, reliable, continuous, and cost effective in the delivery of all generated wastewater leading from and throughout all buildings and structures, to the final outlet. The Contractor shall perform services that include inspection and maintenance of all Wastewater Collection System components to include, but is not limited to: manholes, manhole frames, underground pipe, sewage lift station, manholes, etc. Wastewater collection system work shall be performed through a DMO.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.24. Fencing: The contractor shall perform maintenance and repairs to fencing. Maintenance and repairs may include but are not limited to, reconstruction of fence from tree damage, mending holes or bottom guard, welding top guard, replacing barbed wire, resetting unstable posts, adjusting gates and walk-thrus, replacing vision screening. Fencing work shall be performed through a DMO.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.25. Façade and Brick Work: The Contractor shall perform maintenance and repairs of façade and brick GFP. Maintenance and repairs may include but are not limited to filling cracks, correcting stair step fractures, stabilizing or making safe falling window seals. Façade and brick work shall be performed through a DMO.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.26. Road, Parking Lot and Walkways: The Contractor shall perform corrective paving actions as needed to the roads, parking lot and walkway areas, including but not limited to: adding dirt and gravel to parking areas, repairing asphalt, regrading, repainting, repairing potholes, clearing drainage areas, asphalt filling or patching; paver correction,

replacement, repositioning; curb reconstruction, surface leveling, concrete patching or repair; repair of surfaces to original condition using proper material, concrete, asphalt, pavers; striping, road painting, or removal of pavement markings. Road, Parking lot, and walkway work shall be performed through a DMO.

Required certificates to perform this task: IAW Paragraph 2.5.4

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.27. Door Locks and Keys: The Contractor shall repair all door and gate locks, and provide for the replacement of keys and hardware. The Contractor shall provide maintenance and repairs to include, but not limited to replacement of key cylinders, producing keys/security keys/master keys, altering key/lock hardware for proper entry/exit operation. All new keys (including fire/emergency/ hazmat keys) or replaced key cylinders shall be provided to COR for key control registrations. Lock and key work shall be performed through a DMO.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.28. Exterior Lighting: The Contractor shall repair or replace all inoperable lights and/or lighting fixtures to include lights and fixtures secured to facilities as well as pole lights. The Contractor shall provide maintenance and repairs to include, but not limited to replacement of light bulbs, replacement of light fixtures, and electrical wiring repairs as required. Exterior lighting shall be performed through a DMO.

Required certificates to perform this task: IAW Paragraph 2.5.4.

Applicable publications: Applicable VDMA, DIN standards, US Army Standards or local equivalent

5.2.29. Outdoors Portable Toilets: The Contractor shall deliver outdoors portable toilets when requested by the COR, due to water outages as a result of material failures or repairs. The unit price shall include a 5-day rental, pickups, transports, return, deposal, soap and treatments and all services in relationship with the container: cleaning and sanitizing. The Contractor shall provide the portable toilets as soon as possible and within twenty-four (24) hour after the request by phone, email, or text.

5.3. Service Contract Reporting

5.3.1 System for Award Management (SAM) Service Contract Report (SCR, (if required)): The Contractor shall report ALL Contractor labor hours (including subcontractor labor hours) required for performance of services provided under this contract for the {Insert Component's Name} via a secure data collection site. The Contractor is required to completely fill in all required data fields through the following web address: www.SAM.gov. Reporting inputs will be for the labor executed during the period of performance during each Government FY, which runs from October 1 through September 30. While inputs may be reported any time during the FY, all data shall be reported no later than October 31 of each calendar year. Contractors may direct questions to the help desk by clicking "View Assistance for SAM.gov" which is located at the top of the SAM.gov website. From there, you can the select "Contact Our Service Desk" which will allow you to contact SAM.gov directly. If contract period of performance ends prior to September 30, the Contractor has 30 calendar days from end date of the contract to complete the SAM SCR requirement.

Steps for Submitting a Service Contract Report (SCR)

1. Go to www.sam.gov and log in.
2. Select Entity Registrations and then select Service Contract Reporting.
3. SAM displays your entities which have service contracts and meet the reporting criteria. Select View by entity to see the service contracts for each entity.
4. Next, select Add for the service contract against which you want to create a Service Contract Report. Each service contract which meets the FAR Subpart 4.1703 reporting thresholds is displayed.
5. You will be taken to the Complete Service Contract Report page. SAM displays the contract details and allows you to report. You are required to enter the following information:
 - Total Amount Invoiced: Total dollar amount invoiced for services performed during the previous Government fiscal year under the contract (this amount should include the prime and any subcontract amount).
 - Prime Contractor Hours Expended: Prime contractor direct labor hours expended on the services performed during the previous Government fiscal year. The amount you enter is automatically divided by 2,080 hours to calculate a Full Time Employee (FTE) equivalent, displayed under the Prime Contractor Hours Expended as Prime Contractor FTEs.
6. Report any required Tier 1 subcontractor information by selecting the Add Tier 1 Subcontract Information button.

7. When you are ready to submit the report, select Submit. This saves your report and returns you to the Select Service Contract page where you can create other SCRs or edit an existing SCR.

Steps for Editing a Submitted Report

1. Follow steps 1-4 above. Any previously submitted SCR will have a View/Edit button instead of an Add button.
2. Select View/Edit. You will be able to view the current SCR, edit available fields, and resubmit the record. You can also delete previously entered information altogether

6.0 Technical Exhibit 2 - Deliverables.

7.0 Related Documents.

7.1 Definitions and Acronyms

7.1.1 Definitions.

7.1.1.1 Acceptable Quality Level (AQL). The AQL is the maximum percent defective (or the number of defects per hundred units) for the purposes of sampling inspection can be considered satisfactory.

7.1.1.2 Alternate Contracting Officer's Representative (ACOR). An employee of the U.S. Government provided by the RA and appointed by the KO to provide support to CORs in monitoring and documenting the Contractor's performance. These alternate surveillance support personnel will serve as on-site representatives of the COR in performance of actual contract surveillance if they meet all COR training, experience requirements, and are appointed by the KO as an ACOR.

7.1.1.3 Ashes. The residue from burned wood, coal, coke, and other combustible material.

7.1.1.4 Bulk Waste. Large items of solid waste such as household appliances, furniture, auto parts, pallets, shelving, piping, stone, concrete rubble, brick, lumber, toys, and other wastes; the size or weight of which, precludes or complicates the handling by normal collection, processing, or disposal methods.

7.1.1.5 Bulky Waste. The waste placed at the collection point or curbside that doesn't fit or is too heavy to be placed in the routine collection container. These wastes include but are not limited to: lumber, scrap metals, bricks, blocks, concrete rubble, stones, toys,

furniture, appliances, logs, limbs, televisions, cabinets, automotive components, power equipment, crates, wheels, de-rimmed tires, electronics and their components, etc.

7.1.1.6 Cannibalize. Remove parts from Government property for use or for Installation on other Government property.

7.1.1.7 Carpet Care. Cleaning and maintenance to keep carpet reasonably free of all stains, soil, and dirt. Methods used for carpet care are vacuum cleaners and carpet shampoos.

7.1.1.8 Child, Youth and School Services (CYS). Overarching naming convention for Child Development Center (CDC), Youth Activity Center, and School Age Services (SAS). CYS is used when referencing all programs.

7.1.1.9 Cleaning. Removing stains, soil, and dirt; accomplished by chemical or mechanical means.

7.1.1.10 Collection. The pickup of accumulated recyclable material, solid waste, including bulky waste, from any collection point, regardless of quantity.

7.1.1.11 Collection Frequency. The number of times collection is performed during a specific time frame.

7.1.1.12 Collection Point. The location designated on the drawings or maps or described in this performance work statement where solid waste, including bulky materials, will be temporarily stored for collection by the Contractor.

7.1.1.13 Commercial Solid Waste. All types of solid waste generated by stores, offices, restaurants, warehouses, and other non-manufacturing activities, excluding residential and industrial waste.

7.1.1.14 Construction and Demolition (C&D) Waste. The waste building materials, packaging and rubble resulting from construction, remodeling, repair, and demolition operation on pavement, housing, commercial buildings, and other structures.

7.1.1.15 Contract Administrator (CA). The official Government representative delegated authority by the KO to administer a contract. This individual, normally working in an appropriate contracting or procurement career field, advises on all technical contractual matters.

7.1.1.16 Contract Discrepancy. A failure of the Contractor to perform IAW contract requirements and specifications, e.g., a failure of the Contractor to provide, or provide on time, the required contract products, or services; or it may result because delivered products or services do not meet specific contract requirements.

7.1.1.17 Contract Discrepancy Report (CDR). A report used to document other than satisfactory Contractor performance. The CDR requires the Contractor to explain, in writing, why performance is other than satisfactory; how performance shall be returned to satisfactory levels; and how recurrence of the problem shall be prevented in the future.

7.1.1.18 Contractor. A supplier or vendor awarded a contract to provide specific supplies or service to the Government. The term used in this contract refers to the prime.

7.1.1.19 Contractor Acquired Property (CAP). Property acquired, fabricated, or otherwise provided by the Contractor for performing a contract. Contractor retains title.

7.1.1.20 Contractor Manpower Reporting Application (CMRA). N/A

7.1.1.21 Contracting Officer (KO). A person with authority to enter into, administer, and or terminate contracts, and make related determinations and findings on behalf of the Government. Note: The only individual who can legally bind the Government.

7.1.1.22 Contracting Officer's Representative (COR). An employee of the U.S. Government appointed by the KO to help administer the contract. Such appointment shall be in writing and shall state the scope of authority and limitations. This individual has authority to provide technical direction to the Contractor as long as that direction is within the scope of the contract, does not constitute a change, and has no funding implications. This individual does NOT have authority to change the terms and conditions of the contract.

7.1.1.23 Curb Side Pick-Up. Collection of solid waste or recyclable materials (to include bulky waste) that is placed next to curb, doorway or alley by the supported activity. This refers to locations that are not serviced by bulk containers (dumpsters or compactors).

7.1.1.24 Damage Caused by Contractor. Damages caused by Contractor employees shall be repaired at no cost to the Government. The Contractor shall notify the COR/ACOR and return the damaged area to its previous condition. The Contractor shall furnish all labor, materials, and equipment to perform the repair work including cultivating and applying seed, sprigging, or placing sod. The Contractor shall maintain all turf repair work to ensure successful growth.

7.1.1.25 Damage Report. The Contractor shall submit a monthly damage report to the COR/ACOR that annotates the damage, corrective action, and date corrected.

7.1.1.26 Debris. Includes, but is not limited to, paper, cans, bottles, cigarette butts, cardboard, plastic, limbs and branches, pine straw and pine cones, leaves, rocks, and other similar items.

7.1.1.27 Defective Service. A service output that does not meet the standard of performance associated with the PWS.

7.1.1.28 Deliverable. Anything that can be delivered; can include non-manufactured things, such as meeting minutes or reports.

7.1.1.29 Equipment. A tangible item that is functionally complete for its intended purpose, durable, nonexpendable, and needed for the performance of a contract. Equipment is not intended for sale and does not ordinarily lose its identity or become a component part of another article, when put into use. Equipment does not include material, real property, special test equipment or special tooling.

7.1.1.30 N/A

7.1.1.31 Fertilization. Fertilization is the process of applying nutrient elements to the soil where the soil has become deficient in nutrients essential for proper plant growth.

7.1.1.32 Food Waste. Organic residue generated by the handling, storage, sale, preparation, cooking and serving of foods.

7.1.1.33 Garbage. Animal and vegetable waste resulting from the handling, preparation, cooking, and consumption of foods.

7.1.1.34 General Fund Enterprise Business System (GFEBS). GFEBS is the U.S. Army's web-based enabled financial, asset, and accounting management system that standardizes, streamlines, and shares critical financial data across the Active Army, the Army National Guard, and the Army Reserves. GFEBS is the work management system that the Directorate of Public Works uses for all order types and projects.

7.1.1.35 Generation. The act or process of producing refuse (solid waste) or recyclable materials.

7.1.1.36 Government-Furnished Property (GFP). Property in the possession of, or directly acquired by, the Government and subsequently furnished to the Contractor for performance of a contract. Government-furnished property includes, but is not limited to, spares and property furnished for repair, maintenance, overhaul, or modification. Government-furnished property also includes Contractor-acquired property if the Contractor-acquired property is a deliverable under a cost contract when accepted by the Government for continued use under the contract.

7.1.1.37 Government Property. All property owned or leased by the Government. Government property includes both Government-furnished property and Government purchased Contractor-acquired property. Government property includes material, equipment, special tooling, special test equipment, and real property. Government property does not include intellectual property and software.

7.1.1.38 Grass Cutting. Grass cutting includes cutting and trimming, within the designated area, all grasses, weeds, and other vegetation which is one (1) inch or less in diameter (at ground level).

7.1.1.39 Hard Surface Floor Care. Hard surface floor care includes, but is not limited to tile, vinyl, rubber tile, mosaic tile, quarry tile, ceramic tile, marble, concrete, terrazzo, and linoleum. Floor care includes, but is not limited to dust mopping, wet mopping, scrubbing, stripping, waxing, re-finishing, or sealing.

7.1.1.40 Hazardous Material. Any item or chemical, which is a “health hazard”, or “physical hazard”, as reflected in Federal Standard (FED-STD) 313 *Material Safety Data and Disposal Data for Hazardous Materials Furnished to Government Activities*, defined in OSHA 29 CFR 1910, and pursuant to FAR 23.301 (Hazardous Materials) Definition. It also includes any other material designated by a Government COR/technical representative as potentially hazardous and requiring safety controls (e.g., pesticides, fertilizers).

7.1.1.41 Installation Design Guide (IDG). IDGs provide standards for site planning, buildings, vehicular and pedestrian circulation, landscaping, site elements (e.g., signage, utilities), force protection, and sustainable design. The IDGs are specific to each Army Installation.

7.1.1.42 Institutional Solid Waste. Waste that is generated by educational, health care, correctional and other institutional facilities.

7.1.1.43 Key Personnel. Contractor personnel evaluated in a source selection process and are used in the performance of a contract. When key personnel are used as an evaluation factor in best value procurement, an offer can be rejected if it does not have a firm commitment from the persons who are listed in the proposal. The prime Contractor is responsible for performance of all Subcontractors.

7.1.1.44 Lavatories, Latrines, or Bathrooms. Commodes, urinals, wash basins, bathtubs, shower stalls, sinks, and shower curtains.

7.1.1.45 Loss of Government Property. Unintended, unforeseen, or accidental loss, damage, or destruction of Government property that reduces the Government’s expected economic benefits of the property. Loss of Government property does not include occurrences such as purposeful destructive testing, obsolescence, normal wear and tear, or manufacturing defects. Loss of Government property includes, but is not limited to:

- a. Items that cannot be found after a reasonable search,
- b. Theft,
- c. Damage resulting in unexpected harm to property requiring repair to restore the item to usable condition, or
- d. Destruction resulting from incidents that render the item useless for its intended purpose or beyond economical repair.

7.1.1.46 Lot. A collection of service outputs from which a sample is to be drawn and inspected to determine conformance with the standard. This definition applies to the Performance Requirements Summary (PRS), not the word "lot" in Section B of the contract.

7.1.1.47 Lot Size. The number of service outputs in a lot. This definition applies to the PRS, not the words "lot size" in Section B of the contract.

7.1.1.48 Material. Property that is consumed or expended during the performance of a contract, component parts of a higher assembly, or items that lose their individual identity through incorporation into an end-item. Material does not include equipment, special tooling, and special test equipment or real property.

7.1.1.49 Material Handling Area. The material handling area is used for the accumulation and preparation of bulk solid waste or recyclable materials for transportation to a solid waste management facility.

7.1.1.50 Non-Combustible Material. Material that doesn't burn at ordinary temperatures.

7.1.1.51 Non-Personal Services. The personnel rendering the services are not subject, either by the contract's terms or by the manner of its administration, to the supervision and control usually prevailing in relationships between the Government and its employees. Non-personal service contracts are authorized by the Government IAW FAR 37.104, under general contracting authority, and do not require specific statutory authorization.

7.1.1.52 Organic Storage Site. Area of accumulation for organic materials (e.g., leaves, logs, limbs, and grass clippings).

7.1.1.53 Performance Indicator. The characteristic of an output of a work process that can be measured.

7.1.1.54 Performance Requirements Summary (PRS). Identifies the key service outputs of the contract that will be evaluated by the Government to ensure contract performance standards are met by the Contractor (other services may also be inspected under the authority of the Inspection of Service Clause).

7.1.1.55 Physical Security. Actions that prevent the loss or damage of Government property.

7.1.1.56 Plant. A living organism, of the kind exemplified by trees, shrubs, herbs, grasses, ferns, and mosses, typically growing in a permanent site, absorbing water, and inorganic substances through its roots.

7.1.1.57 Property. All tangible property, both real and personal.

7.1.1.58 Property Administrator (PA). An authorized representative of the KO, appointed IAW agency procedures, responsible for administering the contract requirements and obligations relating to Government property in the possession of a Contractor.

7.1.1.59 Property Records. Records created and maintained by the Contractor in support of its stewardship responsibilities for the management of Government property.

7.1.1.60 Provide. To furnish, as in Government-furnished property, or to acquire, as in Contractor-acquired property.

7.1.1.61 Pruning. Pruning is selectively removing unwanted growth to make a plant or tree grow or respond in a desired manner. Pruning differs from "shearing". Pruning involves selection and judgment. "Shearing" means clipping all growth on a plant at a uniform distance and shape.

7.1.1.62 Public Traffic Areas. Lobbies, hallways, corridors, stairwells, meeting rooms, and lavatories.

7.1.1.63 Quality Assurance (QA). Verification that services being performed by the Contractor are IAW acceptable standards.

7.1.1.64 Quality Assurance Evaluator (QAE). A Government representative responsible for performing surveillance and inspection of Contractor performance.

7.1.1.65 Quality Assurance Surveillance Plan (QASP). An organized document written by the Government specifying the surveillance methodology used for surveillance of Contractor performance.

7.1.1.66 Quality Control. All necessary measures taken by the Contractor to assure that the quality of an end product or service shall meet contract requirements.

7.1.1.67 Raise. Selective pruning of limbs, identified by the COR, or limbs that pose a public safety hazard with a minimum clearance of 14 feet over streets, parking lots, and driveways; eight (8) feet over walk areas; four (4) feet over buildings and three (3) feet from buildings and streetlights, IAW established industry standards.

7.1.1.68 Random Number Table. A table of numbers arranged in random fashion; a table used to select random samples.

7.1.1.69 Random Sample. A sampling method whereby each service output in a lot has an equal chance of being selected.

7.1.1.70 Random Sampling. A method for looking at a few individual items in a lot to measure the quality of that lot against a standard.

7.1.1.71 Real Property. DoD Lands, buildings, structures, utility systems, improvements, and appurtenances, thereto that includes equipment attached to and made part of buildings and structures, but not movable equipment. See Federal Management Regulation 102-71.20 (41 CFR 102-71.20).

7.1.1.72 Recycling. The act of recovering materials from the solid waste stream, separating them by commodity, and returned to the economic mainstream as raw material.

7.1.1.73 Recycling Materials. Commodities include corrugated cardboard, wood, and plastic pallets.

7.1.1.74 Recycling Facility. Any facility employed, beyond the initial collection processes and managing recycling which include, but not limited to electronics, organics, plastics, metals, paper, and cardboard.

7.1.1.75 Regulated Medical Waste. Waste not specifically excluded from the restrictions of Federal regulations, and which meets the criteria listed in 40 CFR 259.

7.1.1.76 Refuse. All garbage, ashes, debris, trash, rubbish and items intended for disposal that are generated in conjunction with the activities in the areas covered in this contract. Items excluded are explosives, incendiary waste, hazardous waste, and pathological waste resulting from medical and radiological processes.

7.1.1.77 Refuse Collection. A system of collecting and transporting solid waste from pick-up stations to points of disposal.

7.1.1.78 Refuse/Recycling Storage Containers. Cans, drums, bins, bags, boxes, crates, sidewalk litter containers, dumpsters, roll-off containers, or similar receptacles which are used for the temporary storage of solid waste while awaiting collection. The term "container" used in this document shall have the same meaning as solid waste storage container.

7.1.1.79 Reporting Labor Hours. N/A.

7.1.1.80 Residential Solid Waste. Waste generated by the normal activities of households, including, but not limited to: food waste, rubbish, ashes and bulky waste.

7.1.1.81 Sample Size. The number of outputs in the sample; a group of one or more tasks drawn from the specified performance.

7.1.1.82 Sampling. A sample consists of one (1) or more service outputs drawn from a lot IAW random sampling procedures to be evaluated by Government personnel.

7.1.1.83 Scavenging. The uncontrolled and unauthorized removal of materials at any point of the solid waste management stream.

7.1.1.84 Sensitive Property. Property potentially dangerous to the public safety or security if stolen, lost, or misplaced, or that shall be subject to exceptional physical security, protection, control, and accountability. Examples include weapons, ammunition, explosives, controlled substances, radioactive materials, hazardous materials or wastes, or precious metals.

7.1.1.85 Service/Maintain. These words are interchangeable.

7.1.1.86 Shrub. A woody plant with several perennial stems. It will usually have a height less of than thirteen (13) feet and stems no more than about three (3) inches in diameter.

7.1.1.87 Soil. Includes, but is not limited to dust, dirt, stains, grease, smudges, streaks, spots, lint, or odors. Soil can be removed chemically, mechanically, or by a combination of both. Mechanical soil removal is removing soil with a machine such as a vacuum cleaner. Chemical soil removal is removing soil with a liquid that contains cleaning agents such as detergents, surfactants, and emulsifiers. The combination of chemical and mechanical methods such as an automatic floor scrubbing machine, uses the chemical method to breakdown and loosen soil which then the mechanical method picks up and carries the soil away. Which soil removal method is used depends on the cleaning objectives and on size, location, and type of surface to be cleaned and is the prerogative of the Contractor.

7.1.1.88 Solid Waste. Garbage, refuse, sludge, and other waste materials not excluded by Federal regulations. Solid waste is any solid, liquid, semi-solid, or contained gaseous material resulting from institutional, industrial, commercial, mining, agricultural, or community operations and activities. Solid wastes are accumulated, stored, or treated before being discarded. A material is discarded if abandoned and not used, reused, reclaimed, or recycled by being disposed of, burned, or treated. Regulated medical wastes are not included in this category.

7.1.1.89 Solid Waste Management Facility (SWMF). Any facility employed, beyond the initial collection processes and managing solid waste including, but not limited to: storage areas or facilities, transfer stations, rail haul or barge haul facilities, landfills, disposal facilities, solid waste facilities, surface impoundment and waste oil storage, repossessing, refining facilities, recyclable handling, recovery facilities and waste tire storage facilities.

7.1.1.90 Source Separation. Source separation is the act of separating recyclable materials at their point of generation by the waste generator.

7.1.1.91 Spray Buffing. Procedure to apply a light coat of wax to maintain the waxed floor after removing minor scratches and scuff marks.

7.1.1.92 Spot Cleaning. Cleaning small areas of carpet by vacuuming, hot water extraction, or shampooing due to accumulation of dirt or soil on heavy traffic patterns or due to leaks or spillage on small areas of floor surface. Spot cleaning is also removal of spots from walls, ceilings, floors, and furniture surfaces.

7.1.1.93 Standard. A measure of comparison; an acceptability criterion; a benchmark or yardstick against which a service will be measured.

7.1.1.94 Stairwell Cleaning. Cleaning of all stairwells in any building. This process includes steps, landing, walls, and handrails.

7.1.1.95 Street Wastes. Materials picked up by manual or mechanical sweepings of alleys, streets, and sidewalks. Waste from solid waste receptacles and catch basins.

7.1.1.96 Stripping. The removal of floor finishes down to the flooring material. Stripping of a floor means floor surfaces are free of dirt, stains, deposits, cleaning solutions, standing water, and have a uniform appearance when dry. Stripping of floor surfaces includes utilizing procedures and equipment to prevent safety hazards.

7.1.1.97 Subcontractor. One that enters into a contract with a prime Contractor. The Government does not have privity of contract with the Subcontractor.

7.1.1.98 Tonnage. Weight measured in tons (not imperial).

7.1.1.99 Transfer Station. A transfer station is a facility which processes collected solid waste in a particular area for transportation to a solid waste management facility.

7.1.1.100 Trash Removal. Trash removal includes the pickup and removal of all papers and other debris in buildings. This includes but is not limited to wastebaskets, boxes, or any substance used for refuse.

7.1.1.101 Tree. A woody plant having one erect perennial stem (trunk), at least three inches in diameter, at a point 4-1/2 feet above the ground, a definitely formed crown of foliage, and mature height of at least 13 feet.

7.1.1.102 Trimming. Cutting of grass and other vegetation around grounds obstacles that prevent mowing.

7.1.1.103 Unit Acquisition Cost.

- a. For Government-furnished property, the dollar value assigned by the Government and identified in the contract; and
- b. For Contractor-acquired property, the cost derived from the Contractor's records that reflect consistently applied generally accepted accounting principles.

7.1.1.104 Vector. A carrier, usually an arthropod, which can transmit a pathogen from one organism to another.

7.1.1.105 Wash. The act of cleansing using water and soap or detergent.

7.1.1.106 Wide Area Workflow (WAWF). A secure web-based system for electronic invoicing, receipt, and acceptance. WAWF allows Government vendors to submit and track invoices and receipt or acceptance documents over the web allowing Government personnel to process those invoices in a real-time, paperless environment.

7.1.1.107 Work Day. The number of hours per day the Contractor provides services IAW the contract.

7.1.1.108 Work Week. Monday through Friday, unless specified otherwise.

7.1.1.109 Yard Wastes. Materials such as: tree and shrub branches, trimmings, brush, grass clippings, leaves, Christmas trees, weeds, etc.

7.1.2 Acronyms.

ACC	Army Contracting Command
ACOR	Alternate Contracting Officer's Representative
AFARS	Army Federal Acquisition Regulation Supplement
AMC	Army Materiel Command
ANSI	American National Standards Institute
AQL	Acceptable Quality Level
ArMA	Army Maintenance Application
AR	Army Regulation
ARC	Army Resource Center
ATO	Anti-Terrorism Officer
CAP	Contractor Acquired Property
CDC	Child Development Center
CDRL	Contract Data Requirements List
CFE	Contractor Furnished Equipment
CFM	Contractor Furnished Material
CFP	Contractor Furnished Property
CFR	Code of Federal Regulations
CLIN	Contract Line Item Number
CMRA	Contractor Manpower Reporting Application
CONUS	Continental United States (excludes Alaska and Hawaii)
COR	Contracting Officer's Representative
CORT	Contracting Officer's Representative Tool
CPARS	Contractor Performance Assessment Reporting System
DA	Department of the Army
DCMA	Defense Contract Management Agency
DES	Directorate of Emergency Services
DFARS	Defense Federal Acquisition Regulation Supplement
DID	Data Item Description
DoD	Department of Defense
DOL	Department of Labor
DOT	Department of Transportation
DPW	Directorate of Public Works
ECO	Environmental Compliance Officer
EM	Engineering Manual, U.S. Army Corps of Engineers (USACE)

EO	Executive Order
EPA	Environmental Protection Agency
ERDC	Engineering Research Development Center
FAR	Federal Acquisition Regulation
FIPS	Federal Information Processing Standards
FPCON	Force Protection Condition
GFE	Government-Furnished Equipment
GFEBS	General Fund Enterprise Business System
GFM	Government-Furnished Material
GFP	Government-Furnished Property
HLO	High Level Objective
HQDA	Headquarters Department of the Army
HSPD	Homeland Security Presidential Directive
IAW	In Accordance With
IMCOM	Installation Management Command
IPM	Integrated Pest Management
IPMC	Integrated Pest Management Coordinator
IPMP	Integrated Pest Management Plan
IT	Information Technology
KO	Contracting Officer
N/A	Not Applicable
NGB	National Guard Bureau
NLT	Not Later Than
OCI	Organizational Conflict of Interest
OCONUS	Outside Continental United States (includes Alaska and Hawaii)
OMB	Office of Management and Budget
OSHA	Occupational Safety and Health Administration
PAM	Pamphlet
PM	Preventive Maintenance
POC	Point of Contact
PoP	Period of Performance
PPIRS	Past Performance Information Retrieval System
PRS	Performance Requirements Summary
PUB	Publication
PWS	Performance Work Statement
QA	Quality Assurance
QAP	Quality Assurance Program
QASP	Quality Assurance Surveillance Plan
QC	Quality Control
QCP	Quality Control Plan
RCRA	Resource Conservation and Recovery Act
SDS	Safety Data Sheets
SF	Standard Form
TE	Technical Exhibit
USARC	U.S. Army Reserve Command
U.S.C.	United States Code

VCE	Virtual Contracting Enterprise
VIP	Very Important Person
WAWF	Wide Area Workflow
WD	Wage Determination

7.2 Applicable Directives, Publications.

ACC PAM 70-1	Interim Army Contracting Command – Contracting Officer's Representative Policy Guide
AASHTO-T11	Standard Method of Test for Materials Finer Than 75-µm (No. 200) Sieve in Mineral Aggregates by Washing
ANSI A300	Standard Practices for Tree Care Operations
ANSI Z60.1	American Standards for Nursery Stock
ANSI Z87.1-2003	Practice for Occupational and Educational Personal Eye and Face Protection Devices
ANSI Z133.1	Safety Requirements for Tree Care Operations
ANSI/ASQC-Z1.4	National American Standard
ANSI Z245.1	Mobile Refuse Collection and Compaction Equipment – Safety Requirements
AR 11-27	Army Energy Program
AR 40-5	Preventive-Medicine (Child Development Centers)
AR 40-400	Medical Services Patient Administration
AR 70-13	Management and Oversight of Service Acquisitions
AR 190-5	Motor Vehicles Traffic Supervision
AR 200-1	Environmental Protection and Enhancement
AR 200-3	Natural Resources; Land, Forest, and Wildlife Management
AR 200-4	Cultural Resources Management
AR 200-5	Pest Management
AR 385-10	Army Safety Program

AR 385-40	Army Accident Investigation and Reporting
AR 420-1	Army Facilities Management
AR 420-70	Facilities Engineering (Transportation Infrastructure and Dams)
AR 420-90	Fire Emergency Services
AR 530-1	Operations Security
AR 600-50	Standards of Conduct for Department of Army Personnel
AR 600-63	Army Health Promotion
AR 608-10	Child Development Services
AR Directive 2014-23	Conduct of Screening and Background Checks for Individuals Who Have Regular Contact with Children in Army Programs
29 CFR Part 1910	Occupational Safety and Health Standards
40 CFR	Protection of the Environment
40 CFR Subchapter I	Solid Wastes
40 CFR 202	Motor Carriers Engaged in Interstate Commerce
40 CFR 257	Criteria for Classification of Solid Waste Disposal Facilities and Practices
40 CFR Part 302	Protection of Environment, Designation, Reportable Quantities and Notification
49 CFR 390-396	Motor Carrier Safety Standards
49 CFR 571	Federal Motor Vehicle Safety Standards
Clean Air Act (CAA)	
Clean Water Act (CWA)	
Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA)	

DA PAM 385-40	Army Accident Investigations and Reporting
DA PAM 420-1-1	Housing Management*
DoD 4160.21-M	Defense Materiel Disposition Manual
DoD Directive 5500.7-R	Joint Ethics Regulation
DoDI 1402.5	Criminal History Background Checks On Individuals in Child Care Services
DoDI 4150.07	DoD Pest Management Program
DoDI 5000.72	DoD Standard for Contracting Officer's Representative (COR) Certification
EM-385-1-1	Safety and Health Requirements Manual
EO 13423	Strengthening Federal Environmental, Energy, and Transportation Management
EO 13693	Planning for Federal Sustainability in the Next Decade
EPA, Method 9095	Paint Liquids Filter Test
EPA, SW-846	Test Methods for Evaluating Solid Wastes, Physical/Chemical Methods
FC 3-260-06F	Air Force Design, Construction, Maintenance, and Evaluation of Snow and Ice Airfields in Antarctica 06-01-2015
Federal Standard #313	Material Safety Data and Disposal Data for Hazardous Materials Furnished to Government Activities
Federal Standard #595	Colors
FIFRA	Federal Insecticide, Fungicide, and Rodenticide Act
FIPS PUB 201-2	Personal Identity Verification (PIV) of Federal Employees and Contractors
Garrison's Snow, Ice, and Sand Removal Control Plan	
HSPD 12 Common	Homeland Security Presidential Directive 12 Policy for a

tor	Identification Standard for Federal Employees and Contractor
IDG	Installation Design Guide
NFPA 1.12-2	Combustible Fibers
OMB M-05-24	Office of Management and Budget (OMB) Guidance Implementation of Homeland Security Presidential Directive (HSPD) 12 – Policy for a Common Identification Standard for Federal Employees and Contractors
OPORD 13-153	Enterprise Municipal Services Performance Standards
SF 95	Position of Public Trust
TB MED 530 5-28(h)(i)	Tri-Service Food Code
TM 5-623	Pavement Maintenance Management
TM 5-624	Maintenance and Repair of Surface Areas
TM 5-634	Solid Waste Management
TM 5-683	Electrical Interior Facilities
TM 5-820-4	Drainage for Areas other than Airfields
TM 9-6150-226-13	Electrical Feeder System
UFC 1-200-01	DoD Building Code (General Building Requirements)
UFC 4-010-1	DoD Minimum Antiterrorism Standards for buildings (Change 1)
UFC 4-021-01	Design and O&M for Mass Notification Systems
UFC 4-021-02NF	Security Engineering Electronic Security Systems
UFC 3-101-01	Architecture 11-28-2011
UFC 3-110-03	Roofing, with Change 1 05-01-2012
UFC 3-110-04	Roofing Maintenance and Repair 01-11-2007
UFC 3-120-01	Design: Sign Standards, with Change 2 03-01-2014

UFC 3-120-10	Interior Design, with Change 1 06-15-2006
UFC 3-190-06	Protective Coatings and Paints 01-16-2004
UFC 3-201-01	Civil Engineering 06-01-2013
UFC 3-201-02	Landscape Architecture, with Change 1 02-23-2009
UFC 3-210-10	Low Impact Development 07-01-2015
UFC 3-220-01	Geotechnical Engineering 11-01-2012
UFC 3-220-04	Backfill for Subsurface Structures 01-16-2004
UFC 3-220-05	Dewatering and Groundwater Control 01-16-2004
UFC 3-220-06	Grouting Methods and Equipment 01-16-2004
UFC 3-220-08	Engineering Use of Geotextiles 01-16-2004
UFC 3-220-10N	Soil Mechanics 06-08-2005
UFC 3-230-01	Water Storage, Distribution, and Transmission, with Change 2 11-01-2012
UFC 3-230-02	O&M: Water Supply Systems 07-10-2001
UFC 3-230-03	Water Treatment 11-01-2012
UFC 3-230-06A	Subsurface Drainage, with Changes 1-2 01-16-2004
UFC 3-240-01	Wastewater Collection, with Change 1 11-01-2012
UFC 3-240-02	Domestic Wastewater Treatment 11-01-2012
UFC 3-240-03N	Wastewater Treatment System Augmenting Handbook Operation and Maintenance 01-16-2004
UFC 3-240-05A	Solid Waste Incineration 01-16-2004
UFC 3-240-10A	Sanitary Landfill 01-16-2004
UFC 3-240-13FN	Industrial Water Treatment Operation and Maintenance 05-25-2005

UFC 3-250-01FA	Pavement Design for Roads, Streets, Walks, and Open Storage Areas 01-16-2004
UFC 3-250-03 2001	Standard Practice Manual for Flexible Pavements 05-15-2001
UFC 3-250-04	Standard Practice for Concrete Pavements, with Change 2 01-16-2004
UFC 3-250-06	Repair of Rigid Pavements Using Epoxy Resin Grouts, Mortars and Concretes 01-16-2004
UFC 3-250-07	Standard Practice for Pavement Recycling 01-16-2004
UFC 3-250-08FA	Standard Practice for Sealing Joints and Cracks in Rigid and Flexible Pavements 01-16-2004
UFC 3-250-09FA	Aggregate Surfaced Roads and Airfields Areas 01-16-2004
UFC 3-250-11	Soil Stabilization for Pavements 01-16-2004
UFC 3-260-01	Airfield and Heliport Planning and Design 11-17-2008
UFC 3-260-02	Pavement Design for Airfields 06-30-2001
UFC 3-260-03	Airfield Pavement Evaluation 04-15-2001
UFC 3-260-05A	Marking of Army Airfield Heliport Operational and Maintenance Facilities, with Change 1 01-16-2004
UFC 3-260-11 FA	Model Design-Build (D-B) Request for Proposal (RFP) For Airfield Contracts 05-25-2005
UFC 3-260-16 FA	FA Airfield Pavement Condition Survey Procedures Pavements 01-16-2004
UFC 3-260-17	Dust Control for Roads, Airfields and Adjacent Areas 01-16-2004
UFC 3-270-01	Asphalt Maintenance and Repair 03-15-2001
UFC 3-270-02	Asphalt Crack Repair 03-15-2001
UFC 3-270-03	Concrete Crack and Partial-Depth Spall Repair 03-15-2001
UFC 3-270-04	Concrete Repair 03-15-2001

UFC 3-270-05	Paver Concrete Surfaced Airfields Pavement Condition Index (PCI) 03-15-2001
UFC 3-270-06	Paver Asphalt Surfaced Airfields Pavement Condition Index (PCI) 03-15-2001
UFC 3-270-07	O&M: Airfield Damage Repair 08-12-2002
UFC 3-270-08	Pavement Maintenance Management 01-16-2004
UFC 3-280-01A	Guidance for Ground Water/Fuel Extraction and Ground Water Injection Systems 01-16-2004
UFC 3-280-04	Army Filtration of Liquids 12-17-2003
UFC 3-301-01	Structural Engineering, with Change 1 06-01-2013
UFC 3-310-04	Seismic Design for Buildings 06-01-2013
UFC 3-310-08	Non-Expeditionary Bridge Inspection, Maintenance and Repair, with Change 1 08-16-2010
UFC 3-320-06A	Concrete Floor Slabs on Grade Subjected to Heavy Loads 03-01-2005
UFC 3-340-01	Design and Analysis of Hardened Structures to Conventional Weapons Effects (FOUO) 06-30-2002
UFC 3-340-02	Structures to Resist the Effects of Accidental Explosions, with Change 2 12-05-2008
UFC 3-400-02	Design: Engineering Weather Data 02-28-2003
UFC 3-401-01	Mechanical Engineering 07-01-2013
UFC 3-410-01	Heating, Ventilating, and Air Conditioning Systems, with Change 1 07-01-2013
UFC 3-410-02	Lonworks (R) Direct Digital Control for HVAC and Other Local Building Systems, with Change 1 05-01-2012
UFC 3-410-04N	Industrial Ventilation 10-25-2004
UFC 3-420-01	Plumbing Systems, with Change 9 10-25-2004

UFC 3-420-02FA	Compressed Air, with Change 1 05-15-2003
UFC 3-430-01FA	Heating and Cooling Distribution Systems 07-25-2003
UFC 3-430-02FA	Central Steam Boiler Plants, with Change 1 05-15-2003
UFC 3-430-07	Operations and Maintenance: Inspection and Certification of Boilers and Unfired Pressure Vessels, with Change 4 07-24-2003
UFC 3-430-08N	Central Heating Plants 01-16-2004
UFC 3-430-09	Exterior Mechanical Utility Distribution, with Change 1 01-16-2004
UFC 3-430-11	Boiler Control Systems 02-14-2001
UFC 3-440-01	Facility-Scale Renewable Energy Systems 07-01-2015
UFC 3-440-05N	Tropical Engineering, with Changes 1-2 01-16-2004
UFC 3-450-01	Noise and Vibration Control 05-15-2003
UFC 3-470-01	Lonworks (R) Utility Monitoring and Control System (UMCS) 05-01-2012
UFC 3-460-01	Design: Petroleum Fuel Facilities, with Change 2 08-16-2010
UFC 3-460-03	O&M: Maintenance of Petroleum Systems 01-21-2003
UFC 3-501-01	Electrical Engineering, with Change 3 02-03-2010
UFC 3-510-01	Foreign Voltages and Frequencies Guide, with Change 2 03-01-2005
UFC 3-520-01	Interior Electrical Systems, with Change 3 02-03-2010
UFC 3-520-05	Stationary Battery Areas, with Change 1 05-01-2015
UFC 3-530-01	Interior and Exterior Lighting Systems and Controls 04-01-2015
UFC 3-535-01	Visual Air Navigation Facilities 11-17-2005

UFC 3-540-01	Engine-Driven Generator Systems for Backup Power Applications 08-01-2014
UFC 3-550-01	Exterior Electrical Power Distribution with Change 1 02-03-2010
UFC 3-555-01N	400 Hertz Medium Voltage Conversion/Distribution and Low Voltage Utilization Systems 01-16-2004
UFC 3-560-01	Electrical Safety, O&M, with Change 5 12-06-2006
UFC 3-570-02A	Cathodic Protection 03-01-2005
UFC 3-570-02N	Electrical Engineering Cathodic Protection 01-16-2004
UFC 3-570-06	O&M: Cathodic Protection Systems 01-31-2003
UFC 3-575-01	Lightning and Static Electricity Protection Systems 07-01-2012
UFC 3-580-01	Telecommunications Building Cabling Systems Planning and Design 06-22-2007
UFC 3-580-10	Navy and Marine Corps Intranet (NMCI) Standard Construction Practices, with Changes 1-3 07-14-2004
UFC 3-600-01	Fire Protection Engineering for Facilities, with Change 3 09-26-2006
UFC 3-601-02	Operations and Maintenance: Inspection, Testing, and Maintenance of Fire Protection Systems; 09-08-2010
42 U.S.C. 6901	Resource Conservation and Recovery Act (RCRA), Solid Waste Disposal Act (SWDA) of 1976, as amended, including Subtitle D

7.3 Technical Exhibits (TE) and Attachments.

7.3.1 Technical Exhibit 1 – Performance Requirements Summary (Section 4.0)

7.3.2 Technical Exhibit 2 – Deliverables Schedule (Section 6.0)

7.3.3 Technical Exhibit 3 - Quality Assurance Surveillance Plan (QASP)

7.3.4 Attachment 1 – Equipment Inventory (Attachment 1)

7.3.5 Attachment 2 – Estimated Annual Workload of and DMOs (Attachment 2)

7.3.6 Attachment 3 – Facility Location and Map (Attachment 3)

7.3.7 Facility Floor Plans (Separate File) (Attachment 4)

7.3.8 Price Book (Separate File) (Attachment 5)

7.4 Government-Furnished Material (GFM)/Property (GFP)/Equipment (GFE).

7.4.1 Utilities. (If applicable) The Government will provide all utilities in the facility will be available for the Contractor's use in performance of tasks outlined in this PWS, access to water and electrical services. The Contractor shall obtain written approval from DPW prior to installing connections and meters. The Contractor shall instruct employees in utilities conservation practices. The Contractor shall be responsible for operating under conditions that preclude the waste of utilities, which include turning off the water faucets or valves after using the required amount to accomplish cleaning vehicles and equipment

7.5 Contractor-Furnished Material (CFM)/Property (CFP)/Equipment (CFE)

7.5.1 All Contractor furnished, material, property and equipment shall meet applicable Federal, State, Local, DoD and Army Laws, Codes, and Regulations. Examples are provided below:

7.5.2 Contractor-Furnished Material and Responsibilities. The Contractor shall furnish all supplies, equipment, facilities, and services required to perform work under this contract.

7.5.2 Contractor-Furnished Items. The Contractor shall provide all facilities, vehicles, equipment, parts, tools, fuel, oil, materials, and any other items required to perform all Contract requirements. The Contractor's property shall be operational as intended by the manufacturer, and be safe, clean, and suitable for use at a Military Installation. All Contractor furnished property and equipment are subject to KO inspection at all times.

7.5.2.1 Identification of Contractor Vehicles and Trailers. The company name shall be displayed on each of the Contractor's vehicles and trailers in a manner and size that is clearly visible. All vehicles and trailers shall display a valid State license plate and meet current local and State vehicle registration requirements.

7.5.2.2 The Contractor's equipment and other slow-moving equipment shall be equipped with the slow-moving vehicle sign.

7.5.3. Contractor Facilities. N/A

7.5.4 Damage Caused by Contractor. Damages caused by Contractor employees shall be repaired at no cost to the Government. In all instances where Contractor's employees damage Government property or equipment, the Contractor shall provide a verbal report to the KO within four (4) hours of occurrence. The Contractor shall notify the COR/ACOR and return the damaged area to its previous condition. All damage done by the Contractor and/or his sub-Contractor/s shall become the Contractor's responsibility. The Contractor shall furnish all labor, materials and equipment to perform the repair work including cultivating and applying seed, sprigging, or placing sod. All turf repair work shall be maintained to ensure successful growth.

7.5.5 Third Party Repair Damaged Areas. In the event the Contractor discovers damages caused by another party, the Contractor shall notify the KO and COR of the extent of the damage and proposed corrective action. The Contractor shall make no repairs until authorized by the KO.

7.5.6 Equipment Replacement (Government Property). If an item of Government property is determined by the Contractor to be beyond economical repair, the Contractor shall recommend to the KO and COR in writing that such equipment be replaced. Substantiating data to support the recommended replacement shall be included. If the Government decides that such equipment should be replaced or repaired, and replacement or repair is authorized, the Contractor shall accomplish the work IAW the appropriate work level criteria. Disposal instructions will be provided by the KO and COR.

7.5.7 Permits. The Contractor shall obtain all appointments, licenses, and permits required for performance of work and for complying with all applicable Federal, State, Local, and Host Nation Laws and regulations. Permits and licenses shall be provided to the COR/ACOR before work commences.

7.6 U.S. Department of Labor (DOL) Wage Determination (WD) . N/A

**ATTACHMENT 1
EQUIPMENT INVENTORY**

**ATTACHMENT 2
ESTIMATED WORKLOAD DATA**

ITEM	FREQUENCY	ESTIMATED QUANTITY
------	-----------	--------------------

1	Preventative Maintenance and Inspections	HOURS	5384
3	On-Call Repairs & Maintenance (T&M)	HOURS	3362
4	On-Call Outdoor Portable Toilets	JOBS	30

On-Call Repairs & Maintenance (T&M)	Estimated Quantity (Hours)
1. Regular Repair Monday-Saturday between 07:00 --17:00 hrs	3200
2. Night Time Work Monday-Saturday between 17:00 --07:30 hrs	300
3. Sunday and Holiday Work Between 00:00 – 24:00 hrs	40

ATTACHMENT 3 FACILITY LOCATION

