

**Annex A—Overarching
Performance Work Statement (PWS)**

Base Operations and Maintenance Contract

Fort Stewart/Hunter Army Airfield, GA

3 Apr 2023

Table of Contents

1.0	INTRODUCTION.....	3
1.1	Background.....	3
1.2	Objectives.....	3
1.3	Climatic Conditions.....	4
1.4	Facility Access.....	4
1.5	Traffic Flow.....	4
1.6	Drainage.....	4
1.7	Restoration of Landscape Damage.....	4
1.8	Dust Suppression.....	4
1.9	Utility Location.....	5
1.10	Excavation Permits.....	5
1.11	Work Clearance.....	5
2.0	REQUIREMENTS.....	5
2.1	Description of Services.....	5
2.2	Work Management.....	17
2.3	As-Built.....	27
2.4	Salvage.....	29
2.5	Special Requirements.....	29
3.0	PERFORMANCE REQUIREMENTS AND STANDARDS.....	37
3.1	Performance Task Requirements, Standards and Acceptable Quality Level (AQL)	37
3.2	Quality Assurance.....	37
3.3	Quality Control Plan (QCP).....	37
3.4	Quality Control Files.....	39
3.5	Customer Feedback Program.....	39
4.0	PERFORMANCE TASK REQUIREMENTS.....	39

5.0	COMMON LEVELS OF SUPPORT (CLS)	40
6.0	DELIVERABLES	41
7.0	RELATED DOCUMENTS	41
7.1	Definitions and Acronyms.....	41
7.2	Applicable Directives, Publications.....	57
7.3	Technical Exhibit (TE)	72
7.4	Government-Furnished Material (GFM)/Government-Furnished Facilities (GFF)/Equipment (GFE).....	72
7.5	Contractor-Furnished Material (CFM)/Property (CFP)/Equipment (CFE).....	73
7.6	U.S. Department of Labor (DOL) Wage Determination (WD).....	74

1.0 Introduction.

This is a non-personal services contract to provide Base Operation and Support Services for the U.S. Army Garrison Fort Stewart (FS) and Hunter Army Airfield (HAAF), GA. The Government will not exercise any supervision or control over the contract service providers. The Contractor shall perform to the standards specified in this Performance Work Statement (PWS). Contract service providers shall be accountable solely to the Contractor who, in turn is responsible to the Government. The Contractor shall provide all personnel, equipment, supplies, facilities, transportation, tools, materials, supervision, and other items and non-personal services necessary as defined in this PWS. The Contractor is responsible for providing all parts required for Preventive Maintenance Orders (PMOs) and all repair parts required for Demand Maintenance Orders (DMOs).

1.1 Background. FS/HAAF has contracted the Base Operations and Support Services since July 2001. The contracted effort has changed over the years to meet Division, Garrisons, and Directorate of Public Works (DPW) missions for our customers. The work described in this contract involves a broad range of non-personal base operations and maintenance services in support of DPW headquartered at FS and HAAF, Georgia.

FS is located near Hinesville, GA, 41 miles southwest of Savannah, GA and is the home of the 3rd Infantry Division, which is the Army's Premier Power Projection Platform on the Atlantic Coast. It is the largest, most effective and efficient armor training base east of the Mississippi, covering 280,000 acres including parts of Liberty, Long, Tattnall, Evans, Chatham, and Bryan Counties in Southeast GA.

HAAF is located in historic Savannah, GA and is home to Army's longest runway on the east coast (11,375 feet) and the Truscott Air Deployment Terminal. Together these assets are capable of deploying units such as heavy, armored forces the 3rd Infantry Division or the elite light fighters of the 1st Battalion, 75th Ranger Regiment.

1.2 Objectives. The Contractor shall ensure all work accomplished in the performance of this PWS meets all maintenance and repair standards consistent with the original equipment manufacturer's recommendations; all applicable Federal, State, and local laws, regulations, and directives to include, but not limited to, the applicable publications listed in Section 7.0, Related Documents. Historical workload data is incorporated at Technical Exhibit (TE) 02, 2A, 2B and 2C.

1.2.1 The Contractor shall ensure all work in support of mission requirements tendered to the Government for acceptance conforms to the measurable performance standards of quality, timeliness, and quantity specified in the PWS of this contract. Without additional expense to

the Government, the Contractor shall obtain/ensure subcontractors obtain all licenses, and permits required to perform this work under this contract. The intent is to establish work requirements that are performance-based and results oriented. This approach is intended to allow the Contractor to determine the best and most cost-effective ways to fulfill base operations and maintenance and their component needs, emphasizing innovation and commercial best practices.

1.3 Climatic Conditions. FS/HAAF is located in the humid subtropics with long, hot summers and mild winters. Summer temperatures average 81 degrees in July and winter temperatures average 50 degrees in January. Summer high temperatures of 106 degrees and winter low temperatures of two (2) degrees have been recorded. The first frost usually occurs in November and continues through February or the beginning of March. The average rainfall is 50 inches (yearly) with slightly over half occurring between June and September. Under normal circumstances wind speeds rarely exceed 10 (ten) knots. The hurricane and tropical storm season normally occurs during July through October.

1.4 Facility Access. The Contractor shall ensure access to all fire detection and suppression systems in case of emergencies or for other Fire Department purposes. The Contractor shall inform the FS/HAAF Fire Department point-of-contact (POC), prior to outages that will impact the function of the system, special problems or circumstances, which require FS/HAAF Fire Department inspection.

1.5 Traffic Flow. The Contractor shall maintain the free flow of vehicular and pedestrian traffic while conducting maintenance and repair activities. The Contractor shall notify the Contracting Officer's Representative (COR)/Alternate Contracting Officer's Representative (ACOR)), in writing, a minimum of fourteen (14) calendar days in advance of any scheduled closure of streets (Deliverable A001). Emergency road closures shall be coordinated with the COR/ACOR.

1.6 Drainage. Maintenance work performed under this contract shall not impede drainage.

1.7 Restoration of Landscape Damage. Trees or other landscape features, and irrigation systems damaged by the Contractor's operations shall be restored to the original state at no additional cost to the Government.

1.8 Dust Suppression. The Contractor shall perform dust suppression, when necessary, during maintenance and repair activities or as directed by the COR/ACOR.

1.9 Utility Location. The Contractor shall perform utility cuts in pavements as required to repair existing utilities after obtaining a digging permit to do so. No excavation shall occur until the site clearance procedure has been completed.

1.10 Excavation Permits. All excavation permits shall be initiated by white lining or staking the excavation site and calling 811, in accordance with (IAW) the GA Dig Law.

1.11 Work Clearance. For work involving digging/excavation operations, the Contractor shall obtain a properly approved digging permit before ground disturbance. In emergency situations the site clearance requirements may be waived by the COR/ACOR

2.0 Requirements

2.1 Description of Services. See Section 5.0 for the specific CLS or Functional Area (FA).

2.1.1 Non-Personal Services. The personnel rendering the services are not subject; either by the contract's terms or by the manner of its administration, to the supervision and control usually prevailing in relationships between the Government and its employees. Non-personal service contracts are authorized by the Government IAW Federal Acquisition Regulation (FAR) Subpart 37.104, under general contracting authority, and do not require specific statutory authorization.

2.1.2 General Information.

2.1.2.1 Transition (Phase In/Phase Out). The Contractor shall prepare and submit a transition plan within ten (10) business days after contract award (Deliverable A002). The transition plan will have a sixty (60) calendar day transition period that will be implemented by the Contractor and shall state when Contractor key personnel will be on board, to include IT/Network accounts and access with the appropriate Government organizations. The Contractor shall provide sufficient experienced personnel during the phase-in and phase-out period to ensure that the services are maintained at the required level of proficiency. During the phase-in, the Contractor shall observe all operations pertinent to the requirements of the PWS, to include office functions, procedures, and operations, repair/maintenance operations, and any other operations as deemed necessary by the Contractor that will enable Contractor personnel to become both knowledgeable in, and familiar with, their assigned areas of responsibility. The Contractor shall commence all operations required by this PWS as of the first day of the contract period. Therefore, on the initial day of performance, the Contractor shall provide a work force which is fully qualified and capable of performing all work required under this contract. During the Phase-In period, the Contractor shall perform, at a minimum, all of the following tasks:

- Upon request, deliver supporting qualification documentation of the Contractor's proposed Project Manager and other key staff.
- Establish the Project Management Office.

- Recruit and hire necessary personnel.
- Obtain all required certifications.
- Obtain minimum required security clearances.
- Participate in all joint inventories and sign for Government Furnished Property (GFP) and Government Furnished Equipment (GFE).
- Obtain all contractor acquired equipment.
- Develop and submit any required deliverables.
- Obtain necessary access to Government computer network system.
- Attend Post Award meetings as required.
- Complete all necessary training to support the services listed in each functional area.
- Start accepting and working Project Work Order (PWO) estimates for work or execution of PWO's

2.1.2.2 Transition (Phase-Out). Sixty (60) calendar days prior to contract expiration will constitute the phase-out period. The Contractor shall develop and implement a plan to affect a smooth and orderly transfer of performance responsibility to a potential successor. The initial phase-out plan shall be submitted to the COR/ACOR for approval no later than six (6) months after the start of the base contract year (Deliverable A003). The plan shall contain details that include but are not limited to; timelines for events, key personnel involved and interface with the Government and follow-on Contractor. The plan shall fully describe how the Contractor shall approach the following issues: Employee notification; Retention of key personnel; Turn-over of work-in-progress, inventories and transfer of Government furnished property; Removal of Contractor property; Data and information transfer; deletion of password access to Government systems, installation clearance actions including turn-in of controlled access cards (CAC) and any other actions required to ensure continuity of operations. The plan shall also include a joint inventory among the incumbent, the Government, and the successor Contractor; reconciliation of all property accounts and requisitions, turn-in of excess property and cleanup of Contractor work areas.

The Contractor shall correct any damage to Government-Owned Property caused by employee negligence or mistake, intentional or otherwise. During the thirty (30) calendar day transition period immediately prior to the end of the previous contract, the Contractor shall permit the successor Contractor (and the successor Contractor's employees) to observe and become familiar with any and all operations under the contract. The Contractor shall not defer any needed repairs or maintenance for the purpose of transferring responsibility to the successor Contractor. The Contractor shall fully cooperate with the successor Contractor and the Government so as not to interfere with their work or duties. The Contractor shall provide reasonable assistance to the Government's contract solicitation process such as verifying workload data and other factual information to be included in a new solicitation and providing access to the workplace for site visit(s) of prospective offerors.

2.1.3 Place of Performance and Hours of Operation.

2.1.3.1 Place of Performance The work to be performed under this requirement will be primarily performed throughout the entire area occupied by FS/HAAF and the surrounding training areas which include Wright Army Airfield (WAAF) and Evans Army Airfield (EAAF), the inner and outer markers in Savannah, railroad tracks, and other isolated communications areas. A map of FS/HAAF is located at TE 01, 01A, and 01B.

2.1.3.2 Hours of Operation. The Contractor shall conduct regular business, between the hours of 0730 to 1600, Monday through Friday, excluding Federal holidays or when the Government facilities are closed due to local or national emergencies, administrative closings, or similar Government directed facility closings except as stated otherwise within applicable Annexes. The Contractor shall maintain an adequate workforce for the uninterrupted performance of all tasks defined within this PWS when the Government facility is not closed for the above reasons. Variances in operating hours must be approved by the KO/COR/ACOR and submitted thirty (30) calendar days in advance of the proposed change.

2.1.3.2.1 The Contractor shall develop an area to receive Priority 1 service calls between the hours of 1600 to 0700 Monday through Friday and on all weekends and holidays. The DPW Work Reception Contractor will forward the calls to the number provided by the Base Maintenance Contractor for these calls. The Contractor shall maintain a log of all calls and actions and give them to the DPW Work Reception Contractor/COR by 0900 every workday.

2.1.4 Federal Holidays. The Contractor's performance shall not be required on the Federal public holidays listed below, except to respond to Priority 1 (Emergency DMO's) or if it is required in the other Annexes. Holidays occurring on weekends will be observed as directed by the Federal calendar (5 U.S.C. 6103), Government Organization and Employees, Holidays).

New Year's Day	1st day of January
Martin Luther King Jr.'s Birthday	3rd Monday of January
Presidents Day	3rd Monday of February
Memorial Day	Last Monday of May
Juneteenth	19th day of June
Independence Day	4th day of July
Labor Day	1st Monday of September
Columbus Day	2nd Monday of October
Veterans Day	11th day of November
Thanksgiving Day	4th Thursday of November
Christmas Day	25th day of December

NOTE: When a holiday falls on a Sunday, the following Monday will be observed as a holiday, and, when a holiday falls on a Friday or Saturday, the preceding Thursday is observed as a holiday by U.S. Government Agencies. Federal holidays also include any Presidential or Congressionally designated days off other than the holidays listed above.

2.1.4.1 The Contractor shall provide personnel support within two (2) hours of notification outside the normal hours of operation as required, including holidays, to support the DPW mission. Prior to performance of services outside the locally established hours of operation, the Contractor shall request and obtain, in writing, approval from the KO. The Project Manager shall be available after normal hours to serve as the central POC for Contractor operations. Contractor personnel shall not be scheduled for overtime work.

2.1.4.2 Installation Closures. When an unforeseen installation closure occurs on a regularly scheduled day of work, the Contractor shall reschedule the work to be performed the business day following the closure unless the following day is a Saturday, Sunday, a recognized Federal holiday, and when routine work is not scheduled for that day.

2.1.4.3 Inclement Weather Delay. If the Contractor determines unsafe weather conditions for continued operations, then the Contractor shall notify the COR/ACOR if inclement weather suspends operations within two (2) hours. The Contractor shall resume operations with COR/ACOR approval.

2.1.4.4 Curtailment of Operations. When operations are curtailed due to manmade or natural conditions on a business day, it may be necessary for the Government to interrupt that day's work under this contract. The Contractor shall reschedule the work on any day acceptable to the Government. If the KO agrees, the Contractor may continue the work as scheduled. The KO will provide verbal announcements of immediate curtailment of operations to the Contractor.

2.1.4.4.1 The Contractor shall coordinate with DPW in preparation for and during emergency operations situations such as inclement weather, flood, active shooter, fire or other emergency situations. The Contractor may be called upon to deliver a wide variety of services to the installation through an emergency DMO/PWO in support of emergency response. The Contractor shall be required to provide all normal services during an emergency response unless otherwise directed by the KO, however emergency response requirements will take precedence over normal DMO/PWO activities.

2.1.4.5 Days of No Scheduled Activities (DONSA). The installation has historically granted Military personnel (Enlisted and Officers) DONSA, for example, the Friday after Thanksgiving, in addition to the listed Federal holidays above.

- DONSA are not considered a day of excused absence for the Government civilian work

force or Contractor employees.

- If a DONSA affects scheduled contract work or access to facilities, the work in affected facilities may be rescheduled to compensate for the DONSA.
- However, announced DONSA or exodus of Military personnel may provide the Contractor with an opportunity for unrestricted access to facilities and areas or uninterrupted performance of work (i.e., training facility and area maintenance and supply inventories).

The Contractor shall vary work schedules to take full advantage of such opportunities by planning maintenance that is better accomplished when personnel are not using facilities during those times.

2.1.5 Emergency Services.

2.1.5.1 Emergency Medical Treatment. The Contractor or their employees shall immediately notify their supervisor of any accident requiring emergency medical treatment. The Contractor shall notify the KO/COR/ACOR no later than (NLT) two (2) hours of the incident (Deliverable A004). The Contractor shall be responsible for the emergency medical treatment services for Contractor personnel. However, WINN Army Community Hospital is available, on an emergency basis, to perform emergency medical services for injuries incurred while an employee is performing under the contract. Emergencies will be treated only during the period of the emergency and appropriate action will be taken to discharge or transfer such patients as soon as the emergency period ends. The Contractor shall be responsible for the expense of the emergency medical services provided, upon receipt of invoice from the medical facility. Reimbursement shall be made to the United States (US) Government.

2.1.5.2 Accident Reporting. The Contractor shall comply with Operational Safety and Health Administration (OSHA) for record keeping and reporting of all accidents resulting in death, injury, occupational disease, or adverse environmental impact. The Contractor shall provide a verbal report to the KO/COR/ACOR within two (2) hours of each such occurrence. A completed typed original plus one (1) copy of ENG Form 3394 *United States Army Corps of Engineers Accident Investigation Report* (or equivalent reporting form) shall be delivered to the KO/COR/ACOR within five (5) business days of occurrence, whenever an accident involving personal injury or Government owned property occurs.

2.1.6 Contract Administration and Management.

2.1.6.1 Post Award Conference/Performance Evaluation Meetings. The Contractor shall attend the post award conference convened by the Contracting Activity or Contract Administration Office IAW FAR Subpart 42.5, Post-award Orientation. The KO, COR and DPW management

will meet monthly with the Contractor to review the Contractor's performance. Written minutes of meetings will be recorded by the Contractor and signed by both the Project Manager (PM) and the KO. The written minutes will be distributed within five (5) business days after the meeting. If the Government does not concur with any portion of the minutes, recorded by the Contractor, the non-concurrence shall be provided in writing by the KO/COR within two (2) business days following receipt of the minutes.

2.1.6.2 Notwithstanding the Contractor's responsibility for total management during the performance of this contract, the administration of the contract requires maximum coordination and cooperation between the Government and the Contractor.

2.1.6.3 The following provides the roles and their respective authority during the performance of the contract:

2.1.6.3.1 Contracting Officer (KO). The KO is the only person authorized to make any changes in any of the requirements listed on this PWS; notwithstanding any provisions contained elsewhere in this contract, said authority remains solely with the KO. In the event the Contractor makes any change at the direction of any person other than the KO, the change will be considered to have been made without authority and solely at the risk and expense of the Contractor. All contract administration will be affected by the KO. Communications pertaining to contractual administrative matters shall be addressed to the KO. No changes in or deviations from the terms and conditions shall be affected without a written modification to the contract, executed by the KO authorizing such changes. The KO will approve all submittals and plans required in this PWS.

2.1.6.3.2 Contracting Officer's Representative (COR). The KO will appoint a COR during the performance of this contract. Additional Government personnel may be assigned to assist in contract oversight IAW AR 70-13, Management and Oversight of Service Acquisitions. Other surveillance personnel may be designated as COR or Alternate Contracting Officer's Representative (ACOR), and shall be trained and appointed IAW DoDI 5000.72, DoD Standard for Contracting Officer's Representative (COR) Certification and DFARS 201.602-2. The ACOR will serve as on-site representatives of the COR in performance of actual contract surveillance, if they meet all COR training, experience requirements, and are appointed by the KO as an ACOR. The COR/ACOR will provide assistance in identification and resolution of problems, conflicts in priority, sub-task requirement definitions, and other operations type problems. The COR/ACOR will perform IAW the responsibilities and duties identified in the appointment letter.

2.1.6.3.2.1 COR Authority. A letter of designation will be issued to the COR/ACOR by the KO. A copy of the letter will be sent to the Contractor. The letter of designation states the

responsibilities and limitations of the COR/ACOR, especially with regard to changes in cost, price estimates, or changes in delivery dates. The COR/ACOR is not authorized to change any of the terms and conditions with regard to cost, quantity, or schedule of the resulting order.

2.1.6.3.3 The Contractor shall not in any way represent the United States (U.S.) Government, or that it has the authority to contract or procure supplies for the account of the United States of America (USA).

2.1.7 COR/ACOR Functions. The COR/ACOR monitors all technical aspects of the contract and assists in contract administration. The COR/ACOR is authorized to perform the following functions: assure the Contractor performs the technical requirements of the contract; perform inspections necessary in connection with contract performance; maintain written and oral communications with the Contractor concerning technical aspects of the contract; issue written interpretations of technical requirements; monitor, document, and report Contractor's performance and notify both the KO and Contractor of any deficiencies; coordinate availability of Government Furnished Property, and provides direction or assistance for site entry requests of Contractor personnel.

2.1.8 Quality Control (QC). Quality Control is the responsibility of the Contractor. The Contractor shall provide a Quality Control Plan (QCP) five (5) business days before contract start. The Contractor shall provide and maintain a QCP that is acceptable to the KO. Changes to the Contractor's QCP shall be submitted to the KO for review and approval within five (5) business days prior to implementation (Deliverable A005).

2.1.9 Contractor Employees.

2.1.9.1 Key Personnel.

2.1.9.1.1 Project Manager (PM). The Contractor shall provide a PM who is responsible for the performance of the work. The PM shall have full authority to act for the Contractor on all contract matters relating to daily operation of the contract. The PM shall have a baccalaureate degree from an accredited College or University and five (5) years' experience in base support management or a contract similar in scope and breadth to this solicitation. The name of the PM shall be provided by the Contractor to the KO at the post award conference and shall be present and on-site and available during normal duty hours. In the circumstances when the PM is not available, the Contractor shall designate an Alternate Project Manager (APM) who can perform the same duties during their absence. The APM will have the same requirements as the PM. If the PM doesn't have a Bachelor of Science Degree in Facility Management, then they shall have two (2) of the following certifications:

- Facility Management Professions (FMP)
- Certified Facility Manager (CFM)
- Sustainability Facility Professional (SFM)
- Facilities Management Certificate

The PM shall be available between 0730 - 1600 hours, Monday through Friday except Federal Holidays or when the Government Facility is closed for administrative reasons. The Project Manager performing work under this contract shall have and maintain a (Tier 3, Secret) clearance at time of the contract start date and for the life of the contract.

2.1.9.1.2 GFEBS PM Coordinator Lead. The GFEBS PM Coordinator Lead shall have demonstrated experience in successfully utilizing GFEBS on a military installation. The name of the GFEBS PM Coordinator Lead shall be provided by the Contractor to the COR/ACOR at the post award conference. The GFEBS PM Coordinator shall be available between 0730-1600 hours, Monday through Friday, except Federal holidays or when the Government facility is closed for administrative reasons. The GFEBS PM Coordinator Lead shall have, at a minimum three (3) years of GFEBS experience, specifically dealing with Property, Plant, and Equipment (PPE), business intelligence, projects, preventive maintenance planning/execution, updating real property inventory, work order processing, material planning and acquisition and analysis of system reports. The GFEBS PM Coordinator Lead shall have the following roles in GFEBS:

- A76 DPW Contractor PM Master Data Maintainer
- A76 DPW Contractor Preventive Maintenance Controller
- A76 DPW Contractor GR Processor
- A76 DPW Contractor Physical Inventory Maintainer
- A76 DPW Contractor PM Material Requirement Planning Maintainer
- A76 DPW Contractor PM Order Approver
- A76 DPW Contractor PM Order Maintainer
- A76 DPW Contractor PM Reporter

2.1.9.1.3 GFEBS Certification. Contractor personnel that will utilize GFEBS shall possess a working knowledge of GFEBS and shall complete GFEBS training modules provided by the Government within thirty (30) business days of being employed. The Contractor shall provide certificates of completion for all roles required to perform the requirements of the position upon Government request. The Contractor shall be responsible for GFEBS data entry and reporting.

2.1.9.1.4 Common Access Card (CAC). Certain administrative personnel will require a CAC to access Government systems. CAC permits installation access to all contract employees. These persons shall have, at a minimum, a (favorable Tier 1 (Investigation) and/or a Tier 3

(Secret). The Contractor shall coordinate with the COR/ACOR for CAC issuance and turn in of CAC cards after employee terminations.

2.1.9.1.5 U.S. Residency. All Contractor employees shall be legal U.S. residents. The Contractor shall immediately remove any employee that is not a legal U.S. resident. The Contractor personnel shall be able to communicate clearly in the English language.

2.1.9.1.6 Qualification Standards. The Contractor shall inspect, repair, and maintain systems and components associated with facilities listed in real property records as required throughout this contract utilizing properly trained, skilled, and qualified employees or subcontractor personnel.

2.1.9.1.7 Mission Essential Personnel Requirements and Qualifications.

2.1.9.1.7.1 Pipefitter/Plumber. The lead plumber/pipefitter at each installation (FS and HAAF), shall have a Master (Unrestricted) Plumbing license.

2.1.9.1.7.2 Boiler Operators. Boiler operators at FS shall have, at a minimum, a Third-Class Power Engineer Certification by the National Institute for the Licensing of Power Engineers (NIULPE) and the Lead shall have, at a minimum, a Second-Class Power Engineer Certification by NIULPE. Boiler operators at HAAF shall have, at a minimum, a Fourth-Class Power Engineer Certification by NIULPE and the Lead shall have, at a minimum, a Third-Class Power Engineer Certification by NIULPE.

2.1.9.1.7.3 Wastewater Treatment Operators. All operators shall possess a Wastewater Operator License Class III or higher certificate issued by the State of Georgia. The Lead Operator at each installation (FS and HAAF) shall possess a Class II or higher certificate issued by the State of Georgia.

2.1.9.1.7.4 Water Treatment Operators All operators shall possess a Water Operator License Class III or higher issued by the State of Georgia. The Lead Water Operator at each installation (FS and HAAF) shall possess a Water Operator Class II or higher issued by the State of Georgia.

2.1.9.1.7.5 Pest Control Applicators. All pest control applicators shall have Georgia Department of Agriculture Commercial and Structural certifications in right of Way, Turf and Ornamental, Aquatic, Mosquito Control. All technicians at each installation (FS and HAAF) will be state permitted for Nuisance Wildlife Control. All applicators are required to have both Household Pest Control (HPC) and Wood Destroying Organism (WDO) certifications from the Georgia Department of Agriculture Structural Pest Control Commission. Personnel shall be trained in pesticide exposure first aid procedure.

2.1.9.1.7.6 Heating, Ventilation, and Air Conditioning (HVAC) Technician. Individuals performing HVAC operations shall be certified in handling and use of all refrigerants (U.S. Environmental Protection Agency (EPA) Certification Requirements, Sections 608 and 609 of the 1990 Clean Air Act Amendments and 40 Code of Federal Regulations (CFR), Part 82, Subpart F, Protection of Stratospheric Ozone.

2.1.9.1.7.7 HAZMAT All personnel handling hazardous wastes must be trained IAW 40 CFR 265.16. Those responding to HAZMAT spills and clean up shall be trained IAW 29 CFR 1910.

2.1.9.1.7.8 Electrician. The Lead Electrician, at each installation (FS and HAAF), shall have a Master Electrical license.

2.1.9.1.7.9 Fire Alarm/Suppression Technicians All personnel performing Inspection, Testing, and Maintenance (ITM) on fire alarm and fire suppression systems shall be certified by the National Institute for Certification in Engineering Technologies (NICET) as follows:

2.1.9.1.7.9.1 ITM on fire alarm systems is to be performed by NICET technicians for fire alarm as follows:

- a. NICET Level III or IV – technicians working independently and lead technician on a working team.
- b. NICET Level II – Technicians working under daily supervision of a technician certified as NICET Level III or higher.
- c. NICET Level I – Technicians working under continuous supervision of a technicians certified as NICET Level III or higher.

2.1.9.1.7.9.2 ITM on water-based fire suppression systems is to be performed by NICET technicians certified for water-based fire suppression systems as follows:

- a. NICET Level III or IV – technicians working independently and lead technician on a working team.
- b. NICET Level II – Technicians working under daily supervision of a technician certified as NICET Level III or higher.
- c. NICET Level I – Technicians working under continuous supervision of a technicians certified as NICET Level III or higher.

2.1.9.1.7.9.3 ITM on special hazard suppression systems is to be performed by NICET technicians certified for special hazard systems as follows:

- a. NICET Level III or IV – technicians working independently and lead technician on a working team.
- b. NICET Level II – Technicians working under daily supervision of a technician certified as NICET Level III or higher.

- c. NICET Level I – Technicians working under continuous supervision of a technicians certified as NICET Level III or higher.

2.1.9.1.7.9.4 All personnel performing ITM on pre-engineered suppression systems shall be certified by the manufacturer of the system. They shall be certified by the state or local authority.

2.1.9.2 Contractor Identification. The Contractor shall ensure that personnel be identified as a Contractor to distinguish themselves (e.g., badge, company logo, or uniform) from Government employees. The Contractor shall ensure all correspondence and reports produced are marked as Contractor products or that Contractor participation is disclosed.

2.1.9.3 Standards of Conduct. Contractor personnel's conduct shall not reflect discredit upon the Government. The Contractor shall ensure all personnel present a professional appearance while working on the Government installation. The Contractor's employees shall observe and comply with all local policies and procedures concerning fire, safety, environmental protection, sanitation, security, and possession of firearms or other lethal or illegal weapons or substance. The Contractor shall ensure all Contractor employees, providing services under this contract, conduct themselves and perform services in a professional, safe, and responsible manner. The Contractor shall remove, from the job site, any employee for reasons of misconduct or security. The Contractor shall ensure employee conduct complies with 41 USC 423, *Procurement Integrity*. The Contractor shall also ensure that no Contractor employees conduct political related activities or events on the installation. The removal of such a person shall not relieve the Contractor of the requirement to provide personnel to perform adequate and timely service.

2.1.9.4 Contractor Hiring Restrictions. The Contractor shall not hire or sub-contract with off-duty or former Government employees whose employment would result in a conflict with Joint Ethics Regulation (JED) DoD 5500.07-R.

2.1.10 Business Relations. The Contractor shall successfully integrate and coordinate all activity needed to execute the requirement of this PWS. The Contractor shall manage the timeliness, completeness, and quality of problem identification to a degree acceptable to the Government. The Contractor shall provide to the COR/ACOR corrective action plans, timely identification of issues, and effective management of Subcontractors. The Contractor shall ensure customer satisfaction and professional and ethical behavior of all Contractor personnel.

2.1.11 Manual Operations. The Contractor shall establish a Contingency Plan for manual operation in the event that power or other utilities prevent the computer processing of the DMOs, OWOs, PWOs and PMOs related work documentation. The plan shall be delivered to the KO within fifteen (15) calendar days of the start of the contract (Deliverable A007). Provision should

also be made for inputting and updating data into the Government System on a delayed basis in case the network or system is down. The Contingency Plan shall include coordination with DPW WR Desk and its operations.

2.1.12 Interactive Customer Evaluation (ICE). The Contractor shall respond to all ICE comments addressed to contractor and shall provide updates to the COR within 24-hours of receipt of comment.

2.2 Work Management. Applicable to all CLS's. All coordination requirement in this section and inherent to this Contract shall take into consideration the DPW WR Desk and their operations. Work requirements and timelines shall include coordination with the DPW WR Desk.

2.2.1 Coordination. As a part of the work scheduling process, the Contractor shall coordinate all work with the Building/Facility Manager in charge of the facility where the work is to be done. The Contractor will make at least two (2) attempts to coordinate the work before notifying the COR/ACOR that they can't get ahold of the POC. After that, the government will attempt to coordinate the work and will advise the contractor on their next actions, i.e. close out the DMO or provide a better POC for the work. The contractor cannot close out a DMO for this reason without approval from the COR/ACOR.

2.2.1.1 Work Status. The status of all assigned work shall be available to the COR/ACOR within one (1) hour of Contractor receipt of request during normal working hours, and two (2) hours at all other times. For emergency DMOs, the Contractor shall respond within thirty (30) minutes to any inquiries from the COR/ACOR and/or DPW management.

2.2.2 General Fund Enterprise Business System (GFEBS). GFEBS is the web-based asset and accounting system that is used as the key component for work that is performed on the Garrison. The Government will use GFEBS as a production scheduling and contract monitoring system for determining the status of work, maintenance, and repair expenditures against individual facilities, as well as minor construction and alteration (new work) project expenditures. The Government will establish and provide the Contractor with work center(s), activity types, and activity rates upon contract award. GFEBS is the official system of record for all Real Property Maintenance Activity (RPMA). NOTE: the initial GFEBS input for DMO's will be accomplished through the DPW WR Desk.

- a. The Contractor shall document, manage, control all work performed under this contract upon receipt of DMO requests from GFEBS. Upon completion of all DMO's, the Contractor shall obtain POC signature, date and phone number indicating acceptance and completion of order. All POC signatures shall be uploaded to GFEBS under the corresponding DMO and provided to the Government upon

request. All work shall be documented in GFEBS. The Contractor shall record, manage, and report, in a chronological order, all work performed under this Contract at a detailed level to clearly and fully describe the repairs performed for each DMO, this includes the date parts are ordered and when they come in.

- b. As a means to document all work performed, the Contractor shall ensure that each Contractor employee, who works on DMOs, PMOs, PWOs or OWO records applicable labor, equipment, and maintaining the Materials Master to capture accurate material costs for all repair/maintenance action. The Contractor shall be responsible for entering all data from these forms into GFEBS.

2.2.2.1 Army Maintenance Application (ArMA): A web service available for customers to request maintenance services by use of computer or mobile devices (smart phone) and receive status updates on requests or orders. Current IMCOM ArMA Business Rules can be found at Main_ArMA_Overview (deps.mil). Requests received through ArMA will follow the same classification and priority of services needed as in Annex B. The current process is the DPW WR Contractor receives these requests and inputs them into GFEBS and the BaseOps Contractor does everything IAW GFEBS paragraph 2.2.2 above. The BaseOps Contractor will not input data into the ARMA system.

2.2.2.1.1 Duplicate Orders. The Contractor shall monitor for duplicate orders. If more than one (1) DMO is submitted for work, similar in nature, associated to the same building and room number (if applicable), the orders shall be treated as a single order and documented as one (1) in GFEBS. The Contractor shall reconcile duplicate orders with the DPW WR Desk in GFEBS and cancel duplicate orders in GFEBS without putting any charges against the DMO.

NOTE: Government systems and database of records are subject to updates, modifications, end of service life preparation and migration to new systems will occur at the discretion of the Army

2.2.3 Demand Maintenance Orders (DMOs).

2.2.3.1 DMO Desk. The Contractor shall establish a DMO desk for the execution of all DMOs. The Contractor shall provide a GFEBS DMO Dispatcher(s) to input all DMO data into GFEBS on a daily basis. This individual(s) shall be on duty Monday through Friday from 0730 hours to 1600 hours. The Contractor shall also produce upon request by the COR/ACOR the following reports: Project Status and Unfunded Requirements lists. The Contractor shall receive notification of work from the DPW WR Desk by means of a telephone call, email, or directly from the KO/COR/ACOR. The Contractor shall establish a dedicated telephone number and email address(s) to be used exclusively for receipt of DMOs. The person(s) performing GFEBS DMO Dispatching shall be fully familiar with the Contractor's organization and procedures as

well as the terms and response factors specified herein. During non-duty hours, the DPW WR Desk DMO call lines will be forwarded to the number provided by the BaseOps Contractor. The Contractor shall maintain a call log (filled in with customer information: work/problem nature; location of service work requirement, including the Facility number; name, email address and telephone number of requestor) and respond to all Priority 1 DMO's within established timelines. The call log will be given to the DPW WR Contractor and/or COR by 0900 the next business day. The Contractor shall receive notification of work from the DPW WR desk. The Contractor is authorized to execute DMOs that do not exceed thirty-two (32) work hours in labor. DMOs exceeding the Contractor's authorized limit shall be executed IAW Annex B, Facilities Maintenance Instruction.

2.2.3.2 DMO Call Receipt and Entry. The DPW WR Contractor assigns all DMO priorities and enters the DMO into GFEBS, see TE. 7 DMO Initiation Process. For life threatening emergencies (DMO priority 1), the GFEBS DMO Dispatcher shall notify the appropriate shop within five (5) minutes and complete the work in one (1) calendar day. Once the DMO has been completed by the appropriate technician, the Contractor shall charge hours and time against the order in GFEBS. All DMOs shall be executed by the Contractor within the following timelines:

- Priority 1 (Emergency/Critical): DMOs are classified as Emergency (Priority 1) when immediate action is required to eliminate life threatening or serious injury hazards to personnel. These DMOs are responded to as soon as possible and NLT one (1) hour after the request. Emergency/Critical DMOs are completed within twenty-four (24) hours of the request, unless the urgency of the work has been reduced to a Priority 2 or 3. Emergency/Critical (Priority 1) DMOs are used to prevent loss or damage to Government property, ensure security to sensitive Government property, restore essential services, correct a condition to prevent it from becoming an emergency, respond to command emphasis, provide basic human services in facilities where individuals sleep, or aid an activity in accomplishing its mission.
- Priority 2 (Urgent): DMOs are classified as Urgent (Priority 2) when the failure in service does not immediately endanger personnel or property, but would soon inconvenience or affect the security, health, or well-being of personnel. Urgent DMOs are to correct conditions which could become an emergency, could seriously affect morale or have command emphasis. These DMOs are to be completed within seven (7) calendar days from receipt, unless reduced to a Priority 3. Examples include, but are not limited to: unstopping a sink drain where there are backup sinks, replacing overhead office lighting that significantly inhibits productivity, and unscheduled fuel deliveries, etc. If parts are not readily available within the seven (7) calendar days for completion, then they need to have been ordered within forty-eight (48) hours of receipt of the Priority 2 DMO request to not be considered below the Acceptable

Quality Level (AQL) as noted in the Performance Requirements Summary (PRS) for deduction. Once parts arrive, then they shall be installed within seventy-two (72) hours.

- Priority 3 (Routine): Routine DMOs are for work that does not meet the criteria of emergency/critical or urgent priority. They are utilized to correct situations that are productivity inhibitors that, if left uncorrected, will cause measurable discomfort or inconvenience to the customer or waste resources or create the need for additional minor repairs. Routine DMOs are to be responded to and completed within thirty (30) calendar days of receipt. Examples include, but are not limited to: dripping faucets, cracked window glass, repairs to door and window hardware and screening, replacement of broken or missing tiles, minor roof leaks, minor repairs to mechanical equipment, air conditioning, etc. If parts are not readily available within the thirty (30) calendar days for completion, then they need to have been ordered within ten (10) calendar days of receipt of the Priority 3 DMO request to not be considered below the AQL as noted in the PRS for deduction. Once parts arrive, they need to be installed within seven (7) calendar days.

2.2.3.3 Completed Work. The Contractor, certifying the work was satisfactorily performed, shall identify within GFEBS (using GFEBS T-CODE IW38) the total labor hours the technician worked and the fully burdened rate based on shop (e.g. carpentry, electrical, plumbing, etc.), and the total materials/parts costs. Within seven (7) days of DMO issuance, the Contractor shall technically complete (TECO) the DMO to close out the order.

2.2.3.4 Materials. The Contractor shall be responsible for all materials required for DMO repair work. For clarity, the price for DMOs reflected in the Pricing Matrix and applicable contract CLINs shall be inclusive of all DMO related repair costs.

2.2.4 Preventive Maintenance Orders (PMOs). The Contractor shall perform all PMOs for the PM Programs listed in TE 08. The Contractor technicians shall complete scheduled PM work within five (5) calendar days for monthly PM's, fourteen (14) calendar days for quarterly PMs, and thirty (30) calendar days for semi-annual and annual PM's. Until the PMO program as described in paragraph 2.2.5 below is complete, the Contractor shall execute PMOs IAW historical PM data provided IAW the applicable attachments. Within seven (7) calendar days of PMO completion, the Contractor shall TECO the PMO in GFEBS. The Contractor shall update, within GFEBS, the PM Plan for any real property and/or equipment to which the Government will take title, or which shall be installed on Government property.

2.2.4.1 PMO Program. The Contractor shall develop and execute a PMO program. The Contractor shall first verify and update the equipment listed in the applicable TE's as referenced in TE 08 PM Programs. During the equipment inventory assessment, the Contractor shall at a

minimum, collect the equipment Maintenance Control Designation (MCD), serial number, equipment description, work center (shop), building number, frequency basis for that equipment (e.g., monthly, quarterly, annually, etc.), maintenance plan and task list. Upon completion of the equipment verification, the PMO program shall be developed and entered into GFEBS. The PMO program shall be completed and fully operational in GFEBS no later than ninety (90) calendar days after contract start date. Refer to TE 03 for a sample of commonly used GFEBS transaction codes that the Contractor shall have experience in utilizing to create and maintain the PMO Program. The Contractor shall be responsible for maintaining the accuracy and currency of the equipment list and associated PM Schedules in GFEBS throughout the life of the contract.

2.2.4.2 PMO Schedules. Once the PMO Program is established in GFEBS, the Contractor shall create a PM scheduler. The Contractor shall continually update the list as required with the COR/ACOR. The PM scheduler shall be Microsoft Excel based and include work center, maintenance plan, equipment number, equipment description, building number, frequency, task list, date called/scheduled, and any additional notes pertinent to the PM (e.g., date added, new building, etc.). Additionally, by close of business each week, the Contractor shall provide the COR/ACOR in Microsoft Excel, a project PM planning schedule of work to be accomplished in the following week (Deliverable A008).

2.2.4.3 Approved PM Schedule. The Contractor shall strictly adhere to the scheduled PM dates to facilitate verification of work by the COR/ACOR in GFEBS. If the Contractor finds it necessary to reschedule a PM, a written request shall be made to the COR/ACOR detailing the reasons for the proposed change at least five (5) working days prior to the originally scheduled PM date. No scheduled PM dates shall be changed without the prior written approval of the COR/ACOR.

2.2.4.4 PMO Stickers/Log. Upon completion of the PM inspection, the Contractor shall attach a sticker to the equipment item (or in the immediate vicinity thereof) indicating the equipment MCD number, the date of maintenance, and the initials and identification number of the Contractor employee who performed the work. PM will not be considered performed unless the sticker is current and affixed, and an L&E Utilization Preventive Maintenance (EHSC Form 4288-2) line entry is made to document the PM action. The PM sticker information which includes the MCD number, date of maintenance and warranty information will be added into GFEBS-by-GFEBS T- code "IE01." In instances where a PMO sticker is not practicable, then the Contractor may elect to maintain a current PMO log in lieu of a sticker and have readily available for government review.

2.2.4.5 Warranty Program. The Contractor shall establish and maintain a Warranty Program to warranty all equipment, parts, components, where the manufacturers provide a warranty and shall be exercised for the duration of this contract. The Contractor shall input the warranty

information into GFEBS and provide the COR/ACOR with a copy of the warranty and manual for all equipment in an excel sheet format. The warranty excel sheet should be updated as warranty information changes for the equipment. The warranty information in the excel sheet should match exactly what is in GFEBS. The Contractor shall provide a plan for managing warranties with the technical proposal. All warranty data shall be returned to the Government at contract completion. When Contractor personnel determine that a warranted item not installed by the Contractor requires service, the Contractor shall notify the COR in writing no later than 9:00 AM the next business day or give telephone notification within fifteen (15) minutes of detection if the deficiency threatens damage to personnel or property. The COR/ACOR will direct the Contractor to: (1) repair the deficiency if potential damage may result from deferring repairs; or (2) clean the work area and stop work. The Contractor shall not receive payment for work not authorized by the COR/ACOR which is performed on warranted equipment, unless the COR/ACOR concurs that such work was a legitimate response to a true emergency condition.

2.2.4.6 Operation and Maintenance (O&M) Manual Digital Library. The Contractor shall create and maintain a current electronic repository of all O&M Manuals from the manufacturer or supplier for all facilities and equipment delineated in the Contractor's PMO program. The repository shall be organized by shop/work center.

2.2.5 Operations Work Orders (OWOs). The Contractor shall respond to, and complete individual tasks related to OWOs. An OWO is recurring maintenance, cyclical in nature, outside of GFEBS scheduled PM, requested demand maintenance, or projects. Support for recurring OWOs is referenced in TE 04. If a new OWO is required in addition to those identified, then a DA Form 4283, Facilities Engineering Work Requests, will be issued and shall serve as the authorization document for the initiation and execution of the OWO. In addition to performing OWOs on TE 04, The Contractor shall perform duties including but not limited to maintaining and updating the TE's referenced in the TE Index as needed. The Contractor shall provide TE updates and TE Index updates electronically to the COR/ACOR as needed throughout the life of the Contract.

2.2.6 Project Work Orders (PWOs).

2.2.6.1 DA Form 4283, Facilities Engineering Work Requests, shall serve as the authorization document for the initiation and execution of PWOs. The DA Form 4283 shall be submitted to the DPW Business Operations and Integrations Division (BOLD) for processing and approval. For DMO generated PWOs, a DA Form 4283 is not required. These PWOs are included in the fixed price CLIN for maintenance services. The PWO (4283 form) should cover the following parameters:

- a. Actual labor hours, materials, and costs for items other than pre-expended bin materials expended.
- b. Government representative signature indicating work has been performed and date. If representative is not available, the Contractor shall so note on the DMO document.
- c. MCD number of equipment item and/or facility worked on under the DMO.
- d. As-built information for any utility infrastructure changes made during the course of the work, or operation and maintenance manuals for any installed equipment (as applicable).
- e. Site sketch indicating area where work was performed and schematic of activities (as applicable).
- f. Digital photos before and after work performance (as applicable).

2.2.6.1.1 Conversion of DMO to PWO. The Contractor shall not at any time exceed thirty-two (32) hours during the performance of a DMO without approval by the KO/COR/ACOR. The Contractor may determine that a DMO, as requested, will exceed the hour threshold during execution or prior to execution. The procedures for each circumstance are detailed below.

2.2.6.1.2 Conversion during Execution. The Contractor shall stop work immediately upon determining that a DMO will exceed the thirty-two (32) hours threshold. The Contractor shall immediately notify the KO/COR/ACOR of the status of the DMO and complete the following tasks:

- The Contractor shall notify the KO/COR/ACOR in writing of the reason for expecting the DMO to exceed the cost threshold.
- The Government may initiate a PWO or cancel the DMO.
- If the Government initiates a PWO, the Contractor shall proceed as described in Section 2.2.6.
- If the Government cancels the DMO, the Contractor shall cease work and leave the work site in a safe and stable condition.

2.2.6.1.3 Conversion Prior to Execution. The Contractor shall immediately notify the KO/COR/ACOR of the expectation that a DMO will exceed the cost threshold and conduct no work. The Contractor shall then complete the following tasks:

- The Contractor shall notify the KO/COR/ACOR in writing of the reason for expecting the DMO to exceed the cost threshold and a preliminary cost estimate.
- The Government may initiate a PWO, cancel the DMO or adjust the DMO scope.
- If the Government initiates a PWO and determines the requirement urgent then the Contractor shall proceed as described in Section 2.2.6.
- If the Government initiates a PWO and does not determine the requirement urgent then the Contractor shall proceed as if receiving a normal PWO request.

2.2.6.2 Cost Estimates for PWOs. The Contractor will provide the Government with the DA Form 4283 that delineates the scope of the project. PWOs that exceed \$150,000 shall be accomplished through a separate contractual vehicle.

The OWO/PWO will be negotiated as follows:

- a. The Contractor shall provide the preliminary desktop (scoping), design as required, and cost estimate based on the DA Form 4283 to the COR/ACOR within five (5) business days of receipt.
- b. When requested in writing by the COR/ACOR, the Contractor will provide detailed scoping, design, and cost estimates within ten (10) business days of receipt of the request.
- c. All other OWO/PWO detailed scoping, design, and cost estimates shall be submitted within thirty (30) business days of receipt of the request.
- d. Negotiate the terms and conditions of the OWO/PWO, to include a scheduled completion date.
- e. DPW BOID will issue a notice to proceed email with KO approval to the Contractor to perform the PWO effort agreed upon.
- f. The Contractor shall bill for all approved OWO/PWOs consistent with the direction provided at FAR 52.232-5, Payments under Fixed-Price Construction Contracts.

It is estimated that the number of detailed estimates required under this contract will be approximately 300 per year.

2.2.6.3 Preparation of Detailed Estimates. The Contractor shall prepare detailed estimate of the labor, equipment and materials required to complete PWO work using industry accepted estimating procedures and data from RSMeans, Building Construction Cost Data, or other appropriate estimating sources approved by the COR/ACOR. All estimates, supporting information, documentation, and calculations shall be submitted to the COR.

2.2.6.4 Subcontract Work. PWOs subcontracted IAW with the Contractor's purchasing system where three (3) independent offers are obtained, and the low offer is accepted will not require a detailed cost estimate. Work, which the Contractor proposes to sub-contract, shall be identified in the estimate. Information, documentation, and calculation required for subcontract work is the same as that required for work to be performed by the Contractor's work force.

2.2.6.5 Specialty Subcontracting Work. For specialized services where estimating software or other estimating standards are not applicable, the Contractor shall prepare a proposal that shall include a minimum of three (3) Subcontractor quotes. Quotes shall include all labor, material, and equipment necessary for Subcontractor to complete the work to be performed on the work request. If the work is of such a type that only one (1) Subcontractor can be found to perform

the work, then a proposal, including breakout of costs, shall be provided sufficient for the KO to determine that the price is reasonable. If only one (1) Subcontractor is solicited the Contractor shall provide information to the KO sufficient to justify the sole source procurement.

2.2.6.6 Execution of PWO Work. The Contractor shall provide proposals for all PWO Work addressing the scope, performance schedule and proposed price. The proposal shall provide supporting data presented including labor, and other direct costs such as equipment, material, and subcontract estimates. The COR will evaluate the Contractor's estimate to determine if: (1) the scope has been clearly and accurately identified, (2) the task hours have been properly estimated with supporting data presented, and (3) equipment, material, and subcontract estimates are reasonable and properly documented and provide recommendations to the KO. After the estimate has been reviewed, the KO will determine whether to approve or negotiate elements of the PWO. Upon KO acceptance or negotiation of the proposed PWO, the KO will execute a Notice to Proceed.

2.2.6.7 Wage Rates for PWOs. Specific work shall be subject to wage rates under the Construction Wage Rates as identified in the Section J of the contract.

2.2.6.8 PWO Bi-weekly Meetings. The Contractor shall attend a biweekly meeting with DPW personnel to provide schedule updates for all current PWOs. Schedules shall include as a minimum for each work order: (a) Change Order Number (if applicable), (b) Facility Designation, (c) Priority, (d) Initials of Quality Assurance Specialist assigned to the work order, (e) Total person hours as issued by ACO, (f) Level of work (II or III, as applicable), (g) Description of Scope of Work, (h) Date Contractor received request for proposal, (i) Date Contractor submitted proposal to Government, (j) Date work order received by Contractor, (k) Date work order will start and required completion date, (l) Percentage complete, and (m) Pertinent comments (i.e., phase of work currently in process, delivery date for materials, reason for stoppage or delay (if applicable), etc.). The Contractor will take meeting minutes during the meeting and will send to the COR/ACOR within two (2) business days.

2.2.6.9 PWO Records. The Contractor shall maintain a record of all PWOs executed under the contract. All records related to PWOs shall be made available to the COR/ACOR upon request. All records are the property of the Government and shall be turned over to the Government upon completion or termination of the contract.

2.2.6.10 PWO Reporting Requirements. The Contractor shall provide a weekly report on PWO's to the COR/ACOR on the first (1st) business day of the week. The report will be in the format IAW TE 05. Format changes can be implemented and/or approved by the COR/ACOR as needed.

2.2.7 Warranty Program. The DPW PM Plan within GFEBS identifies warranty of all equipment, parts, components, where the manufacturers provide a warranty and shall be exercised for the duration of this contract. GFEBS Records identify the item, the nature and expiration date of the warranty, and the name and location of the firm to contact about entitlement under the warranty. The Contractor shall update within GFEBS warranty records on any items of equipment or repair items to which the Government will take title, which shall be installed on Government property.

2.2.7.1 Warranty Enforcement Manager. The Contractor shall designate a Warranty Manager or Point of Contact (POC) to monitor and track all Government-owned equipment as identified by the Government as having a warranty.

2.2.7.2 Warranty Management. The Warranty Manager shall receive a daily listing of all DMOs from the DPW WR Contractor and review all DMOs (including DMOs assigned to other service providers) in facilities under warranty for possible warranty items.

2.2.7.3 Routing of Warranty DMOs. The Contractor personnel shall be familiar with all facilities and equipment under warranty to notify the Warranty Manager of DMOs requests impacting warranties. For DMOs assigned to other service providers, the Warranty Manager shall notify the service provider, who shall then determine if the problem is a valid warranty item. If the item is a valid warranty request, the service provider shall route the DMO back to the Warranty Manager and the DMO shall be routed to the warranty provider for repair. If the repair requirement item is not covered by the warranty, the DMO shall be completed by the service provider. Warranty items that may have been overlooked by the DMO review may be flagged by technicians or workmen as warranty items. In such cases, the DMO shall be routed back to the Warranty Manager and the DMO shall be routed to the warranty provider for repair. Contractor shall place warranty calls and track status until warranty repair has been completed.

2.2.7.4 Warranty Records. The Contractor shall comply with standard Army execution and warranty claim action reporting programs as defined in AR 700-139.

2.2.7.5 Exceptions. The existence of a warranty does not alleviate the Contractor of his responsibility to perform work needed to prevent potential damage to personnel and property or to prevent unnecessary shutdown of facilities and functions.

2.2.7.6 Technical Document Library Operation. The Contractor shall store, maintain, and make technical documents available to all Government personnel and others approved by DPW upon request. If electronic versions are available, the Contractor shall provide these via e-mail or other electronic media. If no electronic copy is available, the hardcopies will be scanned and sent to the Government personnel and others approved by DPW. Contractor shall obtain and record adequate contact information from the borrower, and the documents will be checked

out for no longer than five (5) business days. In the case where only one hardcopy exists, and the document cannot be scanned; the documents shall be made available for reference or for copies. The Contractor shall maintain all warranty documents in an electronic data base.

2.3 As-builts. Applicable only for CLS 411, 414 and 420.

2.3.1 Maintain As-Builts. The Contractor shall maintain as-built drawings. The Contractor shall be provided hard copy drawings, as needed. The maps to be provided are the following: Heating & Cooling System, Installation Grounds, Infrastructure systems (i.e. water, wastewater, natural gas lines) and Running Trails System. Utility repairs, component replacements, modifications, alterations, and additions to all systems and components shall be electronically redlined as well as on the hard copy maps upon completion of work. The Contractor shall redline annotate all components replaced during the period of the contract and annotate all items removed from service.

2.3.1.1 Support. Hard copy markups and electronic redlines shall be delivered to the COR/ACOR at the completion of each major project as identified by the COR/ACOR or, at a minimum, at the end of each contract year quarterly cycle. The Contractor shall validate all maps for accuracy and content.

2.3.2 Real Property Records Updates. When the Contractor is provided plans or drawings as part of a DMO or PWO, the Contractor shall be responsible for providing two (2) copies of marked up red lines drawings reflecting the changes, to the COR/ACOR. The Contractor shall submit these drawings prior to closing out the DMO or PWO. All electronic data and hard copy maps remain the property of the DPW and shall be turned over to the COR/ACOR upon completion of the contract.

2.3.3 Historic Property or Archaeological Site. Historic properties and archaeological sites are subject to the provisions of the National Historic Preservation Act (NHPA). The Contractor shall maintain the historic properties on the installation IAW the NHPA, 54 United States Code (U.S.C) § 300101, National Preservation; 36 Code of Federal Regulations (CFR) Part 800, Advisory Council on Historic Preservation; and United Facilities Guide Specifications (UFGS). The Contractor shall comply with all applicable Federal historical structure and archeological laws. TE A-01 provides more detail on historic properties at FS/HAAF.

If, while performing any type of excavation as part of accomplishing a task under this contract, the Contractor encounters any indication of historical or archeological items, they shall cease work and notify the COR/ACOR, mark the area to avoid inadvertent disturbance, and comply with the requirements in TE A-2 FS SOP #3 (accidental Discovery of Archeological Deposits, Paleontological Deposits, and Human Remains within the Integrated Cultural Resource Management Plan). In emergency operations, the Contractor shall comply with this

requirement to the extent possible without jeopardizing such operations and notify the COR/ACOR. Most National Register of Historic Places eligible archeological sites and cemeteries have their boundaries marked with blue green (teal) paint, signage, and/o seibert stakes. There should be no ground disturbance and no vehicle traffic within the teal painted boundaries, including road maintenance activities.

2.3.4 Repair and Replacement. The Contractor shall report damages to the COR/ACOR within one (1) hour. The Contractor shall repair or replace parts with products similar in appearance to the original. Repairs, renovation, or replacement to historic buildings must be approved by the KO. The Contractor shall coordinate work through the Cultural Resources Manager. The Contractor shall comply with the appropriate provisions and stipulations of the Secretary of Interior's "Standards for Rehabilitation and Guidelines for Rehabilitating Historic Buildings" (Revised 1983) and TE 6, Integrated Cultural Resources Management Plan Location maps are available at the DPW Engineering Section.

2.4 Salvage. The Government retains all salvage rights to replaced property of value. The Government will determine the value of the property. Items of no value shall be disposed of at the Contractor's expense. For items of value, and for all Government equipment regardless of value, the Contractor shall prepare DD Form 1348-1 for property disposal.

2.5 Special Requirements

2.5.1 Security.

2.5.1.1 Access and General Protection/Security Policy and Procedures. The Contractor and all associated subcontractors' employees shall comply with applicable Installation, Facility, and Local Security Policies and Procedures. The Contractor workforce shall comply with all personal identity verification (PIV) requirements as directed by DoD, Headquarters Department of the Army (HQDA), and local policy. The COR/ACOR will request changes in Contractor security matters or processes if the Force Protection Condition (FPCON) at any individual facility or installation changes.

2.5.1.2 Motor Vehicle Operators. Contractor's personnel, whose tasks require operation of any vehicles, shall possess a valid driver's license, certificates, and permits applicable for the type and class of vehicle being operated.

2.5.1.3 Contractor Vehicle Registration. Currently there is no requirement to register Contractor owned vehicles with the Provost Marshal or Department of Emergency Services (DES). However, all vehicles must be registered IAW current state requirements. In addition, the Contractor shall maintain a list of all Contractor-owned or operated vehicles and trailers operating on the Installation at all times. The list may be used in case of emergency and/or

another contingency. Evidence of vehicle ownership and vehicle liability insurance must be presented upon request.

2.5.1.3.1 Contractor and Vendor Access. All privately-owned vehicles, motorcycles, Contractor or vendor-furnished vehicles and equipment must enter the Installation through the designated secure access control points (ACP). Under the present Installation FPCON, vehicle and equipment operators and passengers must possess only a valid photo identification card to access the Installation. Vehicle and equipment operators must also possess and be ready to show a valid state driver's license, current vehicle registration, and proof of state required minimum liability insurance. As determined by the Installation FPCON, an elevated FPCON may require additional security screening and/or limited Installation access.

2.5.1.3.2 All Contractor personnel requesting access to FS/HAAF will enter through the designated Visitor Control Center (VCC). All Contractor personnel will be required to present a United States National or State issued identification that is capable of being scanned for valid entry. Contractor personnel will receive a visitor's badge at the VCC with the length of access allowed. The maximum access length for visitor badging is one year. Once issued a valid visitor's badge, Contractor personnel may enter any Manned Access Control Point/Gate. All Contractor personnel and their vehicles, equipment, and packages are subject to inspection or examination (search) at entry/exit of the FS/HAAF Installation.

2.5.1.3.3 Contractor and all associated subcontractors' employees shall comply with applicable installation, facility and area commander installation/facility access and local security policies and procedures (provided by DES) IAW Army Directive 2014-05. The Contractor shall provide all information required for background checks to meet installation access requirements, to be accomplished by the installation Provost Marshall Office, DES, or Security Office. Contractor workforce must comply with all personal identity verification requirements as directed by DoD, HQDA and/or local policy. In addition to the changes otherwise authorized by the changes clause of this contract, should the Force Protection Condition (FPCON) at any individual facility or installation change, the Government may require changes in contractor security matters or processes.

2.5.1.4 Physical Security. (Only applicable to Government Furnished Property (GFP) and Facilities). The Contractor shall safeguard all Government equipment, information, and property provided for Contractor use IAW AR 190-13, The Army Physical Security Program. The Contractor shall maintain a physical security checklist or log (e.g., Standard Form (SF) 701, Activity Security Checklist), which will be forwarded to the KO/COR, no later than (NLT) the tenth (10th) of each month, following the month of surveillance. The Contractor shall secure Government facilities, equipment, and materials at the close of each work period.

2.5.1.4.1 The Contractor will be provided Government furnished on-site staging area for necessary equipment and materials. The Contractor shall secure the area at the close of each work period. The Contractor shall be solely responsible for any loss or damage of equipment and material. The Contractor shall ensure debris of any type will be disposed of according to local policies and directives.

2.5.1.5 Secure Area Access. Portions of the work under the contract are performed in secure areas and all persons requiring access to a secure area will be escorted by the activity or Government personnel. In the case of escort, forty-eight (48) hours advance notice to the activity shall be required except in emergency or urgent work. Contractor employees requiring access to secure areas shall be free of felony convictions, and prior Military Service Members shall have an honorable discharge (See DD Form 254, Department of Defense Contract Security Classification Specification).

2.5.1.6 Employee Terminations. When an employee is terminated from employment on the contract for any reason, the Contractor shall have an out-processing checklist that identifies the Government issued CAC card and Installation Access Badge/Pass has been turned in to the COR/ACOR and property items accounted for and back in proper custody. A signature shall be required on the checklist from the appropriate person acknowledging receipt of the items. Checklists shall be retained for the duration of the contract. The current DPW checklist will be provided during the phase in period.

2.5.1.7 Departing Employees. The Contractor shall ensure Contractor employees return security photographic identification cards, permits, CAC, GFP, keys, photo passes, range passes, sensor access (slide) cards and that access to the LAN email has been canceled. All out-processing Contractor employee CACs must be returned to the COR/ACOR no later than close of business on the last workday. A formal termination or departing memo must be submitted to the COR/ACOR and security office with the requested items stating they have been collected (Deliverable A009).

2.5.1.8 Key Control. The Contractor shall establish a control system to ensure no keys issued to the Contractor by the Government are lost, misplaced, or used by unauthorized persons. Government keys shall not be duplicated by the Contractor without the COR's/ACOR's authorization. Procedures developed to control Government keys shall be included in the Contractor's QCP. The Contractor shall comply with AR 190-13 The Army Physical Security Program and AR 190-51 Security of Unclassified Army Property (Sensitive and Non-sensitive, applicable to key and lock).

2.5.2 Security Training.

2.5.2.1 iWATCH Training. The Contractor shall brief the local iWATCH program (training standards provided by the Requiring Activity (RA) Anti-Terrorism Officer (ATO)) to all the Contractor's employees and associated Subcontractors. This training is used to inform employees of the types of behavior to watch for and instruct employees to report suspicious activity to the COR/ACOR. The Contractor shall complete the training within thirty (30) calendar days of contract award and within five (5) calendar days of new employees commencing performance with the results reported to the COR/ACOR NLT thirty (30) calendar days after contract award.

2.5.2.2 Anti-Terrorism (AT) Level I Awareness Training. All Contractor employees, to include Subcontractor employees, requiring access to FS/HAAF installation, facilities and controlled access areas shall complete AT Level I awareness training within thirty (30) calendar days of contract start date and within thirty (30) calendar days of new employees commencing performance and send to the COR/ACOR via both electronic and paper copy. The Contractor shall complete the training within thirty (30) calendar days of contract award. AT level I awareness training is available at the following website: <http://jko.jten.mil>.

2.5.2.2.1 If access to a computer is not available, the FS/HAAF Level II Anti-Terrorism Officer (ATO) will conduct AT Level I training for the Contractor and employees within 30 calendar days after contract start and maintain a copy of the attendance roster for one (1) year. If the requiring activity does not have an ATO, the first ATO in the chain of command will conduct this training.

2.5.2.3 Operational Security (OPSEC) Awareness Training. IAW AR 530-1, Operations Security, Contractor employees shall complete Level I OPSEC Awareness training within thirty (30) calendar days of contract award and send to the COR via both electronic and paper copies. All Contractor personnel shall complete Level I OPSEC Awareness training annually. Level I OPSEC training is available at the following website: <https://securityawareness.usalearning.gov/opsec/index.html>.

2.5.2.3.1 All Contractor employees must complete the DoD Cybersecurity Awareness Training before issuance of network access and annually thereafter (Deliverable A10, IA Awareness Training). Upon completion of training, the Contractor shall submit training certificates to the COR.

2.5.3 Safety. The Contractor shall safeguard and maintain all Government and Contractor property, as well as provide for the safety and well-being of personnel employed under this contract. The Contractor shall comply with AR 385-10, The Army Safety Program. All Contractor employees shall wear a reflective vest or suitable substitute while working during darkness hours. Contractor shall be responsible for any injury to any Contractor's representative, or others, as well as for any damage to any personal or public property that

occurs during the performance of this contract that is caused by the Contractor's fault or negligence.

2.5.3.1 Safety Plan. The Contractor shall develop and implement a safety program for its employees. The Contractor shall submit the Safety Plan to the KO/COR/ACOR for review and acceptance within ten (10) business days of commencement of work. Revisions shall be submitted to the KO/COR/ACOR five (5) business days prior to the effective date of change (Deliverable A 011).

2.5.3.2 Occupational Safety and Health (OSHA). The Contractor shall comply with the OSHA standards. The Contractor shall comply with all applicable Federal, State, and local laws, regulations, and directives. If the Contractor fails or refuses to comply promptly with safety requirements, the Government may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to any such order shall be made the subject of claim for extension of time or for excess costs or damages to/by the Contractor. The Contractor shall be responsible for enforcement of all safety requirements by the Contractor and his Subcontractors/teaming partners and/or joint venture partners.

2.5.3.3 A Hot Work Permit. A Hot Work Permit is required any time heat producing devices are used and shall be issued by the Fire Department prior to ANY work being started.

- Example, welding, grinding, cutting, brazing, etc.
- Hot Work Permits will be closed after hot work is completed, and before personnel responsible for the work clears the job site

2.5.4 Training, Physical Requirements, or other Expertise Required.

2.5.4.1 Certification and Licensure. The Contractor shall ensure all its employees and associated subcontractors are certified or licensed in the specific areas as required by the State of Georgia. The Contractor shall ensure its employees are certified or licensed in the appropriate Environmental Protection Agency (EPA) areas required. The Contractor shall ensure all required documentation of certification or licensure for Contractor personnel are filed with the COR/ACOR within twenty-four (24) hours prior to employees commencing performance.

2.5.4.2 New Facilities Equipment Training. The Contractor shall inspect new equipment and systems upon notification by the COR/ACOR that the equipment has been accepted by the Government. The Contractor shall inspect and evaluate new equipment for compliance with the manufacturer's specifications and shall notify the COR/ACOR of all deficiencies noted during this inspection. The Contractor shall attend scheduled training of new equipment and maintenance meetings with the Government as requested by the COR/ACOR as part of accepting a newly built or renovated facility.

2.5.4.3 Asbestos Awareness Training. IAW 29 CFR 1910.1101, all personnel that may come into contact with asbestos while performing work duties shall attend asbestos awareness training annually. This training course is targeted for employees who may disturb asbestos containing materials while performing normal work duties. This includes all operations and maintenance employees (electrician, plumber, and HVAC system), facility coordinators, cleaning and housekeeping personnel.

2.5.4.4 Perform Hazardous Material Work. The Contractor shall perform hazardous material work (Asbestos Containing Material, Lead Based Paint, and mold) incidental to the services provided under this contract, to include but not limited, to facilitate testing and sampling of hazardous materials. The Contractor shall perform removal of animal feces accumulations. The contractor shall have all the required training and license necessary to conduct the activities described in this section. The contractor shall comply with all applicable rules, policies, and regulations associated with work in this section.

2.5.4.4.1. The Contractor shall abate Asbestos Containing Material (ACM) that is incidental to maintenance and repair activities. Disposal of ACM shall be coordinated thru the DPW- ED and IAW applicable regulations.

2.5.4.4.2. The Contractor shall abate lead based paint that is incidental to maintenance and repair activities. Disposal of lead paint containing material shall be coordinated thru the DPW- ED and IAW applicable regulations.

2.5.4.4.3. The Contractor shall abate mold under the negotiated scope of the PWO or in response to a DMO. Disposal of mold contaminated material shall be coordinated thru the DPW-ED and IAW Army Technical Bulletin Medical 531, Facility Sanitation Controls and Inspections and the U.S. Army Public Health Center Technical Guide 277, Army Mold Remediation Guidance and applicable regulations.

2.5.4.4.3.1 Contractor shall fill out Post Remediation Verification Letter (TE A-5) after responding to Mold DMO/PWO) IAW TE A-6 (Army Mold Remediation Guidance), TE A-6A (Fort Stewart Mold Remediation Guidance), and TE A-7 (Mold Assessment Guide).

2.5.4.4.3.2 Mold related DMO prioritization instructions. These instructions apply to Mold related DMOs ONLY. All Mold related DMOs will be processed as "Priority 2 Urgent". Initial response time for Mold Assessment is one (1) business day. Contractor response time for Mold remediation work completion is seven (7) calendar days. DMO restrictions of no more than thirty-two (32) labor hours and \$10,000 in materials and equipment costs remain unchanged.

2.5.4.4.3.3 Contractor will ensure all technicians receive the training located at: [https://armyeitaas.sharepoint-mil.us/sites/IMCOM-HQ-G4/SitePages/Infrastructure-Sustainment-PW-GFEBS-eTraining-\(GeT\).aspx](https://armyeitaas.sharepoint-mil.us/sites/IMCOM-HQ-G4/SitePages/Infrastructure-Sustainment-PW-GFEBS-eTraining-(GeT).aspx).

2.5.5 Environmental Requirements.

2.5.5.1 Green Procurement. Section 6002 of the Resource Conservation and Recovery Act of 1976 (RCRA) requires the use of recycled and recovered products identified in the EPA's Comprehensive Procurement Guidelines.

2.5.5.2 The Contractor shall use these recycled or recovered products unless they cannot be procured within a reasonable period of time not to exceed seven (7) calendar days; at prices not to exceed five (5) percent of prevailing rates; or the product(s) does not meet technical or performance standards. EPA Guidelines are the minimum requirement. The Contractor shall use materials and products commonly used in industry. The Contractor shall maintain records and submit an annual report to the COR/ACOR, along with the annual certification required by FAR 52.223-9 (Certification and Estimate of Percentage of Recovered Material Content for EPA Designated Items), upon completion of the base year and each option year.

2.5.5.3 Environmental Compliance. The Contractor shall comply with all Federal, State, Local, and Installation Environmental Laws, Rules, Plans, and Policies. The Contractor shall use and store all materials, chemicals, and equipment used in the performance of services on the installation IAW with Industry Standards, Local, State and Federal Laws. The Contractor shall be financially responsible for all fines and associated costs for hazardous waste management, transportation, and disposal of waste due to the Contractor's non-compliance. The Contractor shall submit Safety Data Sheets (SDS) for approval on all materials, five (5) calendar days before delivery of the material, to the COR/ACOR. The Contractor shall provide upon request from the COR/ACOR all required data to meet environmental mandated reporting requirements (e.g., air emission data, hazardous material storage/usage, herbicide/pesticide usage, solid/hazardous waste generation). The Contractor shall provide data to meet reporting deadlines and during compliance inspections upon request from the COR/ACOR.

2.5.5.4 Spill Plan. The Contractor shall notify the COR/ACOR within one (1) hour, if the Contractor spills or releases any hazardous substances, i.e., substances listed in 40 CFR 302, Designation, Reportable Quantities, and Notification. The Contractor shall submit a Spill Plan to the KO for approval within thirty (30) calendar days of contract award IAW Spill Prevention Control and Countermeasure Plan.

2.5.6 Contingency Plans (Deliverable A012).

2.5.6.1 General. The Contractor shall establish, maintain, and implement Contingency Plans

for mobilization, disaster, and labor dispute contingencies. The plans shall assume no Government support to the Contractor workforce. The Contractor shall, within thirty (30) calendar days of contract award, designate in writing a single contact Designated Contingency Coordinator (DCC) within the Contractor's organization. The DCC shall participate and coordinate with the installation contingency and mobilization planning activities. The DCC shall participate in the installation contingency, emergencies, mobilization planning and execution conferences; and shall modify and maintain appropriate Contractor contingency plans to compliment or enhance corresponding installation plans. The Contractor shall submit all plans to the KO for approval.

2.5.6.2 Mobilization Contingency Plan. This plan shall establish procedures, personnel, and means of maintaining or expanding performance of all PWS requirements in the event of rapid deployment or sudden build-up of military forces. The Contractor shall submit a Mobilization Contingency Plan within thirty (30) calendar days of contract award and updated annually thereafter. The plan shall be approved by the KO/COR/ACOR prior to the start of work.

2.5.6.3 Disaster Contingency Plan. This plan shall establish procedures, identify personnel, document essential PWS disaster services and identify the means of maintaining essential PWS requirements in the event of a disaster. Disaster means natural disaster (e.g., earthquake, major storm, flash food, or hurricane), utility outage, terrorist attack or other special circumstances identified by the Government. The Contractor shall submit a Disaster Contingency Plan within thirty (30) calendar days of contract award and updated annually thereafter. The plan shall be approved by the COR/ACOR prior to the start of work.

2.5.6.4 Labor Dispute Contingency Plan. This plan shall establish procedures and identify responsible personnel to provide the services below, with no interruption in the event of a labor dispute:

- a. Identify and address critical Preventive Maintenance and inspection tasks.
- b. Maintain electrical emergency generators.
- c. Process and execute emergency and urgent service and work orders.
- d. Maintain wells, lift stations.
- e. Maintain Wastewater treatment plants and associated collection.
- f. Maintain Airfield Lighting.
- g. Maintain air conditioning in Network Operation Centers (NOC's), Sensitive Compartmentalized Intelligence Facility (SCIF's) and computer rooms.
- h. Maintain Central Energy Plants and associated equipment.
- i. Maintain Mass Notification Systems.
- j. Maintain Supervisory Control and Data Acquisition Systems (SCADA).
- k. Maintain Utility Infrastructure and distribution systems, and
- l. Maintain Traffic Control Devices.

The plan shall establish procedures and time frame to secure replacement personnel in the event of a strike and shall also record the Contractor's experience with and establish Contractor procedures for collective bargaining. The Contractor shall submit a Labor Contingency Plan thirty (30) calendar days after contract award date.

2.5.6.5 Plan Updates. The Contractor shall update these plans as changes occur and shall submit a copy of the proposed plan to the KO for approval at least thirty (30) calendar days prior to the proposed effective date of the updated plan.

3.0 Performance Requirements and Standards.

3.1 Performance Task Requirements, Standards and Acceptable Quality Levels (AQLs).

3.2 Quality Assurance (QA). The Government will evaluate the Contractor's performance under the contract IAW the Government's Quality Assurance Surveillance Plan (QASP). QASPs are considered to be "living documents," dynamic, adaptable, and subject to modification based on Contractor performance surveillance results. The QASP is not part of the PWS and will not be issued with the solicitation. The QASP focuses on the procedures and processes the Government will implement to assure the Contractor is performing IAW the performance standards within the PWS. The Government plan defines the criteria of how the Contractor's performance will be evaluated, the frequency of surveillance, and the items to be inspected. Although the Government will develop a QASP, Government surveillance of Contractor performance is not limited to the QASP, or the performance objectives, outlined in the Performance Requirements Summary (PRS). The Government retains the right to evaluate all services required by the contract. The Government will perform inspections and tests in a manner that will not unduly delay the work. If any of the services performed do not conform to contract requirements, the Contractor shall perform the services again at no additional cost to the Government.

3.3 Quality Control Plan (QCP). Quality control is the responsibility of the Contractor. The Contractor shall develop, implement, and maintain an effective quality control program which shall be documented in a QCP to ensure services are performed IAW this PWS. The Contractor shall develop and implement procedures to identify and prevent the recurrence of defective services. The Contractor's QCP is the means by which they assure themselves that the work conforms to contract requirements. The basic principle of the plan is that the Contractor is responsible for quality control. The QCP shall be constructed in such a manner that each CLS service can be extracted and used for that function only and not contain extraneous information. The Contractor's QCP shall include a separate section, which addresses the Contractor's method of managing quality of work. The QCP shall include a description of the inspection system to address services listed in this PWS, and a description

of the methods to be used for identifying and preventing defects in the quality of services performed. The plan shall include a description of the Contractor's inspection system to include specifics as to areas to be inspected on a scheduled and unscheduled basis, frequency of inspections, and the title and organizational placement of the Contractor's inspectors. No lead person or first line supervisor shall be considered a Quality Control Inspector. The Contractor shall develop, maintain, and submit a QCP to the KO for acceptance within thirty (30) calendar days after the contract is awarded. The Contractor shall submit any proposed changes in the QCP to the KO for written approval five (5) business days prior to implementation (Deliverable A013).

3.3.1 Emergency Utilities Operating Procedures. The Contractor shall explain in his QCP how the Contractor proposes to utilize his personnel, materials, and equipment to respond to and accomplish emergency maintenance or repair work during all regular and non-regular duty hours for any utility outages. The QCP shall include a procedure to follow in the event that electrical power to buildings or portions thereof is lost; a procedure to follow in the event of a water supply emergency due to interior or exterior secondary water distribution line ruptures, freeze-ups, or contamination of the water supply; a procedure to follow in the event of a natural gas or propane emergency; a procedure to follow in the event that the Installation sewage collection systems malfunction due to stoppage in the collection mains, failure of sewage lift stations, or a pipeline rupture; and include a procedure to follow in the event of an Uninterrupted Power Supply (UPS) or Emergency Generator outage or breakdown. The plan shall outline a contingency plan for providing repair, replacement, or backup power sources such as rental units during the outage or breakdown.

3.3.1.1 Other Emergency Services to include, but not be limited to:

- Pest Control
- Command-Directed operations support
- Natural disasters
- Emergency work due to loss of operation of emergency generators and water pumps
- Emergency work for the security or protection of Government property
- Emergency work due to loss of air conditioning or heating for data processing equipment and other temperature critical facilities
- Emergency work due to loss of operation of refrigeration and kitchen equipment
- Emergency work due to a malfunction in fire alarm or fire sprinkler systems
- Response to emergency DMOs

3.4 Quality Control Files. The Contractor shall maintain files of all inspections or tests conducted by the Contractor, to include any corrective actions taken. These files shall be subject to Government review at the COR's discretion during the contract term, to include any

extensions of contract term. The Quality Control Files will be the property of the Government and shall be turned over to the Government upon completion or termination of the contract.

3.5 Customer Feedback Program.

The Contractor shall establish and operate a customer feedback program as part of the QCP.

4.0 Performance Task Requirements, Standards and Acceptable Quality Levels (AQLs)

Required Services/Performance Objectives	PWS Para #	Performance Standard	Maximum Allowable Degree of Deviation from Requirement (AQL)	Method of Surveillance	Deduct Schedule
# 1. Priority 1 DMO	Overarching PWS, paragraph 2.2.3.2	Complete 100% of Emergency DMOs within twenty-four (24) hours	No more than zero (0) defects per month.	100% Inspection	\$1500 per defect above AQL
#2. Priority 2 DMO	Overarching PWS, paragraph 2.2.3.2	Complete all Priority 2 DMOs within seven (7) calendar days	No more than two (2) defects per month allowed.	Random Sampling	\$1000 per defect above AQL
			No more than 5% defects per month allowed per end of month overdue DMO reports	100% inspection of all overdue DMO's from the monthly report	\$250 per defect above AQL.
# 3. Priority 3 DMO	Overarching PWS, paragraph 2.2.3.2	Complete all Priority 3 DMOs within thirty (30) calendar days	No more than two (2) defects per month allowed.	Random Sampling 100% inspection of	\$100 per defect above AQL

			No more than 8% defects per month allowed	all overdue DMO's from the monthly report	
#4. PMO Tasks	Vertical Maintenance PWS Attachment, CLS411, paragraph 2.2.4	Execute all PMO tasks scheduled for the month	No more than zero (0) defects per month allowed. 2% Deviation from performance standard	Random Sampling	\$1000 per defect above AQL
#5. PWOs	Overarching PWS, paragraph 2.2.6	Complete PWOs within the scheduled delivery date	No more than 1 defect allowed per month.	100% inspection	\$500 per defect above AQL.
#6 Workload Management in GFEBS	2.2.3.3. for DMOs 2.2.4 for PMOs	TECO DMOs and PMOs in GFEBS within seven (7) calendar days of completion	No more than five (5) defects allowed per month	Random Sample	\$500 per defect above AQL

5.0 Common Levels of Support (CLS)

The Contractor shall provide overall management, supervision, personnel, labor, generalized or specialized equipment necessary to maintain, repair, operate, and perform all the CLS functions of the Base Operations specified below. This shall be done IAW all the terms, conditions, general and special provisions, specifications, drawings, attachments, and exhibits contained herein or incorporated by reference.

The Contractor shall ensure that all work meets or exceeds the specifications for the listed CLS.

CLS	Service Title	Attachment No.
403	Solid Waste Management	Annex E
404	Maintenance - Grounds	Annex F
408	Pavement Clearance	Annex G
411	Facility Maintenance – Vertical	Annex H
420	Facility Maintenance - Horizontal	Annex J
501	Heating and Cooling Services	Annex K

503	Wastewater Services	Annex L
510	Pest Management	Annex M

6.0 Deliverables: Refer to TE A-8

7.0 Related Documents.

7.1 Definitions and Acronyms

7.1.1 Definitions.

7.1.1.1 Acceptable Quality Level (AQL). The AQL is the maximum percent defective (or the number of defects per hundred units) for the purposes of sampling inspection can be considered satisfactory.

7.1.1.2 Alternate Contracting Officer's Representative (ACOR). An employee of the U.S. Government provided by the RA and appointed by the KO to provide support to CORs in monitoring and documenting the Contractor's performance. These alternate surveillance support personnel will serve as on-site representatives of the COR in performance of actual contract surveillance if they meet all COR training, experience requirements, and are appointed by the KO as an ACOR.

7.1.1.3 Ashes. The residue from burned wood, coal, coke, and other combustible material.

7.1.1.4 Bulk Waste. Large items of solid waste such as household appliances, furniture, auto parts, pallets, shelving, piping, stone, concrete rubble, brick, lumber, toys, and other wastes; the size or weight of which, precludes or complicates the handling by normal collection, processing, or disposal methods.

7.1.1.5 Bulky Waste. The waste placed at the collection point or curbside that doesn't fit or is too heavy to be placed in the routine collection container. These wastes include but are not limited to: lumber, scrap metals, bricks, blocks, concrete rubble, stones, toys, furniture, appliances, logs, limbs, televisions, cabinets, automotive components, power equipment, crates, wheels, de-rimmed tires, electronics and their components, etc.

7.1.1.6 Cannibalize. Remove parts from Government property for use or for installation on other Government property.

7.1.1.7 Child, Youth and School Services (CYS). Overarching naming convention for

Child Development Center (CDC), Youth Activity Center, and School Age Services (SAS). CYS is used when referencing all programs.

7.1.1.8 Collection Frequency. The number of times collection is performed during a specific time frame.

7.1.1.9 Collection Point. The location designated on the drawings or maps or described in this performance work statement where solid waste, including bulky materials, will be temporarily stored for collection by the Contractor.

7.1.1.10 Commercial Solid Waste. All types of solid waste generated by stores, offices, restaurants, warehouses, and other non-manufacturing activities, excluding residential and industrial waste.

7.1.1.11 Construction and Demolition (C&D) Waste. The waste building materials, packaging and rubble resulting from construction, remodeling, repair, and demolition operation on pavement, housing, commercial buildings and other structures.

7.1.1.12 Contract Administrator (CA). The official Government representative delegated authority by the KO to administer a contract. This individual, normally working in an appropriate contracting or procurement career field, advises on all technical contractual matters.

7.1.1.13 Contract Discrepancy. A failure of the Contractor to perform IAW contract requirements and specifications, e.g., a failure of the Contractor to provide, or provide on time, the required contract products or services; or it may result because delivered products or services do not meet specific contract requirements.

7.1.1.14 Non-Compliance Report (NCR). A report used to document other than satisfactory Contractor performance. The NCR requires the Contractor to explain, in writing, why performance is other than satisfactory; how performance shall be returned to satisfactory levels; and how recurrence of the problem shall be prevented in the future.

7.1.1.15 Contractor. A supplier or vendor awarded a contract to provide specific supplies or service to the Government. The term used in this contract refers to the prime.

7.1.1.16 Contractor Acquired Property (CAP). Property acquired, fabricated, or otherwise provided by the Contractor for performing a contract. Contractor retains title.

7.1.1.17 Contracting Officer (KO). A person with authority to enter into, administer, and or terminate contracts, and make related determinations and findings on behalf of the Government. Note: The only individual who can legally bind the Government.

7.1.1.18 Contracting Officer's Representative (COR). An employee of the U.S. Government appointed by the KO to help administer the contract. Such appointment shall be in writing and shall state the scope of authority and limitations. This individual has authority to provide technical direction to the Contractor as long as that direction is within the scope of the contract, does not constitute a change, and has no funding implications. This individual does NOT have authority to change the terms and conditions of the contract.

7.1.1.19 Curb Side Pick-Up. Collection of solid waste (to include bulky waste) that is placed next to curb, doorway, or alley by the supported activity. This refers to locations that are not serviced by bulk containers (dumpsters or compactors).

7.1.1.20 Debris. Includes, but is not limited to, paper, cans, bottles, cigarette butts, cardboard, plastic, limbs and branches, pine straw and pinecones, leaves, rocks, and other similar items.

7.1.1.21 Defective Service. A service output that does not meet the standard of performance associated with the PWS.

7.1.1.22 Deliverable. Anything that can be delivered; can include non-manufactured things, such as meeting minutes or reports.

7.1.1.23 Equipment. A tangible item that is functionally complete for its intended purpose, durable, nonexpendable, and needed for the performance of a contract. Equipment is not intended for sale and does not ordinarily lose its identity or become a component part of another article, when put into use. Equipment does not include material, real property, special test equipment or special tooling.

7.1.1.24 Fertilization. Fertilization is the process of applying nutrient elements to the soil where the soil has become deficient in nutrients essential for proper plant growth.

7.1.1.25 Food Waste. Organic residue generated by the handling, storage, sale, preparation, cooking and serving of foods.

7.1.1.26 Garbage. Animal and vegetable waste resulting from the handling, preparation, cooking and consumption of foods.

7.1.1.27 General Fund Enterprise Business System (GFEBS). GFEBS is the U.S. Army's web-based enabled financial, asset, and accounting management system that standardizes, streamlines, and shares critical financial data across the Active Army, the Army National Guard, and the Army Reserves. GFEBS is the work management system that the Directorate of Public

Works uses for all order types and projects.

7.1.1.28 Generation. The act or process of producing refuse (solid waste) or recyclable materials.

7.1.1.29 Government-Furnished Property (GFP). Property in the possession of, or directly acquired by, the Government and subsequently furnished to the Contractor for performance of a contract. Government-furnished property includes, but is not limited to, spares and property furnished for repair, maintenance, overhaul, or modification. Government-furnished property also includes Contractor-acquired property if the Contractor-acquired property is a deliverable under a cost contract when accepted by the Government for continued use under the contract.

7.1.1.30 Government Property. All property owned or leased by the Government. Government property includes both Government-furnished property and Government purchased Contractor-acquired property. Government property includes material, equipment, special tooling, special test equipment, and real property. Government property does not include intellectual property and software.

7.1.1.31 Grass Cutting. Grass cutting includes cutting and trimming, within the designated area, all grasses, weeds, and other vegetation which is one inch or less in diameter (at ground level).

7.1.1.32 Hazardous Material. Any item or chemical, which is a “health hazard”, or “physical hazard”, as reflected in Federal Standard (FED-STD) 313 Material Safety Data and Disposal Data for Hazardous Materials Furnished to Government Activities, defined in OSHA 29 CFR 1910, and pursuant to FAR 23.301 (Hazardous Materials) Definition. It also includes any other material designated by a Government COR/technical representative as potentially hazardous and requiring safety controls (e.g., pesticides, fertilizers).

7.1.1.33 Installation Design Guide (IDG). IDGs provide standards for site planning, buildings, vehicular and pedestrian circulation, landscaping, site elements (e.g., signage, utilities), force protection, and sustainable design. The IDGs are specific to each Army installation.

7.1.1.34 Institutional Solid Waste. Waste that is generated by educational, health care, correctional and other institutional facilities.

7.1.1.35 Key Personnel. Contractor personnel evaluated in a source selection process and are used in the performance of a contract. When key personnel are used as an evaluation factor in best value procurement, an offer can be rejected if it does not have a firm commitment from the persons who are listed in the proposal. The prime Contractor is responsible for

performance of all subcontractors.

7.1.1.36 Loss of Government Property. Unintended, unforeseen, or accidental loss, damage, or destruction of Government property that reduces the Government's expected economic benefits of the property. Loss of Government property does not include occurrences such as purposeful destructive testing, obsolescence, normal wear and tear, or manufacturing defects. Loss of Government property includes, but is not limited to:

- a. Items that cannot be found after a reasonable search,
- b. Theft,
- c. Damage resulting in unexpected harm to property requiring repair to restore the item to usable condition, or
- d. Destruction resulting from incidents that render the item useless for its intended purpose or beyond economical repair.

7.1.1.37 Lot. A collection of service outputs from which a sample is to be drawn and inspected to determine conformance with the standard. This definition applies to the Performance Requirements Summary (PRS), not the word "lot" in Section B of the contract.

7.1.1.38 Lot Size. The number of service outputs in a lot. This definition applies to the PRS, not the words "lot size" in Section B of the contract.

7.1.1.39 Material. Property that is consumed or expended during the performance of a contract, component parts of a higher assembly, or items that lose their individual identity through incorporation into an end-item. Material does not include equipment, special tooling, and special test equipment or real property.

7.1.1.40 Material Handling Area. The material handling area is used for the accumulation and preparation of bulk solid waste for transportation to a solid waste management facility.

7.1.1.41 Non-Combustible Material. Material that doesn't burn at ordinary temperatures.

7.1.1.42 Non-Personal Services. The personnel rendering the services are not subject, either by the contract's terms or by the manner of its administration, to the supervision and control usually prevailing in relationships between the Government and its employees. Non-personal service contracts are authorized by the Government IAW FAR 37.104, under general contracting authority, and do not require specific statutory authorization.

7.1.1.43 Organic Storage Site. Area of accumulation for organic materials (e.g., leaves, logs, limbs, and grass clippings).

7.1.1.44 Performance Indicator. The characteristic of an output of a work process that can be measured.

7.1.1.45 Performance Requirements Summary (PRS). Identifies the key service outputs of the contract that will be evaluated by the Government to ensure contract performance standards are met by the Contractor (other services may also be inspected under the authority of the Inspection of Service Clause).

7.1.1.46 Physical Security. Actions that prevent the loss or damage of Government property.

7.1.1.47 Plant. A living organism, of the kind exemplified by trees, shrubs, herbs, grasses, ferns, and mosses, typically growing in a permanent site, absorbing water and inorganic substances through its roots.

7.1.1.48 Property. All tangible property, both real and personal.

7.1.1.49 Property Administrator (PA). An authorized representative of the KO, appointed IAW agency procedures, responsible for administering the contract requirements and obligations relating to Government property in the possession of a Contractor.

7.1.1.50 Property Records. Records created and maintained by the Contractor in support of its stewardship responsibilities for the management of Government property.

7.1.1.51 Provide. To furnish, as in Government-furnished property, or to acquire, as in Contractor-acquired property.

7.1.1.52 Pruning. Pruning is selectively removing unwanted growth to make a plant or tree grow or respond in a desired manner. Pruning differs from "shearing". Pruning involves selection and judgment. "Shearing" means clipping all growth on a plant at a uniform distance and shape.

7.1.1.53 Public Traffic Areas. Lobbies, hallways, corridors, stairwells, meeting rooms, and lavatories.

7.1.1.54 Quality Assurance (QA). Verification that services being performed by the Contractor are IAW acceptable standards.

7.1.1.55 Quality Assurance Evaluator (QAE). A Government representative responsible for performing surveillance and inspection of Contractor performance.

7.1.1.56 Quality Assurance Surveillance Plan (QASP). An organized document written by the Government specifying the surveillance methodology used for surveillance of Contractor performance.

7.1.1.57 Quality Control. All necessary measures taken by the Contractor to assure that the quality of an end product or service shall meet contract requirements.

7.1.1.58 Raise. Selective pruning of limbs, identified by the COR, or limbs that pose a public safety hazard with a minimum clearance of 14 feet over streets, parking lots, and driveways; eight (8) feet over walk areas; four (4) feet over buildings and three (3) feet from buildings and streetlights, IAW established industry standards.

7.1.1.59 Random Number Table. A table of numbers arranged in random fashion; a table used to select random samples.

7.1.1.60 Random Sample. A sampling method whereby each service output in a lot has an equal chance of being selected.

7.1.1.61 Random Sampling. A method for looking at a few individual items in a lot to measure the quality of that lot against a standard.

7.1.1.62 Real Property. DoD Lands, buildings, structures, utility systems, improvements, and appurtenances, thereto that includes equipment attached to and made part of buildings and structures, but not movable equipment. See Federal Management Regulation 102-71.20 (41 CFR 102-71.20).

7.1.1.63 Regulated Medical Waste. Waste not specifically excluded from the restrictions of Federal regulations and which meets the criteria listed in 40 CFR 259.

7.1.1.64 Refuse. All garbage, ashes, debris, trash, rubbish and items intended for disposal that are generated in conjunction with the activities in the areas covered in this contract. Items excluded are explosives, incendiary waste, hazardous waste, and pathological waste resulting from medical and radiological processes.

7.1.1.65 Refuse Collection. A system of collecting and transporting solid waste from pick-up stations to points of disposal.

7.1.1.66 Refuse Storage Containers. Cans, drums, bins, bags, boxes, crates, sidewalk litter containers, dumpsters, roll-off containers, or similar receptacles which are used for the temporary storage of solid waste while awaiting collection. The term "container" used in this document shall have the same meaning as solid waste storage container.

7.1.1.67 Residential Solid Waste. Waste generated by the normal activities of military housing not including Residential Community Initiative (RCI) , but not limited to: food waste, rubbish, ashes and bulky waste.

7.1.1.68 Sample Size. The number of outputs in the sample; a group of one or more tasks drawn from the specified performance.

7.1.1.69 Sampling. A sample consists of one or more service outputs drawn from a lot IAW random sampling procedures to be evaluated by Government personnel.

7.1.1.70 Scavenging. The uncontrolled and unauthorized removal of materials at any point of the solid waste management stream.

7.1.1.71 Sensitive Property. Property potentially dangerous to the public safety or security if stolen, lost, or misplaced, or that shall be subject to exceptional physical security, protection, control, and accountability. Examples include weapons, ammunition, explosives, controlled substances, radioactive materials, hazardous materials or wastes, or precious metals.

7.1.1.72 Service/Maintain. These words are interchangeable.

7.1.1.73 Shrub. A woody plant with several perennial stems. It will usually have a height less of than 13 feet and stems no more than about three (3) inches in diameter.

7.1.1.74 Soil. Includes, but is not limited to dust, dirt, stains, grease, smudges, streaks, spots, lint, or odors. Soil can be removed chemically, mechanically, or by a combination of both. Mechanical soil removal is removing soil with a machine such as a vacuum cleaner. Chemical soil removal is removing soil with a liquid that contains cleaning agents such as detergents, surfactants, and emulsifiers. The combination of chemical and mechanical methods such as an automatic floor scrubbing machine, uses the chemical method to breakdown and loosen soil which then the mechanical method picks up and carries the soil away. Which soil removal method is used depends on the cleaning objectives and on size, location, and type of surface to be cleaned and is the prerogative of the Contractor.

7.1.1.75 Solid Waste. Garbage, refuse, sludge, and other waste materials not excluded by Federal regulations. Solid waste is any solid, liquid, semi-solid, or contained gaseous material resulting from institutional, industrial, commercial, mining, agricultural, or community operations and activities. Solid wastes are accumulated, stored, or treated before being discarded. A material is discarded if abandoned and not used, reused, reclaimed, or recycled by being disposed of, burned, or treated. Regulated medical wastes are not included in this category.

7.1.1.76 Solid Waste Management Facility (SWMF). Any facility employed, beyond the initial collection processes and managing solid waste including, but not limited to: storage areas or facilities, transfer stations, rail haul or barge haul facilities, landfills, disposal facilities, solid waste facilities, surface impoundment and waste oil storage, repossessing, refining facilities, recovery facilities and waste tire storage facilities.

7.1.1.77 Standard. A measure of comparison; an acceptability criterion; a benchmark or yardstick against which a service will be measured.

7.1.1.78 Street Wastes. Materials picked up by manual or mechanical sweepings of alleys, streets, and sidewalks. Waste from solid waste receptacles and catch basins.

7.1.1.79 Subcontractor. One that enters into a contract with a prime Contractor. The Government does not have privity of contract with the subcontractor.

7.1.1.80 Tonnage. Weight measured in tons (not imperial).

7.1.1.81 Transfer Station. A transfer station is a facility which processes collected solid waste in a particular area for transportation to a solid waste management facility.

7.1.1.82 Tree. A woody plant having one erect perennial stem (trunk), at least three inches in diameter, at a point 4-1/2 feet above the ground, a definitely formed crown of foliage, and mature height of at least 13 feet.

7.1.1.83 Trimming. Cutting of grass and other vegetation around grounds obstacles that prevent mowing.

7.1.1.84 Unit Acquisition Cost.

a. For Government-furnished property, the dollar value assigned by the Government and identified in the contract; and

b. For Contractor-acquired property, the cost derived from the Contractor's records that reflect consistently applied generally accepted accounting principles.

7.1.1.85 Vector. A carrier, usually an arthropod, which can transmit a pathogen from one organism to another.

7.1.1.86 Wide Area Work Flow (WAWF). A secure web-based system for electronic invoicing, receipt, and acceptance. WAWF allows Government vendors to submit and track invoices and receipt or acceptance documents over the web allowing Government personnel

to process those invoices in a real-time, paperless environment.

7.1.1.87 Work Day. The number of hours per day the Contractor provides services IAW the contract.

7.1.1.88 Work Week. Monday through Friday, unless specified otherwise.

7.1.1.89 Yard Wastes. Materials such as: tree and shrub branches, trimmings, brush, grass clippings, leaves, Christmas trees, weeds, etc.

7.1.1.90 Demand Maintenance Order (DMO): *Known in AR 420-1 as Service Order (SO)*. A work authorization document used for work that is either corrective in nature (e.g., repairs, modifications, and replacements) or not generally considered to be a recurring maintenance activity. DMOs, therefore, are unscheduled and not known in advance. Examples include minor electrical, carpentry, and plumbing repairs, or locating utility lines. DMOs may be initiated by the Government, customer, or Contractor upon identification of a need requiring corrective action.

7.1.1.91 General Fund Enterprise Business System (GFEBS): The Government is required to use GFEBS for budgeting, managing, cost accounting and financial reporting of Garrison Operations, including DPW services. The Contractor is tasked by GFEBS Order Documents and is responsible to input all DMO project status and labor confirmations. The Government will utilize GFEBS for preparation of most required status reporting and for monitoring Contractor performance in timeliness and accuracy of data input. GFEBS documents DPW Work Management and Reporting of DMOs PMOs, OWOs, and PWOs. GFEBS is the Government's system of record.

7.1.1.92 Individual Job Order (IJO): *Known in GFEBS as a PWO*. Directive for maintenance and repair which exceed SO or DMO criteria. The term is used in AR 420-1, but in GFEBS the execution work document is referred to as a *Project Work Order (PWO)*.

7.1.1.93 Maintenance: Work required to preserve and maintain a real property facility in such condition that it may be used effectively for its designated functional purpose. Maintenance includes work done to prevent damage which would be more costly to restore than to prevent. Maintenance includes work to sustain components. Examples include renewal of disposable filters, painting, caulking, refastening loose siding, and sealing bituminous pavements.

7.1.1.94 New Work: Work that results in the creation or addition to an existing facility or of a building component or system which did not exist prior to the work, irrespective of

whether the work is funded from a construction or an operation and maintenance (O&M) account. New work that exceeds \$150,000 shall be accomplished through a separate contractual vehicle.

7.1.1.95 Operation Work Order (OWO): Covers services that are recurring, provide CLS, and do not fall into PM.

7.1.1.96 Preventive Maintenance (PM): Routine, recurring sustainment work performed on all real property facilities (RPF). PM is systematic inspection, care, and servicing of equipment, utility plants and systems, buildings, structures, and grounds facilities performed to detect and correct incipient failures and accomplishing minor maintenance. PM is executed by a Preventive Maintenance Order (PMO) in support of a preventive maintenance plan.

7.1.1.97 Preventive Maintenance Order (PMO): *Known in AR 420-1 as Preventive Maintenance.* A PMO is the work authorization document for recurring maintenance work that is performed on a scheduled basis (also referred to as Preventive Maintenance (PM)). All Preventive Maintenance plans will be entered into GFEBS; this is required in order to generate the PMO at the frequency required. PMO tasks include, but are not limited to, annual inspection of sump pumps, grounding point testing, maintenance of Dining Facility (DFAC) equipment, and annual cleaning of cooling towers. PMOs will be approved and issued on DA Form 4283, *Facilities Engineering Work Request*, or equivalent computer-produced facsimile or printout. The Government will identify applicable wage determinations (Service Contract Labor Standards, formerly Service Contract Act or Wage Rate Requirements, formerly Davis Bacon Act) for each PMO prior to issuing to the Contractor. Contractor execution of PMOs will be pre-approved by the Government following the review of Contractor work plans and schedules. Any changes in scheduled workload will be negotiated and incorporated into the contract by modification. Frequency requirements for scheduled tasks are presented at the FA level, as applicable.

7.1.1.98 Project Work Order (PWO): *Known in AR 420-1 as IJO.* A work execution document used for unscheduled work, including project-oriented work such as repairs, modifications, replacements, or installations that exceed the thresholds for a DMO. Project Work Orders can vary significantly in nature, scope, expertise, and location. Each PWO will be fixed priced based on the negotiated proposals required to accomplish the scope of work. Each PWO must have an approved DA Form 4283 authorizing the execution of the work.

7.1.1.99 Repair: Repair is one of the following:

- a. Restoration of a real property facility (RPF) to such condition that it may be used effectively for its designated functional purpose.

- b. Correction of deficiencies in failed or failing components of existing facilities or systems to meet current Army standards and codes where such work, for reasons of economy, should be done concurrently with restoration of failed or failing components. *

*In addition to condition-based failure, a utility system or component of the system may be considered “failing” if it is energy inefficient or technologically obsolete.

7.1.1.100 Scheduled Maintenance: Also referred to as *preventive maintenance (PM)*. Routine, recurring sustainment work performed on all real property facilities to detect and correct incipient failures and accomplishing needed minor maintenance. Systematic and cyclic check, inspection, servicing, and repair of deficiencies of utility plants and systems, buildings, structures, and grounds facilities. These repairs may also include replacement of parts or components necessary to keep equipment and/or systems operating effectively. Scheduled work requires the preplanning of resources resulting from a known requirement and encompasses the scheduling and execution of specific tasks. Scheduled work is planned such that Government operations are not disrupted and the work is executed efficiently without delays due to availability of labor, parts, material, and equipment. Scheduled work is performed through the issuance of PMOs and OWOs.

7.1.1.101 Service Order (SO): Also referred to as *DMO*. A service order is used for minor maintenance and repair or for emergency work, such as broken plumbing or electrical failures. Service orders represent the least controllable and most reactive work performed by the DPW. Service orders have the highest level of customer visibility of any work performed by the DPW.

7.1.1.102 Standing Operating Order (SOO): Also referred to as *Base Operation Support (BOS)*. A service-driven requirement captured on a DA Form 4283. The work execution document for execution of the service to be performed is an OWO. This work is operational in nature that is performed on a recurring basis, such as scheduled grounds maintenance, plant operation, operator maintenance, refuse collection, custodial services, and pest management. Scheduled work requires the preplanning of resources on the basis of a known requirement and encompasses the scheduling and execution of specific tasks. Prior to the creation of an OWO; an approved DA Form 4283 will be required. From the approved DA Form 4283, an OWO or equivalent computer-produced facsimile or printout will be issued when the work is ready for execution. Contractor execution of OWOs will be pre-approved by the Government following the review of Contractor work plans and schedules. Any changes in scheduled workload will be negotiated and incorporated into the contract by modification.

7.1.1.103 Unscheduled Maintenance: *Non-recurring maintenance or unscheduled repair*.

Work required to preserve and sustain a real property facility or its components due to unforeseen occurrences. The work is corrective in nature and not generally used for recurring tasks. Unscheduled maintenance is performed through the issuance of DMOs (less than the 32 work-hours threshold) and PWOs (above the 32 work-hours threshold). Sometimes a DMO is referred to as a SO, a work authorization document used for small-scale maintenance and repair on Government-owned or –leased facilities and equipment. The purpose of a DMO is to provide the Government with a means of remedying unplanned work up to a defined hourly threshold of 32 work-hours, per DFARS 222.402-70, for work requirements occurring outside of the normal recurring work. A DMO exceeding 32 onsite work-hours becomes a PWO and is subject to construction wage rates.

The Contractor shall utilize DMOs to accomplish any work up to the 32 work-hours threshold at the discretion of the COR/ACOR. The Government will combine multiple repair requirements received for the same trade in the same building or structure at the same time into one DMO, as long as the hourly threshold is not exceeded.

7.1.1.104 Work Order: *Also referred to as a work request.* The DA Form 4283 is used to capture the requirements for Individual Job Orders (IJOs), Standing Operating Orders (SOOs), Preventive Maintenance (PM), etc. Local procedures are used to capture the requirements for a DMO. There are 4 work authorization document types. The work authorization document types are as follows: DMO for Service Order, PMO for PM, OWO for Operation Work Order, and PWO for Individual Job Orders.

Order Types:

- DMO – SRM; small maintenance and repair on real property assets; sometimes referred to an SO.
- PMO – Recurring maintenance on real property assets
- PWO – IJO, maintenance and repair that exceeds work-hours of a DMO
- OWO – Base Operating Support (BOS), service driven work (custodial, grounds maintenance, pest control, refuse removal)

7.1.2 Acronyms.

ACC	Army Contracting Command
ACOR	Alternate Contracting Officer's Representative
AFARS	Army Federal Acquisition Regulation Supplement
AMC	Army Materiel Command
ANSI	American National Standards Institute
AQL	Acceptable Quality Level
AR	Army Regulation

ARC	Army Resource Center
ARMA	Army Maintenance Application
ATO	Anti-Terrorism Officer
CAC	Controlled Access Cards
CAP	Contractor Acquired Property
CDC	Child Development Center
CDRL	Contract Data Requirements List
CFE	Contractor Furnished Equipment
CFM	Contractor Furnished Material
CFP	Contractor Furnished Property
CFR	Code of Federal Regulations
CLIN	Contract Line Item Number
COB	Close of Business
CMRA	Contractor Manpower Reporting Application
CONUS	Continental United States (excludes Alaska and Hawaii)
COR	Contracting Officer's Representative
CORT	Contracting Officer's Representative Tool
CPARS	Contractor Performance Assessment Reporting System
DA	Department of the Army
DCMA	Defense Contract Management Agency
DES	Directorate of Emergency Services
DFARS	Defense Federal Acquisition Regulation Supplement
DID	Data Item Description
DoD	Department of Defense
DOL	Department of Labor
DONSA	Days of No Scheduled Activities
DOT	Department of Transportation
DPW	Directorate of Public Works
ECO	Environmental Compliance Officer
EM	Engineering Manual, U.S. Army Corps of Engineers (USACE)
EO	Executive Order
EPA	Environmental Protection Agency
ENV	Environmental
ERDC	Engineering Research Development Center
FAR	Federal Acquisition Regulation
FIPS	Federal Information Processing Standards
FPCON	Force Protection Condition
GFE	Government-Furnished Equipment
GFEBBS	General Fund Enterprise Business System
GFM	Government-Furnished Material
GFP	Government-Furnished Property

HLO	High Level Objective
HQDA	Headquarters Department of the Army
HSPD	Homeland Security Presidential Directive
IAW	In Accordance With
IGSA	Inter-Governmental Support Agreement
IMCOM	Installation Management Command
IPM	Integrated Pest Management
IPMC	Integrated Pest Management Coordinator
IPMP	Integrated Pest Management Plan
IT	Information Technology
KO	Contracting Officer
N/A	Not Applicable
NGB	National Guard Bureau
NLT	Not Later Than
OCI	Organizational Conflict of Interest
OCONUS	Outside Continental United States (includes Alaska and Hawaii)
OMB	Office of Management and Budget
OSHA	Occupational Safety and Health Administration
OWO	Operation Work Order
PA	Property Administrator
PAM	Pamphlet
PM	Preventive Maintenance
PMO	Preventive Maintenance Order
POC	Point of Contact
PoP	Period of Performance
PPIRS	Past Performance Information Retrieval System
PRS	Performance Requirements Summary
PUB	Publication
PWO	Project Work Order
PWS	Performance Work Statement
QA	Quality Assurance
QAP	Quality Assurance Program
QASP	Quality Assurance Surveillance Plan
QC	Quality Control
QCP	Quality Control Plan
RCRA	Resource Conservation and Recovery Act
SDS	Safety Data Sheets
SF	Standard Form
SWMF	Solid Waste Management Facility
TE	Technical Exhibit
USARC	U.S. Army Reserve Command

U.S.C.	United States Code
VCE	Virtual Contracting Enterprise
VIP	Very Important Person
WAWF	Wide Area Work Flow
WD	Wage Determination

7.2 Applicable Directives, Publications.

10 CFR Part 450	Energy
25 TAC 295.212	Standards for Conducting Lead-based Paint
Activities 25 TAC Chapter 295	Subchapter C (25 TAC 295.50)
25 TAC Chapter 295	Subchapter I (25 TAC 295.206)
ACC PAM 70-1	Interim Army Contracting Command – Contracting Officer's Representative Policy Guide
AASHTO-T11	Standard Method of Test for Materials Finer Than 75-µm (No. 200) Sieve in Mineral Aggregates by Washing
AASHTO M247	Road Marking Glass Beads
AFI 13-213	Airfield Operations Management, Chapter
4 ASHRAE, Chapter 22	Fundamentals Handbook
ANSI A300	Standard Practices for Tree Care Operations
ANSI B30.11	Monorails and under hung Cranes
ANSI B30.16	Safety Standards or Overhead Hoists
ANSI/ASME A17.1	Safety Code for Elevators and Escalators
ANSI/ASME A17.2 Escalators	Inspector's Manual for Elevators and
ANSI/ASME A17.3	Safety Code for Existing Elevators and Escalators

ANSI/ASME A17.4	Guide for Emergency Evacuation of Passengers From Elevators
ANSI/ASME A17.5	Elevator and Escalator Electrical Equipment
ANSI/IEEE Std 142 Systems.	Practice for Grounding of Industrial and Commercial Power
ANSI/ASQC-Z1.4	National American Standard
ANSI Z60.1	American Standards for Nursery Stock
ANSI Z87.1-2003	Practice for Occupational and Educational Personal Eye and Face Protection Devices
ANSI Z133.1	Safety Requirements for Tree Care Operations
ANSI Z245.1	Mobile Refuse Collection and Compaction Equipment – Safety Requirements
AR 5-17	The Army Ideas for Excellence Program
AR 11-2	Management Controls
AR 11-27	Army Energy Program
AR 25-2	Information Management: Army Cybersecurity
AR 40-3	Medical, Dental, and Veterinary Care
AR 40-5, Change 1	Preventive Medicine
AR 40-400	Medical Services Patient Administration
AR 70-13	Management and Oversight of Service Acquisitions
AR 95-1	Flight Regulations

AR 95-2	Airspace, Airfields/Heliports, Flight Activities, Air Traffic Control, and Navigational Aids
AR 190-13	Army Physical Security Programs
AR 190-51	Security of Unclassified Army Property
AR 200-1	Environmental Protection and Enhancement
AR 200-2	Environmental Effects of Army Actions
AR 200-3	Natural Resources; Land, Forest, and Wildlife Management
AR 200-4	Cultural Resources Management
AR 200-5	Pest Management
AR 380-5	Information Security Programs
AR 385-10	Army Safety Program
AR 385-40	Army Accident Investigation and Reporting
AR 385-55	Prevention of Motor Vehicle Accidents
AR 420-1	Army Facilities Management
AR 420-74	Natural Resources – Land, Forest, and Wildlife Management
AR 420-76	Pest Management
AR 420-90	Fire Emergency Services
AR 530-1	Operations Security
AR 600-50	Standards of Conduct for Department of Army Personnel
AR 600-63	Army Health Promotion
AR 608-10	Child Development Services

AR 710-2	Supply Policy Below the National Level
ARD 2014-23	Conduct of Screening and Background Checks for Individuals Who Have Regular Contact with Children in Army Programs
29 CFR Part 1910	Occupational Safety and Health Standards
40 CFR	Protection of the Environment
40 CFR Subchapter I	Solid Wastes
40 CFR 202	Motor Carriers Engaged in Interstate Commerce
40 CFR 257	Criteria for Classification of Solid Waste Disposal Facilities and Practices
40 CFR Part 302	Protection of Environment, Designation, Reportable Quantities and Notification
40 CFR Part 60 & 63	AOAP
49 CFR 390-396	Motor Carrier Safety Standards
49 CFR 571	Federal Motor Vehicle Safety Standards
Clean Air Act (CAA)	
Clean Water Act (CWA)	
Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA)	
DA PAM 385-40	Army Accident Investigations and Reporting
DA PAM 420-1-1	Housing Management*
DA Pam 710-2-1	Supply Support Activity Supply System: Manual Procedures
DoD 4160.21-M	Defense Materiel Disposition Manual

DoDD 5500.7-R	Joint Ethics Regulation
DoDI 1402.5	Criminal History Background Checks On Individuals in Child Care Services
DoDI 4150.07	DoD Pest Management Program
DoDI 5000.72	DoD Standard for Contracting Officer's Representative (COR) Certification
EM 385 1 1	Safety and Health Requirements Manual
EO 13423	Strengthening Federal Environmental, Energy, and Transportation Management
EO 13693	Planning for Federal Sustainability in the Next Decade
EPA, Method 9095	Paint Liquids Filter Test
EPA, SW-846	Test Methods for Evaluating Solid Wastes, Physical/Chemical Methods
FC 3-260-06F	Air Force Design, Construction, Maintenance, and Evaluation of Snow and Ice Airfields in Antarctica 06-01-2015
Federal Standard #313	Material Safety Data and Disposal Data for Hazardous Materials Furnished to Government Activities
Federal Standard #595	Colors
FIFRA	Federal Insecticide, Fungicide, and Rodenticide Act
FIPS PUB 201-2	Personal Identity Verification (PIV) of Federal Employees and Contractors
Garrison's	Snow, Ice, and Sand Removal Control Plan
HSPD 12	Homeland Security Presidential Directive 12 Policy for a Common Identification Standard for Federal Employees and Contractor

IDG	Installation Design Guide
NFPA 1.12-2	Combustible Fibers
NFPA 780	Standard Lightning Protection System
OMB M-05-24	Office of Management and Budget (OMB) Guidance Implementation of Homeland Security Presidential Directive (HSPD) 12 – Policy for a Common Identification Standard for Federal Employees and Contractors
OPORD 13-153	Enterprise Municipal Services Performance Standards
OPORD 23-007	IMCOM FY23 Operation Counter Mold
SF 95	Position of Public Trust
TB MED 530 5-28,(h)(i)	Tri-Service Food Code
TM 5-623	Pavement Maintenance Management
TM 5-624	Maintenance and Repair of Surface Areas
TM 5-634	Solid Waste Management
TM 5-683	Electrical Interior Facilities
TM 5-820-4	Drainage for Areas other than Airfields
TM 9-6150-226-13	Electrical Feeder System
UFC 1-200-01	DoD Building Code (General Building Requirements)
UFC 4-010-1	DoD Minimum Antiterrorism Standards for buildings (Change 1)
UFC 4-021-01	Design and O&M for Mass Notification Systems
UFC 4-021-02NF	Security Engineering Electronic Security Systems

UFC 3-101-01	Architecture 11-28-2011
UFC 3-110-03	Roofing, with Change 1 05-01-2012
UFC 3-110-04	Roofing Maintenance and Repair 01-11-2007
UFC 3-120-01	Design: Sign Standards, with Change 2 03-01-2014
UFC 3-120-10	Interior Design, with Change 1 06-15-2006
UFC 3-190-06	Protective Coatings and Paints 01-16-2004
UFC 3-201-01	Civil Engineering 06-01-2013
UFC 3-201-02	Landscape Architecture, with Change 1 02-23-2009
UFC 3-210-10	Low Impact Development 07-01-2015
UFC 3-220-01	Geotechnical Engineering 11-01-2012
UFC 3-220-04	Backfill for Subsurface Structures 01-16-2004
UFC 3-220-05	Dewatering and Groundwater Control 01-16-2004
UFC 3-220-06	Grouting Methods and Equipment 01-16-2004
UFC 3-220-08	Engineering Use of Geotextiles 01-16-2004
UFC 3-220-10N	Soil Mechanics 06-08-2005
UFC 3-230-01	Water Storage, Distribution, and Transmission, with Change 2 11-01-2012
UFC 3-230-02	O&M: Water Supply Systems 07-10-2001
UFC 3-230-03	Water Treatment 11-01-2012
UFC 3-230-06A	Subsurface Drainage, with Changes 1-2 01-16-2004
UFC 3-240-01	Wastewater Collection, with Change 1 11-01-2012

UFC 3-240-02	Domestic Wastewater Treatment 11-01-2012
UFC 3-240-03N	Wastewater Treatment System Augmenting Handbook Operation and Maintenance 01-16-2004
UFC 3-240-05A	Solid Waste Incineration 01-16-2004
UFC 3-240-10A	Sanitary Landfill 01-16-2004
UFC 3-240-13FN	Industrial Water Treatment Operation and Maintenance 05-25-2005
UFC 3-250-01FA	Pavement Design for Roads, Streets, Walks, and Open Storage Areas 01-16-2004
UFC 3-250-03	Standard Practice Manual for Flexible Pavements 05-15-2001
UFC 3-250-04	Standard Practice for Concrete Pavements, with Change 2 01-16-2004
UFC 3-250-06	Repair of Rigid Pavements Using Epoxy Resin Grouts, Mortars and Concretes 01-16-2004
UFC 3-250-07	Standard Practice for Pavement Recycling 01-16-2004
UFC 3-250-08FA	Standard Practice for Sealing Joints and Cracks in Rigid and Flexible Pavements 01-16-2004
UFC 3-250-09FA	Aggregate Surfaced Roads and Airfields Areas 01-16-2004
UFC 3-250-11	Soil Stabilization for Pavements 01-16-2004
UFC 3-260-01	Airfield and Heliport Planning and Design 11-17-2008
UFC 3-260-02	Pavement Design for Airfields 06-30-2001
UFC 3-260-03	Airfield Pavement Evaluation 04-15-2001
UFC 3-260-05A	Marking of Army Airfield Heliport Operationl and Maintenance

Facilities, with Change 1 01-16-2004

UFC 3-260-11 FA	Model Design-Build (D-B) Request for Proposal (RFP) For Airfield Contracts 05-25-2005
UFC 3-260-16 FA	FA Airfield Pavement Condition Survey Procedures Pavements 01-16-2004
UFC 3-260-17	Dust Control for Roads, Airfields and Adjacent Areas 01-16-2004
UFC 3-270-01	Asphalt Maintenance and Repair 03-15-2001
UFC 3-270-02	Asphalt Crack Repair 03-15-2001
UFC 3-270-03	Concrete Crack and Partial-Depth Spall Repair 03-15-2001
UFC 3-270-04	Concrete Repair 03-15-2001
UFC 3-270-05	Paver Concrete Surfaced Airfields Pavement Condition Index (PCI) 03-15-2001
UFC 3-270-06	Paver Asphalt Surfaced Airfields Pavement Condition Index (PCI) 03-15-2001
UFC 3-270-07 O&M	O&M: Airfield Damage Repair 08-12-2002
UFC 3-270-08	Pavement Maintenance Management 01-16-2004
UFC 3-280-01A	Guidance for Ground Water/Fuel Extraction and Ground Water Injection Systems 01-16-2004
UFC 3-280-04	Army Filtration of Liquids 12-17-2003
UFC 3-301-01	Structural Engineering, with Change 1 06-01-2013
UFC 3-310-04	Seismic Design for Buildings 06-01-2013
UFC 3-310-08	Non-Expeditionary Bridge Inspection, Maintenance and Repair, with Change 1 08-16-2010

UFC 3-320-06A	Concrete Floor Slabs on Grade Subjected to Heavy Loads 03-01-2005
UFC 3-340-01	Design and Analysis of Hardened Structures to Conventional Weapons Effects (FOUO) 06-30-2002
UFC 3-340-02	Structures to Resist the Effects of Accidental Explosions, with Change 2 12-05-2008
UFC 3-400-02	Design: Engineering Weather Data 02-28-2003
UFC 3-401-01	Mechanical Engineering 07-01-2013
UFC 3-410-01	Heating, Ventilating, and Air Conditioning Systems, with Change 1 07-01-2013
UFC 3-410-02	Lonworks (R) Direct Digital Control for HVAC and Other Local Building Systems, with Change 1 05-01-2012
UFC 3-410-04N	Industrial Ventilation 10-25-2004
UFC 3-420-01	Plumbing Systems, with Change 9 10-25-2004
UFC 3-420-02FA	Compressed Air, with Change 1 05-15-2003
UFC 3-430-01FA	Heating and Cooling Distribution Systems 07-25-2003
UFC 3-430-02FA	Central Steam Boiler Plants, with Change 1 05-15-2003
UFC 3-430-07	Operations and Maintenance: Inspection and Certification of Boilers and Unfired Pressure Vessels, with Change 4 07-24-2003
UFC 3-430-08N	Central Heating Plants 01-16-2004
UFC 3-430-09	Exterior Mechanical Utility Distribution, with Change 1 01-16-2004
UFC 3-430-11	Boiler Control Systems 02-14-2001
UFC 3-440-01	Facility-Scale Renewable Energy Systems 07-01-2015

UFC 3-440-05N	Tropical Engineering, with Changes 1-2 01-16-2004
UFC 3-450-01	Noise and Vibration Control 05-15-2003
UFC 3-470-01	Lonworks (R) Utility Monitoring and Control System (UMCS) 05-01-2012
UFC 3-460-01	Design: Petroleum Fuel Facilities, with Change 2 08-16-2010
UFC 3-460-03	O&M: Maintenance of Petroleum Systems 01-21-2003
UFC 3-501-01	Electrical Engineering, with Change 3 02-03-2010
UFC 3-510-01	Foreign Voltages and Frequencies Guide, with Change 2 03-01-2005
UFC 3-520-01	Interior Electrical Systems, with Change 3 02-03-2010
UFC 3-520-05	Stationary Battery Areas, with Change 1 05-01-2015
UFC 3-530-01	Interior and Exterior Lighting Systems and Controls 04-01-2015
UFC 3-535-01	Visual Air Navigation Facilities 11-17-2005
UFC 3-540-01	Engine-Driven Generator Systems for Backup Power Applications 08-01-2014
UFC 3-550-01	Exterior Electrical Power Distribution with Change 1 02-03-2010
UFC 3-555-01N	400 Hertz Medium Voltage Conversion/Distribution and Low Voltage Utilization Systems 01-16-2004
UFC 3-560-01	Electrical Safety, O&M, with Change 5 12-06-2006
UFC 3-570-02A	Cathodic Protection 03-01-2005
UFC 3-570-02N	Electrical Engineering Cathodic Protection 01-16-2004
UFC 3-570-06	O&M: Cathodic Protection Systems 01-31-2003

UFC 3-575-01	Lightning and Static Electricity Protection Systems 07-01-2012
UFC 3-580-01	Telecommunications Building Cabling Systems Planning and Design 06-22-2007
UFC 3-580-10	Navy and Marine Corps Intranet (NMCI) Standard Construction Practices, with Changes 1-3 07-14-2004
UFC 3-600-01	Fire Protection Engineering for Facilities, with Change 3 09-26-2006
UFC 3-601-02	Operations and Maintenance: Inspection, Testing, and Maintenance of Fire Protection Systems; 09-08-2010
UL 467	Grounding and Bonding Protection
UL 96A	Installation of Lightning Protection
UL 1449	Surge Protection for Lightning Protection
42 U.S.C. 6901	Resource Conservation and Recovery Act (RCRA), Solid Waste Disposal Act (SWDA) of 1976, as amended, including Subtitle D
(Local publication #)	(Local publication title)
DNR EPD	Rules for Air Quality Control, Chapter 391-3-1
IPMP	USAG FS/HAAF Integrated Pest Management Plan
SPCC	FS/HAAF Spill Prevention Control and Countermeasures
HWMP	FS/HAAF Hazardous Waste Management Plan
SMS	FS/HAAF Sustainability Program Policy
9711-179-0018-V-03-1	FS Title V Permit with Amendments
9711-051-0149-V-03-0	HAAF Title V Permit
CG1790024	FS Main Water Permit

CG0510107	HAAF Main Water Permit
NG1790167	DMPRC Water Permit
NG1790117	Evans Army Airfield Water Permit
NG1790156	Red Cloud Alpha Water Permit
NG1790147	Holbrook Pond Campground Water Permit
NG1790137	Multipurpose Range Complex Water Permit
NG0190036	Camp Oliver Water Permit
NG1790116	Holbrook Area (Skeet Range) Water Permit
NG0510073	HAAF 702nd Radar #4A Water Permit
NG0510230	HAAF Horse Stables #5 Water Permit
NG0510231	HAAF Lott's Island Well #7 Water Permit
NG0510232	HAAF Recreation Area #3 Water Permit
PG0290061	TAC-X Water Permit
089-0003	FS Groundwater Withdrawal Permit
089-0011	FS Groundwater Withdrawal Permit
025-0034	HAAF Groundwater Withdrawal Permit
025-0061	HAAF Groundwater Withdrawal Permit
A11-025-0017	HAAF Permit for Farm Use of Ground and/or Surface Water (Golf Course) Withdrawal Permit
GAR050000	NPDES Storm Water Discharges Associated with Industrial Activity

GA0004308	NPDES Permit for FS IWTP
GA0027588	NPDES HAAF STP
PBR-089-37COL	Notification of Permit by Rule Operation (Solid Waste Handling Permit)
PBR-089-15IL	FS Yard Waste Inert Landfill Permit
GAG480000	NPDES Storm Water Discharges Associated with Small Municipal Separate Storm Sewer Systems at Military Facilities
GAJ030025	Evans Army Airfield LAS Permit
GAJ030624	Camp Oliver LAS Permit
GAJ030332	TAC-X LAS Permit
GAJ030834	Wright Army Airfield LAS Permit
089-020D(L)	FS Main Cantonment Area Landfill Permit
089-010D(L)	FS Sanitary Landfill Permit

7.2.1 Forms. Mandatory records and report forms are listed below.

DA Form 5-34	Repairs and Utilities Operating Log
DD Form 200	Financial Liability Investigation of Property Loss (FLIPL).
DD Form 254	Department of Defense Contract Security Classification Specification
DD Form 577	Appointment/Termination Record
DA Form 958	(paragraph 5.1.2.17; g.)
DD Form 1070	Termite and Wood Decay Inspection
FB Form 1347	(paragraph 5.9.2.1; e.)
DD Form 1348-1	Release/Receipt Document
FB Form 1454V2	Change Form (paragraph 5.1.2.24; f.)
DD Form 1532	Pest Management Control
DD Form 1532-1	Pest Management Maintenance Record
DA Form 2702	Bill of Materials

DA Form 3161	Request for Issue or Turn-In
DA Form 4141	Facilities Engineering Operating Log
DA Form 4178	Facilities Engineering Operating Log (Sewage Supplementary)
DA Form 4247	Facilities Engineering Operating Log (Sewage General)
DA Form 4283	Facilities Engineering Work Request
DA Form 4284	Facilities Engineering Work Order (if work is accomplished in-house)
DA Form 7485-R	Elevator Inspection Checklist

7.3 Technical Exhibit (TE). The Contractor shall update all the technical exhibit documents for all Functional Areas. Documents in which an update is required, shall be provided to the COR/ACOR monthly for review and approval. Approved updated Technical Exhibits will be modified into the current contract by the KO. Reference the TE Index for a list of all TEs in this Contract.

Technical Exhibit 1, 1A, 1B - Area Maps.

Technical Exhibit 2, 2A, 2B, 2C - Estimated Workload Data.

Technical Exhibit 3 - Common GFEBS Codes.

Technical Exhibit 4 - Special Services/Events.

Technical Exhibit 5 – Sample PWO Format

7.4 Government-Furnished Material (GFM)/Property (GFP)/ Equipment (GFE). The Government will furnish, or make available to the Contractor, the property, equipment, and facilities described in TE's A 03 (facilities) and TE A 04 (property and equipment). Once the tools and equipment are deemed unserviceable the government will not replace them and the contractor will need to provide those items. Government- owned computers will be provided for Contractor personnel required to work on Government information systems such as GFEBS. However, the Contractor shall submit to the COR within thirty (30) days after contract award a detailed Utilization of Government-furnished Facilities Plan, which details the manner in which the facilities will be utilized to meet the Contractor's need for on-site facilities. The plan shall also address contingencies should the space become unavailable. The Contractor shall assume responsibility for and accountability of the facilities and take adequate precautions to prevent fire hazards, odors, chemical spills and vermin. At the completion of the contract, all facilities shall be returned to the Government in the same condition as received, except for reasonable wear and tear. The Contractor shall be held responsible for the cost of any repairs caused by negligence or abuse. The Contractor shall

maintain such spaces to the same standards as similar areas occupied by the Government and use such space only in connection with performance under this contract. The Contractor shall not make any alterations to the space except with written permission of the COR/ACOR. Any approved Contractor requested alterations shall be made at no additional cost to the Government. The Contractor shall be responsible for all Government furnished non-expendable property IAW with AR 710-2 and DA Pam 710-2-1 and shall always maintain work areas in a professional manner.

7.4.1 Initial Inventory.

An initial inventory of Government furnished property shall be made jointly by the Contractor and the COR IAW DA PAM 710-2-1, *Using Unit Supply System: Manual Procedures*, on or before the contract start date. The operational or condition status shall be jointly determined. Any item found to be not in working order, or not suitable for its intended purpose, will be recorded and the COR/ACOR and the Contractor shall certify as accurate the joint inventory. All inventory listings will utilize DA Form 2062, *Hand Receipt/Annex Number*, to record inventory data. The Contractor shall keep current the inventory listing. The Contractor shall prepare applicable DA Form 3161, *Request for Issue or Turn-In*, for adjustments to the account IAW DA PAM 710-2-1. Authorized adjustments will be made on DA Form 2062 by the COR/ACOR. The Contractor shall be accountable to the COR/ACOR for equipment and supplies received for use during the contract. The Government will maintain the Property Book.

7.4.2 Utilities.

The Government will furnish electricity, water, sewer, natural gas, liquid propane gas, heating and cooling, and other utility services currently available in the Government furnished facilities. The Contractor shall obtain written approval from DPW prior to installing connections and meters. The Contractor shall instruct employees in utilities conservation practices. The Contractor shall be responsible for operating under conditions that preclude the waste of utilities, which include turning off the water faucets or valves after using the required amount to accomplish cleaning vehicles and equipment.

7.5 Contractor-Furnished Material (CFM)/Property (CFP)/Equipment (CFE). All Contractor furnished, material, property and equipment shall meet applicable Federal, State, Local, DoD and Army Laws, Codes, and Regulations.

7.5.1 Contractor-Furnished Material and Responsibilities. The Contractor shall furnish all supplies, equipment, and services required to perform work under this contract.

7.5.2 Contractor-Furnished Items. The Contractor shall provide all, vehicles, equipment, parts, tools, fuel, oil, materials, and any other items required to perform all Contract requirements. The Contractor's property shall be operational as intended by the manufacturer, and be safe, clean, and suitable for use at a Military Installation. All Contractor furnished property and

equipment are subject to KO inspection at all times.

7.5.2.1 Identification of Contractor Vehicles and Trailers. The company name shall be displayed on each of the Contractor's vehicles and trailers in a manner and size that is clearly visible. All vehicles and trailers shall display a valid State license plate and meet current local and State vehicle registration requirements.

7.5.2.2 The Contractor's equipment and other slow-moving equipment shall be equipped with the slow-moving vehicle sign.

7.5.3 Damage Caused by Contractor. Damages caused by Contractor employees shall be repaired at no cost to the Government. In all instances where Contractor's employees damage Government property or equipment, the Contractor shall provide a verbal report to the KO within two (2) hours of occurrence. The Contractor shall notify the COR/ACOR and return the damaged area to its previous condition. All damage done by the Contractor and/or his sub-contractor/s shall become the Contractor's responsibility. The Contractor shall furnish all labor, materials and equipment to perform the repair work including cultivating and applying seed, sprigging, or placing sod. All turf repair work shall be maintained to ensure successful growth.

7.5.4 Third Party Repair Damaged Areas. In the event the Contractor discovers damages caused by another party, the Contractor shall notify the KO and COR/ACOR of the extent of the damage and proposed corrective action. The Contractor shall make no repairs until authorized by the KO.

7.5.5 Equipment Replacement (Government Property). If an item of Government property is determined by the Contractor to be beyond economical repair, the Contractor shall recommend to the KO and COR/ACOR, in writing, that such equipment be replaced. Substantiating data to support the recommended replacement shall be included. If the Government decides that such equipment should be replaced or repaired, and replacement or repair is authorized, the Contractor shall accomplish the work IAW the appropriate work level criteria. Disposal instructions will be provided by the KO/COR/ACOR.

7.6 U.S. Department of Labor (DOL) Wage Determination (WD). The Contractor shall refer to <https://www.wdol.gov/dba.aspx> for U.S. Department of Labor Wage Determinations (DOL WD).