

CUI

**PERFORMANCE WORK STATEMENT (PWS) FOR THE
J85-5 Maintenance, Repair and Overhaul (MRO)**AFLCMC/LPSCA
TINKER AIR FORCE BASE (AFB), OK

Distribution Statement D: Distribution is authorized to the Department of War and U.S. DoW Contractors only. Administrative/Operational Use. Other requests for this document shall be referred to AFLCMC/LPK, Building 3001, Staff Drive Tinker AFB, OK

Warning: This document contains technical data whose export is restricted by the Arms Export Control Act (Title 22, U.S.C., Sec 2751, et seq.) or the Export Administration Act of 1979, as amended, Title 50, U.S.C., App. 2401 et seq. Violations of these export laws are subject to severe criminal penalties. Disseminate in accordance with provisions of DoW Directive 5230.25.

Destruction: When no longer needed, CUI material may be disposed of by any method which will preclude its disclosure to unauthorized individuals.

Controlled by:	AFLCMC/LPSCA
CUI Category:	Controlled Technical Information
Distribution/dissemination Control:	FEDCON
POC:	Asja Anderson

Summary of Changes

Date	Page	Changes	Version Number
March 2026	Entire Document	Initial Copy	01

Table of Contents

List of Tables	4
Section I – Description of Services/General Information.....	5
1. Executive Summary	5
1.1. Repair Workload Scope	6
1.2. Transition Plan: Transition to Contractor’s Facility	5
1.3. Transition Phase-Out Support.....	7
1.4. Repair Qualification.....	7
1.5. Records and System Maintenance	14
1.6. Miscellaneous Workload	14
1.7. Deficiency Reporting.....	16
1.8. Program Management/Supply Chain Requirements.....	16
1.9. Foreign Object Damage (FOD) Prevention Program	23
1.10. Contractor Induced Damage	23
1.11. Package/Handling/Shipping/Transportation	23
1.12. Government Programs/Databases/Systems/Websites.....	26
1.13. Mission Essential Services.....	29
1.14. Item Unique Identification (IUID).....	29
Section II – Service Summary.....	29
2. Service Summary Requirements.....	29
2.1. Performance Objectives and Thresholds	29
2.2. Performance Surveillance.....	29
2.3. Contractor Performance Evaluation.....	30
Section III – Government Furnished Property (GFP) and Services	31
3. Government Furnished Property.....	31
3.1. General Stewardship and Accountability.....	31
3.2. Comprehensive Inventory Management System	31
3.3. Inventory Reporting and Audits	32
3.4. Loss, Damage, Destruction (LDD) Reporting	32
3.5. GFE Tooling and Parts	32
Section IV – Acronyms and Definitions	34

LIST OF TABLES

Table 1: Respective Engine Configuration and Customer

Table 2: Engine Maintenance Schedule

Table 3: Forecasted Annual Maximum Quantities

Table 4: Meetings and Frequencies

Table 5: Example Contractual MTBR Calculation

Table 6: Contractor System Access Requirements

Table 7: Service Summary (SS) Elements

SECTION I – DESCRIPTION OF SERVICES / GENERAL INFORMATION**1. Executive Summary**

The mission of the J85-5 MRO Operations Jet provides serviceable J85-5 engines to support Air Education and Training Command's (AETC's) Undergraduate Pilot Training (UPT), Specialized Undergraduate Pilot Training (SUPT), Euro NATO Joint Jet Pilot Training (ENJJPT), Pilot Instructor Training (PIT), and Introduction to Fighter Fundamentals (IFF) missions. The Air Force System Program Office (SPO) for the J85-5 engine is in the Propulsion Sustainment Division, Air Force Life Cycle Management Center (AFLCMC) at Tinker AFB, OK.

The MRO currently located at Standard Aero, San Antonio TX, accomplishes repairs on J85 engines for the following operational wings: 12 Flying Training Wing (FTW), Randolph AFB, TX, 47 FTW, Laughlin AFB (LAFB), TX, 71 FTW, Vance AFB, OK, and 80 FTW, Sheppard AFB, TX, 14 FTW, Columbus AFB, MS. The MRO also accomplishes repair on a minimal number of National Aeronautics and Space Administration (NASA) J85-5M Compressor Rotors and, on occasion, supports Air Force Materiel Command (AFMC) J85 engine repair.

Table 1 Respective Engine Configuration and Customer

Engine	User		
	USAF	USN	NASA
J85-5 R	*		
J85-5 S	*	*	
J85-5 M	*		*

1.1. Repair Workload Scope**1.1.1.Target Serviceable Requirement (TSR)**

This PWS provides the technical, logistics management, and repair requirements to ensure an adequate supply of serviceable spare J85-5 engines, measured as the TSR metric, are available to support the missions of field units.

1.1.2.Scope of J85-5 Repair

The contractor shall satisfy engine workload provided by the government, which will consist of an established minimum and maximum for the contract under an Indefinite Delivery Indefinite Quantity (IDIQ) structure. The contractor shall repair IAW Attachment X technical data for engines scheduled for Periodic Inspections (PE) at 1800 hours, Hourly Post Flight Inspections (HPO) at 900 hours, 1T-38C-63 [Special inspections after a specific occurrence and Low Cycle Fatigue (LCF)/Time Change Item (TCI)]/ 2J-J85-6WC-1, Time Compliance Technical Order (TCTO) requirements and unscheduled engine removals shipped for induction and repair.

1.1.3.Contract Operations

The contractor shall be responsible for requisitioning/receipt of material via Commercial Asset Visibility-Air Force (CAV-AF) and FedMALL.

1.2. Transition Plan: Transition to Contractor's Facility

The contractor shall develop and implement a transition plan to relocate J85-5 engine repair operations from Standard Aero to the contractor's facility. This plan must establish full production capability (FOC) at the contractor's facility. A revised transition plan shall be provided to the PCO/ACO NLT 30 working days after contract award IAW CDRL AXXX, outlining the detailed steps, timelines, and resource allocation for this transition. The contractor shall provide progress status IAW CDRL AXXX.

The USAF will provide the following support to the contractor in determining Technical Order (TO) requirements:

- a) **Provide Access to Technical Orders:** The USAF will grant the contractor access to the latest versions of applicable J85-5 TOs within 5 (five) working days of contract award. Access will be provided via Enhanced Technical Information Management System (ETIMS)
- b) **Assign a Technical Point of Contact (POC):** The USAF will designate a Technical POC with expertise in J85-5 tooling requirements. The POCs's contact information will be provided upon contract award. The POC will be available for consultation via telephone or email.
- c) **Provide GFE Inventory List:** The USAF will provide the contractor with a current list of all Government Furnished Equipment (GFE) tooling, including NSNs, quantities, and condition codes, within 30 working days of contract award
- d) **Facilitate On-Site Visit:** The USAF will facilitate on-site visits to the current Standard Aero facility as required (with the outgoing contractor's consent) within 15 working days of contract award to allow the incoming contractor to observe existing tooling configurations.

1.2.1. Transition Plan

The transition plan shall address the following elements:

- a) **Workforce:**
 - a. Hiring Plan to include number of personnel, required skill set, training programs, anticipated start dates and compensation ranges.
 - b. Retention Plan should contain strategies to support employees in their work such as competitive compensation, professional development opportunities, positive work environment and measurable strategies
- b) **Data Transfer:**
 - a. Detailed inventory, data migration strategy, access control and a timeline
- c) **System Access:**
 - a. Identification of systems (the systems requiring access are identified in PWS Table 6), point of contact within 10 (ten) business days of contract award, account request procedures, training plan, and troubleshooting
- d) **GFE Usage Plan**
 - a. Inventory of GFE, usage plan, maintenance plan and storage plan
- e) **GFE Movement, Setup, and Calibration:**
 - a. Transportation Plan to include packaging and crating, shipping arrangements and insurance
 - b. Setup plan to include site preparation, installation and testing
 - c. Calibration Plan to include calibration standards, calibration schedule and documentation
 - d. Government coordination on all aspects of GFE movement, setup and calibration
- f) **Additional Equipment/Tooling:**
 - a. Needs assessment
 - b. Procurement plan to include vendor selection, purchase orders, and delivery schedules
 - c. Installation and setup
- g) **J85-5 Test Cell Capability:**
 - a. Test cell design and construction/modification
 - b. Test cell validation and certification to include testing procedures, documentation and Cognizant Engineering Authority (CEA) Approval
 - c. Operational procedures
- h) **Facility Layout, Workflow, Location, and Methodology:**
 - a. Facility layout
 - b. Workflow
 - c. Methodology to include maintenance procedures, quality control procedures, and safety procedures
- i) **Milestone Based Schedule (IOC/FOC):**

- a. Detailed Gantt Chart, key milestones, weekly status updates
- j) **Risk Management:**
 - a. Risk identification to include GFE delays, workforce shortages, test cell clarification delays, data transfer issues and supply chain disruptions
 - b. Risk assessment
 - c. Mitigation plan
 - d. Contingency plan

IOC is defined as the first two (2) PE engines successfully tested and produced IAW CDRL AXXX. IOC engines shall be tested at the Contractor's test cell facility. The Government reserves the right to treat the first 2 PE engines as First Articles and may conduct a validation/verification on all processes used to produce an engine. FOC is defined as attaining full production rate of up to 32 engines per month one month after full production is met IAW CDRL AXXX. Updated schedule once a week during production meeting until FOC is reached.

1.2.2.GFE Inventory

The contractor shall relocate GFE tooling and parts upon moving operation to contractor facility. An inventory will be conducted IAW PWS Section 3.

1.2.2.1. Required Inventory

Contractor shall conduct an inventory, with an AF representative, and shall sign a document accepting accountability for the list of items reflecting National Stock Numbers (NSNs) and the quantity of the inventory, which will be taken with the Maintenance Operations during relocation to contractor's facility.

1.2.2.2. Accountability

Contractor shall maintain the relocated NSNs as Government Furnished Equipment (GFE) for the life of the contract and shall ensure the same items and equal quantities/condition taken are returned to the Government at the end of the contract.

1.2.2.3. Inventory Management

Contractor shall ensure GFM shelf-life items are used within the shelf life and shall ensure any GFM NSNs that are superseded or replaced during the life of the contract are replaced with current NSNs.

1.3. Transition Phase-Out Support

The contractor shall develop, maintain, and execute a comprehensive Transition-Out Plan to ensure the orderly and efficient transfer of all J85-5 engine repair responsibilities to a successor contractor or to the Government at the end of the contractor. This plan shall detail the procedures for the orderly transfer of all program management responsibilities, operational knowledge, data, and Government property. A preliminary plan shall be delivered as specified in CDRL AXXX. The Contractor shall provide an updated and finalized plan to the PCO no later than 180 days prior to the end of the final contract period.

1.3.1.GFE Inventory

As a key component of the Transition-Out Plan, the Contractor shall support the joint final inventory and disposition of all Government Furnished Property, including GFE tooling and parts. The contractor shall relinquish possession of all Government property upon direction from the PCO at the end of the contract. The final inventory shall be conducted in accordance with PWS Section 3 and the procedures detailed in the approved Transition-Out Plan.

1.4. Repair Qualification

The contractor shall ensure all repairs are provided by Government qualified sources IAW the Source

Approval Request (SAR) process. The contractor shall ensure all repairs, and sub-vendor repairs of critical processes, are IAW the CEA engineering source approval documentation, J85-5 Repair Qualification Requirement (RQR). The contractor shall provide and maintain qualified personnel necessary to meet contractual requirements. A listing of Critical Safety Items (CSI) is provided at Attachment X to this PWS. Any list changes will be ratified via contract modification.

1.4.1.Repair Workload

1.4.1.1. Process Tracking

The contractor shall track engine maintenance in the following systems: Comprehensive Engine Management System (CEMS) IAW TO 00-25-254-1, 00- 20-5-1-10 and Global Integrated Maintenance Management Services (GIMMS). USN engines will instead use DECKPLATE IAW CDRL AXXX.

1.4.2.Induction

1.4.2.1. Timeline

Engines shall be received by the contractor engine manager into CEMS within one (1) working day upon receipt of funded order and asset at the contractor facility. The contractor shall conduct preliminary induction inspection of engine and shipping device NLT five (5) working days after receipt of the engine to identify such issues as damage attributed to mishandling during transportation, obvious missing parts, improper packaging, etc., and report to Government IAW CDRL AXXX. Upon completion of this inspection, the engine shall then be inducted into maintenance. The contractor may request, via email to the PCO, a waiver of this induction requirement. Examples of valid reasons for a waiver include, but are not limited to, a large quantity of engines that arrive within five workdays at the contractor's facility, a government-driven work stop due to a quality escape, etc. Once inducted, the contractor shall report induction date via production report (add CDRL AXXX) then has 35 working days to repair/overhaul the engine and return it to serviceable status ready for shipment. The contractor shall produce no greater than 5% of end items exceeding induction timeline. The J85-5 Program Office may direct specific engines to be prioritized in the induction schedule.

1.4.2.2. Level of Maintenance Determination

Upon induction, the contractor shall determine degree of maintenance required to return unscheduled engine removals (UERs) to serviceable conditions. Upon request by the J85-5 SPO, contractor shall provide documentation and teardown results for engineering review IAW CDRL AXXX, within five (5) working days. Upon completion of any J85-5 jet engine disassembly, the contractor shall ensure the components/parts of the engine are serviceable. All inspection results, serviceability determinations, and related reports shall be recorded in a shared electronic data system accessible to Government personnel, including the DCMA.

Table 2 Engine Maintenance Schedule

PE	Periodic Inspection	1800 hour minimum build limit until next PE	1800 hour overhaul cycle
HPO	Hourly Post Flight Inspection	900 hour minimum build limit until next PE	900 hour overhaul from last PE
HPO+	Hourly Post Flight +	N/A	In addition to normal HPO requirements, compressor rotor replacement if insufficient life remains until next PE
UER	Unscheduled Engine Removal	N/A	Major UER involved indexing engine (2J-J85-116-33, WP 004 00, Para 27)

1.4.3.Maintenance Procedures

1.4.3.1. Repair Data

Maintenance shall be conducted in accordance with the 2J-J85-116 Depot Series and 2J-J85-54 Illustrated Parts Breakdown Technical Orders (TOs) as the highest referenced TOs. The 2J-1-32 Standard Maintenance Practices Manual and all referenced or sub-referenced technical data in the 2J-J85-116 Depot Series and 2J-J85-54 TOs shall also be followed when not already explicitly defined in any other higher referenced TO.

1.4.3.2. Maintenance Practices

The engine shall be in a serviceable state after repair. Any exposed part shall be inspected in accordance with the above repair data. During disassembly, all parts and assemblies must be examined for serviceability in accordance with their applicable work package and inspection table in the 2J-J85-116 Depot Series TOs. Completed engines coming out of repair shall meet the minimum build time requirements defined above. A waiver from the J85 SPO may be requested on build time hour requirements.

1.4.3.3. Turn-Around-Time (TAT)

After induction, the contractor shall deliver serviceable engines within a maximum of 35 working days, ensuring a minimum of 95% compliance quarterly. Exceptions to this may be granted from the PCO/ACO due to government-induced constraints, such as (but not limited to) engines in awaiting parts (AWP) status, a government-driven work stop due to a quality escape, etc. The contractor shall adhere to the 35-working day TAT to make an engine serviceable and Ready For Installation (RFI) as reflected in TO 2-1-18 and IAW Performance Summary SS-2. The contractor shall produce no greater than 5% of end items exceeding TAT. TAT metric will not be measured until FOC has been achieved.

1.4.3.4. Time Compliance Technical Order (TCTO) Incorporation

The contractor shall ensure all engines inducted for maintenance, incorporate all applicable TCTOs in their overhaul processes and report IAW CDRL AXXX. The contractor shall not implement new TCTOs that have a cost impact without PCO/ACO approval. TCTO compliance shall be recorded in CEMS IAW 00-25-254-1. Any deviations or issues related to TCTO implementation must be reported to the PCO/ACO within 3 working days.

Safety TCTOs will be accomplished on all engines unless waived by CEA. If not accomplished, notification will be sent to MAJCOM and SRAN Engine Managers

1.4.3.5. Navy Workload

The contractor shall perform MRO under separate CLIN for Navy J85-5 engines. The contractor shall document maintenance IAW CDRLs AXXX and AXXX in the Navy's reporting system, Decision Knowledge Programming for Logistics Analysis and Technical Evaluation (DECKPLATE), located at <http://www.navair.navy.mil/logistics/deckplate> for engines assigned to Patuxent River, NAS. Life limited components on Navy engines will be strictly segregated from non-Navy assets.

1.4.3.6. Material Review Board (MRB)

1.4.3.6.1. Purpose

To define the scope, responsibilities, and procedures of the Material review Board (MRB) in evaluating, dispositioning, and documenting discrepancies found during J85 engine maintenance, repair and overhaul (MRO).

1.4.3.6.2. Scope

This work scope applies to all J85-5 engine modules undergoing MRO activities at the facility. It includes inspection findings, non-conformances, and component/material dispositions related to airworthiness, cost-effectiveness, and compliance with USAF approved repairs/processes.

1.4.3.6.3. MRB Team Composition

- a) MRB Chairperson (USAF Cognizant Engineering)
- b) Contractor assigned engineer

1.4.3.6.4. Responsibilities

- a) Review discrepancies and non-conformances found during engine teardown, inspection, or testing
- b) Determine disposition: Acceptable as Is, Repair, or Scrap
 - a. If dispositioned for repair, USAF cognizant engineering will determine whether or not the part requires validation of successful repair.
- c) The contractor shall ensure compliance with customer-approved work scope or guidelines
- d) Provide cost-justified recommendations
- e) Document finding and MRB decisions in the engine maintenance records

1.4.3.6.5. MRB Process Steps

- a) Discrepancy Identification
 - a. Non-conforming parts shall be evaluated that violate TO limits found during teardown or inspection
 - i. Detailed pictures of discrepancies where defect location is discernable
 - ii. Discrepancy dimensions to be included in submission
- b) Technical Evaluation
 - a. Engineering to evaluate the discrepancy
- c) Disposition Determination
 - a. MRB convenes to assign one of the following
 - i. Use as is – Discrepancy will be documented to assist future decision-making upon next inspection
 - ii. Repair – Rework or USAF cognizant engineering direction
 - iii. Reinspect
 - iv. Scrap – Part cannot be reused or repaired
 - v. HFFR (Hold for Future Repair)

1.4.3.6.6. Cost threshold

Parts over \$10,000 must be a part of a material review board and signed off by the CEA before condemned.

1.4.3.6.7. Documentation

- a) MRB findings recorded on:
 - i. MRB Disposition Log
 - ii. Engine Assembly Record
 - iii. Part Tags (Red/Yellow/Green)
- b) Updates made to the final engine work scope and billing package
- c) Document discrepancies
- d) The contractor shall use the Government-designated electronic system for al

- submission, tracking, and disposition of MRB activities
- e) Upload to MRB system within 15 working days
- f) The government will provide a formal response (approval, rejection, or request for additional information) within ten (10) business days of receipt of a complete submission package

1.4.3.6.8. Customer Notification

Significant or high-cost decisions (>predefined threshold) are communicated to the customer for approval before final disposition

1.4.3.6.9. Deliverables

- a) Signed MRB disposition log
- b) Updated work package and traceability documentation
- c) Digital images, engineering analysis, or OEM correspondence for major items

1.4.3.7. Component Repair Requirements

The contractor shall repair all components IAW 2J-J85-116 Depot Series technical orders. If the contractor determines a repair is out of technical order scope or would negatively impact reliability, a waiver request may be submitted IAW CDRL AXXX to the PCO and CEA for review / disposition.

1.4.3.7.1. Air Force Managed Parts

The contractor shall, IAW established maintenance and repair procedures, process and send all Air Force managed parts determined to be Not Repairable This Station (NRTS) to the following address:

SRAN SW3211 – Mark For: Account 09
DLA Distribution Depot Oklahoma
3301 F. Ave. CEN REC (Bldg # 506 – DR# 22)
Tinker AFB, OK 73145-8000

At Air Force direction, some parts may be disposed of in place IAW DoDM 4160.28-M Vol 3, AFMAN 23-122, and AFI 23-101 and CDRL AXXX.

1.4.3.7.2. Defense Logistics Agency (DLA) Managed Parts

The contractor shall dispose of unserviceable DLA managed parts IAW DoDM 4160.28-M Vol 3, AFMAN 23-122, and AFI 23-101. A MILSTRIP fund cite will be provided after award for ordering of DLA managed parts.

1.4.3.7.3. Beyond Economical Repair (BER) Material

The contractor shall adhere to the definition that “Economically Repairable End Items” are end items which can be restored to as serviceable condition, IAW applicable requirements, when the cumulative (labor and material) cost of repair will not exceed 75% of the Government’s current replacements cost. If the contractor estimates the repair of any end item will exceed this 75% limit, the Contractor shall cease work on the item and promptly notify the PCO/ACO in writing. The contractor shall not perform further services or dispose of any Government property until receiving written direction from the PCO/ACO. These disposition instructions will be based on whether the asset is managed by the Air Force Sustainment Center (AFSC) or Defense Logistics Agency (DLA). The PCO reserves the right to authorize the Contractor, through the ACO, to exceed the 75% economical repair limit when an item is identified as being critical supply status or when otherwise determined to be in the best interest of the Government.

1.4.3.8. Engine Test

The contractor shall test the engine IAW TO 2J-J85-111-1 to determine engine serviceability. The contractor shall deliver repaired engines in tested, serviceable and RFI (Ready for Install) condition. Upon completion of final test, after Contractor final inspection, then Contractor shall contact the DCMA Quality representative to complete final inspection / acceptance procedures while the engine is on the maintenance stand. The contractor shall provide engines without quality workmanship deficiencies.

1.4.3.8.1. 1.4.4.8.1. JOAP Baselineing

Three (3) full engine runs shall be performed and documented in engine records to develop a JOAP baseline, defined in TO 2J-J85-111-1 to establish a trend before selling engines.

1.4.4.Deviation Requests

The Contractor shall submit an Engineering Technical Assistance Request (ETAR) to obtain Government approval for any proposed deviation from published technical data or to address technical problems not covered by existing technical orders. All ETARs shall be submitted via the Government-designated electronic system (e.g., SharePoint, DCMA eTools) for formal tracking and disposition by the Cognizant Engineering Authority (CEA), in accordance with CDRL AXXX and TO 00-25-107.

1.4.5.Forecasted Annual Workload

The contractor shall be prepared to provide MRO services for a workload up to the maximum annual quantities and maximum monthly induction rates detailed in Table 3. These quantities represent the Government's estimated ceiling and are not guaranteed orders. The Government is only obligated to order the minimum guarantee stated elsewhere in the contract. Actual induction quantities will be determined by operational requirements and funding and will not exceed the specified monthly or annual maximums without a contract modification.

To facilitate contractor planning, the Government will provide a rolling 90-day induction forecast, to be updated no later than the 15th of each month. This forecast is for planning purposes only and does not constitute a formal order. The formal induction schedule for any given month will be confirmed via the issuance of a delivery order.

1.4.5.1. Annual Workload Review

Prior to the start of each contract option year, commencing with the lead-in to Year 6, the Government will conduct a joint workload planning review with the contractor. The purpose of this review is to discuss forecasted requirements based on projected operational tempo, funding availability, and strategic planning. The outcome of this review will inform anticipated induction schedule for the forthcoming year.

Table 3 Forecasted Annual Maximum Quantities

Contract Year	Maximum Monthly Production Quantity	Total Maximum Annual Quantity
Year 1	24-32	384
Year 2	23-31	372
Year 3	23-31	372
Year 4	21-29	348
Year 5	21-29	348
Year 6 (Option)	To Be Determined*	To Be Determined*
Year 7 (Option)	To Be Determined*	To Be Determined*
Year 8 (Option)	To Be Determined*	To Be Determined*

Year 9 (Option)	To Be Determined*	To Be Determined*
Year 10 (Option)	To Be Determined*	To Be Determined*

*NOTE: Years 6 through 10 are Option Years. The Government may choose to exercise these options based on operational needs, funding availability, and contractor performance. Maximum quantities for any exercised option year will be established based on the Annual Workload Review described in section 1.4.5.1 and finalized via contract modification.

1.4.6. Miscellaneous Workload

1.4.6.1. NASA Compressor Blade Grinding

Contractor shall perform compressor blade grinding IAW TO 2J-J85-116-63 and per NASA's dimensional requests/requirements for Compressor Rotors sent from NASA each year during contract execution, and under separate Contract Line Item Number (CLIN).

1.4.6.2. FMS Workload

Contractor shall perform repair on the Foreign Military Sales (FMS) workload at a price negotiated at the time of requirement. FMS workload may include the J85-5, -13, -17, and -21 series engines, in addition to the J85-5-CAN-40.

1.4.6.3. Additional US Government Workload

Contractor shall perform repair on the J85-5 Air Combat Command (ACC), Air Force Materiel Command (AFMC), and NASA whole engine workloads at a price negotiated at the time of requirement.

1.4.7. Reliability Centered Maintenance

All activities, tools, and reports described in this section require J85-5 SPO approval. The contractor shall implement a Reliability Centered Maintenance (RCM) approach IAW CDRL AXXX to optimize J85-5 engine repair, maximizing engine reliability and minimizing lifecycle costs. This RCM approach will guide engine build decisions to achieve improved Estimated Time on Wing (ETOW).

The contractor may utilize USAF's RCM optimization tool (available at no cost) or a J85-5 SPO-approved contractor-owned RCM tool. Regardless of the tool used, the contractor shall provide a report generated for each engine, documenting the RCM analysis and resulting work scope, IAW CDRL AXXX.

1.4.7.1. RCM Tool Requirement

The RCM tool employed by the contractor (USAF-provided or contractor-owned) must possess the following capabilities:

1.4.7.1.1. Estimated Time on Wing (ETOW) Prediction

The RCM tool shall use statistical distributions representing the failure modes of J85-5 engine components to predict ETOW for a specific engine (by serial number) when a defined work scope (set of corrective actions) is applied. The tool shall provide a predicted ETOW value that meets or exceeds the ETOW goal set by the J85-5 SPO and approval at the MAJCOM level during the Maintenance Planning Working Group (MPWG)

1.4.7.1.2. Cost Optimization - Lowest Lifecycle Cost per Flight Hour (CPFH)

The RCM tool shall evaluate various work scopes that achieve the required ETOW goal and identify the work scope that results in the lowest long-term CPFH. The ETOW goal shall be adjustable within the tool to allow for trade-off analysis. Cost calculations must consider lifecycle costs, not just immediate expenses, to optimize long-term CPFH.

1.4.7.1.3. Shop Optimization - Maximize Total ETOW

The contractor shall utilize the RCM tool to simultaneously optimize the combination of serviceable modules and components across multiple engines under repair, maximizing the sum of the individual engine ETOW values. The contractor's performance in maximizing total ETOW across all engines will be measured quarterly.

1.4.7.1.4. Shop Optimization - Minimize CPFH across Multiple Engines

The RCM tool shall be capable of optimizing the allocation of components across multiple engines to minimize overall long-term CPFH. This includes evaluating the use of new, overhauled, and used components to achieve the lowest possible fleet-level CPFH.

1.4.7.1.5. Deviation from RCM Recommendations

The contractor shall consult with the J85-5 SPO prior to implementing any engine build configurations that deviate from the recommendations generated by the approved RCM tool. Formal approval from the J85-5 SPO is required for any such deviations.

1.5. Records and System Maintenance**1.5.1. Life Cycle Management of Documentation**

Contractor shall document and retain all maintenance/inspection/test work records generated during repair. The contractor shall convert all records to a searchable portable document format (PDF) or a spreadsheet format. Upon request of the PCO/ACO (whether at contract expiration or at any time during the contract period), the contractor shall provide maintenance records for engines within 3 business days. Upon expiration of the contract, the contractor shall send a records index and all records to the Government IAW CDRL AXXX. IAW FAR 4.703, the contractor shall retain any records generated for (3) three years after final payment is made on the contract. Additionally, for any Critical Safety Items (CSI) records generated, the contractor shall maintain records for (10) ten years after final payment.

1.5.2. Engine Management/CEMS

The contractor shall update CEMS within one (1) business day after receipt of engine and/or any time status of tracked engine changes. The contractor shall report and update all maintenance actions on engines and on repairs to serially tracked items in CEMS IAW CDRLs AXXX and AXXX and IAW TO 00-25-254-1 to include, but not limited to, TCTO compliance, life-limited parts and component service time and time since overhaul, for items repaired at the MRO Maintenance facility. The contractor shall submit a request for Stock Record Account Number IAW CDRL AXXX.

1.6. Miscellaneous Workload

The contractor shall respond to repair requirements and other workload not covered under other CLINs, utilizing a Fixed-Price Labor Wrap Rate.

1.6.1. Technical Assistance and Engineering Analysis

Contractor shall provide technical assistance/engineering production analysis and support services as mutually agreed upon by the contractor and the PCO/ACO. Services may include but not limited to support of, and facility access for, TO validation/verification by the Government CEA or an agent on their behalf, via hands-on demonstration, technical analysis to determine and accomplish necessary rework, replacement, or modification, and engineering assistance for workarounds and other production related activities.

1.6.2. Safety Investigation Board (SIB)

The contractor shall support the SIB or Single Investigating Officer (SIO) on mishap investigations in coordination with the CEA IAW DAFI 91-204. Contractor shall include reprioritizing engine induction schedules, impounding hardware (to include quarantine of whole engine and its parts, or quarantine of parts of an engine as directed by the SIO or CEA), coordinating workflow (disassembly, inspections, test, subcontracted O&A analyses, etc.), photographic support, damage assessment and cost determination. The contractor shall contact the Defense Contract Management Agency (DCMA) and J85-5 Program Office for direction prior to providing investigation support. These efforts relate to formal SIB investigations from the safety office and are separate from the 645 Base Safety Reporting process informing local Base Safety Offices of engine report requirements.

1.6.2.1. Safety Reporting

All engine rotating component failures must be reported to the owning base wing safety office where incident occurred by telephone within 3 hours of any significant event during normal duty hours or the beginning of the next day if after hours IAW DAFI 21-101. The contractor shall perform actions required on flameout or compressor stall jet engines IAW T.O. 2J-J85-111-1.

In addition to the above requirements, the contractor shall accomplish mishap and safety reporting with the respective Base Safety Office for those engines that arrive with safety reporting requirements. IAW DAFMAN 91-204 and applicable supplements, the contractor shall complete and submit an AF Form 978, Supervisor's Mishap Report, or its current equivalent, within the timelines specified by the local Base Safety Office, not to exceed 30 calendar days from receipt of the engine. For ongoing issues, reporting shall continue monthly until the engine is completed. Reports shall include, at a minimum, a detailed failure analysis, estimated cost of remedies, and parts required to restore the engine to a serviceable condition.

1.6.3. Teardown Reporting

The contractor shall provide teardown reports upon request to support and/or identify root cause analysis, primary failed item, failure mode and corrective action IAW CDRL AXXX. The Government may request these reports be provided for each UER teardown. The contractor shall send an email notification to the PCO/ACO, and Program Office of the associated UER Repair CLIN (minor or major) as a result of the teardown analysis within (5) five working days from the conclusion of the investigation

1.6.4. Analytical Condition Inspection (ACI)

The contractor shall participate in ACIs by performing extensive engine disassembly, performing hardware inspections which will include dimensional and visual inspections, for the purposes of engineering assessment as needed. Documentation shall include pictures of hardware and other pertinent information as requested by government personnel. Contractor shall not be held to the normal repair TAT of 35 working days for ACI / Investigation engine repairs.

1.6.5. OVER & ABOVE (O&A)

Contracts for the performance of the repair of various items generally contain over and above work requirements. Unknown repairs or other supporting actions for production may be added to the contract as an O&A CLIN. The definition of over and above work per DFARS 252.217-7028 is work discovered during performing overhaul, maintenance, and repair efforts that is:

- a) Within the general scope of the contract
- b) Not covered by the line item(s) for the basic work under the contract; and
- c) Necessary in order to satisfactorily complete the contract

The requirements are for J85-5 components that are outside of normal CLIN repairs and will be requested by the PCO or ACO and must be incorporated via task order.

1.7. Deficiency Reporting

1.7.1. Joint Deficiency Reporting System (JDRS)

The contractor shall investigate and report all Product Quality Deficiency Reports (PQDRs) through the JDRS IAW CDRL AXXX on materiel received to be used in the repair or maintenance of engines or components, and comply with disposition instructions on PQDR materiel

1.7.2. DR Process

Using JDRS, the contractor shall review reported engine discrepancies from the field and, in conjunction with J85-5 SPO engineering, schedule exhibits for investigation. For PQDRs, the contractor shall notify the DCMA Quality Assurance Representative (QAR) and DCMA Property Administrator (PA). Upon receipt of the exhibit, the applicable representative shall be present for a joint opening of the exhibit. The contractor shall schedule and investigate the discrepancy.

1.7.3. Engineering Investigations (EIs)

For all EIs, a statement of work will be provided through the PCO/ACO. The contractor shall schedule exhibit inductions after receipt of exhibit and funding authorization by the PCO/ACO. These efforts relate to Government Engineering requested efforts for investigation, ACIs, and other engineering related items and shall be worked under the Investigations CLIN.

1.7.4. Responses

Contractor shall provide interim and final EI responses IAW TO 00-35D-54. The contractor shall communicate projected Teardown Deficiency Report (TDR) completion dates to the J85-5 SPO. Contractor shall submit TDR with investigation findings to include root cause analysis, preventative actions, determination of responsibility, and a recommendation to preclude recurrence, as well as a corrective action against all PQDRs and EIs.

1.7.5. Deficiency Report Repair

The contractor shall repair deficiency report items as directed by the Government. The contractor shall repair deficiencies within 90 calendar days of disposition from the Government. The Contractor shall also provide the DCMA PA a copy of the repair deficiency report.

1.7.6. Metric

Contractor shall complete Not Less Than (NLT) 98% of investigations within the established timelines as follows: 15 calendar days from receipt of asset for Category I Mishap, 30 calendar days from receipt of asset for Category II Mishap, 20 calendar days from receipt of asset for Category I DR, and 30 calendar days from receipt of asset for Category II DR, as reflected in SS-5.

1.8. Program Management/Supply Chain Requirements

1.8.1. Program Management

The contractor shall exercise management and full operational control over all contractor personnel and retain full responsibility for performance requirements meeting mission requirements as set forth in this PWS.

Contractor employees shall identify themselves as contractor personnel by introducing themselves or being introduced as contractor personnel and displaying distinguishing badges or other visible identification for meetings with Government personnel. In addition, contractor personnel shall appropriately identify themselves as contractor employees in telephone conversations and in formal and informal written correspondence.

The contractor shall allow facility access to government personnel (or agents on their behalf) to common areas within the contractor facility. Furthermore, the contractor shall allow all government personnel access to contractor facility for the purpose of engine investigations, inspections, and validation/verification of repair processes.

1.8.1.1. Utilization of Government Facilities

For any operations performed at a government location, the contractor shall ensure that they comply with all Air Force regulations. Base Support Agreement will be provided to identify what services will be supported for any performance on government installation(s).

1.8.1.2. Emergency Procedures

For any performance on a Government installation, Contractor employees shall follow the direction of Government employees in regard to emergency procedures, i.e. fire, tornado, active shooter, bomb threats. It is the responsibility of the contractor to provide guidance and establish procedures for responding to an emergency for their employees. It is the contractors' responsibility to account for their employees following an emergency evacuation. Contractor Personnel shall participate with government personnel in all fire and tornado drills at no additional cost to the Government.

1.8.1.3. Holidays

For any performance on a government installation, federal Government holidays are observed in the United States.

1.8.1.4. Combating Trafficking in Persons

- a) The Contractor and its employees, including all subcontractor employees at any tier, shall comply with the requirements of FAR clause 52.222-50, Combating Trafficking in Persons, which is incorporated into this Performance Work Statement by reference.
- b) The Contractor shall not engage in severe forms of trafficking in persons, procure commercial sex acts, or use forced labor in the performance of this contract. The Contractor shall take appropriate steps to ensure that its employees and subcontractors are aware of these prohibitions and shall promptly report to the Contracting Officer any credible information it receives from any source that alleges a violation of these prohibitions.
- c) The Contractor shall notify its employees, including subcontractor employees at all tiers, of the U.S. Government's zero-tolerance policy regarding trafficking in persons and the actions that will be taken against employees for violations of this policy. The Contractor shall fully cooperate with any Government agencies responsible for investigating allegations of trafficking in persons.

1.8.2. Supply Chain and Logistics

The contractor shall obtain and maintain all supply chain services and materials necessary to support production and maintenance requirements, strictly adhering to all applicable Air Force regulations, policies, and procedures. This includes:

- a) Utilize Commercial Asset Visibility-Air Force (CAV-AF) and FedMall for all parts ordering, ensuring orders are processed, tracked, and closed out in accordance with official guidelines and regulatory guidelines.
- b) Collaborating with designated Air Force supply chain POCs for all supply-related actions, maintaining open and regular communication for operation transparency.
- c) Executing MICAP (Mission Impaired Capability Awaiting Parts) guidance and supply priority ordering procedures IAW AFI 23-101, DLM 4000.25 Volume 2, Chapter 4, and the CAV-AF User Guide. The Contractor shall stay current on updates to all referenced directives and incorporate new policies or procedures within ten (10) business days of official notification.

- d) Maintaining comprehensive auditable records of all parts orders, supply chain communications. These records shall be retained in accordance with Air Force data retention requirements and made available upon Government request for review or audit.
- e) Applying relevant security protocols for supply chain actions involving controlled, sensitive, or classified items. The Contractor shall consult with the USAF Security Officer to determine the appropriate application of additional controls when required.
- f) Remaining informed of and proactively responding to changes in Air Force regulation, policies, and technologies related to supply chain management, including the implementation of contingency procedures to address and mitigate potential supply chain disruptions.

1.8.2.1. Fuel Management

The Contractor shall use only fuels specified in applicable technical data during dynamic testing of uninstalled engines. Any deviations or concerns shall be addressed through the CEA. If performing engine testing at a government location, the contractor shall utilize fuel available on the base. The government shall have consideration for engine testing. The government shall negotiate a discount factor for any testing required at a government facility. Once engines are relocated to the contractor's facility, the contractor shall source Jet A-1 fuel, or a DoW-approved equivalent such as JP-8, which shall meet all applicable quality and performance specifications, for use in the maintenance and repair process.

1.8.2.2. Contractor Facility Operations Parts Management

The contractor shall manage both USAF and DLA managed parts inventories in their respective systems, ensuring segregation of tracked parts between service branches. The contractor shall establish and maintain a parts storage plan aligned to Air Force/DLA operational guidelines. The contractor shall report supply chain issues, systemic changes, or problems to the DCMA COR and PCO within 48 hours of identification. The contractor shall support the government in funding and budget reconciliation drills through provision of required data, participation in meetings, and reconciliation of discrepancies.

1.8.2.2.1. DLA Managed Items

The contractor shall establish a FedMALL account and profile per the current instructions provided at <https://www.fedmall.mil>. The contractor shall forecast and order required material through FedMALL to support J85-5 engine/component repair, and provide consumption reports IAW CDRL AXXX when requested by the J85-5 SPO.

1.8.2.2.2. Air Force Managed Items

The contractor shall order all Air Force managed materiel through Commercial Asset Visibility Air Force (CAV AF) IAW CDRL AXXX and Attachment X, to order replacement, accomplish receipts and turn-ins of AF managed items. Contractor shall perform CAVAF reporting on asset transactions within 72 hours of actual supply or maintenance occurrence IAW Attachment X. The Government will establish a Table of Allowance (ToA) for AF-managed items to support J85-5 whole-engine repair.

1.8.2.3. Parts Forecasting

- a) DLA System Access: To facilitate forecasting to DLA, the contractor shall obtain access for purposes of collaboration to DLA forecasting systems to input Demand Data Exchange (DDE) actions to provide demand planning requirements.
- b) Non-Standard Source: If the contractor utilizes parts from a Government approved source (i.e., cannibalized from another USAF serviceable J85-5 engine, consumable parts approved for use via waiver, Materiel Review Board (MRB) assets, etc.) other than DLA, for each

occurrence, the contractor shall submit a Demand History Adjustment (DHA) to DLA to document the usage/requirement for that part.

1.8.2.4. Supportability Risks

If a piece parts supportability risk/issue is identified, the contractor shall notify the USAF in writing within 24 hours of identification, providing a summary of the risk and recommended mitigation steps.

1.8.2.5. Component Turn-Around-Time

The Contractor shall comply with DIFM (Due-In for Maintenance) management and reporting procedures for applicable items specified in CAVAF guidelines, ensuring delivery dates are met as defined in the applicable task order.

1.8.3. Program and Status Reviews and Travel

The contractor shall participate in the meetings listed in Table 4 to ensure effective program management and communication. The contractor shall provide required documentation, as applicable, IAW CDRL AXXX. The contractor shall also conduct weekly production and constraints meetings to address production, technical, and parts constraints issues, including developing get-well plans. A bi-weekly report shall be submitted in accordance with CDRL AXXX. The contractor shall participate in additional meetings as directed by the PCO/ACO, briefing information requested by the Government.

All contractor travel directed by the Government will be reimbursed IAW FAR Part 31 and Joint Travel Regulations (JTR) in effect at the time of travel, along with DCAA-approved General and Administrative (G&A) rates. Travel will be separately priced and requires PCO approval prior to the trip. The Government will not pay any additional costs (overheads, sub-contractor costs/add-ons, bulks, fees, or profit) associated with travel.

Table 4 Meetings and Frequencies

Meeting	Frequency	Host	Attendees	Purpose
Production Meeting	Weekly	Contractor	J85 SPO, Contractor, DLA, OEM, Supply Chain	Track progress, resolve roadblocks, ensure on-time delivery
Constraints Meeting	Quarterly	Contractor	J85 SPO, Contractor, DLA, OEM, Supply Chain	Identify, analyze, and create a plan to overcome achievement of goal
Program Management Review	Twice a Year	Contractor	Je5 SPO, Contractor, Customers	Review project performance, identify risks, plan corrective actions
Maintenance Planning Working Group (MPWG)	Twice a Year	J85 SPO Maintenance Team	J85 SPO, Contractor, OEM, DLA, Customers	Coordinate maintenance schedules, address maintenance issues, improve reliability
Collaborative Forecasting (COFO)	Twice a Year	J85 SPO	J85 SPO, Contractor, OEM, DLA, OEM,	Develop accurate demand forecasts, optimize inventory

			Supply Chain	levels, reduce shortages
Post Award Conference	Once	J85 SPO	J85 SPO, Contractor, Customer	Kick off project, define roles and responsibilities, establish communication channels

1.8.4.Contract Data Requirements List (CDRL) Management

1.8.4.1. Data Delivery and Management

The contractor shall prepare and submit all data deliverables as specified in the CDRL, DD Form 1423, attached to this contract. All submissions shall be delivered to the government point of contact via the method designated in Block 16 of the respective CDRL form.

1.8.4.2. Timeliness

Timely delivery of data is critical to program success. Performance will be measured on a quarterly basis. The contractor's performance will be considered unacceptable if more than one (1) report is submitted late in a single quarter, or if any single report is delivered more than five (5) business days beyond its due date.

1.8.4.3. Accuracy and Quality

All data deliverables are expected to be complete and accurate at the time of initial submission. The Government will review each submission for accuracy and compliance with the requirements outlines in the Data Item Description (DID). If a submission is found to be inaccurate or incomplete, the COR will return it for correction. The contractor's performance is considered unacceptable if more than two (2) reports in a single quarter require such correction.

1.8.4.4. Safety-Related Reporting

The contractor shall pay attention to the critical reporting requirements for CDRL AXXX, Safety Alert Report, and CDRL AXXX, Safety Alert Response. Given their critical nature, any failure to meet the specified timeliness and accuracy standards for these specific CDRLs will automatically trigger the requirement for a Corrective Action Plan.

1.8.5.Service Provider Labor Hours

The contractor shall report all service provider labor hours (including sub- contractor labor hours) required in the performance of services provided under this contract via a secure data collection site. The contractor shall completely fill all required data fields at the Department of the Air Force Contractor Manpower Reporting Application SAM.gov website. Note: User manuals are available at the Army CMRA link on the website. Contractors may direct questions to the CMRA help desk.

1.8.5.1. Period of Performance for Reporting

Reporting inputs will be for the labor hours executed during the period of performance for each Government fiscal year (FY), which runs 1 October through 30 September. While inputs may be reported any time during the FY, all data shall be reported NLT 31 October of each calendar year. The contractor shall notify the CO when all inputs are complete.

1.8.5.2. Small Business Participation Plan

The Contractor shall prepare and submit a Small Business Participation Plan NLT 15 days after contract award that identifies how the contractor intends to meet and maintain a minimum 2.5% annual Small Business participation (by % of total contract value) throughout the period of

performance. This plan is in addition to the requirement for a Small Business Subcontracting Plan IAW FAR 52.219-9. The contractor shall be required to provide a subcontractor report IAW CDRL AXXX, which shall include a separate section detailing progress towards meeting the Small Business Participation Plan goals, including actual dollars and percentage of subcontracted funds going to small businesses.

1.8.6. Program Improvement/Incentives

1.8.6.1. Engine Reliability

The contractor shall improve fleet-wide Mean Time Between Removal (MTBR) each year by at least 2% in each of years 4 and 5. Evaluations will occur at the end of each year. The contractor will have an opportunity to earn a performance incentive with at least a 2% increase in MTBR in years 6, 7, and 8.

1.8.6.2. MTBR Determination

The current MTBR is ~190 hours, based on engines last maintained by the CRF. MTBR is evaluated quarterly. MTBR will be calculated utilizing data pulled from CEMS. MTBR calculation will only include engine caused removals (i.e., inherent issues).

1.8.6.3. Contractual MTBR Calculation(s)

The contractual baseline MTBR will be the actual MTBR at the time of contract award date. The contractor shall maintain the MTBR established at contract award date as a minimum for performance during years 1 through 3. The MTBR will be recalculated at the end of each performance period beginning in year 3. The contractual MTBR will then be re-established each year from years 3 through 8 as the higher of the most recent contractual baseline MTBR or the recalculated MTBR. For example, see the table below:

Table 5 Example Contractual MTBR Calculation

	Actual MTBR	Contractual MTBR
Contract Award Date	190	190
End of Year 3	193	193
End of Year 4	200	200
End of Year 5	195	200

Note: At the sole discretion of the Government the contractual MTBR may be adjusted downward based on circumstances outside the reasonable control of the contractor -- for example a TCTO for a safety issue.

1.8.6.4. Process Improvement Initiatives

The contractor shall submit any process improvement initiatives to the PCO utilizing Publication Change Request (PCR) in the Enhanced Technical Information Management System (ETIMS), or similar document, which includes space for sufficient detail for analysis to specifically address cost and reliability IAW TO 00-5-1. The PCO will send official notification of government approval/disapproval.

1.8.7. Surge Requirements

The contractor shall plan for flexibility in operations to ensure no performance degradation while accommodating surges in response to crisis or national emergency which may create a significant, unexpected increase in engine repair/maintenance requirements and/or workload. The contractor shall submit a detailed surge plan after contract award IAW CDRL AXXX demonstrating the contractor's flexibility to rapidly accelerate and sustain production utilizing existing facilities and

equipment of at least a 30% increase of the annual production Best Estimated Quantity (BEQ).

1.8.8.Warranty

1.8.8.1. Warranty

Contractor shall provide a warranty on engines returned with less than 100 Engine Flying Hours (EFH) or one year, whichever comes first, since last visit to the contractor's CRF. Warranty repair applies when the removal is determined to be the result of workmanship deficiencies. Failures due to Foreign Object Damage (FOD), fuel/oil contamination, over-temperature, and other field maintenance or aircraft operation/flying induced faults are excluded. Removals attributed to LRUs do not fall within this warranty coverage. When removed for potential warranty repair, If the deficiency is found to be workmanship, the contractor will provide the Government with full warranty consideration and shall perform all work required to bring the engine back to serviceable condition, at no cost to the Government. If the removal was not related to the contractor's workmanship (i.e., the result of an LRU failure), the contractor will provide the Government with an FFP quote to return the engine to serviceable condition.

1.8.8.2. Metric

The Contractor shall ensure total product quality deficiencies for workmanship of whole engines operating over 100 EFH time on wing shall not exceed 2% of all engines produced as reflected in SS-4.

1.8.8.3. Low Time Removals

For the basic period and any option exercised, the contractor shall minimize low time removals (defined as engine removal under 100 EFHs of operation not attributed to Line-Replaceable Unit (LRU) failure or FOD) by ensuring low time removals do not exceed 2% for all engines produced, as reflected in SS-4.

1.8.9.Program Quality

1.8.9.1. Quality System/Assurance/Management

Contractor shall develop, maintain, and implement a Quality Management Plan which assures the requirements of the contract are satisfied IAW Repair Qualification Requirement (RQR) for J85-5 Whole Engine and Major Subassemblies.

1.8.9.2. Point of Contact

Contractor shall identify to the Government their Quality Point of Contact following contract award.

1.8.9.3. Surveillance

Contractor performance shall be monitored in accordance with the Quality Assurance Surveillance Plan (QASP). Surveillance methods 100% inspection, periodic surveillance, customer complaint, audit review, and random sampling. Details of surveillance responsibilities and metrics are included in the QASP provided as attachment X.

1.8.9.4. Corrective Actions

Contractor shall implement appropriate corrective actions to bring the quality system into compliance and correct findings issued through Corrective Action Requests (CAR).

1.8.9.5. Complaints

The contractor shall minimize MAJCOM and customer complaints validated by the PCO/ACO. The contractor shall receive no more than two (2) MAJCOM or J85-5 SPO customer complaints

validated by PCO/ACO per quarter, as reflected in SS-7. DCMA/COR Level 1 Corrective Action Reports (CARs) will not be counted as customer complaints. MAJCOM/customer complaints validated by the PCO/ACO and DCMA/COR Level 2, 3 and 4 CARs will be counted as customer complaints.

1.9. Foreign Object Damage (FOD) Prevention Program

The contractor shall maintain a FOD prevention program IAW NAS 412. In the event of a FOD incident, the contractor shall notify the PCO/ACO via email within three (3) business hours of confirming the FOD event. Following notification, a FOD Incident Report IAW NAS 412 shall be submitted to the PCO/ACO and the owning base Safety Office via email with three (3) working days of the incident. Furthermore, the contractor shall perform damage analysis and report final damage to the affected base Safety Office. The contractor shall ensure that no preventable FOD incidents occur due to actions or inactions by the contractor.

1.10. Contractor Induced Damage

The contractor shall notify the DCMA Property Administrator (PA) and the PCO/ACO via email within 24 hours of all Lost, Damaged, Destroyed, or Theft (LDDT) incidents involving Government property (excluding DLA-managed items not integrated into a contractor-managed system or end item) caused by the contractor or their sub-contractors(s). In addition to the initial notification, the contractor shall:

- a) **Report Logistics Discrepancies (LDDT):** Submit an LDDT report to the PCO/ACO, DCMA PA, and any other parties specified by applicable regulations (LIST REGULATION). This report shall track discrepancies in shipping and packaging of materials, identifying issues related to shipper responsibility, including government sources and vendors.
- b) **Report Supply Discrepancies (SDR):** For Government material (assets/GFM) received damaged, misdirected, or with missing parts, the contractor shall submit a Supply Discrepancy Report via WebSDR to report shipping or packaging discrepancies attributable to the shipper's responsibility, aiming to determine the cause of discrepancies, effect corrective actions, and prevent recurrence.
- c) **SF364 Reporting (if applicable):** In addition to the LDDT report and SDR, if the incident involves loss, damage, or destruction of government property, the contractor shall also submit SF364 Report of Discrepancy, IAW TO 00-35D-54 and FAR 52.245-1. This SF364 shall be submitted to the PCO/ACO, DCMA PA, and any other parties specified in TO 00-35D-54

The Government will provide disposition instructions for the damaged item IAW TO 00-35D-54. The contractor shall be liable for damage to components resulting from negligence or failure to adhere to established procedures, including but not limited to machining errors or dropped item damage.

1.11. Packaging/Handling/Shipping/Transportation

The contractor shall ensure all engines and components are packaged, handled, and transported to prevent damage and contamination, strictly adhering to the latest versions of applicable Technical Orders (TOs), Department of Air Force Instructions (DAFIs), and customer-specific regulations.

1.11.1. General Packaging & Preparation Requirements (Applicable to all Engines/Rotors unless specified otherwise)

1.11.1.1. Packaging Instructions:

Utilize the most current packaging instructions as reflected in the Special Packaging Instructions Retrieval & Exchange System (SPIRES) and IAW TO 00-85-20

If SPIRES does not contain packaging instructions for a specific item, the Contractor shall utilize commercial packaging instructions and submit them to the Government CEA for deviation approval

1.11.1.2. Preparation for Shipment:

Prepare engines for shipment IAW TO 2J-J85-111-1 and 2J-1-18

1.11.1.3. Asset Tagging:

Ensure proper tagging of all assets in compliance with applicable AFIs. Each tag shall include the asset identification, National Stock Number (NSN), and condition code and be securely placed both inside the shipping package (accompanying the item) and on the package's exterior

1.11.2. USAF Engine Specific Requirements**1.11.2.1. Packaging:**

- a) Engines shall be packaged to preserve their integrity during transport
- b) Reusable containers must comply with TO 2J-J85-111-1 and 2J-1-18
- c) The contractor shall track, store, and repair reusable containers and engine crates for USAF customers

1.11.2.2. Documentation with Shipment: The following information will be included with engines being returned to the field:

- a) Paper/digital/CD copy of work performed during the repair/overhaul, documented IAW TO 00-20-5-1-10. Include the as-shipped E407 CEMS report
- b) Copy of any waivers (107) granted by J85-5 Engineering for life-limited components or any other waivers issued during the process
- c) Joint Oil Analysis Program (JOAP) records including engine serial number
- d) Serviceable tag for the engine and any others for new/overhauled parts installed
- e) Copy of the test cell run sheet

1.11.2.3. Transportation:

- a) The contractors, along with the J85-5 Program Office, shall review the CEMS Propulsion Unit Automatic Resupply report for J85-5 engines daily to identify priority of engines for shipment to supported bases
- b) The contractor shall communicate with the J85-5 Program Office via email to request shipping instructions for serviceable engines. The contractor may also request shipping instructions for empty crates to be sent to the field in addition to whole engines deliveries, as coordinated with the J85-5 Program Office.
- c) A list of possible addresses for engine shipment per the Program Office disposition is provided at Attachment X to this PWS. While this list of addresses does not change, the POC information for each base may change. The most current POC and address can be verified in the CEMS SRAN manager list.
- d) The contractor will establish means to transport/ship assets IAW appropriate government instructions, utilizing the Transportation Account Code (TAC) F8KA
- e) The contractor shall ship serviceable engines within (3) three working days after receiving shipping instructions, unless instructed to ship sooner
- f) Contractor shall ship Ready-For-Issue (RFI) engines to recipient AETC operation bases, as specified using the TAC provided in the contract

1.11.3. US Navy Engine Specific Requirements**1.11.3.1. Packaging:**

- a) Navy engine shipment containers received with engines shall be reused exclusively for Navy engines
- b) Damaged containers shall be repaired or replaced as directed by the PCO. If a Navy

container is damaged, the contractor shall send the container to the address referenced for repair

1.11.3.2. 1.14.3.2. Transportation:

Contractor shall use a specific Navy TAC for shipment of Navy Engines

All Navy Engines shall be shipped to:
U.S. Naval Test Pilot School
Hangar 110 Room 108R
22777 Saufley Road
NAS Patuxent River MD 20670

1.11.4. NASA Compressor Rotors Specific Requirements

1.11.4.1. Packaging:

- a) NASA owned compressors shall be packaged to prevent contamination and damage during transport
- b) Packaging must comply with NASA regulations
- c) The contractor shall track, store, and repair reusable containers and engine crates for NASA customers
- d) Contractor shall perform inspections, maintenance, and upkeep on NASA furnished shop support equipment as required
- e) Rotors will be packaged and shipped IAW SPIRES or NASA regulations as required

1.11.4.2. Transportation:

- a) NASA will select a vendor to deliver and pickup compressor rotors
- b) The contractor shall request disposition instructions for serviceable NASA-owned compressors from NASA Aircraft Operations

1.11.5. Air Force Managed Items and Lateral Support

1.11.5.1. Air Force Managed Items (Unserviceable/Reparable)

The contractor shall prepare and ship unserviceable/reparable Air Force Managed Items that are Not Repairable This Station (NRTS) from maintenance shop areas to the appropriate AF Item Management for subsequent repair. These items shall be shipped utilizing transportation code F2RS and transportation priority (TP02) to the following address:

SW3211
DLA DISTRIBUTION DEPT OKLAHOMA 3301 F AVE CEN REC
BLDG 506 DR 22
TINKER AFB, OK 73145-8000

1.11.5.1.1. Packaging:

The contractor shall thoroughly inspect containers, trailers, stands, and other associated equipment to ensure they are clean, complete, and free from structural and mechanical damage, and that all attaching points are complete and secure. The contractor shall ensure that reusable shipping containers are not destroyed. If a container is beyond economic repair, the contractor shall use Military Standard Packaging IAW AFMC Form 158 Packaging Requirement and TO 00-35D-54 and submit a Supply Discrepancy Report (SDR).

1.11.5.1.2. Preparation & Item Integrity

The contractor shall ensure Not Less Than (NLT) 98% of Line Replaceable Units (LRUs) being readied for shipment are properly identified and complete with no missing parts IAW Performance Summary SS-6. The contractor shall ensure all parts remain with LRUs throughout the repair process so that all LRUs are turned in wholly assembled. Should there be rare instances where LRUs are missing parts, the contractor shall make every attempt to locate and assemble them. If parts cannot be found, the contractor shall include a comprehensive list of missing items to accompany the LRU during shipment.

1.11.5.1.3. Records and Labeling

The contractor shall ensure the unserviceable tag includes all pertinent information regarding the reason for depot level repair, clearly documenting the DoDAAC of the turning-in location. The LRU shall be properly identified with regard to NSN and condition.

1.11.5.2. Lateral Support

The contractor may be required to provide serviceable assets to field locations. Instructions for such requirements will be provided on a case-by-case basis by the J85-5 System Program Office (SPO).

1.12. Government Programs/Databases/Systems/Websites

1.12.1. Access

The contractor shall obtain access to U.S. Government automated information system resources which process sensitive, unclassified, or Privacy Act information, as directed by the PCO.

1.12.2. Applicability

All contractor personnel requiring access to Government data systems and a Common Access Card (CAC) shall have a National Agency Check for Inquiries (NACI). The Contractor must have or hire a United States National, capable of passing favorable NACI background check to obtain the CAC, and process reporting requirements. CEMs access will not be granted to foreign nationals. The contractor shall not allow access to foreign nationals or foreign agencies, nor release information without Government approval. The contractor shall notify the PCO/ACO in writing within one (1) business day with information pertaining to any request.

1.12.3. System Access (Required)

The contractor shall obtain and maintain the accounts identified below for access to programs, databases & websites. A Public Key Infrastructure (PKI) / CAC card certificate is required when necessary for access.

Due to the Government's requirement for digital fingerprints and background investigations/clearances to obtain a PKI/CAC Card for Government system access, and the associated processing time, a phase-in period is permitted for system reporting requirements on systems requiring CAC card access.

During this interim period, the Contractor remains responsible for providing all applicable maintenance data/system reporting to the Government via email to the PO for all items inducted into maintenance/repair. This interim reporting shall continue until the Contractor obtains CAC cards and associated system access and training.

Table 6 Contractor System Access Requirements

System Name	Purpose
Procurement Integrated Enterprise Environment (PIEE)	Secure point of access for various procurement-related tasks and modules

Commercial Asset Visibility Air Force (CAVAF)	Air Force asset visibility tracking
FedMALL (formerly EMALL) for DLA forecasting	DLA forecasting
Joint Deficiency Reporting System (JDRS)	Reporting system for identifying and tracking deficiencies
D042 Comprehensive Engine Management System (CEMS)	Engine Management system *No foreign nationals may access
Enhanced Technical Information Management System (ETIMS)	Management of technical information
Web-based Supply Discrepancy Report (SDR) system	Reporting supply discrepancies
Work scope Cost Optimizer Tool (WCOT) for Reliability Centered Maintenance (RCM)	Optimizes work scope costs using RCM principles
Plant Clearance Automated Reutilization Screening System (PCARSS)	Screening and reutilization of plant clearance materials
Electronic Data Access (EDA)	Access to electronic data (contracts and procurement)
Wide Area Work Flow (WAWF)	Electronic invoicing and payment system
DLA Forecasting Systems (for DDEs and DHAs)	Forecasting systems used by DDEs and DHAs
Decision Knowledge Programming for Logistics Analysis and Technical Evaluation (DECKPLATE)	Logistics analysis and technical evaluation
Navy Aircraft Engine Management System (AEMS) (Part of DECKPLATE) P-700 Common Naval Packaging (CNP)	Navy's engine management system, part of DECKPLATE, involving CNP
Contractor Performance Assessment Rating System (CPARs) ECMRA	Performance assessment and rating
Special Packaging Instructions Retrieval & Exchange System (SPIRES)	Retrieving and exchanging special packaging instructions (Randolph AFB PMEL SharePoint Site Access)
DoDSAFE	Securely transfer large files

1.12.4. Information Systems (IS)

Reserved.

1.12.5. Maintenance Information Systems (MIS)

The contractor shall support and participate in all surveys, studies, tests, system upgrades and changes relating to MIS software and hardware as required by the Government. This includes providing subject matter experts

1.12.5.1. MIS Guidance/Instruction

The contractor shall use MIS products and perform all MIS input tasks IAW AFI 21-101, AFI 21-103, Equipment Inventory, Status and Utilization Reporting, TO 00-25-254-1, AFCSM 21-556 (V2), AFCSM 21-303 (V2) and 00-20 series TOs.

1.12.5.2. Accuracy of Data

The contractor shall ensure data entered MIS Programs and annotated on official forms (e.g., DD Forms, AF Forms, AFTO Forms, etc.) is accurate, complete and maintained IAW AFI 21-101, applicable 00-20 series TOs, and all other pertinent DAF directives.

1.12.6. Technical Library Maintenance**1.12.6.1. System Access**

The contractor shall obtain access to the applicable Government Technical Orders (TOs), Technical Manuals (TMs) and other Technical Directives for the J85-5 engine MRO

Maintenance contract requirements. The Contractor shall obtain and submit an approved DD Form, or its most current equivalent, for requesting system authorization access (currently DD Form 2875, System Authorization Access Request (SAAR)) to gain viewing access of the applicable Government TOs for the J85-5 engine contract requirements. Upon contract award, the contractor shall acquire and maintain a Technical Order Distribution Office (TODO) Account to maintain all TOs, TCTOs, Computer Program Identification Number (CPIN) and other technical directives listed in this PWS in an updated and current status IAW TO 00-5-1 and 00-5-3.

1.12.6.2. Conflict Reporting

The contractor shall notify the PCO if a conflict arises between the requirements of this PWS and the Technical Documents within 5 working days of found discrepancy. The Contractor shall provide a courtesy copy of the notice to the ACO. The contractor shall utilize ETIMS to obtain current TOs and TCTOs.

1.12.6.3. Review of Changes

The contractor shall review all updates to the TOs, TCTOs, CPINs and other directives within 10 working days of receipt. Within this timeframe, the contractor may request an extension from the PCO with a copy to the ACO for the directive if the complexity of the review will require more than 10 working days to complete.

The contractor shall review all changes or publications identified as Safety directives, within one business day of receipt.

Note: For this and the following sections, “Safety” directives are to include any change or publication that are identified as “Safety” within the publication, or submitted to the contractor as “Safety” or “Safety Related” by the PCO/ACO.

1.12.6.4. Implementation of Changes

The contractor shall implement all changes or publications identified as Safety directives within one business day of technical review for no cost changes, and within one business day after receipt of PCO/ACO approval and funded authorization for changes that have a cost impact. The contractor shall notify the PCO/ACO within 3 working days that changes have been incorporated.

1.12.6.4.1. Safety Directives

For all Safety directives, the contractor shall immediately stop work on product requiring the directed change and shall not deliver this product to the Government until the change has been incorporated, unless otherwise directed by the PCO/ACO. The applicable product shall be put on hold within one business day of the technical review being completed.

1.12.6.4.2. Implementation of Changes

The contractor shall implement all routine changes that have no cost impact within 10 working days of completing the review. The contractor shall implement all routine changes with a cost impact within 10 working days of PCO/ACO approval and funded authorization.

Where new technical directives incorporate many changes that are split between having a cost impact and no cost impact, the contractor shall incorporate each individual change per the above guidance and timelines. A single “cost impact change” shall not constitute reason to delay the other “no cost changes” within the same publication. The contractor shall request a deviation within 10 working days of review when technical data is partially incorporated but “cost impact changes” are pending PCO/ACO approval and funded

authorization. Once deviation is approved, the contractor shall implement partially incorporated manual or technical change within 10 working days.

1.12.6.4.3. Routine Technical Publications or Changes

For all routine technical publications or changes, regardless of cost impact, the contractor shall continue to produce under previously authorized technical guidance until the time the change is required to be implemented as stated above. For all routine changes, the contractor shall incorporate tech data changes at the specified timeline as stated above for all future products inducted, and all products in work that have not yet been processed past the technical requirements affected, unless otherwise directed by the PCO/ACO. The PCO/ACO may specifically direct and fund routine changes to be incorporated into products already in-work.

1.12.7. Cost Impact of Changes

The contractor shall notify the PCO/ACO in writing of estimated cost impact within 30 work days for routine changes and 15 workdays for Safety changes if the Contractor determines the changes will result in cost impact. The contractor shall submit a cost proposal to the PCO/ACO for all cost impact technical directives received.

1.13. Mission Essential Services

IAW DFARS Subpart 237.76, Continuation of Essential Contractor Services, the services identified in this PWS are explicitly designated as not Mission Essential Services.

1.14. Item Unique Identification (IUID)

IUID part-marking compliance is a Department of War (DoW) mandate for items contained within Government inventory systems and as identified by DoW criterion requirements. All IUID requirements are defined in DODI 8320.04. The contractor shall follow the latest DoW instructions to install IUID compliant marks. When directed by the PCO/ACO, the contractor shall follow the latest DoD instructions to install IUID compliant marks.

SECTION II - SERVICE SUMMARY

2. Service Summary Requirements

The contractor shall ensure the performance objectives, performance thresholds, and support for surveillance methods are achieved IAW PWS CDRLs, prescribed procedures and USAF directives.

2.1. Performance Objectives and Thresholds

The contractor shall achieve performance thresholds identified in Table 7 of this PWS.

The performance thresholds are designed to:

- a) Align contractor performance with objectives.
- b) Focus on critical success factors in meeting performance objectives.
- c) Reflect performance goals.
- d) Promote continuous improvement in performance.
- e) Support minimum mission requirements.
- f) Facilitate overall program improvement.
- g) Maximize efficiencies.

As applicable, the DCMA and the PCO/ACO will exercise surveillance over the performance thresholds.

2.2. Performance Surveillance

The Government will monitor contractor performance against the objectives detailed in the Service Summary. The Defense Contract Management Agency (DCMA) will perform primary contract surveillance IAW DCMA policies. The contractor shall support surveillance activities, which will be conducted using the specific methods outlined for each objective in the “Method of Surveillance” column in the Service Summary table. These methods include, but are not limited to:

- a) 100% Inspection
- b) Period of Surveillance
- c) Customer Complaint
- d) Audit Review
- e) Random Sampling

2.3. Contractor Performance Evaluation

The contractor’s performance will be formally evaluated against the specific thresholds established for each objective in the Service Summary.

In the event a performance objective is not met, the DCMA will issue a written notification (Corrective Action Request) to the contractor. The contractor shall respond and take corrective action based on the severity of the deficiency as follows:

- a) **For Minor Deficiencies:** The contractor shall correct the issue and provide evidence of correction to the PCO/ACO within 10 business days of notification
- b) **For significant Deficiencies:** The contractor shall provide a formal Plan of Action & Milestones (POA&M) to the PCO/ACO within 5 business days of notification. The contractor shall then fully implement the approved plan within 30 calendar days of notification, unless a different timeline is approved in writing by the PCO.
- c) **For Critical Deficiencies:** The contractor shall take immediate action within 24 hours to mitigate the issue and shall provide a formal report on the incident and initial containment actions to the PCO/ACO within 48 hours of notification.

Failure to meet these timelines for corrective action may result in further administrative or contractual remedies by the PCO/ACO.

TABLE 7 Service Summary (SS) Elements

Performance Objective	PWS Paragraph	Threshold
SS-1 Transition Planning and Reporting	1.2	Submit a complete and compliant Transition Plan (CDRL AXXX) NLT 30 working days after contract award Provide weekly progress reports (CDRL AXXX)
SS-2 Achieve Operational Capability	1.2.1	Achieve Initial Operational Capability (IOC) by the date in the approved schedule Achieve Full Operational Capability (FOC) – a sustained rate of up to 32 engines/month – by the date in the approved schedule
SS-3 Establish a Certified J85-5 Test Cell Capability	1.2.1	Achieve full J85-5 test cell validation and certification, evidenced by final, written approval from the Cognizant Engineering Authority (CEA), by the date specified in the approved transition plan
SS-4 Minimize Low Time Engine Removals	1.8.8.3.	Low time removals (engine removal < 100 EFHs not due to LRU failure or FOD) shall not exceed 2% of all engines produced annually

SS-5 Timely and Accurate Deficiency Investigation and Reporting	1.7.6.	NLT 98% of investigations are completed within the following timelines from receipt of asset CAT I Mishap: 15 calendar days CAT II Mishap: 30 calendar days CAT I DR: 20 calendar days CAT II DR: 30 calendar days 100% of required reports (PQDRs, TDRs) are submitted IAW CDRLS/Tos and contain all required data (root cause, corrective action, etc)
SS-6 Timely Repair of Deficiency Report Items	1.7.6.	NLT 98% of all deficiency report items are repaired within 90 calendar days of receiving disposition instructions from the Government
SS-7 Timely and Accurate Submission of Contract Data Requirements Lists (CDRLs)	1.8.4.	The contractor shall meet the following standards for all CDRL submissions No more than one (1) late CDRL submission per quarter. No single late document shall be more than five (5) working days overdue No individual report submitted during the quarter shall require more than two (2) rounds of corrections
SS-8 Minimize Validated Customer Complaints	1.8.9.5.	No more than two (2) validated customer complaints per quarter (Note: Validated complaints include MAJCOM/SPO complaints and DCMA/COR Level 3 & 4 CARs. Level 1&2 CARs are excluded)

SECTION III – Government Furnished Property (GFP) and Services

3. Government Furnished Property

3.1. General Stewardship and Accountability

The Government will provide Government Furnished Property (GFP), including but not limited to Government Furnished Equipment (GFE) and parts, as specified in this PWS. The Contractor shall be responsible and accountable for all GFP in its possession in accordance with Federal Acquisition Regulation (FAR) 52.245-1, Government Property, and the requirements herein. The Contractor shall establish, maintain, and assume full stewardship of said property from the moment of receipt until formal disposition or relief of responsibility is granted in writing by the PCO.

3.2. Comprehensive Inventory Management System

The contractor shall establish, maintain, and operate a comprehensive electronic inventory management system for all GFP provided under this contract, including all USAF and DLA managed property.

3.2.1. Inventory System Requirements

The Contractor's Inventory System shall be electronic, auditable, and compliant with all applicable FAR and DFARS clauses. The system shall, at a minimum:

- a) **Unique Identification:** Be capable of tracking and managing assets using a unique item identifier, such as a serial number, lot number or other Government-approved tracking number.
- b) **Full Lifecycle Tracking:** Provide a complete, auditable transaction history for each asset,

documenting all events from receipt, movement, storage, and issue, to final disposition. The system must be capable of distinctly identifying and reporting on assets designated for “Cycle 2” or other secondary repair processes.

- c) **Data Accuracy and Integrity:** Maintain a data accuracy rate of no less than 98% and include internal controls to prevent unauthorized or erroneous data entry.
- d) **Government Access:** Provide read-only access to authorized Government personnel, including DCMA and the ACO, for the purpose of oversight and audit.

3.2.2. Physical and Systemic Segregation

The Contractor shall implement and maintain a Government-approved Parts Storage Plan that ensures the strict physical and systemic segregation of assets.

- a) **Physical Segregation:** USAF-managed parts and DLA-managed parts shall be stored in separate, clearly designated, and secure physical locations to prevent commingling.
- b) **Systemic Segregation:** The inventory System shall logically segregate asset records by ownership (USAF or DLA) to ensure clear accountability and facilitate reporting.

3.3. Inventory Reporting and Audits

3.3.1. Joint Inventories

The contractor shall conduct joint physical inventories with the Government at the start of the contract performance period and upon contract completion to establish a baseline and for the final reconciliation.

3.3.2. Routine Reporting

- a) **Monthly Inventory Reports:** The Contractor shall submit a Monthly Inventory Status Report to the PCO and COR no later than the tenth (10th) day of each month. The report shall detail, by owning service (USAF/DLA), the quantity on hand, location, and status of all managed parts.
- b) **Annual Physical Inventory:** The Contractor shall conduct a comprehensive, 100% wall-to-wall physical inventory of all GFP annually, to be reconciled against the Inventory System records. A final report detailing the results, including any discrepancies, shall be submitted to the PCO within fifteen (15) business days of completion.

3.3.3. Unscheduled Government Audits

In addition to scheduled inventories, the Government reserves the right to conduct unscheduled, “no-notice,” or “short notice” physical inventories and audits if all GFP under the Contractor’s control. The Contractor shall provide immediate access and full cooperation to Government personnel, including DCMA and ACO representatives, for such audits.

3.4. Loss, Damage, Destruction (LDD) Reporting

In accordance with FAR 52.245-1(f)(1)(vii), the Contractor shall report any instance of Loss, Damage, or Destruction (LDD) of Government Property to the PCO and DCMA. This report shall be made within 24 hours of discovery. The initial report may be verbal, followed by a formal written report submitted through the Government’s Property Loss system within three (3) business days. The contractor shall provide all necessary documentation to support the investigation and resolution of any LDD case.

3.5. GFE Tooling and Parts

3.5.1. GFE Tooling

GFE tooling identified in Attachment X will be made available to the contractor. The Contractor shall be responsible for performing all required preventative maintenance, calibration, and minor repairs or GFE tooling in its possession. All maintenance and calibration shall be performed in accordance with the equipment manufacturer’s specifications and Air Force technical guidance.

3.5.2.GFP Parts

The Government will provide GFP parts based on the established Table of Allowances (ToA). The Contractor shall use the CAV-AF system for all transactions involving Air Force managed GFP parts, including receipt, turn-in, and inventory reporting.

SECTION IV: ACRONYMS AND DEFINITIONS

ACA	Associate Contractor Agreement
ACC	Air Combat Command
ACI	Analytical Condition Inspection
ACO	Administrative Contracting Officer
AEMS	Navy Aircraft Engine Management System
AETC	Air Education and Training Command
AFB	Air Force Base
AFEMS	Air Force Equipment Management System
AFI	Air Force Instruction
AFMC	Air Force Material Command
AQL	Acceptable Quality Level
ATOW	Average Time on Wing
AWM	Awaiting Maintenance
BEQ	Base Engine Quantity
BER	Beyond Economical Repair
BSL	Base Stock Level
CAC	Common Access Card
CA/CRL	Custodian Authorization Custody Receipt Listing
CAFB	Columbus Air Force Base
CAR	Corrective Action Report
CAV	Commercial Asset Visibility
CAV-AF	Commercial Asset Visibility Air Force
CDB	Central Data Base
CDRL	Contract Data Requirements List
CEA	Cognizant Engineering Authority
CEM	Command Engine Manager
CEMS	Comprehensive Engine Management System
CFE	Contractor Furnished Equipment
CFM	Contractor Furnished Materials
CIP	Component Improvement Program
CLIN	Contract Line Item Number
CMRA	Contractor Manpower Reporting Application
CNP	Common Naval Packaging
CO	Contracting Officer
COR	Contracting Officer Representative
CPARS	Contractor Performance Assessment Rating System
CPIN	Computer Program Identification Number
CPG	Comprehensive Procurement Guidelines
CRF	Centralized Repair Facility
CSI	Critical Safety Items
CTK	Composite Tool Kit
DCMA	Defense Contract Management Agency
DCMA PA	Defense Contract Management Agency Property Administrator
DDE	Demand Data Exchange
DECKPLATE	Decision Knowledge Programming for Logistics Analysis and Technical Evaluation
DEMIL	Demilitarization
DFARS	Defense Federal Acquisition Regulation Supplement
DHA	Demand History Adjustment

DIFM	Due In For Maintenance
DLA	Defense Logistics Agency
DNACI	DoD National Agency Check plus written Inquiries
DODAAC	Do Activity Address Code
DR	Deficiency Report
ECMRA	Enterprise Contractor Manpower Reporting Application
EDA	Electronic Data Access
EFH	Engine Flying Hours
EI	Engineering Investigation
ENJJPT	Euro-NATO Joint Jet Pilot Training
ENMCS	Engine Not Mission Capable due to Supply
EPA	Environmental Protection Agency
ERRC	Engine Regional Repair Center
ESRS	Electronica Subcontracting Reporting System
ESS	Electronic System Supply
ETIMS	Enhanced Technical Information Management System
ETOW	Engine Time on Wing
FAR	Federal Acquisition Regulations
FEDMALL	Federal Mall
FFP	Firm Fixed Price
FMS	Foreign Military Sales
FOC	Full Operational Capability
FOD	Foreign Object Damage
FTW	Flying Training Wing
FY	Fiscal Year
GE	General Electric
GFE	Government-Furnished Equipment
GFP	Government Furnished Property
GPP	Green Procurement Program
HFFR	Hold For Future Repair
JPO	Hourly Post-flight Inspection
IA	Information Assurance
IAT	Information Assurance Technical
IAW	In Accordance With
IDIQ	Indefinite Delivery Indefinite Quantity
IFF	Introduction to Fighter Fundamentals
ILS-S	Integrated Logistics System Supply
IMDS	Integrated Maintenance Data System
IOC	Initial Operating Capability
IS	Information Systems
IUID	Item Unique Identification
LDDT	Lost/Damaged/Destroyed/Theft
JDRS	Joint Deficiency Reporting System
JEIM	Jet Engine Intermediate Maintenance
LDD	Loss, Damage, or Destruction
LRU	Line Replaceable Unit
LRS	Logistics Readiness Squadron
MAJCOM	Major Command
MIS	Maintenance Information Systems
MPWG	Maintenance Planning Working Group

MRB	Material Review Board
MTBR	Mean Time Between Removal
NACI	National Agency Check for Inquiries
NAS	Naval Air Station
NASA	National Aeronautics and Space Administration
NATO	North Atlantic Treaty Organization
NLT	No Later Than
NRTS	Not Repairable This Station
NSN	National Stock Number
OEM	Original Equipment Manufacturer
O&A	Over and Above
PA	Property Administrator
PCARSS	Plant Clearance Automated Reutilization Screening System
PCO	Procuring Contracting Officer
PDF	Portable Document Format
PE	Periodic Inspection
PIT	Pilot Instructor Training
PKI	Public Key Infrastructure
PMEL	Precision Measurement Equipment Laboratory
PMO	Program Management Office
PMP	Propulsion Modernization Program
PMP	Program Management Plan
PMR	Program Management Review
PoP	Period of Performance
PQDR	Product Quality Deficiency Report
PWS	Performance Work Statement
QAR	Quality Assurance Representative
QASP	Quality Assurance Surveillance Plan
QR	Qualification Requirement
RAW	Repair Assessment Worksheet
RCM	Reliability Centered Maintenance
REMIS	Reliability & Maintainability Information System
RFI	Ready for Install
RTS	Repair This Station
SAR	Source Approval Request
SEEMPL	System Engineered Maintenance Planning & Logistics
SIB	Safety Investigation Board
SDR	Supply Discrepancy Report
SIO	Single Investigating Officer
S/N	Serial Number
SPIRES	Special Packaging Instructions Retrieval & Exchange System
SPO	System Program Office
SS	Service Summary
SUPT	Specialized Undergraduate Pilot Training
TAC	Transportation Account Code
TAT	Turn-Around-Time
TCTO	Time Compliance Technical Order
TDR	Teardown Deficiency Report
TMO	Transportation Management Office
TO	Technical Order

TOA	Table of Allowance
TODO	Technical Order Distribution Office
TSR	Target Serviceable Requirement
TWO	Time on Wing
UER	Unscheduled Engine Removal
UPT	Undergraduate Pilot Training
USAF	United States Air Force
USN	United States Navy
WAWF	Wide Area Workflow
WCOT	Workscope Cost Optimizer Tool
Web SDR	Web Supply Discrepancy Report