

PERFORMANCE WORK STATEMENT (PWS) Kitchen Hood Fire Suppression Services



509 Civil Engineer Squadron
660 Tenth Street, Ste 201
Whiteman AFB MO 65305-5316
U.S. Air Force
02/27/2026

TABLE OF CONTENTS

1. Requirement 3

2. Contractor Responsibilities 4

3. Service Summary/ Quality Assurance 9

4. Appendix 1: Kitchen Fire Control System Locations and Service Details.....12

1. Requirement

1.1. Scope: The Contractor shall provide all necessary parts, equipment, supplies, transport, materials, and labor necessary to provide annual, semiannual, and periodic inspections, certifications and maintenance services, as well as additional in-scope work for the kitchen fire suppression systems, commercial and residential, utilized on Whiteman Air Force Base (WAFB). Additional In-Scope work shall include unscheduled maintenance or servicing, such as inspecting, testing, recharging, or service (preventive) and emergency repairs. See Appendix 1 - Kitchen Fire Control Systems Building Location and Details of Service for facilities list.

1.2. General Description: The following description shall serve as general information along with performance objectives as required by the Government. The contractor shall conform to all state and local regulations in accordance with (IAW) industry standards and best practices. The contractor shall provide all travel, personnel, transportation, equipment, tools, materials, supervision, and quality controls, as defined in this Performance Work Statement (PWS).

1.2.1. Travel and Transportation: The Contractor is responsible for mobilization of personnel and equipment to and from all individual facilities including all shipping, delivery of materials, loading and offloading of materials, tools, and necessary equipment, including storage, to perform the required activities to accomplish the PWS. Contractor and/or personnel are responsible for obtaining the required security clearances for base access. The government will provide escorts where required.

1.2.2. Period of Performance (PoP)/Hours of Service/Holidays

1.2.2.1. Anticipated PoP: The Period of Performance shall be one base year of 12 months and four 12-month option years for a total period of five years. A one-time extension of six months at the end of this period of performance may be determined to be in the best interest of the Government, per FAR 52.217-8. The award document will note the Period of Performance (PoP) and the definitive performance period.

1.2.2.2. Hours of Service: Services shall be performed between the hours of 0730 and 1630, Monday through Friday, excluding Federal Holidays, base closures, government closures, and during periods of national emergency, unless prior arrangements are made.

1.2.3. Government Furnished Property (GFP): There is no GFP for this requirement.

2. Contractor Responsibilities

2.1. Program Management: The contractor shall provide materials and services to accomplish all tasks outlined in this PWS throughout the period of performance of the contract. Contractor shall perform this service at Whiteman AFB, Missouri.

2.1.1. Contract Manager (CM): The contractor shall designate a CM who shall ensure performance under this contract. The name of this person and an alternate, who are authorized to act for the contractor shall be designated in writing to the CO. The CM or alternate shall have full authority to act for the contractor on all contract matters relating to daily operation of this contract. The CM shall work through the COR to resolve issues, receive technical instructions, and ensure adequate performance of services. The CM shall ensure that contractor employees do not perform any services outside the scope of the contract without an official modification issued by the CO. The CM shall ensure contractor employees understand that services performed outside the scope of the contract are performed wholly at the expense of the contractor. Within 15 days of contract award, within 15 days of each option year, and upon any personnel changes, the Contractor shall provide a list of primary and alternate contacts & phone numbers.

2.1.2. Technician Certification: Contractor employees shall be certified. All technicians that perform inspection, testing, and maintenance must be, at a minimum, National Institute for Certification in Engineering Technologies (NICET) Level 2 certified in special hazard systems. Any issues that arise and require design or reconfiguration of system components shall require oversight by NICET Level 3 certified technician in special hazard systems. The Contractor shall supply a copy of certification for any technician to the CO/COR at least five business days prior to the employee performing service. All contractor employees shall always carry proper identification with them and are subject to checks as may be deemed necessary. The Contractor shall ensure compliance with all regulations and orders of the installation, which may affect performance. The Government reserves the right to direct the removal of an employee for misconduct or security reasons. Removal of contractor employees for reasons stated above does not relieve the Contractor from responsibility for total performance of this contract.

2.1.3. Service Compliance: Contractor and service technicians shall comply with the most current versions of National Fire Protection Association (NFPA) 96 – Standard for Ventilation Control and Fire Protection of Commercial Cooking Operations, NFPA 17A – Standard for Wet Chemical Extinguishing Systems, and American National Standards Institute/ Underwriters Laboratories (ANSI/UL) 300 – Fire Suppression System Requirements. Maintenance shall be performed in accordance with manufacturer's specifications and recommendations or equivalent standards in accordance with the requirements of the listing will be used or referenced. Maintenance of the fire-extinguishing systems and listed exhaust hoods containing a constant or fire-activated water system that is listed to extinguish a fire in the grease removal devices, hood exhaust plenums, and exhaust ducts shall be made by properly trained, qualified, and certified person(s) acceptable to the authority having jurisdiction. Listed hoods containing mechanical or

fire-actuated dampers, internal washing components, or other mechanically operated devices shall be inspected and tested by properly trained, qualified, and certified persons every six months or at frequencies recommended by the manufacturer. All technicians that perform inspections and/or maintenance shall be properly trained, qualified, and certified person(s) acceptable to the authority having jurisdiction and NFPA 96.

2.1.4. Service Coordination: Contractor will coordinate service scheduling with 509 Civil Engineer Squadron (CES). A schedule of inspection and periodic maintenance shall be provided to CES no later than ten business days before service starts at first scheduled facility. CES will coordinate with the contractor if there is a need to adjust the dates of the inspections, according to the status and schedule of each facility. The schedule shall include all applicable facilities, fire suppression systems, and the dates on which inspection and maintenance shall be provided for each. Facilities shall be scheduled to provide full services to the facility in one service call. Each building will be serviced completely before moving to the next facility.

2.1.5. Government Escort: The contractor shall comply with all applicable local security policies and procedures, which may be obtained from the COR. Ten business days prior to scheduled maintenance in a secure area in which escort is required, the contractor shall contact CES for coordination/ scheduling of government-provided escort and entry into this area.

2.1.6. Identification of Contractor Employees: All Contractor personnel are required to identify themselves as contractors to avoid creating an impression that they are Government employees. The Contractor shall ensure that all documents or reports produced are suitably marked as contractor products and that contractor participation is appropriately disclosed. The Contractor's status as a "contractor" shall be predominantly displayed in all correspondence types and dealings with Government or non-Government entities.

2.1.7. Contractor Required Identification: The Contractor shall ensure each employee obtains a contractor pass. This shall be accomplished by completing an Entry Authorization List (EAL) through the CE Service Contracts office. All employees shall have the contractor pass in their possession at all times when on base. For personnel that will be working in a restricted access area, additional checks may apply. All contractor personnel will be required to obtain and wear badges, specific uniforms, etc., in the performance of this contract. Badges or clothing shall have the company name, employee name, and the word "contractor" displayed prominently and in a visible location. The Contractor shall retrieve all identification media (including vehicle passes) from its employees who depart employment.

2.1.8 Invoicing: The Contractor shall submit a full and complete invoice in Wide Area Work Flow (WAWF) within 30 days of service. The invoice description in WAWF shall include the date(s) the service was provided.

2.2. TASK 2 Inspection and Maintenance

2.2.1. Fire Suppression Inspection/Certification Commercial: Periodic inspection and maintenance of each commercial fire suppression system shall be performed (semi-annual) at the frequency stated in Appendix 1. The Contractor shall comply with NFPA 96, NFPA 17A, and ANSI/UL 300. Technicians shall verify signal is sent to fire dispatch if/when suppression system is activated. During the inspection of the fire suppression systems, the Contractor shall perform routine maintenance of packing, seats, seals, and other leak control components; this is considered to be included in the inspection process. Replacement of individual heat detectors (not flame or gas detectors), pressure gauges and valves (up to and including 2-inch) up to two percent (2%) of the total equipment inspection, is also considered to be included in the inspection process. These measures are intended to cover incidental costs associated with any small and miscellaneous break fix events. Technicians shall ensure the system has not been tampered with or damaged there by preventing proper operation and notification if activated. Any evidence of tampering will be annotated on the system reports (para 2.2.3 Reports).

2.2.2. Fire Suppression Inspection/Certification Residential: Periodic inspection and maintenance of each residential fire suppression system shall be performed (annual) at the frequency stated in Appendix 1. The Contractor shall comply with Guardian 3 (III) Owner's manual model G300-A. During the process, at a minimum, inspect all components, including fire extinguisher unit, appliance nozzles, sensor, distribution assembly, and shutoffs. Replace battery in the central processing unit control board and the "Optional Gas Sonic Shutoff" part # 306-A unit annually from the date of installation. Technicians shall keep the Guardian III system free of cooking grease residue.

2.2.3. Service/Emergency Call: The contractor shall be responsible for providing all parts, labor, and agent needed to keep fire suppression systems in service and certified. A thorough examination of the fire suppression system should be provided upon a service call from the installation. Service calls are intended to give maximum assurance that an extinguishing system will operate effectively and safely and maintenance must be done IAW NFPA 17A and Guardian 3 (III) Owner's Manual publications. The Contractor must respond to emergency calls, from CES, within 2 hours of request. Billable emergency service hours will be accrued from the time the contractor arrives at the facility until work is completed. If repairs should be necessary beyond normal inspection, maintenance service and/or emergency repairs for the kitchen hood fire suppression systems, the Contractor shall submit the description of work and pricing to the CO for review and approval before repairs are accomplished under Additional InScope Work contract line item number (CLIN). Material, labor, meals, lodging, travel, or transportation of materials and personnel is to be included in pricing. Recharging is considered part of a service/emergency call and shall be done in accordance with NFPA 17 A, (section 7.4 Recharging) for commercial kitchens or Guardian 3 Owner's Manual for residential kitchens.

2.2.4. Additional In-Scope Work: At the request of the Government, the Contractor shall provide cost estimates to repair additional items not included in contract, such as but not limited

to 12-Year Hydrostatic Test/Certification or replacing a fire suppression system. Funding this CLIN is optional until the Government decides there is a need. No work shall start until a bilateral contract modification has been issued. The Government reserves the right to negotiate costs. The estimated labor, materials, supplies, and parts shall be provided to the COR and CO in the form of an itemized quote. Cost Estimates (additional work quotes) shall be provided to the Government upon request within five business days. The Government reserves the right to utilize its own stock or supply chain to procure material and/or Government labor and/or outsourced labor. Upon approval of the cost by the CO via a contract modification, the contractor shall make repairs. Additional work shall be completed within 15 days of issuance of contract modification. The only exception shall be when proof of extended delivery lead-time is provided to and accepted by the Government.

2.2.5. Certificates: All maintenance, inspection, and testing procedures shall be documented on certificate of maintenance and inspection. Separate Certificates of Inspection for each fire suppression system shall be provided, to include building number, system number, details of inspection, date of inspection, and signature of the inspector. These certificates will be provided to the contract administrator/contracting officer (CA/CO), 509 CES, and facility manager upon completion of the inspection.

2.2.6. Reports: Following each maintenance/service call, the contractor shall submit a report of their findings with all required information IAW NFPA 96 and NFPA 17A. The Contractor shall submit a report for each fire suppression system receiving maintenance or inspection to be provided to 509 CES and CA/CO electronically within 7 days after servicing. The report shall include building number, room number, system number, manufacturer serial number, signature of inspector and date of inspection or maintenance and for 12-year inspection, the date performed and date due of each facility. The condition of each fire suppression system shall be identified using one of the following four designations and include details/argument for the choice:

- Operational – Fully functional.
- Impaired – May not function as intended.
- Marginal – Will not operate without some manual action not normally required.
- Compromised– Will not function.

2.2.7. Unserviceable Equipment and Materials and Clean-up: For fire suppression system cylinders that are determined to be unserviceable, a written notice shall be given to CES explaining its unserviceability. The fire suppression system shall not be out of service for maintenance and repair for more than five hours. Unserviceable fire extinguishing system cylinders and any disposable materials shall become the property of the contractor and disposed of in a legal manner. Any clean up and disposal of fire suppression water and/or agents from actual fires and false activation during the course of the contract (other than during inspections or service/ emergency repairs) shall be accomplished by the Government. All debris and rubbish not specified to become Government property resulting from the inspection and testing of the fire systems shall be disposed of by the contractor off Government property. Disposal will be in compliance with all applicable Federal, state and local hauling and disposal.

2.2.8. Site Conditions: Facilities will be occupied during the performance of inspection and testing of fire suppression systems. Contractor is responsible for returning the site to the condition it was prior to start of inspection and maintenance. This includes cleaning the area and disposing of waste products off base and IAW all local, state, and federal environmental regulations.

2.2.9. Safety Requirements: While on Whiteman Air Force Base, all contractor personnel shall comply with applicable safety requirements of the Occupational Safety and Health Act (OSHA). All replacement parts and materials for the fire suppression systems shall have parts specifically designed for that system, as recommended by the manufacturer. If any circuits need to be turned off during inspections/servicing, the contractors shall coordinate with the Facility Manager/Building Representative prior to work being started.

2.2.10. Warranty: The contractor shall provide the Government with a one-year warranty on workmanship or parts related to work covered under section 2.2.1 through 2.2.4 of this Statement of Work.

2.3. Technical Exhibit

2.3.1. TECHNICAL EXHIBIT 1: Estimated Workload Data

This information is provided for historical background only. It is not a guarantee of workload quantities.

Item	Name	Estimated Quantity
1	Number of kitchen fire suppression systems to receive recurring/ periodic maintenance, service, testing and certification inspections	24
2	Frequency of Certification Inspections	Annual & Bi- annual
3	Frequency of Service/Emergency Calls	Quarterly
4	Additional In-Scope Work	Monthly

3. Service Summary (SS)/ Quality Assurance(QA)

This SS includes performance objectives the Government will use to determine contractor performance and will compare contractor performance to the Acceptable Quality Level (AQL).

SS	PWS Reference / Performance Objective	Performance Standard	Surveillance Method
1	2.1.2 Employee/Technician Certification	Submitted NLT 5 business days prior to technician performing service	100% inspection
2	2.1.1 Contract Manager	Submitted NLT 15 days after contract award Submitted NLT 15 days after beginning of option year -update upon personnel change	100% inspection
3	2.1.4 Service Coordination 2.1.5 Government Escort	Submitted NLT 10 business days prior to start of service	100% inspection
4	2.1.6 Contractor IDs	Employees shall be easily identified as “Contractor”	100% inspection
5	2.1.3 Service Compliance 2.2.5 Certificates	Separate certificate of inspection for each system to be posted and/or provided to applicable parties NLT 7 days after service	100% inspection
6	2.1.8 Invoicing	Invoice submitted within 7 business days of service completion	100% inspection
7	2.2.6 Reports	NLT 7 days after servicing required report must be submitted to 509 CES & CA/CO	100% inspection
8	3.1.2 Quality Control Plan (QCP)	NLT 15 th day after award & 15 th day after option year starts	100% inspection

3.1. Quality Control/ Quality Assurance

3.1.1. Post Award Conference / Periodic Progress Meetings: The Contractor agrees to attend any post award conference convened by the contracting activity or contract administration office in accordance with Federal Acquisition Regulation Subpart 42.5. The Contracting Officer (CO), Contracting Officer's Representative (COR), Contracting Officer's Technical Representative (COTR), and other Government personnel, as appropriate, may meet periodically with the contractor to review the contractor's performance. At these meetings, the contracting officer will apprise the contractor of how the Government views the contractor's performance and the contractor will apprise the Government of problems, if any, being experienced. Appropriate action shall be taken to resolve outstanding issues. These meetings shall be at no additional cost to the government. Meetings may be held in person, by conference call, or by email.

3.1.2. Quality Control (QC): The contractor shall develop and maintain an effective Quality Control Plan (QCP) to ensure services are performed in accordance with this PWS. The contractor shall develop and implement procedures to identify, prevent, and ensure non- recurrence of defective services. The contractor's QCP is the means by which it assures itself that its work complies with the requirements of the contract. As a minimum, the contractor shall develop QC procedures that address the areas identified in Technical Exhibit 2, Service Summary (SS). A final QCP shall be submitted to the CO NLT 15 days after contract award. After acceptance of the QCP, the contractor shall obtain the CO's acceptance in writing of any proposed changes to its QCP. The QCP shall be reviewed annually and an updated plan provided to the CO NLT 15 days after option exercise. CO acceptance will be in writing and include proposed changes.

3.1.3. Quality Assurance:

3.1.4. COR/COTR Surveillance with QASP: The Government will evaluate the contractor's performance under this contract in accordance with the Quality Assurance Surveillance Plan (QASP). This plan is primarily focused on what the Government will do to ensure that the contractor has performed in accordance with the

performance standards. It defines how the performance standards will be applied, the frequency of surveillance, and acceptable quality level(s) or defect rate(s). The COR and/or COTR is the primary contact for surveillance and contract performance. The COR and/or COTR does not have the authority to make any contract changes or authorize additional work.

- 3.1.5. Customer Complaints:** All valid customer complaints shall require services to be re- performed, if applicable, as soon as possible after notification, but prior to the next service period. Re-performance however does not eliminate the customer complaint and it still applies against the contractor's performance threshold. If the contractor challenges the validity of the complaint and the COR and contractor cannot come to agreement, the customer complaint will be forwarded to the CO for resolution. Customer complaints will be tracked and if the performance threshold is exceeded, action will be taken by the CO IAW the applicable inspection/acceptance clause.

Appendix 1: Kitchen Fire Control Systems Building Location and Details of Service

Facility Name	# of Systems	Bldg.#	Annual (Mar)	Semi Annual (Sept)
Commercial				
In-Flight Kitchen	3	34	x	x
Bowling Center	1	541	x	x
DFAC	4	1553	x	x
Club	1	3008	x	x
Youth Center	1	3019	x	x
CDC	1	3021	x	x
Golf Course	1	3077	x	x
Residential				
Dorm Enterprise	2	1551	x	
Dorm Atlantis	2	1552	x	
Dorm Columbia	2	1556	x	
Dorm Endeavor	2	1559	x	
Dorm Challenger	2	1560	x	
Dorms Discovery	2	1561	x	
	24			