

Statement of Work
for
80-Ton Rough Terrian Crane
at the
704th Test Group, Detachment 1

28 January 2026

1.0 PURPOSE

The 704th Test Group, Detachment 1 (704 TG, Det 1), National Radar Cross Section Test Facility (NRTF), mission is conducted on the Radar Target Scatter (RATSCAT) Advanced Measurement System (RAMS) site approximately 50 miles from Holloman AFB. The NRTF has an Operations and Maintenance contract that includes building, ground and utility maintenance. These contractors also support daily testing requiring frequent moving and flipping of large test targets with the assistance of the assigned crane. This crane is used on a regular basis to load/unload trucks, mount targets for test and flips, dismount targets quickly during weather emergencies as well as move targets safely. Due to the remote location of the RAMS site and frequency of use of the crane, this crane must be available on site and cannot be rented or borrowed. NRTF is seeking to purchase this used crane, serial #236124, to fill an open authorization and save over \$1M dollars over buying new.

2.0 SCOPE

The Contractor shall deliver an 80-ton crane that meets the following requirements:

2.1. Physical requirements:

- 2.1.1. 80-Ton lift capacity
 - 2.1.1.1. 360 degree rotating planetary swing, with multi disc brakes and hydraulic swing parking brake
 - 2.1.1.2. 40-to-135-foot boom length
 - 2.1.1.3. One double-acting hydraulic cylinder (-3° to 80°) with integral holding valve
 - 2.1.1.4. Heated and cooled cab with skylight and cab mounted work lights
 - 2.1.1.5. One-piece 22,000 lb. hydraulically installed and removed
 - 2.1.1.6. 4-wheel drive, 4 -wheel / 4-mode steering
 - 2.1.1.7. Grooved drum main hoist, infinitely variable speed power up and down with automatic multi-disc brake, electronic hoist rotation indicator and hoist mirror. 3rd wrap indicator standard with standard wire rope
 - 2.1.1.8. Minimum 700 ft. of 3/4 in. diameter 35 x 7 class (rotation resistant) installed on main hoist
 - 2.1.1.9. Water cooled diesel engine with 3 forward and 3 reverse speeds x 2 ranges (3 HI/ 3LO)
 - 2.1.1.10. Full lighting package includes turn indicators, headlights, taillights, brake lights, 4-way hazard lights, and cab mounted work lights
 - 2.1.1.11. Multiple outriggers with position monitoring system
 - 2.1.1.12. Dual line full hydraulic braking system with front axle mounted spring applied parking brake

2.2. Safety and regulatory requirements:

- 2.2.1. Installed Fire extinguisher
- 2.2.2. Single, swivel hook with safety latch
- 2.2.3. Back up alarm
- 2.2.4. Dual rear view mirrors
- 2.2.5. Front Storage well

3.0 MILESTONES

The contractor shall complete the contract acquisition within 60 days after receipt of order (ARO).

4.0 CONTACT INFORMATION

Shane Eastman (575) 572-1045 or Jason Hutchinson (575) 572-1008. Any electronic paperwork is to be sent to email address shane.eastman.2@us.af.mil and jason.hutchinson.5.ctr@us.af.mil