

Multi-Stage Liquid Oxygen (LOX) Pressure Control Valves Statement of Work (SOW)

1. Overview

This Statement of Work outlines the general expectations for the procurement of multi-stage Liquid Oxygen (LOX) Pressure Control Valves. The accompanying spreadsheet provides all technical requirements, valve configurations, materials, and performance details. The technical data sheet takes precedent over this SOW in the event of a conflict.

2. Supplier Responsibilities

The supplier shall review the provided data sheet and deliver valves that fully meet the specifications. The supplier is responsible for fabrication, assembly, LOX cleaning, functional testing, packaging, and providing all supporting documentation.

3. Cleaning and Testing

Valves shall be cleaned for LOX service and undergo all standard factory testing appropriate for cryogenic pressure-control valves. Test results and cleanliness certification shall be included with delivery.

4. Documentation

The supplier shall provide drawings, test reports, material certifications, cleaning certificates, and any special tools or soft-goods kits required for maintenance.

5. Delivery Requirements

Valves shall be delivered fully assembled, cleaned, bagged, and ready for installation. All supporting documentation must accompany the shipment.

6. Acceptance

Acceptance will occur upon verification that the delivered valves match the technical data sheet, meet cleanliness and testing requirements, and include all required documentation.