

GROUND MAINTENANCE SERVICES
PERFORMANCE WORK STATEMENT (PWS)

Wiesbaden, Germany

21. July 2025

Table of Contents

1.0	General.....	1
1.1	Description of Services/Introduction.	1
1.2	Background.....	1
1.3	Objectives.	1
1.4	Scope.....	2
1.4.1	Quality Control Plan (QCP):.....	2
1.5	Period of Performance (PoP).....	3
1.6	Traffic Flow.	3
1.7	Restoration of Real Property Damage.	3
1.8	General Information.	3
1.8.1	Scope.	4
1.8.2	Place of Performance	4
1.8.3	Recognized Holidays.....	4
1.8.4	Hours of Operation.	4
1.8.5	Installation Closures.	5
1.8.6	Emergency Delays.	5
1.8.7	Unforeseen Closures of Service Areas.	5
1.8.8	Place of Performance.	5
1.8.9	Type of Contract.	5
1.8.10	Security Requirements	5
1.8.11	Access and General Protection/Security Policy and Procedures.	5
1.8.11.1	Installation Access.....	6
1.8.11.2	Background Checks	7
1.8.11.3	Local Nationals and Third Country Nationals.....	7
1.8.12	Physical Security.	7
1.8.13	Security Training.....	7

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

1.8.14 Anti-Terrorism (AT) Level I Training.	7
1.8.15 iWATCH Training.....	8
1.8.16 Operational Security (OPSEC) Awareness Training.	8
1.8.17 Threat Awareness and Reporting Program Training.	8
1.8.18 Local Health Protection Conditions	8
1.8.19 Key Control.....	9
1.8.20 Lost Keys.....	9
1.8.21 Prohibited use of Government provided keys or key cards.	9
1.8.22 Lock Combinations. N/A.....	9
1.8.23 Post Award Conference/Periodic Progress Meetings.....	9
1.9 Government Roles and Responsibilities	10
1.9.1 Contracting Officer (KO).	10
1.9.2 Contracting Officer's Representative (COR).	10
1.9.3 COR Authority.	11
1.9.4 COR or Designated Government Representative Functions.....	11
1.10 Specific Contractor Requirements, Roles and Responsibilities.	11
1.10.1 U.S. Residency. N/A.....	11
1.10.2 Contractor Hiring Restrictions.....	11
1.10.2.1 Authorization to Perform Services in Germany.	11
1.10.3 Contractor Identification.....	12
1.10.4 Standards of Conduct.....	12
1.10.5 Contractor Key Personnel.	13
1.10.5.1 Other Key Control Personnel required	13
1.10.6 Project Manager (PM).	13
1.10.7 Quality Control Manager (QCM).....	14
1.10.8 Quality Control Inspectors (QCI).	14
1.10.9 Phase In /Phase Out Period. N/A.....	14
1.11 Emergency Services.....	14
1.11.1 Emergency Medical Treatment.....	14
1.11.2 Accident Reporting.	15
1.12 Environment and OSHA.	15
1.12.1 Safety.	15
1.12.2 Safety Plan.	16
1.12.3 Spill Plan.....	16
1.12.4 Asbestos Awareness. N/A.....	16
1.13 Environmental Compliance.....	16

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

1.13.1 Safety Data Sheets.....	16
2.0 Definitions and Acronyms.....	18
2.1 Definitions.....	18
2.2 ACRONYMS.....	21
3.0 Government Furnished Property, Equipment and Services.....	23
3.1 Property. The Government will not furnish any office space for the Contractor under this contract.....	23
3.2 Equipment. The Government will not provide any equipment under this contract.	23
3.3 Services. The Government will not provide any services under this contract.....	23
3.4 Utilities.....	23
3.5 Materials. The Government will not provide any materials under this contract.....	23
4.0 Contractor Furnished Items and Services.....	24
4.1 General.....	24
4.1.1 Classified Controlled Facility Clearance. N/A	24
4.2 Materials.....	24
4.3 Equipment.....	24
4.4 Unserviceable Contractor Equipment.....	24
5.0 Specific Tasks for Grounds Maintenance.....	25
5.1 General.....	25
5.2 Description of Services.....	25
5.2.1 Scope.....	26
5.2.2	27
5.2.3	27
5.2.4 Edging.....	28
5.2.5 Trimming.....	Error! Bookmark not defined.
5.2.6 Fertilizing and Liming.....	29
5.2.7 Seeding and Sodding.....	29
5.2.8 Hydroseeding.....	29
5.2.9 Sodding.....	29
5.2.10 Aerating and Overseeding.....	29
5.2.11 Maintain Flower Beds.....	29
5.2.12 Weed Control.....	29
5.2.13 Remove Debris, Leaves, and Litter.....	30
5.2.14 Service/Maintain Trees.....	32
5.2.15 Perform Mechanical Tree Spading and Transplanting.....	33
5.2.16 Tree Mulching. N/A	33

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work
Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

5.2.17 Trees Service/Maintenance and Safety.....	33
5.2.18 Tree Pruning.....	34
5.2.19 Tree Inspection Removal and Replacement.	34
5.2.20 Emergency Tree Removal.....	37
5.2.21 Reforestation.	37
5.2.22 Hedge and Shrub Maintenance. N/A.....	37
5.2.23 Hedge and Shrub Mulching.....	37
5.2.24 Hedge and Shrub Fertilization.....	37
5.2.25 Hedge and Shrub Pruning.....	37
5.2.26 Irrigation / Watering.....	38
5.2.27 Operation of Irrigation Systems.....	39
5.2.28 Maintenance of Irrigation Systems.....	39
5.2.29 Service/Maintain Xeriscape Areas.....	39
5.2.30 Athletic Fields Grounds Maintenance.....	39
5.2.31 Special Services.....	39
5.2.32 Special Event Services.....	40
5.2.33 Service Common Areas.....	40
5.2.34 Service Fire Breaks and Ranges.....	40
5.2.35 Service Unimproved Areas.....	40
5.2.36 40	
5.3 Other Special Services. N/A.....	41
5.3.1 Refuge and Nature Trail Maintenance.....	41
5.3.2 Special Equipment Requirements.....	41
6.0 Applicable Publications (Current Editions).....	42
6.1 Regulations, Publications, Manuals, Local Policies and Procedures.....	42
7.0 Mandatory Records and Report Forms.....	45
8.0 Attachment/Technical Exhibits (TEs).....	46
8.1 Attachment 1/TE-1 – Performance Requirements Summary.....	47
8.2 Attachment 2/TE-2 – Deliverables Schedule.....	48

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

1.0 General.

This is a non-personal services contract to provide Grounds maintenance Services for the U.S. Army Garrison (USAG) Wiesbaden Germany. The Government will not exercise any supervision or control over the contract service providers.

- The Contractor shall perform to the standards specified in this Performance Work Statement (PWS).
- Contract service providers shall be accountable solely to the Contractor who, in turn is responsible to the Government.
- The Contractor shall provide all personnel, equipment, supplies, facilities, transportation, tools, materials, supervision, and other items and non-personal services necessary to complete the requirements as outlined and defined in this PWS.

1.1 Description of Services/Introduction.

The Contractor shall provide all personnel, equipment, supplies, facilities, transportation, tools, materials, supervision, and other items and non-personal services necessary to perform all grounds maintenance service tasks and frequencies as described and defined in this Performance Work Statement (PWS), Part 5 Specific Tasks and Part 8 Attachment 1 Performance Requirements Summary, except for those items specified as Government furnished property and services (If applicable, see Part 4 Contractor Furnished Items and Services). The Contractor shall perform to the standards in this contract.

1.2 Background.

(USAG) Wiesbaden is located in Hessen, Germany, consists of approximately 12 Sites within Wiesbaden and Mainz. The population base consists of approximately 10,000 military and Government civilian and Contractor personnel, as well as 13,540 resident family members.

1.3 Objectives.

The Contractor shall ensure all work accomplished as fulfillment of this PWS meets all applicable Federal, State, and local laws, regulations, directives and other requirements (LOR) (See Definitions & Acronyms, 2.2 Acronyms --- Legal and Other Requirements) to include, but not limited to the documents in Part 6 Applicable Publications.

Attachment 10 – Exhibit A AFH, and Exhibit B OMA Area (and related Tree Assessments) identifies for USAG Wiesbaden, which areas belong to each ground type, the square footage of the grounds/areas, any special security considerations, and any constraints as to when during the day or week scheduled services can be performed to the grounds/area.

- Improved Grounds
- Semi-Improved Grounds
- Un-Improved Grounds

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

Attachment 3 – Work Capability Levels Enterprise Municipal points out the Grounds Maintenance Services Performance Standards and Frequencies identifies tasks and frequencies for minimum standards for each type of area.

1.4 Scope.

The Contractor shall inspect, service, maintain, and landscape grounds of USAG Wiesbaden. The contractor shall provide Grounds Maintenance for all High Visibility (Improved Grounds), Common Areas (Semi-Improved Grounds), Fire Breaks and Ranges, as well as Un-improved Grounds. The work shall include scheduling and performance of mowing and trimming; turf replacement; leaf and debris removal; Tree assessment, tree, hedge, and shrub planting, maintenance, irrigation, and fertilization; policing of areas; fence line clearing, removing fallen leaves, weed control, trash pick-up and removal at playgrounds and barbecue areas, disposal of debris, and cleaning of paved areas tree and stump removal. The Contractor shall provide all labor, materials, equipment, supervision and management for all work necessary to maintain the grounds to the standards specified herein. The Contractor shall provide for tree preservation and protection during all maintenance and construction activities as specified by the USAG Wiesbaden Grounds Maintenance and Tree Assessment Services Performance Work Statement.

1.4.1 Quality Control Plan (QCP):

The Contractor shall develop and maintain a QCP to ensure services are performed in accordance with (IAW) this PWS. The Contractor shall develop and implement procedures to identify, prevent, and ensure non-recurrence of defective services. The Contractor's QCP shows how the contractor assures that the work provided complies with the requirements of the contract.

The Contractor's proposed QCP shall be submitted to the Contracting Officer Representative (COR) for review within 10 business days after date of contract award (Deliverable 1).

The COR will review and either notify the Contractor in writing of acceptance of the plan or return their comments to the Contractor within 10 business days. If the Government provides comments, the Contractor shall resubmit a final QCP to the COR within five (5) business days. After receiving the final QCP, the Contractor will receive the COR's acceptance in writing. Any proposed changes to the accepted QCP shall be resubmitted to the COR for acceptance no later than 30 business days prior to the anticipated change and before implementation by the Contractor. The timeline above shall apply for review and acceptance of proposed changes. At a minimum, the QCP must include and answer the following to be acceptable:

- a. A chart showing the organizational structure and lines of authority, the names, qualifications, duties, responsibilities, and classification of each member of the Contractor's Quality Control Team.
- b. How the Contractor will monitor work to ensure that performance complies with all deliverables (etc. timelines, deadlines, and goals).

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

- c. How the Contractor will monitor work to ensure that performance complies with all specifications and requirements of the contract, including clauses?
- d. How the Contractor will monitor and ensure staff qualifications remain current and valid throughout contract performance?
- e. Analysis of quality control and timeliness reports shall be sent to the COR.
- f. How the Contractor will identify, investigate, and correct any non-conforming performance and prevent similar deficiencies in the future?
- g. How the Contractor will file and save all Quality Control related documents for the life of the contract plus 5 years?

The Contractor shall inform the COR of issues or potential issues that might affect the performance within two (2) hours of identifying those issues. All reports regarding these potential issues shall be followed by written reports within two (2) business days (Deliverable 2).

The Contractor shall create a weekly Work Plan and send it to the COR within five (5) days of contract award (Deliverable 3).

1.5 Period of Performance (PoP).

The period of performance shall be for 5-year ordering period. The Period of Performance reads as follows:

OY 01	06.01.2026 – 05.31.2027
OY 02	06.01.2027 -- 05.31.2028
OY 03	06.01.2028 -- 05.31.2029
OY 04	06.01.2029 -- 05.31.2030
OY 05	06.01.2030 -- 05.31.2031

1.6 Traffic Flow.

The Contractor shall maintain the free flow of vehicle and pedestrian traffic while conducting grounds maintenance service tasks.

1.7 Restoration of Real Property Damage.

Any damage to Government Real Property by the Contractor's operations shall be restored to the original state at no additional cost to the Government (e.g., structural damage, damage to landscape or fencing, et al).

1.8 General Information.

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

1.8.1 Scope.

Previously mentioned on paragraph 1.4.

1.8.2 Place of Performance

The work to be performed under this contract will be performed at Army Family Housing (AFH) and Operation and Maintenance Army (OMA) areas within the United States Army Garrison (USAG) Wiesbaden. The Contractor shall provide the KO/COR with a Work plan / schedule no later than (10) business days prior to commencing work (Deliverable 3). Schedule shall outline tasks to be performed by specific building and identify the timeline for the task to be accomplished. The KO will provide the Contractor with requirements to make changes to the schedule as they occur. A map of the locations can be found in Part 8 and Attachments 4 to 10.

1.8.3 Recognized Holidays.

U.S. Federal Holidays

New Year's Day	Labor Day
Martin Luther King Jr.'s Birthday	Columbus Day
President's Day	Veteran's Day
Memorial Day	Thanksgiving Day
Independence Day	Christmas Day
Juneteenth	

Host Nation Holidays

New Year's Day	01 January
Good Friday	varies yearly
Easter Monday	varies yearly
Labor Day	01 May
Ascension Day	varies yearly
Whit Monday	varies yearly
Corpus Christi	varies yearly
Day of German Unity	03 October
1st Christmas Day	25 December
2nd Christmas Day	26 December

1.8.4 Hours of Operation.

Normal hours of operation are between the hours of 0715 to 1600, Monday through Friday, excluding Federal holidays or when the Government facilities are closed due to local or national emergencies, administrative closings, or similar Government directed facility closings.

- The Contractor shall coordinate with COR to establish a schedule to conduct business if services are required outside of normal hours of operation.

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

- The Contractor shall maintain an adequate workforce for the uninterrupted performance of all tasks defined within this PWS when Government facilities are not closed for the above reasons.

1.8.5 Installation Closures.

When an unforeseen installation closure occurs on a regularly scheduled day of work, the Contractor shall reschedule the work to be performed the following day unless the following day is a Saturday, Sunday, a recognized Federal holiday, and when routine work is not scheduled for that day; or reschedule the work for the next business day following the closure.

1.8.6 Emergency Delays.

If the Contractor determines unsafe weather conditions or work environment is cause for an interruption of services, the Contractor shall notify the COR (2) hours prior to curtailing operations. The Contractor shall obtain COR approval to resume operations. The Contractor shall coordinate with the DPW designated representative(s) in preparation for and during emergency operations situations such as inclement weather, flood, active shooter, fire or other emergency situations.

1.8.7 Unforeseen Closures of Service Areas.

When an unforeseen closure occurs on a regularly scheduled day of work (i.e., severe weather, training holiday, day of mourning, etc.).

- The Contractor shall reschedule the service on any day satisfactory to the customer and minimizes impact on the Contractor's normal work schedule.

1.8.8 Place of Performance.

Previously mentioned in paragraph 1.8.2.

1.8.9 Type of Contract.

The government intends to award a FIRM FIXED PRICE (FFP) single award IDIQ Contract.

1.8.10 Security Requirements. N/A

1.8.11 Access and General Protection/Security Policy and Procedures.

Contractor and all associated subcontractors' employees shall provide all information required for background checks to meet installation access requirements to be accomplished by installation Provost Marshal Office, Director of Emergency Services or Security Office. Contractor workforce must comply with all personal identity verification requirements (i.e., FAR clause 52.204-9, Personal Identity Verification of Contractor Personnel) as directed by DOD, HQDA and/or local policy. In addition to the changes otherwise authorized by the changes clause of this contract, should the Force Protection

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) **(ISR 404 – Grounds Maintenance Services)**

Condition (FPCON) at any individual facility or installation change, the Government may require changes in contractor security matters or processes.

1.8.11.1 Installation Access

Access to U.S. installations and controlled areas is limited to personnel who meet security criteria and are authorized by Host Nation law to work in that country. Failure to submit required information or data and obtain required documentation or clearances in accordance with Army in Europe (AE) Regulation 190-16 Installation Access Control or AE Regulation 604-1 Local National Screening Program for Germany specific contracts, will be grounds for denying access to U.S. installations and controlled areas. The Contractor shall ensure that any subcontractor used in performance of this contract complies with these requirements and that all employees, of both the Contractor and any subcontractor utilized by the Contractor, are made aware of and comply with these requirements. Should anything in this paragraph conflict with AE Reg 190-16 or AE Reg 604-1, the regulation takes precedent.

The Government is not liable for any costs associated with performance delays due solely to a firm's failure to comply with Installation Access Control System (IACS) processing requirements.

AE Reg 190-16 (and AE 190-16-G German translation) can be found on the following website: <https://www.aepubs.eur.army.mil/AE-Regulations/>.

In addition, the Contractor shall provide the COR with an installation pass log within Ten (10) business days after contract award (Deliverable 4). The log shall, at a minimum, contain the following information: Police good conduct certificate (Fuehrungszeugnis) not older than one (1) year and copies of passport (Deliverable 5). The log shall be updated as employees are added or removed and submitted to the COR within five (5) days after any changes to the log (Deliverable 4.1). The updated installation pass log shall be current and available at any time upon request by the Government.

Upon the termination of employment, the Contractor shall collect the installation access passes the same day employment of an individual has expired or been terminated and return them to the issuing office within 10 business days (Deliverable 4.2).

Upon termination or cancellation of this contract, the Contractor shall collect all outstanding installation access passes and return them to the issuing office within 30 business days of termination or cancellation of this contract. (Deliverable 4.3).

Below is the responsible Organizational Sponsor & Installation Access Control Office for this contract:

Organizational Sponsor:
Location: Clay Kaserne
DSN Phone No: 548-4063

USAG Wiesbaden, Clay Kaserne
Building No: 1057
Commercial Phone No: 0611-143 548 4063

Installation Access Control Office:
Location: Clay Kaserne

Building No: 1062

DSN Phone No: 548-7080/1/2/3
7080/1/2/3

Commercial Phone No: 0611-143 548

1.8.11.2 Background Checks

AE Regulation 604-1 provides guidance pertaining to background checks for U.S. and Host Nation Contractors. The Contractor shall provide all information required for background checks to meet installation access requirements to be accomplished by the installation Provost Marshal Office, Director of Emergency Services, or Security Office, and residence permits for local national installation passes and access rosters. The Contractor workforce shall comply with all personal identity verification requirements as directed by DoD, HQDA, and local policy. The Contractor may have to complete additional security training to comply with the security standards of this contract. In addition to the changes otherwise authorized by the changes clause of this contract, should the Force Protection Condition (FPCON) at any individual facility or installation change, the Government may require changes in Contractor security matters or processes.

1.8.11.3 Local Nationals and Third Country Nationals

See Paragraph 1.8.11.1 for requirements.

1.8.12 Physical Security.

At the close of each work period, the contractor shall ensure government facilities, equipment, and materials are secured.

1.8.13 Security Training.

In the event of a National Defense Emergency affecting USAG Wiesbaden, the USAG Wiesbaden COR will immediately notify the contract POC. At that time, the contractor shall take immediate steps to cease all activities on the installation(s) and will cause all personnel to leave the installation(s) property until notice is given by the installation and USAG Wiesbaden POC that National Defense Emergency conditions are no longer in effect.

1.8.14 Anti-Terrorism (AT) Level I Training.

IAW Department of Defense Instruction (DoDI) 2000.16, Vol. 1 DoD Antiterrorism Standards and Army Regulation (AR) 525-13 Antiterrorism, all Contractor employees, including subcontractor employees, requiring access to Army installations, facilities, or controlled access areas shall complete Antiterrorism (AT) Level I awareness training within 30 calendar days after contract start date. The Contractor shall submit certificates of completion for each affected contract employee and subcontractor employee to the KO or COR within 30 calendar days after completion of training by all employees and subcontractor personnel on a recurring annual basis. AT Level I awareness training is available at the following site: <http://ko.jten.mil> (See Deliverables Schedule, Deliverable 6).

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

If access to a computer is not available, the Government will provide AT Level I training for Contractor employees within 30 business days after contract starts and maintain a copy of the attendance roster for one (1) year. Any Contractor hired after contract start will be required to receive AT Level I training within 30 calendar days either online or as provided by the Government. The Contractor must present the training certificate to the KO or designated Government representative/COR within 30 calendar days (Deliverable 6).

1.8.15 iWATCH Training.

The Contractor shall brief the local iWATCH program (training standards provided by the Installation Anti-Terrorism Officer (ATO)) to all its' employees and associated subcontractors. This training is used to inform employees of the types of behavior to watch for and instruct employees to report suspicious activities to USAG Wiesbaden, Military Police and the COR. The Contractor shall complete the training within 30 calendar days after contract award and within 30 calendar days of new employees commencing performance and send to the KO or designated Government representative/COR via both electronic and paper copy within 30 calendar days of completion (Deliverable 7).

1.8.16 Operational Security (OPSEC) Awareness Training.

For contracts that require OPSEC Training. All contractor employees, including subcontractor's employees, requiring access to Army installation, facilities, controlled, access areas, and/or installation computers shall complete OPSEC Level I training within 30 days after contract start date or effective date of incorporation of this requirement into the contract.

OPSEC Level I training is available at

<http://www.cdse.edu/catalog/elearning/GS130.html>. Contractor personnel must complete refresher training every 12 months. Verification of the training shall be provided to the COR within ten (10) business days after completion of the training by all employees and subcontractor personnel (Deliverable 8)

1.8.17 Threat Awareness and Reporting Program Training.

For all DA contractors. Training will be completed within 30 days of assignment or employment to an organization and will undergo live environment TARP training respective Counterintelligence Awareness and Reporting (CIAR) training will be completed annually, IAW AR 381-12 Threat Awareness and Reporting Program. The Contractor shall provide either certificates of completion or dates of attendance at the Clay Kaserne Wiesbaden, for each affected contractor employee and subcontractor employee to the COR, or to the KO if a COR is not assigned, with 15 calendar days after completion of training by all employees and subcontractor personnel (Deliverable 9).

1.8.18 Local Health Protection Conditions

Contractors will comply with all national and DoD policies regarding health protection issues including pandemic outbreaks. Local Health Protection Conditions (HPCON) change based on risk levels in the surrounding area USAG Wiesbaden and in

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) **(ISR 404 – Grounds Maintenance Services)**

cooperation with local, state and national guidance. The Contractor shall comply with installation and higher headquarters policies aimed at mitigating the spread of dangerous communicable diseases.

1.8.19 Key Control.

The Contractor shall establish and implement methods of making sure all keys/key cards issued to the Contractor by the Government are not lost or misplaced and are not used by unauthorized persons. NOTE: All references for keys include key cards.

- No keys issued to the Contractor by the Government shall be duplicated.
- The Contractor shall develop procedures covering key control that shall be included in the QCP.

Such procedures shall include turn-in of any issued keys by personnel who no longer require access to locked areas.

1.8.20 Lost Keys.

The Contractor shall immediately report any occurrences of lost keys/key cards to the KO in the event keys, other than master keys are lost or duplicated.

In the event a key is lost, the Contractor shall, upon direction of the KO, have the Government re-key or replace the affected lock or locks.

When the replacement of locks or re-keying is performed by the Government, the total cost of re-keying or the replacement of the lock or locks shall be deducted from the monthly payment due the Contractor.

In the event a master key is lost, all locks and keys for that system shall be replaced by the Government and the total cost deducted from the monthly payment due to the Contractor.

1.8.21 Prohibited use of Government provided keys or key cards.

The Contractor shall prohibit the use of Government issued keys/key cards by any persons other than the Contractor's employees.

No keys issued to the Contractor by the Government shall be duplicated.

The Contractor shall prohibit the opening of locked areas by Contractor employees to permit entrance of people other than Contractor employees engaged in the performance of assigned work in those areas, or personnel authorized entrance by the KO.

1.8.22 Lock Combinations. N/A

1.8.23 Post Award Conference/Periodic Progress Meetings.

The Contractor shall attend the post award conference convened by the Contracting Activity or Contract Administration Office as agreed upon and stated in the contract award document.

The Contractor shall attend, participate in, and furnish input to scheduled and unscheduled meetings, conferences, and briefings that relate to the functions and services herein as required by the Government to provide effective communication and

impart necessary information. The Contract Manager or designated representative shall attend meetings as requested by the Government. Meeting attendees shall at times include Contractor managerial, supervisory, and other personnel knowledgeable of the subject matter. Meetings may start or end outside of regular duty hours. When the KO, COR and DPW management meet with the Contractor to review the Contractor's performance, written minutes of meetings will be recorded by the Government and signed by the Requirements Authority (RA) and the KO.

The written minutes will be written by the COR during the meeting and afterwards distributed. The contractor should sign the minutes' report (Deliverable 21) and send the file within five (5) business days after the meeting. If any party does not concur with any portion of the minutes, the non-concurrence shall be provided in writing to the KO/COR within two (2) business days following receipt of the minutes.

Notwithstanding the Contractor's responsibility for total management during the performance of this contract, the administration of the contract requires maximum coordination and cooperation between the Government and the Contractor.

1.9 Government Roles and Responsibilities.

1.9.1 Contracting Officer (KO).

The KO is the only person authorized to make any changes in any of the requirements listed on this PWS; notwithstanding any provisions contained elsewhere in this contract, said authority remains solely with the KO.

- In the event the Contractor makes any change in the direction of any person other than the KO, the change will be considered to have been made without authority and solely at the risk and expense of the Contractor.
- All contract administration will be affected by the KO.
- Communications pertaining to contractual administrative matters shall be addressed to the KO.
- No changes in or deviations from the terms and conditions shall be affected without a written modification to the contract, executed by the KO authorizing such changes.

1.9.2 Contracting Officer's Representative (COR).

The KO will appoint a COR during the performance of this requirement.

- Additional Government personnel may be designated to assist in contract oversight IAW AR 70-13 Management and Oversight of Service Acquisitions.
- Other surveillance personnel may be designated as COR and shall be trained and appointed IAW DoDI 5000.72, Department of Defense (DoD) Standard for Contracting Officer's Representative (COR) Certification.
- The COR will provide assistance in identification and resolution of problems, conflicts in priority, subtask requirement definitions, and other operations type problems.
- The COR will perform IAW the responsibilities and duties identified in the appointment letter.

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

- The COR will submit deliverable reports on PIEE for KO approval of all deliverables and plans required in this PWS.

1.9.3 COR Authority.

A letter of designation will be issued to the COR by the KO.

- A copy of the letter will be sent to the Contractor.
- The letter of designation states the responsibilities and limitations of the COR, especially regarding changes in cost, price estimates, or changes in delivery dates.
- The COR is not authorized to change any of the terms and conditions regarding cost, quantity, or schedule of the resulting order.

1.9.4 COR or Designated Government Representative Functions.

The COR or designated Government representative shall monitor all technical aspects of the contract and assist in contract administration.

- The COR or designated Government representative is authorized to perform the following functions:
 - assure the Contractor performs the technical requirements of the contract.
 - perform inspections necessary in connection with contract performance.
 - maintain written and oral communications with the Contractor concerning technical aspects of the contract.
 - issue written interpretations of technical requirements.
 - monitor, document, and report Contractor's performance and notify both the KO and Contractor of any deficiencies.
 - coordinate availability of Government-Furnished Property and provide direction or assistance for site entry requests of Contractor personnel.

1.10 Specific Contractor Requirements, Roles and Responsibilities.

1.10.1 U.S. Residency. N/A

1.10.2 Contractor Hiring Restrictions.

The Contractor shall not hire or subcontract with off-duty or former Government employees whose employment would result in a conflict of interest as defined in the most current version of DOD 5500.7-R Joint Ethics Regulation 30 August 1993.

1.10.2.1 Authorization to Perform Services in Germany.

- Contractors performing services in the Federal Republic of Germany (FRG) shall comply with German law. The Contractor shall determine whether performance requires registration with German authorities or authorization to do business in Germany and, if so, shall comply with all requirements. Whether or not registration or authorization to do business is required, the Contractor shall

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) **(ISR 404 – Grounds Maintenance Services)**

determine what documents or authorization its employees and any subcontractor employees must possess to work in Germany. The Contractor shall ensure affirmatively that its employees and subcontractor employees possess such documents or authorizations.

- Contractor employees who: (a) are not nationals of Germany or other European Union countries; (b) are not members of the force, the civilian component, or their dependents; or c) do not have assimilated status under Articles 71, 72, or 73 of the Supplementary Agreement to the NATO SOFA shall possess work and residence permits.
- By acceptance of and performance under this contract, the Contractor affirms that it has complied with the requirements above. Compliance with this requirement and German law is a material contract requirement. Noncompliance by the Contractor or subcontractor at any tier shall be grounds for issuing a negative past performance evaluation and terminating this contract for default.
- The Contractor personnel shall be able to communicate clearly in the English language.

1.10.3 Contractor Identification.

The Contractor shall ensure that personnel can be identified as a Contractor to distinguish themselves (e.g., badge, company logo, or uniform) from Government employees.

- The Contractor shall ensure all correspondence and reports produced are marked as Contractor products or that Contractor participation is disclosed.
- Contractor-owned/leased vehicles and trailers shall be clearly identified.

1.10.4 Standards of Conduct.

Contractor personnel's conduct shall not reflect discredit upon the Government. The Contractor shall ensure all personnel present a professional appearance while working on the Government installation.

- The Contractor's employees shall observe and comply with all local policies and procedures concerning fire, safety, environmental protection, sanitation, security, and possession of firearms or other lethal or illegal weapons or substance.
- The Contractor shall ensure all Contractor employees providing services under this contract conduct themselves and perform services in a professional, safe, and responsible manner.
- The Contractor shall remove any employee for reasons of misconduct or security from the job site.
- The Contractor shall ensure employee conduct complies with 41 USC §423, *Procurement Integrity*.
- The Contractor shall also ensure that no Contractor employees conduct political related activities or events on the installation.
- The removal of such a person shall not relieve the Contractor of the requirement to provide personnel to perform adequate and timely service.

1.10.5 Contractor Key Personnel.

The Project Manager (PM), Quality Control Manager (QCM) and Quality Control Inspector (QCI) are considered Key Personnel for this contract. The contractor shall provide a resume of key personnel, who will be designated in writing, to the KO within 10 days of the contract award (Deliverable 10).

These key personnel shall be available during normal duty hours and shall be able to understand, speak, read, and write the English language.

1.10.5.1 Other Key Control Personnel required

Certified Gardener: at minimum Gärtnergeselle, HWK or LWK plus 2 years of experience for work described under para 5.1. Work which shall be performed only under direct supervision (presence) of a certified Gardener (Gärtnergeselle).

Technical Project Manager and Alternate Project Manager, Tree Assessment: Graduate certificate in the field of Agronomist for Tree Maintenance (Fachagrarwirt Baumflege/Baumsanierung) or European Tree Technician.

Monitor/Inspector: FLL certified tree assessor (FLL zertifizierter Baumkontrolleur) or equal, with a minimum of five years of experience in the recognition of tree damage or symptoms of damage in accordance with FLL tree guideline, assessment of damage according to type and extent and the effect on overall tree health; knowledge of and ability to identify appropriate remedial actions and classify urgency of need. The tree assessor shall provide experience in areas of comparable size and complexity. Comparable size and complexity would be at minimum 2000 mature trees over 50 years of age (planted 1960 and older).

Contractor or Contractor personnel for tree assessment shall be member of trade association as e.g. QBB (Qualitätsgemeinschaft Baumpflege und Baumsanierung e. V.), FLL (Forschungsgesellschaft Landschaftsentwicklung Landschaftsbau), SAG Baumstatik (Sachverständigen Arbeitsgemeinschaft Baumstatik) or comparable organizations. Applicable would be also the RAL Qualification for Tree Maintenance (RAL Baumpflege Fachverband geprüfter Baumpfleger e. V.) to ensure qualification for the tree safety assessment.

NOTE: All information and certificates of his employees shall be provided within 10 days of contract award to the COR (Deliverable 10). When new personnel are employed by the Contractor to perform services on this contract, the Contractor shall submit their names and qualifications to the COR for review prior to performing on this contract. New key personnel shall be introduced to COR during first presence at work location. The qualifications shall match experience and education as described in this PWS.

1.10.6 Project Manager (PM).

The Contractor shall provide a PM and an PM Alternate who is responsible for the performance of the work. At minimum the PM shall have:

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

- Certified Master Gardener (Gärtnermeister HWK, Handwerkskammer,
 - or LWK, Landwirtschaftskammer (Chamber of Crafts, or Chamber of Skilled Crafts and Chamber of Agriculture)) plus 5 years of experience
 - or Dipl.-Ing. (Master of Science or M.Eng.) FH Landespflege
 - or certified Project Manager with 3 years of experience in field of practice.
 - The PM shall have full authority to act for the Contractor on all contract matters relating to daily operation of the contract.
 - The name and contact information of the PM shall be provided to KO and COR no later than 10 business days after contract award (Deliverable 10).
-
- In the circumstances when the PM is not available, the Contractor shall designate an alternate who can perform the same duties during the absence.

The Project Manager or Alternate Project Manager shall be available during normal hours of operation and when emergencies occur. The Contractor shall ensure that the key personnel can be reached by telephone during regular working hours (i.e., 07:30 - 16:00), respond within 2 hours.

1.10.7 Quality Control Manager (QCM).

The Contractor shall designate a QCM on site during normal duty hours.

- As a minimum, QCM shall have at least two (2) years of documented grounds maintenance services experience and shall be responsible for the overall management and implementation of the Contractor's Quality Control Plan.

1.10.8 Quality Control Inspectors (QCI).

The Contractor shall designate QCI personnel to monitor Contract work to assure compliance with Government requirements.

- The QCM may also serve as the QCI.

1.10.9 Phase In /Phase Out Period. N/A

1.11 Emergency Services.

1.11.1 Emergency Medical Treatment.

The Contractor or their employees shall immediately notify their supervisor of any incident requiring immediate emergency medical treatment.

The Government may provide emergency support ambulance service and/or DoD medical facility, if available (Phone: 0611-143-548 0112) (See Attachment 11)

If injuries occurred while an employee is performing work under this contract, the contractor shall verbally notify the KO/COR no later than (NLT) two (2) hours after an emergency medical event, followed by a documented summary of events (Deliverable 11)

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

The Contractor shall be responsible for reimbursement of any cost of provided emergency medical treatment services provided to Contractor personnel. Reimbursement shall be paid to the U.S. Treasury.

1.11.2 Accident Reporting.

The Contractor shall comply with Operational Safety and Health Administration (OSHA) as well as with the ArbStattV (German Workplace Ordinance) for record keeping and reporting of all accidents resulting in death, injury, occupational disease, or adverse environmental impact (See Attachment 11 USAG WI Red Plan).

The Contractor shall provide a verbal report to the KO/COR within two (2) hours of each such occurrence followed up by an email documenting each such occurrence (See Attachment 11).

The Contractor shall adhere to reporting of mishaps IAW AR 385-10, The Army Safety Program (Chapter 3 Accident Investigation and Reporting, Chapter 4 Contracting Safety) and DA Pam 385-40, Army Accident Investigations and Reporting.

1.12 Environment and OSHA.

Environmental Compliance Plan and Program

USAG Wiesbaden has implemented an Environmental Management System (EMS) that conforms to Army policy, EMS requirements in Executive Order (EO) 13423 ("Strengthening Federal Environmental, Energy and Transportation Management"). As required by Army Regulation 200-1, our EMS is mission-enhancing, conforms to the ISO 14001 Standard, and is garrison-wide in scope. The Contractor shall ensure that all its operations and activities conform to the USAG Wiesbaden's EMS policy requirements. The Contractor shall ensure that all contract personnel have obtained appropriate levels of training on the handling, use, storage, and disposal of hazardous materials (HM). In addition, the Contractor shall ensure that all Contractor controlled activities on USAG Wiesbaden installations are conducted IAW USAG Wiesbaden EMS Policy, Final Governing Standards Germany, and applicable German environmental laws and standards. The Contractor must provide this information before bringing the hazardous materials onto USAG Wiesbaden. The Contractor shall contact the COR or the USAG Wiesbaden Directorate of Public Works Environmental Division (DPW-ED), DSN 337-5587, CIV 0611-705-5587, Bldg. 1059, Clay Kaserne for a copy of the garrison EMS policy and German Final Governing Standards.

1.12.1 Safety.

The Contractor shall safeguard and maintain all Government and Contractor property, as well as provide for the safety and well-being of personnel employed under this contract. The Contractor shall comply with AR 385-10, *The Army Safety Program*.

All unsafe acts or conditions fostered by the Contractor or Contractor personnel may be grounds for the KO to halt all Contractor performance until such unsafe conditions are corrected.

The Contractor shall take due caution not to endanger personnel during performance of this contract.

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

Upon discovery of a serious hazard such as, but not limited to, fire, or fuel spill, the Contractor shall immediately notify the KO and designated authorized representatives verbally followed up with an email notification (See Attachment 11).

1.12.2 Safety Plan.

The Contractor shall develop and implement a safety plan for employees.

The Contractor shall submit the safety plan to the KO/COR for review and acceptance within 30 business days after contract award (Deliverable 11.1).

Revisions shall be submitted to the KO/COR five (5) business days prior to the effective date of change.

The Contractor shall ensure that proper safety measures are provided at work sites at all times (such as caution tape, traffic signs). At the close of each workday, the Contractor shall ensure that work sites are clean and safe for traffic.

1.12.3 Spill Plan.

The Contractor shall comply with the USAG Wiesbaden Spill Prevention Control and Countermeasure Plan (See Attachment 11 – USAG WI Red Plan (Spill Plan)).

The Contractor shall verbally notify the KO and COR, followed by written notification as required in the USAG Wiesbaden Spill Plan, if the Contractor spills or releases any hazardous substances, (*i.e.*, substances listed in 40 CFR 302, *Designation, Reportable Quantities, and Notification.*)

The Contractor shall clean up at its own expense any contamination, including soil and ground water contamination caused by HM he has brought to the garrison or by his activities. The Contractor must immediately report any HM spills to the garrison Fire Department at CIV 0611-705-117.

1.12.4 Asbestos Awareness. N/A

1.13 Environmental Compliance.

The contractor shall implement the following environmental objectives in accordance with FAR 23.4; FAR 23.7; FAR 52.223-1 through 52.223-5; and based on EPA-issued guidance):

- Maximize the utilization of environmentally preferable products.
- Maximize the utilization of bio-based products. See USDA-designated items at <http://www.biopreferred.gov> or 7 CFR part 3201.
- Maximize the reutilization of nonhazardous and recovered materials.
- Promote recycling and other cost-effective waste reductions.
- Eliminate or reduce the generation of hazardous waste and the need for special material processing (including special handling, storage, treatment, and disposal).
- Promote energy-efficiency and water conservation.

1.13.1 Safety Data Sheets.

For materials that have Safety Data Sheets (SDS):

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

- The Contractor shall adhere to all applicable requirements of the Installation Hazardous Waste Management Plan.
- The Contractor shall provide all materials, labor, training, transportation, and equipment for the handling and storage of hazardous materials or toxic materials.
- The Contractor shall inform the KO and the COR of the types and quantities of hazardous materials that they plan to bring into the garrison to meet their contractual duties, to include the Safety Data Sheets and storage requirements for the hazardous materials.

PART 2 DEFINITIONS & ACRONYMS

2.0 Definitions and Acronyms.

2.1 Definitions.

Acceptable Quality Level (AQL).

The AQL is the maximum percentage defective (or the number of defects per hundred units) that, for purposes of sampling inspection can be considered satisfactory.

Contractor.

A supplier or vendor awarded a contract to provide specific supplies or service to the Government. The term used in this contract refers to the prime.

Contracting Officer (KO).

A person with authority to enter, administer, and or terminate contracts, and make related determinations and findings on behalf of the Government. Note: The only individual who can legally bind the Government.

Contracting Officer's Representative (COR).

An employee of the U.S. Government appointed by the KO to administer the contract. Such appointment shall be in writing and shall state the scope of authority and limitations. This individual has authority to provide technical direction to the Contractor as long as that direction is within the scope of the contract, does not constitute a change, and has no funding implications. This individual does NOT have authority to change the terms and conditions of the contract.

Deficient Service.

A service output that does not meet the standard of performance associated with the Performance Work Statement.

Deliverable.

Objective evidence that can be physically delivered but may include non-manufactured things such as meeting minutes or reports.

Equipment.

A tangible item that is functionally complete for its intended purpose, durable, nonexpendable, and needed for the performance of a contract. Equipment is not

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

intended for sale and does not ordinarily lose its identity or become a component part of another article when put into use. Equipment does not include material, real property, special test equipment or special tooling.

Government Property.

All property owned or leased by the Government. Government property includes both Government- furnished property and Contractor-acquired property. Government property includes material, equipment, special tooling, special test equipment, and real property. Government property does not include intellectual property and software.

Government Project Manager.

The DPW Project Engineer/Technician assigned to manage this PWS.

Legal and Other Requirements.

Applicable Federal, State, local, DoD and Army laws, codes, regulations and other requirements.

Loss of Government Property.

Unintended, unforeseen or accidental loss, damage, or destruction of Government property that reduces the Government's expected economic benefits of the property. Loss of Government property does not include occurrences such as purposeful destructive testing, obsolescence, normal wear and tear, or manufacturing defects. Loss of Government property includes, but is not limited to:
Items that cannot be found after a reasonable search.

Theft

Damage resulting in unexpected harm to property requiring repair to restore the item to usable condition; or

Destruction resulting from incidents that render the item useless for its intended purpose or beyond economical repair. Contractor shall prepare damage reports monthly and submit them to COR.

Material.

Property that may be consumed or expended during the performance of a contract, component parts of a higher assembly, or items that lose their individual identity through incorporation into an end-item. Material does not include equipment, special tooling, and special test equipment or real property.

Non-Personal Services.

The personnel rendering the services are not subject; either by the contract's terms or by the manner of its administration, to the supervision and control usually prevailing in relationships between the Government and its employees. Non personal service contracts are authorized by the Government in accordance with FAR 37.012, under general contracting authority, and do not require specific statutory authorization.

Performance Requirements Summary (PRS).

Identifies the key service outputs of the Contractor.

Physical/Community Fitness Centers.

Physical/Community Fitness Center facilities may include a gymnasium, athletic courts, work out areas, weight rooms, showers, restrooms, locker rooms, indoor handball courts, whirlpool, sauna, administrative space, and storage space. Outdoor fitness/recreation facilities, indoor/outdoor swimming pools, ice- and/or roller-skating rinks, physical educational training facilities, and areas that house a fitness center are not included.

Physical Security.

Actions that prevent the loss or damage of Government property.

Property.

All tangible property, both real and personal.

Property Records.

Records created and maintained by the Contractor in support of its stewardship responsibilities for the management of Government property.

Provide.

To furnish, as in Government-furnished property, or to acquire, as in Contractor-acquired property.

Public Traffic Areas.

Lobbies, hallways, corridors, stairwells, meeting rooms, and lavatories.

Quality Assurance.

The Government procedures to verify that services being performed by the Contractor are performed according to acceptable standards.

Quality Assurance Surveillance Plan (QASP).

An organized document written by the Government specifying the surveillance methodology used for surveillance of Contractor performance.

Quality Control.

All necessary measures taken by the Contractor to assure that the quality of an end product or service shall meet contract requirements.

Real Property.

See Federal Management Regulation 102-71.20 (41 CFR 102-71.20).

Spill Plan.

A plan designed to identify steps to prevent the discharge of one or more hazardous substances that adversely impact, or threaten to adversely impact, human health, welfare or the environment and requires an immediate response.

Subcontractor.

One that enters a contract with a prime Contractor. The Government does not have privity of contract with the subcontractor.

Wide Area Work Flow (WAWF).

A secure web system for electronic invoicing, receipt, and acceptance. WAWF allows Government vendors to submit and track invoices and receipt/acceptance documents over the web and allows Government personnel to process those invoices in a real-time, paperless environment.

Workday.

The number of hours per day the Contractor provides services in accordance with the contract.

Work Week.

Monday through Friday, unless specified otherwise (Installation specific or as defined by the Collective Bargaining Agreement).

2.2 ACRONYMS.

ACC	Army Contracting Command
ACS	Army Community Service
ACOR	Alternate Contracting Officer's Representative
AQL	Acceptable Quality Level
ATO	Anti-Terrorism Officer
CFR	Code of Federal Regulations
CLIN	Contract Line Item Number
CLS	Common Levels of Support
COR	Contracting Officer's Representative
CPARS	Contractor Performance Assessment Reporting System
DA	Department of the Army
DES	Directorate of Emergency Services
DFARS	Defense Federal Acquisition Regulation Supplement

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

DoD	Department of Defense
DPW	Directorate of Public Works
ENV	Environmental
FAR	Federal Acquisition Regulation
GOV	Government
HQDA	Headquarters Department of the Army
HVAC	Heating, Ventilation and Air Conditioning
IAW	In Accordance With
IG	Inspector General
IMCOM	Installation Management Command
KO	Contracting Officer
LOR	Legal and Other Requirements
N/A	Not Applicable
NLT	Not Later Than
OCI	Organizational Conflict of Interest
OPSEC	Operational Security
OSHA	Occupational Safety and Health Administration
PIEE	Procurement Integrated Enterprise Environment
PM	Project Manager
POC	Point of Contact
PoP	Period of Performance
PRS	Performance Requirements Summary
PWS	Performance Work Statement
QA	Quality Assurance
QAP	Quality Assurance Program
QASP	Quality Assurance Surveillance Plan
QC	Quality Control
QCP	Quality Control Plan
SAM	System for Award Management
SDS	Safety Data Sheets
SF	Square Foot
SPM	Surveillance and Performance Monitoring
SSP	Service Support Program
TARP	Threat Awareness and Reporting Program
TE	Technical Exhibit
WAWF	Wide Area Work Flow
WD	Wage Determination
YC	Youth Centers
ZTV Baumpflege	ZTV Tree maintenance (technical code)

PART 3
GOVERNMENT FURNISHED PROPERTY, EQUIPMENT, AND SERVICES

3.0 Government Furnished Property, Equipment and Services.

3.1 Property. The Government will not furnish any office space for the Contractor under this contract.

3.2 Equipment. The Government will not provide any equipment under this contract.

3.3 Services. The Government will not provide any services under this contract.

3.4 Utilities.

The Government will provide water and electricity from existing outlets at no additional cost to the contractor. The contractor shall make no changes to existing outlets. The Contractor shall instruct employees in utilities conservation practices. The contractor shall be responsible for operating under conditions that preclude the waste of utilities, which include turning off the water faucets or valves after using the required amount for the contractor to perform the tasks outlined in this PWS.

3.5 Materials. The Government will not provide any materials under this contract.

PART 4

CONTRACTOR FURNISHED ITEMS AND SERVICES

4.0 Contractor Furnished Items and Services.

4.1 General.

The Contractor shall furnish all supplies, equipment, facilities, transportation, tools, materials, supervision, and other items necessary to perform services as described in the PWS and associated contract documents, except for those items specified under Section 3, Government Property and Services.

4.1.1 Classified Controlled Facility Clearance. N/A

4.2 Materials.

The Contractor shall furnish all materials, supplies, and equipment necessary to meet the requirements identified in this PWS. All plants utilized for the services under this contract shall be from a certified tree nursery and produced to meet “Bund deutscher Baumschulen” (BdB) Quality.

Other materials furnished shall be in accordance with pertinent German accident and safety regulations to meet the requirements under this PWS. All exchanged parts/materials shall be provided to or disposed of as directed by the COR. The Contractor shall provide warranty for the PX trees and additionally planting warranty for all trees already planted and replanted during the timeframe of contract, and according to pertinent regulations.

4.3 Equipment.

The Contractor shall ensure all equipment meets applicable Federal, State, local, DoD and Army laws, codes, regulations and other requirements. In addition, the Contractor shall maintain or have backup capability to provide continued service in the event primary equipment or vehicles are down for extended maintenance or repairs.

Equipment failure shall not alleviate the Contractor from performing any requirement contained in this contract. Equipment shall include all necessary and customary hand and mechanical appliances routinely used for ground maintenance operations.

The Contractor shall provide all equipment, tools, safety equipment, and vehicles needed to perform the services described in this PWS. The COR may inspect the Contractor’s vehicles and equipment at any time.

4.4 Unserviceable Contractor Equipment.

Contractor furnished equipment or items, inoperable or unserviceable for whatever reason including failure to meet Federal, State, or local safety requirements, shall be removed from the installation within twenty-four (24) hours after failure. Equipment that is not repaired within thirty (30) calendar days will be removed from the installation.

PART 5 SPECIFIC TASKS

5.0 Specific Tasks for Grounds Maintenance.

5.1 General.

The Contractor shall provide all management, tools, equipment, and labor necessary to ensure that grounds maintenance services are performed at USAG Wiesbaden footprint. See Part 4 Contractor Furnished Items and Services. The Contractor shall inspect, service, maintain, and landscape grounds of USAG Wiesbaden. The work shall include scheduling and performance of mowing and trimming; turf replacement; leaf and debris removal; tree, hedge, and shrub planting, maintenance, irrigation, and fertilization; policing of areas; tree and stump removal, and other associated work as directed by the Contracting Officer's Representative (COR) or Alternate Contracting Officer's Representative (ACOR). The Contractor shall provide all work necessary to maintain the grounds to the standards specified herein. The Contractor shall provide for tree preservation and protection during all maintenance and construction activities as specified by USAG Wiesbaden. The Contractor shall provide a Work Schedule for scheduled services (Deliverable 3).

The Contractor shall ensure that all maintenance services under this contract result in the proper maintenance of the grounds area IAW all Host Nation regulations. The tree assessment and detailed inspection is a requirement to ensure traffic safety at the installations. All maintenance and assessments shall be IAW all pertinent German and US Government accident Regulations, DIN Standards, and the "Standards of the Industry" provisions of the German Trade Association.

Debris resulting from services performed under this contract shall be removed daily, or by the weekend when more extensive work is performed. Debris shall be disposed of in accordance with applicable regulations. The Contractor shall provide disposal documents upon request to the COR ten (10) days after disposal (Deliverable 12). Disposal is the responsibility of the Contractor and will not be reimbursed by the Government. The Contractor shall dispose of trash from housing areas. All detailed services are outlined in the price book (Attachment 10, Exhibits A & B) and each service shall be invoiced as indicated in the price book (ELIN). All waste cutting, debris and other refuse shall be removed and disposed of in accordance with all applicable regulations.

The Contractor shall provide a telephone number, a fax number and an e-mail address, which shall be used for receipt of service requests. The contractor shall be available from 0730 – 1600 hours, Monday through Friday. All telephone calls shall be answered by a responsible person representing the Contractor's firm. Additionally, the Contractor shall provide a 24/7 telephone number for emergency requests. (Deliverable 13).

5.2 Description of Services.

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

5.2.1 Scope. The Contractor shall provide Grounds Maintenance for all High Visibility (Improved Grounds), Common Areas (Semi-Improved Grounds), Fire Breaks and Ranges, and Unimproved Grounds. The Contractor shall ensure all work accomplished maintains and presents a healthy, clean, neat, and professional appearance to all grounds included and covered by this contract in support of mission requirements for users, residents, and visitors. The Contractor shall mow grass only when the minimum cutting height is reached or exceeded as indicated by the Work Capability Levels Attachment - 3. The Contractor shall set the mower height to 2 inches for Athletic Field areas and Army Family Housing (AFH), General Flag Officer Quarters (FGOQ), and Unaccompanied Personnel Housing (UPH) (AFHUPH). The Contractor shall set the mower height to three (3) inches for all other areas. The Contractor shall replace any new trees which show severely reduced vitality within 3 years after planting or shrubs that die within one (1) year at no cost to the Government. All work shall be performed by personnel qualified in accordance with (IAW) applicable laws, regulations, and Attachment 1 - Performance Requirements Summary. (Attachment 1). At the end of the service work shall be complete. If the maintenance cannot be completed during the service, due to, for example, weather conditions, the Contractor shall notify the COR immediately, and complete the service as coordinated with the COR at no additional cost to the Government. If lack of service results in damage to Government property, the Contractor shall provide replacement.

Service requests will be placed by the COR or authorized personnel of the USAG Wiesbaden Directorate of Public Works (DPW). After contract award, the COR will provide the Contractor with the names and phone numbers of the personnel authorized to place a service call.

Work within this contract is work/services to be scheduled and services on request. Services shall be provided in accordance with task orders issued by the Government. Services are identified in task orders as SCHEDULED or ON DEMAND. The Contractor shall submit a work schedule for scheduled services in MS Excel or compatible format to the COR for approval within ten (10) working days after receipt of the task order (Deliverable 3). Work which shall be performed regularly and scheduled is identified in Attachment 1. All other work shall be performed when ordered and within the amount funded for the respective task order. Due to deviations related to weather conditions a weekly work schedule (Deliverable 3) shall be delivered to the COR NLT Friday of week before start of performance. This schedule shall be coordinated with the COR.

Work Certificate: The Contractor shall submit a detailed Work Certificate for all conducted work, including contract and task order number, exact location, services performed, quantities performed or delivered, completion date and person providing the service, signed by her- or himself. Location of performance shall be marked on area map, further details to determine work performed (e.g. building or tree number, hours of performance) shall be provided. Copies of delivery tickets as well as weighing tickets if applicable shall be provided with the work certificate where required. The Work Certificate (Deliverable 14) shall be submitted to the COR at the latest on Mondays close of business (CoB) every week for work completed during the previous week and as an attachment to the related invoice (Deliverable 15). If subsequent inspection of work performed is not possible when submitted weekly, an earlier and effective information chain shall be established for these tasks upon request by the COR.

5.2.2 Service High Visibility Areas.

High Visibility Areas are developed areas of the installation that require an intensive level of maintenance. The work performed in these areas by the Contractor shall include mowing grass, edging and trimming grass, removing grass trimmings from paved areas, irrigating, aerating lawn areas, applying fertilizer and/or lime, applying herbicide to lawn and landscape areas, maintaining athletic fields, plants, shrubs, and flowers, performing seasonal planting of plants and flowers, removing leaves, applying mulch, pruning trees, removing grass from cracks in sidewalks and pavements, and litter control.

5.2.3 Mowing.

High Visibility Areas are indicated in the Installation Grounds Maps referenced in Attachment 4 – AFH Grounds Maps incl tree Assessment and Attachment 5 OMA Grounds Maps incl tree Assessment. The Contractor shall remove trash, litter, tree limbs, debris, etc., prior to mowing, and dispose of it at designated collection points or an adequate disposal facility, with the Government not liable for any damage to the Contractor's equipment caused by debris. Paved areas and walkways shall be free of lawn clippings/debris the same day the mowing is performed. The Contractor shall mulch, mow the grass and remove visible grass clippings after mowing, before leaving the work area. The Contractor CAN NOT salvage grass clippings as silage feed. Paved areas and walkways must be cleared of lawn clippings and debris on the same day mowing services are performed. The lawn must be uniform in appearance, free of skips, gaps, rutting, or scalping. Mowing operations in any area must not exceed two working days, and areas that do not achieve a uniform appearance must be re-mowed at no additional cost to the Government, as inspected by the COR, to meet the specifications of this PWS. The Contractor must mow lawns that may be contaminated with pet waste (e.g., dog droppings) and is responsible for any damage incurred during grass cutting operations. All Public green areas, green areas, Lawn Areas shall be maintained in accordance with DIN 18919 (Gebrauchsrassen DIN18919).

Additionally, the Contractor shall not commence or continue mowing during excessive rainfall or frost-covered grass unless directed by the KO or their authorized COR, and must obtain concurrence when mowing may cause rutting, soil compaction, or scalped areas; otherwise, the Contractor will be liable for repairing damaged areas.

- The Contractor shall mow grass in barracks and housing areas. Grass shall be cut when it reaches a height of 4 inches and reduced to a height of 2 inches.
- The Contractor shall cut grass to a height of 3 inches at lawn Areas - ETC Mainz-Kastel.
- Mowing, Semi Improved Grounds - ETC Mainz-Kastel.
- Lawns in antenna areas shall be mowed to a height of 3 inches. The grass shall be trimmed to a height of 3 inches. Grass clippings shall be removed during or immediately after the mowing process and shall be disposed of in accordance with applicable HN disposal regulations.
- Mowing, Improved Grounds, with removal of grass.

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) **(ISR 404 – Grounds Maintenance Services)**

- Mowing of Berms (Wackernheim Rifle Range) and steep sites along sport field Hainerberg school shall be mowed four times annually or 16 inches, whichever comes later. Special focus shall be kept on all corners and edges to prevent growth of shrubs. Completion of work shall be announced as requested by phone or e-mail to schedule an on-site acceptance of work performed. When requested, clippings shall be removed.
- Grounds maintenance services for the open air bullet trap area in Wackernheim Rifle Range, shall include the routine removal and disposal of all vines, weeds and unwanted vegetation within and immediately surrounding the bullet trap structure. Work shall ensure that climbing vines are fully to cut back and removed from walls, fencing, and structural components, and that all weeds are clear from the ground surface to maintain a safe, accessible, and well-maintained condition. Vegetation shall be removed in a manner that prevents regrowth and does not damage the bullet trap structure or surrounding surfaces. All debris generated from maintenance activities shall be collected and properly disposed of off-site.

A.- Mowing of Layenhof training area, semi-improved grounds

Grass at Layenhof training area, adjacent antenna area (see Attachment - 5), heating plant and ground level surface of Rainwater Retention Basins (RRBs) shall be mowed. The grass shall be trimmed to a height of 3 inches. Grass clippings at retention basins shall be removed during or immediately after the mowing process and shall be disposed of in accordance with applicable regulations. Mowing this may include also other semi-improved grounds areas at the Wackernheim locations (McCully, Schwabenwäldchen).

B.- Rainwater Retention Basins (RRB) Treatment of vegetation inside Rainwater Retention Basins

The basin itself at Clay Kaserne (RRB South) and Mc Cully shall be mowed and all material removed, so that clogging of drains will be avoided. Additionally, all bushes shall be removed with root during the mowing. Higher bushes shall be trimmed back fully during every service, so that the drainage layer will remain unscathed. See Attachment 5.

Mowing of semi-improved grounds with removal of hay

Grass shall be mowed during a dry weather period. If ordered, sections of area to be mowed shall be treated in intervals. Mulching is interdicted for these areas.

5.2.4 Edging.

The Contractor shall edge to present a neat appearance. Edging responsibilities shall include, but not be limited to, flowerbeds, mulched areas, sidewalks, driveways, street edges, curbs, and other concrete (except against asphalt edges) located in the Improved Grounds. Edging includes the removal of all grass or weeds sprouting from cracks in sidewalks, pavement, and curb joints. The use of post-emergent herbicides by the Contractor, for edging purposes, is limited to grass in cracks and shall not be used to edge the entire area. The Contractor shall collect and dispose of all edging debris the same day edging is performed.

5.2.5 Trimming

The Contractor shall trim grass and weeds around trees, shrubs, areas, fences, poles, posts, fire hydrants, parking lot bumper blocks, boulders, and all other fixed objects that project above the ground, so grass height is maintained consistent with adjacent grass. The use of herbicides by the Contractor shall be limited to the post perimeter fence line and for use in preventing grass growth on sidewalks. The Contractor shall remove all trimming debris from sidewalks and driveways on the same day trimming is performed.

The Contractor shall repair any damage to trees and shrubs caused by trimming. If a plant damaged by trimming dies or becomes unhealthy, the Contractor shall replace the damaged plant with a plant of the same size and type at no additional cost to the Government. The Contractor shall provide a one (1) year warranty on all replacement trees and shrubs. Tree and shrub replacements shall be performed within fifteen (15) days of the date the Contractor is notified to replace the plant.

5.2.6 Fertilizing and Liming.

Lawn areas: The Contractor shall fertilize lawn areas with a mineral fertilizer (20%Nitrate+ 5%Phosphate+ 8%Potassium). The Contractor shall apply 30 g/m² per service. A copy of the delivery note shall be submitted to the COR before start of service (Deliverable 18).

Planting beds: The Contractor shall deliver organic fertilizer (Hornspäne/horn shavings, or equal) to planting beds. The Contractor shall apply 150g of organic fertilizer per square meter and shall work it 3 inches deep into the ground.

5.2.7 Seeding and Sodding.

The Contractor shall repair damaged lawn areas by excavating unsuitable material, backfilling with shredded topsoil, leveling and seeding and maintaining adjacent turf areas IAW with the Work Capability Levels table. All seeded areas must be covered with two to three (2 - 3) inches of loose straw mulch immediately after the seed has been applied.

5.2.8 Hydroseeding. N/A

5.2.9 Sodding. N/A

5.2.10 Aerating and Overseeding. N/A

5.2.11 Maintain Flower Beds.

The Contractor shall maintain flower beds in general areas of use (playgrounds). The Contractor shall maintain only low maintenance and indigenous flowering species. The Contractor shall fertilize, weed, mulch, water, add compost, and till. The Contractor shall remove all annual plants, add compost, and mulch flowerbeds annually prior to planting perennials. Leaf/grass compost and shredded hardwood bulk mulch shall be used. Any use of herbicides shall be approved by the KO/COR.

5.2.12 Weed Control.

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) **(ISR 404 – Grounds Maintenance Services)**

Herbicide application shall be limited to parade fields and athletic fields and only application approved by HN law and authorities (permit) shall be performed by the Contractor. Contractor personnel that apply herbicide shall have a German herbicide application certificate or license. The Contractor shall ensure training and licenses and/or certificates of Contractor personnel are kept current. The Contractor shall provide copies of these licenses or certifications (Deliverable 18.1) to the Contracting Officer (KO), not later than (NLT) ten (10) calendar days during the phase-in period, and again within ten (10) calendar days upon a change in personnel.

The Contractor shall submit a consolidated list of all chemicals (Deliverable 18.2) used during the month, in a monthly herbicide application record to the COR/ACOR. All mixing and storage of herbicide shall be performed off the installation. If the Contractor spills or releases any hazardous substances, *i.e.*, substances listed in 40 CFR 302, *Designation, Reportable Quantities, and Notification*, the Contractor shall immediately notify the KO, followed by written notification within one (1) hour. The Contractor shall submit an herbicide usage report of all herbicides use to the KO within one (1) day after application of any herbicide.

Sapling removal, starving out

The Contractor shall cut back sprouts from saplings which can't be removed by the root every month during May to October. Contractor shall invoice by the linear meter.

Weeding and Hoeing special areas

The Contractor shall remove wild growth and weeds in planting beds shall be removed with the root. This Para has been generated to provide FFP for reimbursable customer, European Technology Center Mainz Kastel.

5.2.13 Remove Debris, Leaves, and Litter.

The contractor shall remove trash from all existing trash receptacles weekly.

The Contractor shall remove unwanted vegetation and weeds from the garbage container areas, which are approximately 20 sqm in size. The Contractor shall separate all trash lying around at the site into locally available containers. Steam-cleaning of paved areas may be necessary for the removal of stains and other matters. Additional cleaning fee when garbage container area is cluttered (with photo documentation).

Leaves on vegetation areas shall be mulched. Where leaves are not accessible for mulching (e.g. under bushes, hard surfaces, etc.), the Contractor shall collect and mulch them at an adjacent lawn area. The Contractor shall remove leaves if thickness of mulch cover would hinder lawn growth in the following spring. Leaf removal includes all sidewalks in the area and inner parking lots. The Contractor shall remove leaves and litter at all exterior basement stairs on the rear side of multiple unit dwellings during regular leaf removal. The Contractor shall remove leaves and litter from the light wells of multiple unit dwellings. The leaves can be mulched at the site, if thickness of mulch layer will not interfere with subsequent vegetation growth. Litter shall be disposed of IAW host nation regulations.

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) **(ISR 404 – Grounds Maintenance Services)**

- Leaves on vegetation areas in vacant Duplex and Single Quarters and the adjacent paved areas, including sidewalks, playgrounds, garbage container areas, basement stairwells, patios, and related parking lots, shall be collected, removed and disposed of in accordance with applicable regulations. The Contractor shall report all clogged drains observed during leave collection and removal. Report of clogged drains shall be submitted with the weekly report or work certificates (Deliverable 14).

- The Contract shall remove leaves and litter from exterior basement stairs and floor at the rear of areas when ordered. Especially the drains shall be uncovered and cleaned where required to prevent flooding of basements. The Contractor shall report all clogged drains observed during leave collection and removal. Report on clogged drains shall be submitted with the weekly report.

The Contractor shall clean barbecue huts and empty trash receptacles. The Contractor shall ensure floors of barbecue huts are swept and free of litter.

- The Contractor shall remove vegetation in the splices of the stone floors on a regular basis as described in Attachment 3.

- The Contractor shall empty trash receptacles including dog poop stations throughout Aukamm, Crestview, Hainerberg, and Newman housing areas on regular basis as described in Attachments 4 and 5. Solar bins shall be cleaned twice annually. Dog poop stations shall be refilled as required, with the respective dog poop bags.

- Contractor shall sweep walkways and other surfaced areas free of dirt, debris, weeds and litter. Sweeping methods shall be in conformance with standards of the industry and appropriate for respective surface. Contractor shall invoice per square meter.

- The Contractor shall clean paved area free of dirt, debris and litter and remove and dispose of weeds growing in joints of concrete areas, e.g., parking lots, sidewalks, patios, around and on paved area of street light poles, between interlocking blocks, in joints of slabs or gutter tiles. The Contractor shall employ appropriate environmentally benign methods for weed removal, e.g. steel brush, weed eaters. Contractor shall invoice per square meter.

- The Contractor shall remove and dispose of weeds growing along curbs, walls or similar locations. Contractor shall invoice by the linear meter.

- Upon receipt of notice from the COR that vacant quarters are to be occupied, the Contractor shall ensure that weeds and all debris are removed from all paved areas and as described. Upon request by customer pressure washing of paved areas shall be performed. Work shall be completed in the latest 3 working days after receipt of notice. Contractor shall invoice per square meter.

- The Contractor shall remove and dispose of weeds growing in joints of concrete areas, e.g., parking lots, sidewalks, patios, between interlocking blocks, in joints of slabs or gutter tiles. The Contractor shall perform weed removal with heat or hot water as ordered by Government. Contractor shall remove all weeds from site after method shows effectiveness. Contractor shall invoice per square meter.

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) **(ISR 404 – Grounds Maintenance Services)**

- The Contractor shall remove wild growth and weeds in gravel strips and other surfaces along areas. Cleaning of gravel stripes includes also adjacent paved areas, including exterior stairwells. Contractor shall invoice by the linear meter.
- The Contractor shall remove wild growth and weeds in front of walls and at outdoor stairs. Contractor shall invoice by the linear meter.
- Contractor shall remove wild growth and weeds in planting beds with the root. The ground shall be loosened. Plants, bushes, shrubs and flowers shall be pruned and dead sections removed. The Contractor shall remove and dispose of litter found in planting beds.

Area to be cleaned shall be cordoned off temporarily by Contractor to ensure that site is accessible for weed removal action and cordon off when situations of imminent danger (LHS/GIV) occur and ensure that parking cars are removed at site. Contractor shall also notify tenants about ongoing work when required with a flyer placed on under the car windshield wiper and building entrance doors. Contractor shall invoice per service.

(Reimbursable) Cleaning of area and trash pick-up - European Technology Center

The Contractor shall ensure the area is clean of rank growth and moss, including the spaces between interlocking and other pavement stones and along railroad tracks located on parking lot. Fence lines around building 4009 and 4010 shall be kept free of upcoming weeds and saplings. The Contractor shall use environmentally benign methods to remove weeds. Prior to start of work, the Contractor shall remove and properly dispose of all debris and clippings in accordance with the applicable regulations.

Cleaning of trench Clay Rain Retention Basin (RRB)

The trench at RRB shall be emptied of mud and the mud removed from the site. When required, automated machines should be used to perform work.

5.2.14 Service/Maintain Trees. The Contractor shall service all trees annotated in Attachment 10 A and B. Trees that become diseased or die shall be removed and replaced with like trees.

Explanation: Due to location in the urban area of Wiesbaden and surroundings, the local tree ordinance must be followed and trees to be replanted mandatorily per regulation.

Planting of trees:

The Contractor shall plant trees where indicated by the Government. Planting work shall be performed in accordance with DIN 18916. Standard quality: high trunk trees 3 times replanted, from wide cultivation with ball of earth (Hochstämme, 3 x verpfl., aus extra weitem Stand, mit Drahtballierung) 16 – 18 cm or 18 – 20cm, side branches shall be significant smaller than lead branch (Seitentriebe müssen dem Leittrieb deutlich untergeordnet sein). Planting holes shall be excavated in adequate size. The excavated material shall be upgraded with tree specific planting material as mycelium, brickstone parts 8-16mm and EM (effective microorganisms). Trees shall be provided with a

watering trench and a three-stake anchor. The Contractor shall water and maintain newly planted trees in proper condition and deliver a list of the newly planted trees within two (2) weeks after inspection has been performed (Deliverable 20). Dead trees and/or trees showing major damage or failure to thrive shall be replaced without additional cost to the Government. COR will perform site meeting to check vitality in September after planting action.

- Tree planting / replacement shall be in the same year; November/December timeframe (ELIN *001BT / *002BD).
- Remove dead trees before planting. This position is applicable for trees planted less than 5 years before re-planting.
- Dead trees, including roots, shall be removed and disposed of (This position is applicable for trees planted less than 5 years before re-planting.) (ELIN *001BV / *002BE).
- Dead trees including roots shall be removed and disposed (This position is applicable for trees planted 5-10 years before re-planting.) (ELIN *001BX / *002BF).

5.2.15 Perform Mechanical Tree Spading and Transplanting. N/A

5.2.16 Tree Mulching. N/A

5.2.17 Trees Service/Maintenance and Safety

- Tree Fertilization.

The Contractor shall water and fertilize all trees, including saplings, medium-to-mature trees, and other trees. The Contractor shall apply sufficient water and fertilizer to maintain the health of the trees.

- Fertilize trees

The Contractor shall fertilize young trees with Compo Baumkraft fluid, 80-150g, during first watering of trees in May or June. The fertilizer shall be applied once a year during tree watering and when ordered by Government. Liquid fertilizer shall be applied using a watering barrel.

- Trees, establish mycelium

Apply tree mycelium during wet weather period in spring on trees as ordered by Government. Applied type of mycelium shall be plant specific, predominantly oaks shall be treated.

- Maintenance of young trees

The Contractor shall coat young trees with a trunk protection paste specifically developed to prevent or reduce thermal bark damage caused by weather fluctuation according to the German guide ZTV Baumpflege 2017. The Contractor shall inspect tree anchors and repair/replace where necessary. Minimum of 20 trees per service.

The Contractor shall remove or repair tree anchors as required. Where needed the watering dike around the tree shall be repaired, if necessary, soil/mulch shall be added or removed. All weeds on watering dike shall be removed.

Where trees are planted too deep, soil needs to be removed to uncover the root base and area around tree reshaped. Trees shall be lifted and replanted at a higher level at the same site.

5.2.18 Tree Pruning.

The Government will identify trees that require trimming/pruning. Upon notification, the Contractor shall trim all tree limbs which are damaged, unsightly, or present unsafe conditions, and remove all associated debris. Pruning shall be accomplished IAW ZTV Baumpflege ZTV (Tree Maintenance (technical code)) and ANSI A300 (Part 1)-2001, *Tree, Shrub, and Other Woody Plant Management – Standard Practices (Pruning)* and ANSI Z133.1-2006, *Arboricultural Operations – Pruning, Trimming, Repairing, Maintaining, and Removing Trees and Cutting Brush – Safety Requirements*, or the most current approved update, and National Arborist Association standards.

5.2.19 Tree Inspection Removal and Replacement.

The Contractor shall inspect for dead, damaged, and diseased trees within High Visibility Areas and provide a written report (Deliverable 17.1) to the COR/ACOR within five (5) working days of the end of each month in the format provided in the VTA Guidelines and USAG Wiesbaden Tree Inventory, see Attachment 8 Urban Tree Inventory Data. The report shall identify by species, size, class, and location of all hazardous trees, insects, and disease problems that require immediate attention and a specific plan of action for corrections. Dead trees to be removed and new replacement plantings shall be identified on an approved site plan. All tree removals and the associated schedules shall be approved by the Directorate of Public Works (DPW) Environmental and Natural Resources Division (ENRD) prior to implementation. All debris shall be removed within ten (10) calendar days of tree removal and damaged area shall be raked, leveled and seeded.

An inspection to assess the tree condition is mandatory by HN regulations to ensure traffic safety and adherence to the LHS regulations.

Once a year, the Contractor shall inspect all USAG Wiesbaden trees (approximately 6700 each “AFH” trees and approximately 2260 each “OMA” trees) in current inventory and all new planted trees within a period of two months. Inspections shall be performed in accordance with the FLL-Tree Inspection Guidelines / Forschungsgesellschaft Landschaftsentwicklung Landschaftsbau e.V. All currently existing trees are registered in the US Urban Tree Inventory. Newly planted trees shall be registered, described and tagged. Rating of trees includes required maintenance actions as well as urgency of required actions and rating of most recently performed tree maintenance actions. During the assessment the tree height might need to be corrected. This should be performed at least for trees where more urgent maintenance actions must be performed (treatment priority 2-4, see attachment 8, Urban Tree Inventory Data entries).

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

The Contractor shall report trees which are unsafe (Sofortmassnahme Sicherheit) immediately to COR per e-mail as well as trees with Eichenprozessionsspinner/ Oak Processionary Caterpillars (EPS/OPC) infestation (Deliverable 17). In the event that mature trees are not yet registered through tree inventory these trees shall be inspected and tagged. Tree tags shall identify tree numbers, and installation and be similar to the existing tags. The tree tags shall be bolted to the tree with wood screw (DIN 571, SH A2, 5x70mm), on young trees cable ties shall be used to attach the tree tags. Tree tags shall be loosened during inspection whenever required at no additional cost, missing tree tags shall be replaced.

The location (x/y) data of trees shall be at least in accuracy of 1m, most current aerial image will be provided upon request.

- **USAG Wiesbaden tree inventory**

(Geographic Information System / GIS data) for assessment entries will be provided by the COR immediately after contract award. The updated USAG Wiesbaden tree inventory with individual tree assessments (Deliverable 18), shall be delivered to the COR not later than 31 July of each contract year, if not specified otherwise by COR in coordination with Garrison SME. All information and data generated shall be submitted in a format compatible with the IMA-E Standard Tree Inventory database (GIS data - see also Attachment 8, Urban Tree Inventory Data Entries). Additionally, the attribute list shall be provided as MS Access or MS Excel table. An update to this table shall be delivered on a weekly basis during tree inspection per e-mail.

- **Detailed Inspection of Trees**

Contractor shall perform a detailed inspection to assess tree condition of approximately 25 each tree to be able to evaluate their traffic safety annually. This includes detection of stability and safety of the tree against breakage for highly valuable old trees. Relevant criteria for evaluation must be collected (e.g. tree species, vitality, habitus, compensation, wind load, height/diameter relationship). Expert opinions shall include photo-documentation, detailed written reports and analysis about stability and safety of trees in question, as well as recommendation of measures to be taken. The electronic document and one hardcopy format of inspection report shall be submitted within one month after inspection has been performed. Inspection shall be performed with most appropriate tool for circumstance, the report shall include a brief report describing all required actions to preserve the tree when recommended. (Deliverable 19).

- **Tree inspection with Resistograph**

The Contractor shall perform measurement of tree stability and safety with resistograph with "Resi PD 400" or equal (according FLL Regulation "eingehende Untersuchungen", "technical inspection procedures"). This includes the measurement of remaining healthy wood to determine the safety of the tree against breakage. Digital records of drills shall be submitted with report as well as evaluation and analysis of drill graph. Contractor shall perform 3 to 5 inspection drills per tree inspection. Approximately 15 "AFH" trees shall be investigated.

- **Tree inspection through sonic tomography**

The Contractor shall perform measurement of tree stability and safety through sonic tomography (Schalltomographie) with "Picus sonic tomograph", or equal (according FLL Regulation "eingehende Untersuchungen", "technical inspection procedures"). Digital

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) **(ISR 404 – Grounds Maintenance Services)**

records of tomography shall be submitted with report as well as evaluation and analysis of measurements. Approximately 3 each “AFH” trees shall be investigated.

- **Tree inspection with tensile test**

The Contractor shall perform measurement of tree stability and safety with static tensile test / Zugversuch (according to DIN 1056 and FLL Regulation “eingehende Untersuchungen”, “technical inspection procedures”). “Inclino- und Elasto-Method” or equal shall be used to provide written expert opinion about stability and safety of tree in question and provide recommendation for maintenance action. Digital records of static tensile test shall be submitted with report as well as evaluation and analysis of measurements. Wind load calculation and determination of storm resistance shall be included in the report. Approximately 2 each “AFH” trees shall be investigated.

- **Massaria-control**

The Contractor shall perform qualified tree inspection for massaria on whole tree crown for tree stability and safety. Written documentation of results with detailed information on how to trim the branches to provide maximum safety at the given time. Approximately 11 each “AFH” trees shall be investigated.

- **Inspect crown bracing**

Contractor shall inspect dynamic crown bracing to assess proper functioning. Crown bracings that need to be replaced shall be reported to the COR. Approximately 3 each “AFH” trees shall be inspected additionally.

- **Inspection of tree site**

Assessment of tree areas, e.g. at the Rheinblick Golf Course to identify hazardous trees and actions to be performed to establish safety for LHS.

- **Inspection of trees after severe weather**

The Contractor shall provide emergency inspection after severe weather, storms, or other unforeseen events, within 24 hours of notification by the COR or other Government representative (e.g., Directorate of Emergency Services personnel), including weekends and holidays. Hazardous trees shall be identified as well as action to be performed.

- **Additional inspection of newly planted trees**

Approximately 50 each newly planted “AFH” trees, respectively approximately 180 each newly planted “OMA” trees including about 10 valuable specimen trees (Solitäre) shall be inspected once a year in September to provide expertise whether trees are vital enough to allow a healthy growth and settlement at the planting location or need to be replanted. The exact week of this inspection will be determined by the Government. A written report after tree inspections shall be delivered within 2 weeks after inspection to the COR (Deliverable 20).

- **Inspection and rating of plant material**

Upon request the acceptance of delivered trees to be planted at USAG Wiesbaden areas shall be performed by a trained expert for plant material to identify correct quality of root bale, integrity of trunk and appropriate development of tree crown. Upon request a report on the findings shall be delivered.

- **Prepare Tree pit**

The Contractor shall prepare a tree pit at assigned locations. The tree pit shall be 118 x118 inches in size and 60 inches deep. Loosen site and bottom 4 inches deep, soil class 3-4, DIN 18915, suitable soil at the location shall be mixed with tree plantation substrat 1:1, if soil at the location is not appropriate (e.g. construction waste) this soil shall be disposed of and only plantation substrat shall be filled in. Topsoil (without lawn/plant layer) shall stay in the top 16 inches of soil mixture. The bottom layer (10 inches) shall consist of loosened soil only. Compaction of ground needs to be avoided when refilling the tree pit.

- **Improvement of tree location with addition of material**

Subsoil ventilation with injector lance (terra lift or equal) shall be performed to compensate soil compaction and prevent death of roots as well as instability of tree and early death. Porous and stable material shall be injected to improve air ventilation. Service includes use of compressed air generators, and material, and is up to a depth of 80 cm. Service shall be provided when soil conditions are suitable for action. COR and Garrison SME shall be informed at least 2 days before start of service to schedule meeting at the site before start of performance. Payment will be by whole, at minimum 50 each per service. All treated holes shall be marked with color, after treatment; Fotos shall be submitted after treatment and with related invoice.

- **Install STS sensor to ensure tree growth and monitor humidity**

Install Smart Tree Screening (STS) soil humidity sensor with all components to allow daily humidity monitoring of tree stand with virtual transmittal.

- **Soil analysis basic parameter and botanical tolerance test**

Soil sampling and analysis of the following parameters: soil type, pH, bioavailable phosphate, potassium, magnesium and salt content combined with botanical tolerance test at the planting site.

5.2.20 Emergency Tree Removal.

When removal of a tree, or part thereof, is required to eliminate a safety hazard or restore traffic flow, the Contractor shall accomplish the action within two (2) hours of notification by the COR/ACOR.

5.2.21 Reforestation. N/A

5.2.22 Hedge and Shrub Maintenance. N/A

5.2.23 Hedge and Shrub Mulching. N/A

5.2.24 Hedge and Shrub Fertilization.

The Contractor shall fertilize all hedges and shrubs. Fertilizer shall be incorporated into the surface area around shrubs, which are to receive applications of granular fertilizer. The Contractor shall apply sufficient fertilizer to maintain the health of hedges and shrubs.

5.2.25 Hedge and Shrub Pruning.

The Contactor shall cut back and thin existing bushes of various species and size according to standard trade practices. The Contractor shall remove wild-growing shrubbery including roots. Cut material and refuse shall be removed and disposed of in accordance with applicable regulations.

The Contractor shall trim hedges (e.g. Ligustrum), up to 1.30m in height, at all locations. New sprouts shall be cut back to the previous cut. Dead sections shall be cut out to its basis, and wild growth shall be removed including roots. Cut material and debris shall be removed and disposed of.

- The Contractor shall trim hedges (e.g. beech or hornbeam), up to 2.00m in height. New sprouts shall be cut back to the previous cut. Dead sections shall be cut out to their basis, and wild growth shall be removed including roots. Cut material and debris shall be removed and disposed of.
- The Contractor shall trim, hedges and shrubbery as ordered by Government to ensure shrub growth and rejuvenation. Trimming shall be performed at the base of the branches or at the branch junctions.

Trimming of formal shaped hedges and shrubs

- The Contractor shall trim hedges (e.g. Ligustrum), up to 1.30m in height, at all locations as indicated in Attachment 7. New sprouts shall be cut back to the previous cut. Dead sections shall be cut out to its basis, and wild growth shall be removed including roots. Cut material and debris shall be removed and disposed of.
- The Contractor shall trim hedges (e.g. beech or hornbeam), up to 2.00m in height. New sprouts shall be cut back to the previous cut. Dead sections shall be cut out to its basis, and wild growth shall be removed including roots. Cut material and debris shall be removed and disposed of.
- The Contractor shall trim, hedges and shrubbery as ordered by Government to ensure shrub growth and rejuvenation. Trimming shall be performed at the base of the branches or at the branch junctions.

The Contactor shall plant shrubs where indicated by the Government. Planting work shall be performed in accordance with DIN 18916. Planting holes shall be excavated in adequate size. The excavated material shall be replaced with sieved topsoil. Upon completion of planting work, shrubs shall be watered. Shrubs shall be anchored only when required. The Contractor shall water and maintain newly planted shrubs in proper condition. Dead plants, and/or plants showing major damage or failure to thrive shall be replaced without cost for the Government. COR will perform site meeting to check vitality in September after planting action. Plant replacement, if not vital, shall be in the same year in November/December timeframe.

5.2.26 Irrigation / Watering.

- Watering of trees including watering with water bags

The Contractor shall water the trees as identified broadly around the tree (about 1m surrounding) with a spray head unless agreed otherwise. Contractor shall ensure that

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

watering is performed independently during dry weather. When ordered by the Government watering shall start not later than 3 days after order has been placed.

- Young trees shall be watered with 150 l/per service and tree. About 100 trees must be watered at a minimum per task. The Contractor may obtain water from Government water hydrants at no charge.
- . The Contractor shall water the trees using a water barrel placed on a vehicle. The Contractor may obtain water from next available rainwater basin or water hydrant at no charge.
- The Contractor shall water the trees using watering bags. At every tree identified by COR two connected watering bags shall be placed, mesh wire or equal shall be used around trees between watering bag and tree to protect the tree stem.
- The Contractor shall install grey watering dike, 10mm wall strength, 100l PVC-U, diameter 800, 250/300 mm height, tool less linking solution with centering pins to ensure easy sealing, water quantity marking, robust design, reusable. Watering dikes shall be labeled and reused at another tree site on USAG WI Grounds as directed by COR.

5.2.27 Operation of Irrigation Systems. N/A.

5.2.28 Maintenance of Irrigation Systems. N/A.

5.2.29 Service/Maintain Xeriscape Areas. N/A.

5.2.30 Athletic Fields Grounds Maintenance.

The Contractor shall maintain athletic fields, including baseball, softball, multi-purpose and other recreational/athletic fields, IAW the Work Capability Levels table.

5.2.31 Special Services.

The Contractor shall provide additional services as necessary due to unforeseen circumstances, including but not limited to, Very Important Person (VIP) visits, retreats, ribbon cutting ceremonies, and open houses. The Contractor shall provide extra labor and equipment to service pre-identified locations within the High Visibility and Common Areas beyond the normal ground maintenance. The COR/ACOR will notify the Contractor of special service requirements NLT forty-eight (48) hours prior to the event. The Contractor shall coordinate special service requirements with the existing grounds maintenance schedule.

Disposal of storm debris / Windfall.

The Contractor shall provide emergency services due to severe weather, storms, or other unforeseen events, within 24 hours of notification by the COR or other Government representative (e.g., Directorate of Emergency Services personnel), including weekends and holidays. A list of authorized Government personnel will be provided to the Contractor not later than 10 days after contract award. Areas and trees with storm damage, including roads and walkways, shall be cordoned off until safe conditions are

restored. Broken tree branches and storm debris shall be collected for pick up, removed and disposed.

The Contractor shall provide all required labor, tools (e.g., cutting, digging and cleaning tools, chain saws) and safety materials (e.g., warning signs, caution tape). Where required, weighing notes from the recycling/compost plant shall be provided to the COR after completion of disposal services. All single tasks of this Paragraph are listed in Attachment 10, Technical Exhibits AFH and OMA).

5.2.32 Special Event Services.

Upon receiving directions from the COR/ACOR, the Contractor shall complete work prior to the event. In the event the Contractor must deviate from their schedule to meet special event requirements, the Contractor shall do so at no additional cost to the Government. The Contractor shall be authorized/entitled one (1) additional duty day to return to their normal operations. Furthermore, the Contractor will not be held accountable for any unsatisfactory performance results, on a quality assurance inspection or complaint, due to KO-directed schedule change(s), until such point when the Contractor resumes normal operations.

5.2.33 Service Common Areas.

Semi-Improved Grounds used for operational and maintenance purposes. Erosion control shall be the predominant grounds maintenance work performed in this area by the Contractor.

5.2.34 Service Fire Breaks and Ranges.

These are acreage on which periodic recurring maintenance shall be performed. Activities include mowing for life, health, safety, brush control, erosion control, dust control, and drainage maintenance. Bush control, including prescribed burning and plowing to reduce fire risks in order to mitigate injuries from wildlife or damage to real property. The Contractor shall maintain drainage and sustain non-impact area range berms, real property facilities (excluding impact areas) on the ranges and training areas. Ranges include maneuver and training land, live-fire ranges, and other field training sites but shall exclude all impact areas. The Contractor shall obtain from the COR/ACOR schedules for periodic recurring maintenance activities on ranges during the available timeframes, in compliance with the installation Range Facilities Management Support System (RFMSS). In the event the Contractor deviates from the COR/ACOR provided schedule, the Contractor shall do so at no additional cost to the Government.

5.2.35 Service Unimproved Areas.

Undeveloped areas, grazing lands, forests, lakes, ponds, wetlands, and special natural areas: refuges, natural areas, forests and wildlife corridors where low levels of maintenance are acceptable, and visibility is minimal. Services are not provided for Unimproved Areas as identified in the Work Capability Levels table.

5.2.36 Service Specialized Locations. N/A

5.3 Other Special Services. N/A

5.3.1 Refuge and Nature Trail Maintenance. N/A.

5.3.2 Special Equipment Requirements.

All rotary mowers used within High Visibility Areas shall be equipped with mulching blades and have discharges blocked. All equipment used to perform grass mowing and leaf removal operations on High Visibility Areas shall be equipped with turf type tires. Equipment not essential for the performance of grass mowing or leaf removal functions (e.g., equipment with agricultural tires, wheel weights, snow blades, or other accessories that may damage turf or tree root zones by compaction, rutting, or scalping), shall not be permitted on High Visibility Areas. A rotary mower capable of negotiating steep slopes and cutting heavy clumps and brushy vegetation shall be used to service Unimproved Grounds and perform grassland habitat maintenance. The Contractor shall submit a complete equipment list including make, model, specifications and catalog cut sheets for KO approval with the proposal.

PART 6 APPLICABLE PUBLICATIONS

6.0 Applicable Publications (Current Editions).

Publication Sources include but are not limited to DoD Issuances (<https://www.esd.whs.mil/DD/DoD-Issuances/>); Army Publishing Directorate (<https://armypubs.army.mil/>), Code of Federal Regulations (<https://www.ecfr.gov/>) and Federal Acquisition Regulations (<https://www.acquisition.gov/>).

6.1 Regulations, Publications, Manuals, Local Policies and Procedures.

The Contractor must abide by all LOR including but not limited to the following.

ACC PAM 70-1	Interim Army Contracting Command – Contracting Officer's Representative Policy Guide
ANSI Z87.1-2003	Practice for Occupational and Educational Personal Eye and Face Protection Devices
AR 25-2	Information Management: Army Cybersecurity, section 2-34 All personnel, 4-25 Privately owned information technology.
AR 70-1	Army Acquisition Policy
AR 70-13	Management and Oversight of Service Acquisitions
AR 190-13	Army Physical Security Programs, Chapter 5 Security Identification Cards and Badges, Chapter 8 Army Installation and Facility Access Control, Chapter 20 Vehicle control
AR 190-51	Security of Unclassified Army Resources (Sensitive and Non-sensitive), Appendix D Policy for locks and keys
AR 200-1	Environmental Protection and Enhancement, Green Procurement policies.
AR 215-1	Military Morale, Welfare, and Recreation Programs and Non-appropriated Fund Instrumentalities
AR 381-12	Threat Awareness and Reporting Program
AR 380-5	Army Information Security Program, 1-14.

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

AR 385-10	Army Safety Program, Chapter 3 Accident Investigation and Reporting, Chapter 4 Contracting Safety
AR 420-1	Army Facilities Management, section VI Grounds maintenance Services.
AR 530-1	Operations Security, section 2-22, All Army personnel, to include contractors.
AR 608-10	Child Development Services, section 5-37 Grounds maintenance and housekeeping services
29 CFR Part 1910	Occupational Safety and Health Standards
40 CFR	Protection of the Environment
40 CFR Subchapter I	Solid Wastes
40 CFR Part 302	Protection of Environment, Designation, Reportable Quantities and Notification
49 CFR 390-396	Motor Carrier Safety Standards
49 CFR 571	Federal Motor Vehicle Safety Standards
CAA	Clean Air Act (CAA)
CWA	Clean Water Act (CWA)
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA)
DA PAM 5-20	Competitive Sourcing Implementation
DA PAM 385-10	Army Safety Program, Chapter 4, Contracting Safety
DA PAM 385-40	Army Accident Investigations and Reporting
DoDD 5500.7	Standards of Conduct
DoDI 2000.16, Vol. 1	DOD Antiterrorism Standards
DoDI 5000.72	DoD Standard for Contracting Officer's Representative (COR) Certification
EM 385 1. 1.	Safety and Health Requirements Manual
EO 14042:	Ensuring Adequate COVID Safety Protocols for Federal Contractors

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

FAR Part 23.4	Use of Recovered Materials and Biobased Products
Federal Standard #313	Material Safety Data and Disposal Data for Hazardous Materials Furnished to Government Activities
FIPS PUB 201-2	Personal Identity Verification (PIV) of Federal Employees and Contractors
HSPD 12	Homeland Security Presidential Directive 12 Policy for a Common Identification Standard for Federal Employees and Contractors
MEDCOM Reg. 40-35	Management of Regulated Medical Waste
NFPA 1.12-2	Combustible Fibers
OMB M-05-24	Office of Management and Budget (OMB) Guidance Implementation of Homeland Security Presidential Directive (HSPD) 12-Policy for a Common Identification Standard for Federal Employees and Contractors
TB MED 531	Facility Sanitation Controls and Inspections
TM 5-609	Military Grounds maintenance Services Manual
TM 5-630	NATURAL RESOURCES LAND MANAGEMENT

PART 7 FORMS AND REPORTS

7.0 Mandatory Records and Report Forms.

DD or DA Form Sources include but are not limited to: DoD Forms Home
(<https://www.esd.whs.mil/Directives/forms/>); Army Publishing Directorate
(<https://armypubs.army.mil/>)

DA Form 5513	Key Control Register and Inventory
DD Form 200	Financial Liability Investigation of Property Loss (eFLIPL)
DD Form 254	DoD Contract Security Classification Specification
DD Form 577	Appointment/Termination Record
DD Form 1348-1	Release/Receipt Document
SF 85P	Position of Public Trust
SF 701	Activity Security Checklists

PART 8

ATTACHMENT/TECHNICAL EXHIBIT LISTING

8.0 Attachment/Technical Exhibits (TEs).

TEs identify which areas are to receive grounds maintenance service, the type of floor coverings, the square footage (SF) of the building/areas, any special security considerations, and any constraints as to when during the day or week scheduled services can be performed at these building(s)/area(s).

- SF is calculated by taking the net SF from ePRISMS or another Army authorized rendering of the area to be maintained.
- TEs identify tasks and frequencies for minimum standards for each type of area.
- TEs identify total SF to receive ground maintenance service under this contract.
- This is expected to change throughout the contract period as new facilities are added, and other facilities are removed from the contract due to demolition/renovations or other situations.
- Total requirement may change by as much as +/- XX% over the life of the contract and at any given point in time due to changes in facility usage, e.g.:
 - Quantities of lawn maintenance are expected to change throughout the contract period.
 -
 - **Attachment 1** – Performance Requirements Summary
 -
 - **Attachment 2** – Deliverables Schedule
 -
 - **Attachment 3** – Work Capability Levels
 -
 - **Attachment 4** – AFH_Grounds_Maps_incl_tree_assessment
 -
 - **Attachment 5** – OMA Grounds_Maps_incl_tree_assessment
 -
 - **Attachment 6** – AFH Duplex – Single Quarter info
 -
 - **Attachment 7** – ETC (Reimbursable Customer) Info & Maps
 -
 - **Attachment 8** – Urban Tree Inventory Data Entries
 -
 - **Attachment 9** – Environmental Benign Maintenance
 -
 - **Attachment 10** - Exhibit A AFH and B_OMA_Area Mass (and related Tree Assessments)
 - **Attachment 11** – USAG WI Red Plan (Spill plan)

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

8.1 Attachment 1/TE-1 – Performance Requirements Summary.

Performance Objective	Standard	Performance Threshold
PRS # 1 Contractor shall comply with PWS provisions relating to Management and Administration.	Requirements	>100% Compliant
PRS # 2 The Contractor shall mow grass only when the minimum height is reached or exceeded as indicated by the Work Capability Levels, TE 3.	Capability Levels, TE 3	>100% Compliant
PRS # 3 When Grounds Maintenance operations are started within any area, services shall be pursued diligently to ensure timely completion and a uniform appearance of the area.	Once work on an area is started, it shall be carried out continuously, during the Contractor's regular working hours, until work in this area is completed. Mowing operations shall not exceed two (2) working days in any assigned area.	100% Compliant
PRS # 4 Contractor shall comply with PWS provisions relating to Contractor Furnished Items and Services processes	Standard PWS	100% Compliant
PRS # 5 Contractor shall comply with PWS provisions relating to Attachment and Exhibit Listing processes	Standard PWS	100% Compliant
PRS # 6 The Contractor shall service all trees across the USAG Wiesbaden footprint when directed by the COR.	Trees that become diseased or die shall be removed and replaced with like trees.	100% Compliant

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (ISR 404 – Grounds Maintenance Services)

8.2 Attachment 2/TE-2 – Deliverables Schedule.

1) Quality Control Plan (QCP) in accordance with (IAW) Para 1.4.1, including analysis of quality control and timeliness reports.	Within ten (10) business days of contract award.	1 copy in a digital format	Delivery in electronic format via email (i.e. Excel Spreadsheet)	COR/USAG Wiesbaden Directorate of Public Works
2) Report of potential issues which might affect performance (IAW) Para 1.4.1 of PWS.	Within two (2) business day as soon as possible before the issue develops.	1 copy in a digital format	Delivery in electronic format via email (i.e. Excel or Word Spreadsheet)	COR/USAG Wiesbaden Directorate of Public Works
3) Contractor Work Plan and Work Schedule, IAW Para 1.8.2 1.4. 1 and 5.1 of PWS.	Within 10 days of contract award. Revised version within additional three (3) business days after return of Work Plan with COR comments. Work Schedule once per week.	1 copy in a digital format	Delivery in electronic format via email (i.e. Excel Spreadsheet)	COR/USAG Wiesbaden Directorate of Public Works
4) Installation Pass Log submission, (IAW) Para 1.8.11.1 of PWS.	Installation pass log submission within Ten (10) business days after contract award	Original and digital	Delivery in accordance with the process	To the issuing office
4.1) Update of Installation pass access (IAW) Para 1.8.11.1 of PWS.	Installation pass log update submission within five (5) days of any addition or removal.	Original and digital	Delivery in accordance with the process	To the issuing office
4.2) Collection of installation pass upon termination of employment (IAW) Para 1.8.11.1 of PWS	Installation access pass return within ten (10) days	Original and digital	Delivery in accordance with the process	To the issuing office
4.3) Collection and return of all installation passes upon termination or cancellation of the contract. (IAW) Para 1.8.11.1 of PWS	Installation access passes return within thirty (30) days	Original and digital	Delivery in accordance with the process	To the issuing office
5) Police good conduct certificate (polizeiliches Führungszeugnis) and Passport Part 1.8.11.1 of PWS.	Within 10 days of contract award.	Original and 1 digital copy	Hardcopy (issued not longer than 4 months ago) and delivery in electronic format via email.	To the issuing office
6) Certificate Anti-Terrorism Training Level 1 verification, IAW 1.8.14 of PWS.	Within 30 days of contract award,	1 copy in a digital format	Delivery in electronic format via email.	COR/USAG Wiesbaden Directorate of Public Works
7) iWATCH training, IAW Para 1.8.15 PWS.	Within 30 days of contract award, and within 30 days of employment under this contract. To be provided NLT 10 days after completion of training. Refresher training: every 12 month, to be provided 10 days after completion of training. Classroom	1 copy in a digital format	Delivery in electronic format via email.	COR/USAG Wiesbaden Directorate of Public Works

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) **(ISR 404 – Grounds Maintenance Services)**

	training within 10 days after completion of training.			
8) OPSEC training IAW Para 1.8.16 PWS	Within 30 days after contract start, or within 30 days of employment under this contract. To be provided NLT 10 business days after completion of training. Refresher training: every 12 months, to be provided 10 days after completion of training. Classroom training within 10 days after completion of training.	1 copy in a digital format	Delivery in electronic format via email.	COR/USAG Wiesbaden Directorate of Public Works
9) Threat Awareness and Reporting Program Training (TARP) 1.8.17	Within 30 days of assignment or employment, Refresher training every 12 months. Classroom training within 15 days after completion of training.	1	Electronically	COR
10) Information and Certificates for Contract Manager and alternate and Information for Contractor Employees IAW section 1.10.5 of PWS.	Names shall be submitted Within 1 week of contract award. All certificates shall be provided within 1 week of contract award. For new employees prior to start of performance for review and approval.	1	Electronically	COR
11) Safety Plan IAW Para 1..2 of PWS	Within 30 business days of contract award, or within 30 days of employment under this contract. To be provided NLT 10 days after completion of training.	1	Electronically	COR
12) Disposal Documents IAW Para 5.1 of PWS	10 days after disposal.	1	Electronically in MS Excel or compatible format	COR
13) 24/7 telephone number in the event emergency maintenance is required IAW Para 5.1 of PWS.	Within ten (10) days of contract award.	1	Electronically	COR/USAG Wiesbaden Directorate of Public Works and Contracting Officer RCOW
14) Work Certificate for work completed IAW Para 5.2.1 of PWS.	Weekly, latest on Monday close of business (CoB) for work completed during previous week, or earlier for subsequent inspection.	1	Electronically	COR
15) Invoice IAW paragraph 5.2.1 of PWS.	As attachment to the related invoice.	1	Same as above	COR
16) Delivery note of mineral fertilizer IAW Para 5.2.6 of PWS .	Before start of service	1	Electronically	COR
17) Report of unsafe trees and trees with EPS/OPC infestation IAW 5.2.19 of PWS.	Immediately at the day of finding.	1	Electronically, unsafe trees additionally per phone	COR and Government SME
17.1) Tree inspection, Tree removal and Tree	within five (5) working days of the end of each month	1	Electronically and one hardcopy format	COR

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (**ISR 404 – Grounds Maintenance Services**)

replacement Report IAW 5.2.19 of PWS.				
18) Tree Inventory with individual tree assessment report IAW 5.2.19 of PWS.	NLT 31 July of each year if not specified otherwise with COR.	1	Electronically and one hardcopy format	COR
18.1) German herbicide application certificates or license IAW 5.2.12 of PWS.	Not longer than ten (10) days during the phase-in period	1	Electronically	COR
18.2) List of chemicals used monthly IAW 5.2.12 of PWS.	Monthly	1	Electronically	COR
19) Annual detailed inspection of trees IAW 5.2.19 of PWS.	Not longer than one month after inspection has been performed.	1	Electronically and one hardcopy format	COR
20) Additional inspection of newly planted trees. Report IAW 5.2.14 of PWS.	Within two (2) weeks after inspection has been performed.	1	Electronically and one hardcopy format	COR and Government SME
21) Minutes report IAW 1.8.23 of PWS	Within five (5) days after the meeting	1	Electronically	COR

USAG Wiesbaden Grounds Maintenance Services Enterprise-wide Performance Work Statement (PWS) (ISR 404 – Grounds Maintenance Services)



