

PERFORMANCE WORK STATEMENT (PWS)

FOR

Iowa Army National Guard

Controlled Humidity Asset Program Preventative Maintenance Services

1.0 General:

1.1 Scope: The contractor shall provide all personnel, equipment, tools, materials, supervision, and quality control necessary, except as specified in Paragraph 3.0 as Government Furnished, to perform Preventative Maintenance (PM) Service on 21 Iowa Army National Guard Controlled Humidity Asset Program (CHAP) systems. Regular preventive maintenance servicing is vital to maximizing equipment efficiency and longevity, and reducing unscheduled downtime. PM Service for CHAP systems shall include CHAP air dehumidification units (ADUs), controls, sensors, and safety devices services, as defined in this PWS.

1.1.1 Objective: Provide scheduled PM services, based upon the recommendations of the equipment manufacturer, which are designed to extend the useful service life of the equipment and maintain the equipment in an operational state.

1.2 Background: A service contract is required to provide PM to CHAP that utilizes controlled humidity systems located in IA ARNG shelters for entire equipment protection to protect the crew/interior compartments of weapons systems and electronics shelters or containers. Contractor shall maintain installed CHAP systems; maintaining the CHAP dehumidifiers, controls and sensors, safety devices and report CHAP system condition for CHAP systems Iowa Army National Guard (IA ARNG) designated under the PWS.

1.3 Period of Performance (PoP): The Period of Performance to complete CHAP PM services shall be 120 days from the date of award.

1.4 General Information:

1.4.1 Place and Performance of Services: The contractor shall provide services between the hours of 0800-1530 on Monday through Friday, except on recognized US holidays or when the Government facility/installation is closed due to local or national emergencies, administrative closings, or similar Government-directed facility/installation closings. Performance shall be at IA ARNG CHAP SYSTEM SITES. The contractor shall at all times maintain an adequate work force for the uninterrupted performance of all tasks defined within this PWS when the Government facility/installation is not closed for the above reasons. When hiring personnel, the contractor shall keep in mind that the stability and continuity of the work force are essential. **Teleworking is not authorized.**

1.4.1.1 Telework: The Government **does not permit** the contractor to telework in support of this requirement. In furtherance of Continuity of Operations Planning (COOP), a telework program may be enacted to ensure that the Government's mission-critical operations stay operational during times of national emergency or incidents of national significance. Telework shall be at no additional cost to the Government.

1.4.1.2 Unscheduled gate closures by the Security Police may occur at any time causing all personnel entering or exiting a closed installation to experience a delay. This cannot be predicted or prevented. Contractors are not compensated for unexpected closures or delays. Vehicles operated by contractor personnel are subject to search pursuant to applicable regulations. Any moving violation of any applicable motor vehicle regulation may result in the termination of the contractor employee's installation driving privileges.

1.4.1.3 The contractor's employees shall become familiar with and obey the regulations of the installation; including fire, traffic, safety and security regulations while on the installation. Contractor employees should only enter restricted areas when required to do so and only upon prior approval. All contractor employees shall carry proper identification with them at all times, and shall be subject to such checks as may be deemed necessary. The contractor shall ensure compliance with all regulations and orders of the installation, which may affect performance. The Government reserves the right to direct the removal of an employee from Government property or revoke access to Government systems for misconduct, security reasons, or any overt evidence of communicable disease. Removal of contractor employees for reasons stated above does not relieve the Contractor from responsibility for total performance of this contract.

1.4.2 Recognized Holidays: The following are recognized United States (US) holidays. The contractor **shall not** perform services on these days:

- 1.4.2.1 New Year's Day: January 1st
- 1.4.2.2 Martin Luther King, Jr.'s Birthday
- 1.4.2.3 President's Day
- 1.4.2.4 Memorial Day
- 1.4.2.5 Juneteenth National Independence Day: June 19th
- 1.4.2.6 Independence Day: July 4th
- 1.4.2.7 Labor Day
- 1.4.2.8 Columbus Day
- 1.4.2.9 Veteran's Day: November 11th
- 1.4.2.10 Thanksgiving Day
- 1.4.2.11 Christmas Day: December 25th

1.4.3 Quality Control (QC): The contractor shall develop and maintain an effective QC Plan (QCP) to ensure services are performed in accordance with this PWS. The contractor shall develop and implement procedures to identify, prevent, and ensure non-recurrence of defective services. The contractor's QCP is the means by which it assures itself that its work complies with the requirements of the contract. As a minimum, the

contractor shall develop QC procedures that address the areas identified in Technical Exhibit 1, Performance Requirements Summary (PRS). A final QCP shall be submitted to the Contracting Officer Representative (COR) NLT 10 days after contract award. After acceptance of the QCP, the contractor shall obtain the Contracting Officer's (KO's) acceptance in writing of any proposed changes to its QCP.

1.4.4 Quality Assurance (QA): The Government will evaluate the contractor's performance under this contract in accordance with the Quality Assurance Surveillance Plan (QASP). This plan is primarily focused on what the Government will do to ensure that the contractor has performed in accordance with the performance standards. It defines how the performance standards will be applied, the frequency of surveillance, and acceptable quality level(s) or defect rate(s).

1.4.5 Installation Access and Security Requirements. The contractor shall comply with all applicable installation/facility access and local security policies and procedures, which may be obtained from the COR. The contractor and all associated subcontractor employees shall provide all information required for background checks to meet installation access requirements to be accomplished by installation Provost Marshal Office, Director of Emergency Services, or Security Office. The contractor shall ensure compliance with all personal identity verification requirements as directed by Department of Defense (DoD), Headquarters Department of Army (HQDA) and/or local policy (see PWS 6.0). Should the Force Protection Condition (FPCON) change, the Government may require changes in contractor security matters or processes.

1.4.5.1 Reserved.

1.4.5.2 For contractors that do not require a CAC, but require access to a DoD facility or installation: Contractor and all associated sub-contractors employees shall comply with adjudication standards and procedures using the National Crime Information Center Interstate Identification (NCIC-III) and Terrorist Screening Database (TSDB) (Army Directive 2014-05), and applicable installation, facility and area commander installation/facility access, and local security policies and procedures (provided by a Government representative).

1.4.5.3 Reserved.

1.4.5.4 iWATCH Training: The contractor and all associated subcontractors with an area of performance within an Army-controlled installation, facilities or area shall brief all employees on the local iWATCH program (training standards provided by the requiring activity Antiterrorism Officer (ATO)). This local developed training shall be used to inform employees of the types of behavior to watch for and instruct employees to report suspicious activity to the COR or the KO. This training shall be completed within 30 calendar days of contract award and within 30 calendar days of new employees commencing performance. The contractor shall report completion for each contractor employee and subcontractor employee to the COR, within 15 calendar days after completion of training.

1.4.5.5 Communications Security/Information Technology (COMSEC/IT) Security. All communications with DoD organizations are subject to COMSEC review. All telephone communications networks are continually subject to intercept by unfriendly intelligence organizations. DoD has authorized the military departments to conduct COMSEC monitoring and recording of telephone calls originating from, or terminating at, DoD organizations. Therefore, the contractor is advised that any time contractor personnel place or receive a call they are subject to COMSEC procedures. The contractor shall ensure wide and frequent dissemination of the above information to all employees dealing with DoD information. The contractor shall abide by all Government regulations concerning the authorized use of the Government's computer network, including the restriction against using the network to recruit Government personnel or advertise job openings.

1.4.5.6 Reserved.

1.4.5.7 Reserved.

1.4.5.8 Reserved.

1.4.5.9 Reserved.

1.4.5.10 Reserved.

1.4.5.11 Reserved.

1.4.5.12 Reserved.

1.4.5.13 Reserved.

1.4.5.14 Reserved.

1.4.6 Physical Security. The contractor shall safeguard all Government property provided for contractor use. At the close of each work period, Government facilities, equipment and materials shall be secured.

1.4.6.1 Key Control. NOTE: All references to keys include key cards. The contractor shall establish and implement methods of ensuring that no keys/key cards issued by the Government are lost or misplaced or are used by unauthorized persons. No keys issued by the Government shall be duplicated. Such procedures shall include turn-in of any issued keys by personnel who no longer require access to locked areas.

1.4.6.1.1 The contractor shall immediately report any occurrences of lost or duplicated keys/key cards to the COR.

1.4.6.1.2 In the event keys, other than master keys, are lost or duplicated, the contractor shall, upon direction by the KO, re-key or replace the affected lock or locks; however, the Government, at its option, may replace the affected lock or locks or perform re-keying. When the Government replaces or re-keys the locks, the Government will deduct the total cost of lock replacement or re-keying from the monthly payment due the contractor. In the event a master key is lost or duplicated, the Government will replace all locks and keys for that system, and will deduct the total cost from the monthly payment due the contractor.

1.4.6.1.3 The contractor shall prohibit the use of the Government issued keys/key cards by any persons other than the contractor's employees. The contractor shall prohibit the opening of locked areas by contractor employees to permit entrance of persons other than contractor employees engaged in the performance of services in those areas, or personnel authorized entrance by the KO.

1.4.7 Special Qualifications: The contractor must ensure that any personnel performing under a contract are fully trained, licensed, certified, and otherwise qualified to provide CHAP services. (NOTE: The Government does not provide training to contractors).

1.4.8 Post Award Conference/Periodic Progress Meetings: The contractor agrees to attend any post award conference convened by the KO. The KO, COR and other Government personnel, as appropriate, may meet periodically with the contractor to review the contractor's performance. At these meetings, the KO will apprise the contractor of how the Government views the contractor's performance and the contractor shall apprise the Government of problems, if any, being experienced. The contractor shall resolve outstanding issues raised by the Government. Contractor attendance at these meetings shall be at no additional cost to the Government.

1.4.9 Contract Manager (CM): The contractor shall designate a CM who shall ensure performance under this contract. The name of this person, and an alternate who shall act for the contractor when the CM is absent, shall be designated in writing to the KO. The CM or alternate shall have full authority to act for the contractor on all contract matters relating to daily operation of this contract. The CM shall work through the COR, to resolve issues, receive technical instructions, and ensure adequate performance of services. The CM shall ensure that contractor employees do not perform any services outside the scope of the contract without an official modification issued by the KO. The CM shall ensure contractor employees understand that services performed outside the scope of the contract are performed wholly at the expense of the contractor.

1.4.10 Reserved.

1.4.11. Combating Trafficking in Persons: The United States Government has adopted a zero tolerance policy regarding trafficking in persons. Contractors and contractor employees shall not engage in severe forms of trafficking in persons during the period of performance of the contract; procure commercial sex acts during the period of performance of the contract; or use forced labor in the performance of the contract. The

Contractor shall notify its employees of the United States Government's zero tolerance policy, the actions that will be taken against employees for violations of this policy. The contractor shall take appropriate action, up to and including termination, against employees or subcontractors that violate the US Government policy as described at RFO FAR 22.17.

1.4.12 Reserved.

1.4.13 Reserved.

1.4.14 Organizational Conflicts of Interest (OCI): The contractor and subcontractor personnel performing services under this contract may receive, have access to or participate in the development of proprietary or source selection information (e.g., cost or pricing information, budget information or analyses, specifications or work statements, etc.) or perform evaluation services which may create a current or subsequent OCIs, as defined in FAR Subpart 9.5. The contractor shall notify the KO immediately whenever it becomes aware that such access or participation may result in any actual or potential OCI and shall promptly submit a plan to the KO to avoid or mitigate any such OCI. The contractor's mitigation plan will be determined to be acceptable solely at the discretion of the KO. In the event the KO unilaterally determines that any such OCI cannot be satisfactorily avoided or mitigated, the KO may impose other remedies as he or she deems necessary, including prohibiting the contractor from participation in subsequent contracted requirements which may be affected by the OCI.

1.4.15 Reserved.

2.0 Definitions and Acronyms:

2.1 Definitions:

2.1.1 Contractor: A supplier or vendor awarded a contract to provide specific supplies or service to the Government. The term used in this contract refers to the prime.

2.1.2 Defective Service: A service output that does not meet the standard of performance associated with the PWS.

2.1.3 Deliverable: Anything that can be physically delivered and includes non-manufactured things such as meeting minutes or reports.

2.1.4 Key Personnel: Contractor personnel that are evaluated in a source selection process and that may be required to be used in the performance of a contract by the PWS. When key personnel are used as an evaluation factor in best value procurement, an offer can be rejected if it does not have a firm commitment from the persons that are listed in the proposal.

2.1.5 Physical Security: Actions that prevent the loss or damage of Government property.

2.1.6 Quality Assurance: The Government procedures to verify that services being performed by the Contractor are performed according to acceptable standards.

2.1.7 Quality Assurance Surveillance Plan (QASP): An organized written document specifying the surveillance methodology to be used for surveillance of contractor performance.

2.1.8 Quality Control: All necessary measures taken by the Contractor to ensure that the quality of an end product or service shall meet contract requirements.

2.1.9 Subcontractor: One that enters into a contract with a prime contractor. The Government does not have privity of contract with the subcontractor.

2.2 Acronyms:

ADU	Air Dehumidification Unit
CHAP	Controlled Humidity Asset Program
CM	Contract Manager
COR	Contracting Officer Representative
DFARS	Defense Federal Acquisition Regulation Supplement
DoD	Department of Defense
FSR	Field Service Report
RFO FAR	Revolutionary FAR Overhaul, Federal Acquisition Regulation
GFP/M/E/S	Government Furnished Property/Material/Equipment/Services
HQDA	Headquarters, Department of the Army
HSPD	Homeland Security Presidential Directive
IS	Information System(s)
KO	Contracting Officer
OCI	Organizational Conflict of Interest
OEM	Original Equipment Manufacturer
PM	Preventative Maintenance
POC	Point of Contact
PRS	Performance Requirements Summary
PWS	Performance Work Statement
QA	Quality Assurance
QASP	Quality Assurance Surveillance Plan
QC	Quality Control
QCP	Quality Control Program
RH	Relative Humidity
TE	Technical Exhibit

3.0 Government Furnished Property, Material, Equipment and Services (GFP/M/E/S): The Government will provide the property, material, equipment, and/or services listed below solely for the purpose of performance under this contract:

3.1 Property: **None**

3.2 Materials: **None**

3.3 Equipment: **None**

3.4 Services: **None**

3.5 Utilities: All utilities in the facility will be available for the contractor's use in the performance of this contract. The contractor shall instruct employees in utilities conservation practices. The contractor shall operate under conditions that preclude the waste of utilities, which include turning off the water faucets or valves after using the required amount.

4.0 Contractor Furnished Property, Materials, and Equipment (CFP/M/E):

4.1 General: Except for those items specifically stated to be Government-Furnished in Paragraph 3.0, the contractor shall furnish everything required to perform these services as indicated in Paragraph 1.1.

4.2 Reserved.

4.3 Reserved.

5.0 Requirements: The contractor shall:

5.1 Provide PM services for designated IA ARNG CHAP systems designated in TE #3.

5.1.1 Standard of Measurement: The Contractor shall maintain the CHAP systems so they can maintain a daily average relative humidity (RH) of less than 50% RH 100% of the time, and maintain a daily average RH of less than 45% RH 90% of the time.

5.1.2 Exceptions to Standard of Measurement is when systems are not operational due to acts of nature, Force Majeure, damage caused by anyone other than contractor, improper maintenance or repair attempts from 3rd party or due to other actions by the customer (ex. power turned off, shelter doors are open, control sensors left on ground or improperly installed, improperly tarped vehicles etc.), when the electrical power is otherwise off or if there is a CHAP system component (dehumidifier, control system, shelter door, etc.) failure.

5.2 Maintenance Program

5.2.1 Preventive Maintenance: The contractor shall:

5.2.1.1 Perform On-site Preventive Maintenance no less than as required by the OEM.

5.2.1.2 Provide scheduled PM services, based upon the recommendations of the equipment manufacturer, which are designed to extend the useful service life of the equipment and maintain the equipment in an operational state. These PM actions (i.e., filter cleaning, belt adjustment, rotor and seal inspections and tool/sensor calibration) are based on either hourly or calendar timeframes, but the Contractor shall ensure that the PM schedule supports the environmental conditions of each site above OEM recommendations.

5.2.1.3 Document all system actions and observations on a Field Service Report (FSR) for each site visited. Contractor shall provide copies of the FSR upon request. Alternatively, the FSRs shall be available on the Contractor website, and the IA ARNG COR shall be provided access to the website.

5.2.2 On Site Evaluation: The Contractor shall:

5.2.2.1 Perform on-site system checks beginning with a visual walk-through to identify apparent system anomalies. Visual checks shall include inspection of all CHAP Systems components, including: dehumidifier (ADU), controls, air distribution, adapters, safety devices, exhausting systems, building, door seals, door sensors and power monitoring devices as appropriate.

5.2.2.2 For systems with shelters, inspect the enclosure for structural integrity, damage, points of moisture intrusion and any other identifiable defects that impact upon the environment envelope.

5.2.2.3 Visually check the dehumidifier for system faults, damage, rotor rotation, and any other indication of system problems and complete a full system operational inspection to verify performance meets OEM guidelines. Filters shall be cleaned and/or replaced.

5.2.2.4 In cases where an identified malfunction is determined to be simple, the Contractor shall attempt to resolve the malfunction and return the system to full mission capable (FMC) status. However, in no case is a Contractor to bypass, tamper with, or otherwise modify or alter explosion prevention, personnel safety and energy conservation devices installed as integrated components of the CHAP system. If a Corrective Maintenance (CM) is identified outside of the Preventative Maintenance (PM) scope, the Contractor shall quote all costs associated with repair action and submit to COR for disposition within 10 days after completion of the evaluation.

5.2.3 PM Checklists: The Contractor shall develop and utilize an established set of checklists for the performance of PM. The checklists shall be supplemented by

information contained in Original Equipment Manufacturer (OEM) manuals for all CHAP system components.

5.2.3.1 The IAARNG and Contractor shall mutually agree to PM checklist prior to beginning of contract.

5.2.4 Personnel and Equipment Safety Devices: When performing PM Inspections of Personnel and Equipment Safety Devices, the Contractor shall:

5.2.4.1 Perform a visual inspection of each safety device for any physical damage or tampering and document all pertinent repair actions.

5.2.4.2 Perform a visual check of all wiring. Check for fault conditions or error indications. Initiate corrective actions, perform combustible fume calibration at regular intervals of full calibration IAW OEM manuals.

5.2.4.3 Perform a full system test of each safety device and record on the FSR. Provide report within 10 days after completion of inspection.

5.2.5 Energy Conservation Devices: When performing PM Inspections of Energy Conservation Devices, the Contractor shall:

5.2.5.1 Perform a visual inspection of each Energy Conservation device for any physical damage or tampering and document all pertinent repair actions.

5.2.5.2 Perform a visual check of all wiring or wireless transmitter/receivers. Check and Test lights for fault conditions as indicated by a specific device. Initiate corrective actions, including battery replacement as required.

5.2.5.3 Perform a full system test of each energy conservation device and record on the FSR.

5.2.6 Damage Reporting:

5.2.6.1 If, during the on-site inspection, the contractor identifies damaged system components, the Contractor shall evaluate the damage to determine the severity and impact on system operation and determine if the damaged component can be repaired during the visit or whether it will require another visit.

5.2.6.2 Minor damage such as torn hoses and cut sensor wire, etc. shall be repaired by the contractor where it will not impact costs of the PM or CM visit.

5.2.6.3 Severe damage due to acts of nature, damage caused by any party other than the Contractor and damage to the system due to customer neglect are not covered by the contract unless separately funded. Examples of damage not covered include but are not limited to: damage to vehicle interface adapters, control system components,

OP system posts or metal duct, severe damage to metal building panels (not repairable by the contractor), damage to shelter support structure, damage to doors and locks and damage to the dehumidifier.

5.2.6.4 All damage will be recorded on a damage report. Following review by the Contractor, if damage is deemed severe, it impacts system operation and repairs will be costly, the Contractor shall send the damage report and a quote for repair to the COR for disposition instructions within 24 hours of any occurrence of damage.

5.2.7 Inventory and Modernization Plan: The Contractor shall inventory major CHAP system components and present a plan for budgeting to the Customer for modernization of aging components including but not limited to cellular and control components, dehumidifiers, rotors, hoses and vehicle interface adapters.

5.3 Reporting:

5.3.1 Onsite Contacts. The Contractor shall check in and out with and provide a brief outline of services and findings to, site POC. Any pertinent POC questions or concerns shall be noted in the FSR.

5.3.2 Field Service Report (FSR). After each Site Visit (PM, CM, or combined), an electronic FSR shall be sent to the COR, within 10 days of site visit. The Contractor shall maintain an online repository of all FSRs for the duration of the contract.

5.3.3 The FSR shall include the following minimum information:

- Site Name
- Date of Visit
- Type or Reason for Visit
- System Usage Information (Points Used on OP, % of Shelter Utilized)
- Equipment Type
- System Status, Fully Mission, Partial Mission or Non-Mission Capable
- Any Discrepancies or Observations
- Dehumidifier Run Time
- Customer POC if available

6.0 Applicable Publications: Publications applicable to this PWS are listed below:

Publication (Chapter/Page)	Date of Publication	Mandatory or Advisory	Website
Revolutionary FAR Overhaul (RFO FAR)	Current	Mandatory	https://www.acquisition.gov/?q=browsefar
Defense Federal Acquisition Regulation Supplement	10 Nov 2025	Mandatory	http://www.acq.osd.mil/dpap/dars/dfarspgi/current/index.html or https://www.acquisition.gov/dfars

6.1 Applicable Forms: None

TECHNICAL EXHIBIT #1

Performance Requirements Summary (PRS)

This PRS includes performance objectives the Government will use to determine contractor performance and will compare contractor performance to the Acceptable Quality Level (AQL).

Performance Objective	Performance Standard	Acceptable Quality Levels (AQL)	Surveillance Method / By Whom
5.1 Provide PM Services	CHAP systems maintain a daily average relative humidity (RH) of less than 50% RH 100% of the time, and maintain less than 45% RH 90% of the time	CHAP systems fail to maintain a daily average relative humidity (RH) of less than 50% RH 100% of the time and fail to maintain less than 45% RH 10% of the time	Periodic Inspection / COR, with feedback from Site POC.
5.2.1.1 Preventive Maintenance	On-site Preventive Maintenance be performed as required by the OEM.	10% failure to perform PM once as required by the OEM.	Random monitoring / COR, with feedback from site POC

TECHNICAL EXHIBIT #2

Deliverables Schedule

PWS Reference / Deliverable Title	Frequency	Number of Copies	Medium/Format	Submit To
1.4.1 Quality Control Plan (QCP)	Provide within 10 days after contract award	1	Electronic Submission	Contracting Officer COR
1.4.9 Designation of Contract Manager (CM)	Provide within 10 days after contract award, and within 10 days after appointment of a new/replacement CM.	1	Electronic Submission	Contracting Officer COR
5.2.2 On Site Evaluation	Provide report within 10 days after service completion.	1	Electronic Submission	COR
5.2.4 Personnel and Equipment Safety Devices	Provide report within 10 days after inspection, full calibration IAW OEM manuals	1	Electronic Submission	COR
5.2.6 Damage Reporting	Any occurrence of damage shall be reported within 24 hours of any occurrence of damage.	1	Electronic Submission	COR
5.2.7 Inventory and Modernization Plan	Provide modernization of aging component plan within 120 days after completion of site visit.	1	Electronic Submission	COR
5.3 Field Service Report (FSR)	Provide monthly, within 10 days after each site visit	1	Electronic Submission	COR

TECHNICAL EXHIBIT #3

Controlled Humidity Asset Program (CHAP) Shelters - as of May 2025				
Location	Owning Unit	BLDG Name	ADU OEM	MODEL NUMBER
Boone 700 Snedden Dr Boone, IA 50036	248th ASB	Shelter 1	Munters	ADU-1125-DGA
	2BCT	Shelter 2	Munters	ADU-2250
Camp Dodge 7105 NW 70th Ave Johnston, IA 50131	113TH RSTA	S-32	Munters	ADU-1125
	113TH RSTA	S-35	Munters	ADU-600
	3655th Maint Co	W-11	Munters	ADU-600
	194th FA	S-75	Munters	ADU-1125
	168 INF	S-74	Munters	ADU-1125
	334 BSB	W-0	Munters	ADU-1125
Clinton 1200 13th Ave N Clinton, IA 52732	1034th CSC	Shelter 1	Munters	ADU-750-55-G
	1034th CSC	Shelter 2	Munters	ADU-1150-55-G
Dubuque 1035 Radford Road Dubuque, IA 52002	1034th CSC	Shelter1	Munters	ADU-2250-DGA
	133rd INF	Shelter2	Munters	ADU-1125-DGA-SFS
	1034th CSC	Shelter3	Stulz	ADU-1500-G
Estherville 403 S 18th St Estherville, IA 51334	1-194 FA	Shelter1	Munters	ADU-600-EA
Fort Dodge 1659 Nelson Ave Fort Dodge, IA 50501	FMS 11	Shelter1	Munters	ADU-600
	194TH FA	Shelter 2	Munters	ADU-1125G
Le Mars 1050 Lincoln St NE Le Mars, IA 51031	113TH RSTA	Shelter1	Munters	ADU-1125-DGA-SFS
Sioux City 3200 2d Mech Dr Sioux City, IA 51111	113TH RSTA	Shelter1	Munters	ADU-1125-DGA
Spencer 11 E 23rd St Spencer, IA 51301	194 FA	Shelter1	Munters	ADU-600-EA
Storm Lake 1601 Park St Storm Lake, IA 50588	334TH BSB	Shelter1	Munters	ADU-600-EA
Waterloo 3106 Airport Blvd Waterloo, IA 50703	133 INF	Shelter 1	Munters	ADU-1125-DGA