

1. PROVIDE CHILLER COMPOUND ENLARGEMENT AND EQUIPMENT PAD.

2. PROVIDE CHILLER. PROVIDE NEW AND MODIFY EXISTING PIPING TO CHILLERS. CHILLER TO BE :

MINIMUM 112 TONS Ⓢ 54°F EWT, 40°F LWT,
192 GPM, 95°F EAT, MAXIMUM WATER PRESSURE
DROP-7', 460V/3~~0~~/60Hz

MINIMUM ADJUSTED EFFICIENCY SHALL BE .98KW/TN,
AS CALCULATED BY; .2xKW/TN Ⓢ 100% CAPACITY

+ .3xKW/TN Ⓢ 85% CAPACITY

+ .3xKW/TN Ⓢ 65% CAPACITY

+ .2xKW/TN Ⓢ 35% CAPACITY

= KW/TN ADJUSTED

EFFICIENCY SHALL INCLUDE CONDENSER FAN ENERGY.

3. REUSE EXISTING CHILLED WATER PUMP. TEST, ADJUST, AND BALANCE WATER FLOW FOR 575 GPM Ⓢ 107' DISCHARGE HEAD. AFTER TOTAL SYSTEM BALANCE, TRIM IMPELLOR TO ACTUAL CONDITIONS + 10% DISCHARGE PRESSURE. EXISTING PUMP IS ARMSTRONG 3/4/10, MODEL 4600, 3485 RPM.