

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE		PAGE 1 OF 6 PAGES	
2. AMENDMENT/MODIFICATION NO. AMENDMENT NO. 0008		3. EFFECTIVE DATE 03/19/26		4. REQUISITION/PURCHASE REQ. NO.		5. PROJECT NO. (If applicable) 25-0029	
6. ISSUED BY NAVFAC Mid-Atlantic Resident Officer in Charge of Construction 1107A Birch Street Camp Lejeune, NC 28547-2521		7. ADMINISTERED BY (If other than Item 6) See Item 6		CODE			
8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code)				(X)	9A. AMENDMENT OF SOLICITATION NO. N40085-26-R-9012		
				X	9B. DATED (SEE ITEM 11) 02/05/26		
					10A. MODIFICATION OF CONTRACT/ORDER NO.		
					10B. DATED (SEE ITEM 11)		
CODE		FACILITY CODE					
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS							
☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☐ is extended, ☒ is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment your desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.							
12. ACCOUNTING AND APPROPRIATION DATA (If required)							
13. THIS ITEM ONLY APPLIES TO MODIFICATION OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.							
CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.						
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).						
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:						
	D. OTHER (Specify type of modification and authority)						
E. IMPORTANT: Contractor ☐ is not, ☐ is required to sign this document and return _____ copies to the issuing office.							
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) 25-0029 - P1625 MARSOC Storage and Training Facilities Amendment 0008, Responses to RFI's. This amendment should be acknowledged when your proposal is submitted. Failure to acknowledge the amendment may constitute grounds for rejection of a proposal.							
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.							
15A. NAME AND TITLE OF SIGNER (Type or print)				16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)			
15B. CONTRACTOR/OFFEROR		15C. DATE SIGNED		16B. UNITED STATES OF AMERICA		16C. DATE SIGNED	
(Signature of person authorized to sign)				(Signature of Contracting Officer)			
NSN 7540-01-152-8070 Previous edition unusable				STANDARD FORM 30 (REV. 10-83) Prescribed by GSA FAR (48 CFR) 53.243			

CONTINUATION SHEET

1. **QUESTION:** Working on this project and with the current water flow test and doing a preliminary calculation I cannot get the system to work. I have an 8" riser and 8" feed with 4" lines and I am short by about 5psi. Currently it will take a fire pump. Please advise

ANSWER: The design/proof of concept calculations were based on the following pipe sizes:

- 12-in incoming service
- 8-in RPZ backflow preventer
- 8-in sprinkler riser
- 8-in feed main
- 6-in cross main
- 4-in branch lines

This resulted in a 5.4 psi safety factor.

2. **QUESTION:** Can it be confirmed by Amendment that the Mass Notification System Transmitter indicated on FA101 for Project 23-0033 will be furnished by the Contractor and installed by the Government?

ANSWER: Build per project drawings and specs.

3. **QUESTION:** Spec Section 01 20 00, Paragraph 1.6.2.b for Project 23-0033 & Project 22-0047 indicates that conduits, gypsum board, glass and insulation are not acceptable for progress payments. However, Paragraph 1.6.2. c states that these materials are to be considered for progress payment prior to installation must be specifically and separately identified in the Contractor's estimates of work submitted for the Contracting Officer's approval in accordance with Schedule of Prices requirement of this Contract. Can it be confirmed by amendment that conduits, gypsum board, glass and insulation material will be considered as acceptable for progress payments if properly identified on the Contractor's Schedule of Prices?

ANSWER: NO

4. **QUESTION:** Spec Section 01 30 00, Paragraph 1.3 for Project 23-0033 & Project 22-0047 requires the contractor to provide monthly, and within one month of the completion of work, digital photographs, 1600x1200x24 bit true color minimum resolution in file format showing the sequence and progress of work. However, contractor personnel are prohibited from taking any pictures within the MARSOC compound area. Can the requirement for monthly progress pictures be removed from the project by amendment?

ANSWER: THE AWARDED CONTRACTOR WILL BE REQUIRED TO ATTEND A SECURITY BRIEFING WITH MARSOC SECURITY PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION ACTIVITIES. PHOTOGRAPH REQUIREMENTS WILL BE PROVIDED AT THIS TIME.

5. **QUESTION:** Spec Section 01 31 23.13 20 for Project 23-0033 & Project 22-0047 requires the contractor to utilize the Naval Facilities Engineering Systems Command's (NAVFAC's) Electronic Construction and Facility Support Contract Management System (eCMS) for the transfer, sharing, and management of electronic technical submittals and documents for the project. eCMS is a web-based program that should be available for the Government's and Contractor's use during the project's normal working hours of 7AM to 4:00PM. However, eCMS continues to have ongoing technical difficulties that cause the program to be periodically unavailable for use during normal working hours by the Government and the Contractor. In addition, there is no sense of urgency by the eCMS technical support team to restore service to eCMS when support tickets are submitted to them by contractor personnel. Can it be confirmed by Amendment that eCMS will be functional during normal working hours for this project after award?

ANSWER: No

6. **QUESTION:** Spec Section 01 35 29.13 for Project 23-0033 & Project 22-0047 indicate HEALTH, SAFETY, AND EMERGENCY RESPONSE PROCEDURES FOR CONTAMINATED SITES these projects. However, the RFP Drawings for Projects 23-0033 & 22-0047 do not identify any existing contamination on these sites. Can Spec Section 01 35 29.13 for these projects be removed by amendment?

ANSWER: No

7. **QUESTION:** Spec Sections 07 27 10 and 07 27 19 for Project 23-0033 & Project 22-0047 require the contractor to provide an Air Barrier System and associated testing for the (2) new facilities required for the project. However, Executive Order 14154 (Unleashing American Energy) eliminated the mandatory requirement for High Performance and Sustainable Buildings via the elimination of Executive Orders EO14030 (Climate-Related Financial Risk), EO 14057 (Catalyzing Clean Energy Industries and

Jobs Through Federal Sustainability) and EO 14082 (Implementation of the Energy and Infrastructure Provisions of the.

8. Inflation Reduction Act of 2022). These Executive Orders can be accessed at <https://www.federalregister.gov/documents/2025/01/29/2025-01956/unleashing-american-energy> . Also, the additional costs to provide and install the required air barrier system will far exceed the cost savings achieved via energy efficiency over the total life cycle of these (2) facilities. Can the air barrier requirements for Spec Sections 07 27 10 and 07 27 19 be removed from the project by Amendment since this requirement is no longer mandatory?

ANSWER: Yes

9. **QUESTION:** Spec Section 13 34 19, Paragraph 1.2.3 for Project 23-0033 & Project 22-0047 states for the contractor to design metal building systems to comply with the requirements of UFC 4-010-01 (DOD MINIMUM ANTITERRORISM STANDARDS FOR BUILDINGS). However, Drawing S-1 on the RFP Drawings for Projects 23-0033 & 22-0047 state that UFC 4-010-01 has already been incorporated into the design of this project. Can Paragraph 1.2.3 for Spec Section 13 34 19 be removed by amendment?

ANSWER: Yes

10. **QUESTION:** Drawing A-101 for project 23-0033 indicates that the FURNITURE PACKAGE SHOWN ON PLANS IS A SEPARATE CLIN. However, there is no CLIN for the Furniture Package on the RFP Pricing Sheet and there is no FF&E Specification Section included in the RFP Specifications for this project. Can the requirements for the Furniture Package be clarified by Amendment?

ANSWER: Delete reference on A101.

11. **QUESTION:** Drawing G2 and M-101 for Projects 23-0033 & 22-0047 indicate that the Contractor shall obtain and pay for all permits, fees and inspections necessary to complete their work under this contract. However, Spec Section 01 57 19 Paragraph 1.8.1 for Projects 23-0033 & 22-0047 state that the contractor obtain licenses and permits pursuant to "FAR 52.236-7, Permits and Responsibilities". Historically, the FAR 52.236-7 Permits have already obtained by the Government prior to Project Award. Can it be confirmed by Amendment that all permits required for Projects 23-0033 & 22-0047 will be obtained by the Government prior to Project Award?

ANSWER: Bid per specifications.

12. QUESTION: Please identify the water main sizes to be tapped for both the storage facility and the training facility.

ANSWER: The Prac App building water line connection is an 8" line. The MRSG building water line connection is a 12" line

13. QUESTION: Spec. section 31 00 00 Par. 3.2.1 references requirements for borrow approval if not purchased from a commercial entity from which soil material is directly purchased. If borrow material is purchased from a commercial entity from which soil is directly purchased will submission of state approved mining permit be substantial enough information to meet the Environmental Requirements for Off-Site soil?

ANSWER: Allow state-approved mining permit.

14. ASI 1 – PROJECT # 22-0047 NARRATIVE OF CLARIFICATIONS/ADDITIONS TO DOCUMENTS ARE INCORPORATED AS FOLLOWS:

1) Sheet C-001

a. Additional Erosion Control Notes and addition of Sequence of Land Disturbance notes.

2) Sheet CD100

a. Removal of open cut/patch asphalt keynote for communications utility connection. Utility will have to be installed by boring underneath road.

3) Sheet CS100

a. Removal of patch asphalt depiction and corresponding keynote for communications utility connection. Utility will have to be installed by boring underneath road.

4) Sheet CU100

a. Depiction of communications utility connection via bore underneath road with updated keynote 13.

b. Addition and depiction of temporary blow-off assembly at waterline stub for future extension (with updated keynote 11).

5) Sheet CU101

a. Depiction of communications utility connection via bore underneath road with updated keynote 13.

b. Addition and depiction of temporary blow-off assembly at waterline stub for future extension (with updated keynote 11).

6) Sheet CG100

a. Removal of patch asphalt depiction for communications utility connection.

7) Sheet CG101

- a. Removal of patch asphalt depiction for communications utility connection.
- b. Depiction of potential contractor laydown areas and stockpile locations (with additional keynotes 9 & 10).
- c. General sheet note added that contractor is required to pay annual NCG01 permit fee until the COC is terminated.

8) C-500

- a. Spoil Storage Berm detail edited to state 10' maximum height per NCDEQ regulation.

9) C-503

- a. Addition of 2-inch Temporary Blow-off Assembly detail.

15. ASI 1 – PROJECT # 23-0033 NARRATIVE OF CLARIFICATIONS/ADDITIONS TO DOCUMENTS ARE INCORPORATED AS FOLLOWS:

- 1) ADD clarification to spec section 13 34 19, paragraph 1.2.1 Design Parameters: Design building canopies in configurations shown on drawings, with support brackets to the building wall on each end of each canopy. Design connection thru the brick veneer and exterior wall sheathing/insulation to be supported by the cold formed metal framing system.

16. SEE ATTACHED 22-0047 PRAC APP COMBINE SHEETS. (NOTE: ATTACHED SEPERATELY)

17. The time and date for receipt of proposals remains unchanged.

18. All other terms and conditions remain unchanged.