





REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPH REVISION 2	03.09.20	

- GENERAL NOTES:
- SEE SHEET M-001 FOR GENERAL NOTES, LEGEND & ABBREVIATIONS
 - PLAN DRAWINGS ARE DIAGRAMMATIC IN NATURE AND DO NOT ILLUSTRATE SPECIFIC DUCT TAKE-OFF CONFIGURATIONS OR TAPS.
 - FAN COIL UNITS AND ASSOCIATED DUCTWORK SHOWN IS LOCATED IN ATTIC AND SHOWN ON FLOOR PLANS FOR COORDINATION PURPOSES ONLY. SEE ATTIC AND SECTION VIEWS FOR ELEVATIONS AND LOCATIONS OF EQUIPMENT.

- PLAN NOTES
- PROVIDE WALL MOUNTED EMERGENCY HVAC SHUTDOWN SWITCH. SEE SHEET M-701 FOR MORE INFORMATION. SEE ENLARGED SHEETS FOR MORE INFORMATION.



A1 FIRST FLOOR PLAN - OVERALL - MECHANICAL HVAC
1/8" = 1'-0"

		MH101	
CRENSHAW CONSULTING 205 South Street, Suite 200 Raleigh, North Carolina 27601 919-871-9270 Fax: 919-880-0000		DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND	
MARINE CORPS BASE CAMP LEJEUNE, NORTH CAROLINA			
DES: LWM DR: PJR CHK: JDL SUBMITTED BY: DESIGN DIR: JENNI REED APPROVED: PWO OR OICC SATISFACTORY TO:		FIRST FLOOR PLAN - OVERALL - MECHANICAL HVAC NAVIFAC DRAWING NO. 60042066 CONSTR. CONTR. NO. N40085-24-F-5940 SCALE: AS NOTED SPEC: SHEET 59 OF 119	



REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PP1 REVISION 2	03.09.20	

GENERAL NOTES:

- SEE SHEET M-001 FOR GENERAL NOTES, LEGEND & ABBREVIATIONS
- PLAN DRAWINGS ARE DIAGRAMMATIC IN NATURE AND DO NOT ILLUSTRATE SPECIFIC DUCT TAKE-OFF CONFIGURATIONS OR TAPS.
- FAN COIL UNITS AND ASSOCIATED DUCTWORK SHOWN IS LOCATED IN ATTIC AND SHOWN ON FLOOR PLANS FOR COORDINATION PURPOSES ONLY. SEE ATTIC AND SECTION VIEWS FOR ELEVATIONS AND LOCATIONS OF EQUIPMENT.

PLAN NOTES

- PROVIDE 4-PIPE FAN COIL UNIT ABOVE SECOND GYPSUM BOARD CEILING. PROVIDE RETURN DUCT PLENUM TO MATCH DUCT INLET CONNECTION. PROVIDE TRANSITION OR TAP AS SHOWN AND ROUTE SUPPLY AND RETURN DUCTWORK DOWN THROUGH GYP CEILING TO LAY-IN CEILING GRILLES. PROVIDE DUCT MOUNTED BALANCING DAMPER BETWEEN GYP CEILING AND GRILLE.
- PROVIDE VENTILATION DUCTWORK DOWN FROM DOAS MAIN DUCTWORK IN ATTIC. TO LAY-IN CEILING MOUNTED GRILLES AS SHOWN. SEE ATTIC PLANS FOR CONTINUATION. (TYPICAL)
- PROVIDE EXHAUST DUCTWORK DOWN FROM DOAS MAIN DUCTWORK IN ATTIC. ROUTE TO VERTICAL EXHAUST DUCTWORK IN CHASE DOWN TO SIDEWALL MOUNTED GRILLE AS SHOWN. (TYPICAL)
- PROVIDE EXHAUST VENT DUCTWORK FROM DRIVERS TO EXTERIOR WALL CAP(S) AS SHOWN. REUSE EXISTING PENETRATIONS.
- PROVIDE WALL MOUNTED EMERGENCY HVAC SHUTDOWN SWITCH. PROVIDE SWITCH WITH A DIFFERENT COLOR THAN FIRE ALARM PULL STATIONS. SEE SHEET M-701 FOR MORE INFORMATION.
- PROVIDE WALL MOUNTED DUCTLESS SPLIT AIR HANDLER ABOVE DOOR. PROVIDE MANUFACTURER'S RECOMMENDED CLEARANCES AND COORDINATE INSTALLATION WITH OTHER EQUIPMENT IN SPACE.
- PROVIDE AIR DOOR ABOVE EXTERIOR DOOR. OPERATION MUST BE TIED TO DOOR SWITCH.
- PROVIDE EXHAUST HOOD DUCTED UP TO EXHAUST FAN IN ATTIC. EXHAUST HOOD AND FAN OPERATION MUST BE TIED TO WALL MOUNTED SWITCH, AND ONLY BE ENERGIZED UPON PROOF OF CLOSURE OF MOTORIZED DAMPER IN DOAS EXHAUST DUCT SERVING SPACE.
- PROVIDE CONDENSING UNIT MOUNTED ON EQUIPMENT SUPPORT PAD ON EXTERIOR OF BUILDING AS SHOWN. COORDINATE EXACT LOCATION WITH CIVIL AND ENSURE MANUFACTURER RECOMMENDED CLEARANCES ARE MAINTAINED.

A5 KEY PLAN - EAST WING
NTSGRAPHIC SCALE: 3/16"=1'-0"
6' 0' 4' 10'A1 FIRST FLOOR PLAN - EAST WING - MECHANICAL HVAC
3/16" = 1'-0"

CRENSHAW CONSULTING
ENGINEERS
INC.
NO LICENSE #0-185
205 East Street, Suite 200
Raleigh, North Carolina 27601
919-871-9270 Fax: 919-880-0001

DES: LWM
DR: PJR
CHK: JDL
SUBMITTED BY:
DESIGN DIR: JENNI REED
APPROVED: PWO OR OICC
SATISFACTORY TO:

DEPARTMENT OF THE NAVY
NAVFACILITIES ENGINEERING SYSTEMS COMMAND
MARINE CORPS BASE
CAMP LEJEUNE, NORTH CAROLINA

MECHANICAL REPAIRS
BUILDING TT113

FIRST FLOOR PLAN - EAST WING - MECHANICAL HVAC

E1 80091

60042067

CONSTR. CONTR. NO. N40085-24-F-5940

SCALE: AS NOTED SPEC. SHEET 60 OF 110




REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	

GENERAL NOTES:

1. SEE SHEET M-001 FOR GENERAL NOTES, LEGEND & ABBREVIATIONS
2. PLAN DRAWINGS ARE DIAGRAMMATIC IN NATURE AND DO NOT ILLUSTRATE SPECIFIC DUCT TAKE-OFF CONFIGURATIONS OR TAPS.
3. FAN COIL UNITS AND ASSOCIATED DUCTWORK SHOWN IS LOCATED IN ATTIC AND SHOWN ON FLOOR PLANS FOR COORDINATION PURPOSES ONLY. SEE ATTIC AND SECTION VIEWS FOR ELEVATIONS AND LOCATIONS OF EQUIPMENT.

PLAN NOTES

1. PROVIDE EXHAUST VENT DUCTWORK FROM DRYERS TO EXTERIOR WALL CAP(S) AS SHOWN. REUSE EXISTING PENETRATIONS.
2. PROVIDE 4-PIPE FAN COIL UNIT ABOVE SECOND GYPSUM BOARD CEILING. PROVIDE RETURN DUCT PLENUM TO MATCH DUCT INLET CONNECTION. PROVIDE TRANSITION OR TAP AS SHOWN AND ROUTE SUPPLY AND RETURN DUCTWORK DOWN THROUGH GYP CEILING TO LAY-IN CEILING GRILLES. PROVIDE DUCT MOUNTED BALANCING DAMPER BETWEEN GYP CEILING AND GRILLE.
3. PROVIDE VENTILATION DUCTWORK DOWN FROM DOAS MAIN DUCTWORK IN ATTIC. TO LAY-IN CEILING MOUNTED GRILLES AS SHOWN. SEE ATTIC PLANS FOR CONTINUATION. (TYPICAL)
4. PROVIDE EXHAUST DUCTWORK DOWN FROM DOAS MAIN DUCTWORK IN ATTIC. ROUTE TO VERTICAL EXHAUST DUCTWORK IN CHASE DOWN TO SIDEWALL MOUNTED GRILLE AS SHOWN. (TYPICAL)
5. PROVIDE WALL MOUNTED EMERGENCY HVAC SHUTDOWN SWITCH. PROVIDE SWITCH WITH A DIFFERENT COLOR THAN FIRE ALARM PULL STATIONS. SEE SHEET M-701 FOR MORE INFORMATION.

A5 KEY PLAN - SOUTH WING
NTSGRAPHIC SCALE: 3/16"=1'-0"
6' 0' 4' 10'A2 FIRST FLOOR PLAN - SOUTH WING - MECHANICAL HVAC
3/16" = 1'-0"

CRENSHAW CONSULTING
engineers
NO LICENSE #FC-785
205 East Street, Suite 200
Raleigh, North Carolina 27601
919-871-9270 Fax: 919-880-0000

DES: LWM
DR: PJR
CHK: JDL
SUBMITTED BY:
DESIGN DIR: JENNI REED
APPROVED: PWO OR OICC
SATISFACTORY TO:

DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND
MARINE CORPS BASE
CAMP LEJEUNE, NORTH CAROLINA

**MECHANICAL REPAIRS
BUILDING TT113**

FIRST FLOOR PLAN - SOUTH WING - MECHANICAL HVAC

SIZE: E1
CODE IDENT. NO.: 80091
NAVIFAC DRAWING NO.: 60042068
CONSTR. CONTR. NO.: N40085-24-F-5940

SCALE: AS NOTED SPEC. SHEET 61 OF 119

MH103


REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	

GENERAL NOTES:

- SEE SHEET M-001 FOR GENERAL NOTES, LEGEND & ABBREVIATIONS
- PLAN DRAWINGS ARE DIAGRAMMATIC IN NATURE AND DO NOT ILLUSTRATE SPECIFIC DUCT TAKE-OFF CONFIGURATIONS OR TAPS.
- FAN COIL UNITS AND ASSOCIATED DUCTWORK SHOWN IS LOCATED IN ATTIC AND SHOWN ON FLOOR PLANS FOR COORDINATION PURPOSES ONLY. SEE ATTIC AND SECTION VIEWS FOR ELEVATIONS AND LOCATIONS OF EQUIPMENT.

PLAN NOTES

- PROVIDE 4-PIPE FAN COIL UNIT ABOVE SECOND GYPSUM BOARD CEILING. PROVIDE RETURN DUCT PLENUM TO MATCH DUCT INLET CONNECTION. PROVIDE TRANSITION OR TAP AS SHOWN AND ROUTE SUPPLY AND RETURN DUCTWORK DOWN THROUGH GYP CEILING TO LAY-IN CEILING GRILLES. PROVIDE DUCT MOUNTED BALANCING DAMPER BETWEEN GYP CEILING AND GRILLE.
- PROVIDE VENTILATION DUCTWORK DOWN FROM DOAS MAIN DUCTWORK IN ATTIC. TO LAY-IN CEILING MOUNTED GRILLES AS SHOWN. SEE ATTIC PLANS FOR CONTINUATION. (TYPICAL)
- PROVIDE EXHAUST DUCTWORK DOWN FROM DOAS MAIN DUCTWORK IN ATTIC. ROUTE TO VERTICAL EXHAUST DUCTWORK IN CHASE DOWN TO SIDEWALL MOUNTED GRILLE AS SHOWN. (TYPICAL)



B1 FIRST FLOOR PLAN - WEST WING - MECHANICAL HVAC

3/16" = 1'-0"

A5 KEY PLAN - WEST WING

NTS

GRAPHIC SCALE: 3/16"=1'-0"

6' 0' 4' 10'



CRENSHAW CONSULTING
Engineers
NO LICENSE #C-105
205 East Street, Suite 200
Raleigh, North Carolina 27601
919-871-9270 Fax: 919-871-9880

DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND

MARINE CORPS BASE

CAMP LEJEUNE, NORTH CAROLINA

MECHANICAL REPAIRS
BUILDING TT113


FIRST FLOOR PLAN - WEST WING - MECHANICAL HVAC

E1 80091

NAVFAC DRAWING NO.
60042069


CONSTR. CONTR. NO. N40085-24-F-5940

SCALE: AS NOTED SPEC: SHEET 62 OF 119



REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	

- GENERAL NOTES:
1. SEE SHEET M-001 FOR GENERAL NOTES, LEGEND & ABBREVIATIONS
 2. PLAN DRAWINGS ARE DIAGRAMMATIC IN NATURE AND DO NOT ILLUSTRATE SPECIFIC DUCT TAKE-OFF CONFIGURATIONS OR TAPS.



A1 ATTIC PLAN - OVERALL - MECHANICAL HVAC
1/8" = 1'-0"

		MH105	
		DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND	
		MARINE CORPS BASE	
		CAMP LEJEUNE, NORTH CAROLINA	
DES: LWM DR: PJR CHK: JDL SUBMITTED BY: DESIGN DIR: JENNI REED APPROVED: PWQ OR OICC SATISFACTORY TO:		MECHANICAL REPAIRS BUILDING TT113	
DATE: _____		ATTIC PLAN - OVERALL - MECHANICAL HVAC	
DATE: _____		NAVIFAC DRAWING NO. 60042070	
DATE: _____		CONSTR. CONTR. NO. N40085-24-F-5940	
SCALE: AS NOTED		SHEET 63 OF 119	


REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	

GENERAL NOTES:

- SEE SHEET M-001 FOR GENERAL NOTES, LEGEND & ABBREVIATIONS
- PLAN DRAWINGS ARE DIAGRAMMATIC IN NATURE AND DO NOT ILLUSTRATE SPECIFIC DUCT TAKE-OFF CONFIGURATIONS OR TAPS.


PLAN NOTES

- PROVIDE DOAS MOUNTED ON EQUIPMENT PLATFORM IN ATTIC. COORDINATE EXACT LOCATION ON PLATFORM WITH STRUCTURE AND PROVIDE MANUFACTURER RECOMMENDED CLEARANCES.
- PROVIDE OUTSIDE AIR VENTILATION DUCTWORK FROM EXTERIOR WALL LOUVER WITH CLASS 1A MOTORIZED DAMPER TO DOAS OA INTAKE AS SHOWN. PROVIDE DUCT PLENUM BEHIND ARCHITECTURAL LOUVER. SIZE TO MATCH MOTORIZED DAMPER SIZE. SEE ARCHITECTURAL SHEETS FOR MORE INFORMATION ON LOUVER TYPE AND SIZE.
- PROVIDE EXHAUST AIR DUCTWORK FROM EXTERIOR WALL LOUVER WITH CLASS 1A MOTORIZED DAMPER TO DOAS EXHAUST OUTLET AS SHOWN. PROVIDE DUCT PLENUM BEHIND ARCHITECTURAL LOUVER. SIZE TO MATCH MOTORIZED DAMPER SIZE. SEE ARCHITECTURAL SHEETS FOR MORE INFORMATION ON LOUVER TYPE AND SIZE.
- PROVIDE EXHAUST AIR DUCTWORK FROM DOAS EA INLET AND ROUTE AS SHOWN TO SPACES BELOW. SEE FLOOR PLANS FOR CONTINUATION.



A5 KEY PLAN - SOUTH WING
NTS

GRAPHIC SCALE: 3/16"=1'-0"
6' 0 4' 10'



A2 ATTIC PLAN - SOUTH WING - MECHANICAL HVAC
3/16" = 1'-0"


		MH107	
CRENSHAW CONSULTING Engineers NO LICENSE #C-785 205 East Street, Suite 200 Raleigh, North Carolina 27601 919-871-9270 Fax: 919-880-0000		DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND MARINE CORPS BASE CAMP LEJEUNE, NORTH CAROLINA	
DES: LWM DR: PJR CHK: JDL SUBMITTED BY: DESIGN DIR: JENNI REED APPROVED: PWV OR OICC DATE: _____		MECHANICAL REPAIRS BUILDING TT113 ATTIC PLAN - SOUTH WING - MECHANICAL HVAC NAVIFAC DRAWING NO. 60042072 CONSTR. CONTR. NO. N40085-24-F-5940	
Satisfactory To: _____ DATE: _____		SCALE: AS NOTED SPEC. SHEET 65 OF 119	

SCALE AS NOTED	SPEC.	SHEET 66 OF 115
----------------	-------	-----------------


REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	

GENERAL NOTES:

1. SEE SHEET M-001 FOR GENERAL NOTES, LEGEND & ABBREVIATIONS
2. SEE CHILLED AND HOT WATER SYSTEM DIAGRAMS FOR PIPE SIZING AND MORE INFORMATION
3. FAN COIL UNITS AND ASSOCIATED PIPING SHOWN IS LOCATED IN ATTIC AND SHOWN ON FLOOR PLANS FOR COORDINATION PURPOSES ONLY. SEE SECTION VIEWS FOR ELEVATIONS AND LOCATIONS OF EQUIPMENT.





GRAPHIC SCALE: 1/8"=1'-0"



A1 FIRST FLOOR PLAN - OVERALL - MECHANICAL PIPING

1/8" = 1'-0"



CRENSHAW CONSULTING
ENGINEERS
INC.
2015 Sun. Blvd., Suite 200
Raleigh, North Carolina 27609
919-871-9270 Fax: 919-871-9280

DES: LWM
DR: PJR
CHK: JDL
SUBMITTED BY:
DESIGN DIR: JENNI REED
APPROVED: PWO OR OICC
DATE:
SATISFACTORY TO: DATE:

DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND
MARINE CORPS BASE
CAMP LEJEUNE, NORTH CAROLINA

MECHANICAL REPAIRS
BUILDING TT113
FIRST FLOOR PLAN - OVERALL - MECHANICAL PIPING
CODE IDENT. NO.: 60042074
CONSTR. CONTR. NO.: N40085-24-F-5940
SCALE: AS NOTED SPEC: SHEET 67 OF 119

MP101


REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	

GENERAL NOTES:

1. SEE SHEET M-001 FOR GENERAL NOTES, LEGEND & ABBREVIATIONS
2. SEE CHILLED AND HOT WATER SYSTEM DIAGRAMS FOR PIPE SIZING AND MORE INFORMATION
3. FAN COIL UNITS AND ASSOCIATED PIPING SHOWN IS LOCATED IN ATTIC AND SHOWN ON FLOOR PLANS FOR COORDINATION PURPOSES ONLY. SEE SECTION VIEWS FOR ELEVATIONS AND LOCATIONS OF EQUIPMENT.

PLAN NOTES

1. PROVIDE 4-PIPE FAN COIL UNIT (FCU) ABOVE SECOND GYPSUM BOARD CEILING. ROUTE CHILLED AND HOT WATER PIPING TO UNIT AND PROVIDE MANUFACTURER RECOMMENDED CLEARANCES FOR SERVICE OF COILS AND VALVING. PROVIDE FCU WITH SECONDARY CONDENSATE DRAIN PAN. SEE FAN COIL DETAIL FOR MORE INFORMATION.
2. PROVIDE WALL MOUNTED THERMOSTAT MOUNTED AT 54" AFF.
3. PROVIDE CHILLED AND HOT WATER PIPING UP FROM UNDERGROUND AND ROUTE TO EQUIPMENT IN ATTIC. SEE ATTIC PLANS FOR CONTINUATION.
4. PROVIDE HOT WATER UNIT HEATERS SUSPENDED FROM STRUCTURE. COORDINATE EXACT LOCATION WITH EQUIPMENT IN SPACE.
5. PROVIDE WALL MOUNTED DUCTLESS SPLIT AIR HANDLER ABOVE DOOR. PROVIDE AIR HANDLER WITH CONDENSATE PUMP AND ROUTE CONDENSATE TO NEAREST DRAIN. ROUTE REFRIGERANT PIPING IN MOST DIRECT ROUTE POSSIBLE TO EXTERIOR CONDENSING UNIT MOUNTED ON EQUIPMENT PAD ON GRADE..




A5 KEY PLAN - EAST WING
NTS

GRAPHIC SCALE: 3/16"=1'-0"
6" 0 4' 10'

B1 FIRST FLOOR PLAN - EAST WING - MECHANICAL PIPING
3/16" = 1'-0"

		MP102	
CRENSHAW CONSULTING ENGINEERS 2015 Sun. Blvd., Suite 200 Raleigh, North Carolina 27609 919-871-9270 Fax: 919-880-0000		DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND MARINE CORPS BASE CAMP LEJEUNE, NORTH CAROLINA	
DES: LWM DR: PJR CHK: JDL SUBMITTED BY: DESIGN DIR: JENNI REED APPROVED: PW/O OR O/C DATE: SATISFACTORY TO: DATE:		FIRST FLOOR PLAN - EAST WING - MECHANICAL PIPING NAVIFAC DRAWING NO. 60042075 CONSTR. CONTR. NO. N40085-24-F-5940 SCALE: AS NOTED SPEC: SHEET 68 OF 110	




A2 FIRST FLOOR PLAN - SOUTH WING - MECHANICAL PIPING
3/16" = 1'-0"

REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	

- GENERAL NOTES:
- SEE SHEET M-001 FOR GENERAL NOTES, LEGEND & ABBREVIATIONS
 - SEE CHILLED AND HOT WATER SYSTEM DIAGRAMS FOR PIPE SIZING AND MORE INFORMATION
 - FAN COIL UNITS AND ASSOCIATED PIPING SHOWN IS LOCATED IN ATTIC AND SHOWN ON FLOOR PLANS FOR COORDINATION PURPOSES ONLY. SEE SECTION VIEWS FOR ELEVATIONS AND LOCATIONS OF EQUIPMENT.

- PLAN NOTES**
- PROVIDE 4-PIPE FAN COIL UNIT (FCU) ABOVE SECOND GYPSUM BOARD CEILING. ROUTE CHILLED AND HOT WATER PIPING TO UNIT AND PROVIDE MANUFACTURER RECOMMENDED CLEARANCES FOR SERVICE OF COILS AND VALVING. PROVIDE FCU WITH SECONDARY CONDENSATE DRAIN PAN. SEE FAN COIL DETAIL FOR MORE INFORMATION.
 - PROVIDE WALL MOUNTED THERMOSTAT MOUNTED AT 54" AFF.



A5 KEY PLAN - SOUTH WING
NTS

GRAPHIC SCALE: 3/16"=1'-0"
6' 0 4' 10'

		MP103	
CRENSHAW CONSULTING engineers NO LICENSE #C-1765 2015 State Street, Suite 200 Raleigh, North Carolina 27609 919-871-8270 Fax: 919-871-8880		DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND MARINE CORPS BASE CAMP LEJEUNE, NORTH CAROLINA	
DES: LWM DR: PJR CHK: JDL SUBMITTED BY: DESIGN DIR: JENNI REED APPROVED: PWV OR OICC SATISFACTORY TO:		MECHANICAL REPAIRS BUILDING TT113 FIRST FLOOR PLAN - SOUTH WING - MECHANICAL PIPING NAVIFAC DRAWING NO. 60042076 E1 80091 CONSTR. CONTR. NO. N40085-24-F-5940 SCALE: AS NOTED SPEC: SHEET 69 OF 110	

REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	

GENERAL NOTES:

- SEE SHEET M-001 FOR GENERAL NOTES, LEGEND & ABBREVIATIONS
- SEE CHILLED AND HOT WATER SYSTEM DIAGRAMS FOR PIPE SIZING AND MORE INFORMATION
- FAN COIL UNITS AND ASSOCIATED PIPING SHOWN IS LOCATED IN ATTIC AND SHOWN ON FLOOR PLANS FOR COORDINATION PURPOSES ONLY. SEE SECTION VIEWS FOR ELEVATIONS AND LOCATIONS OF EQUIPMENT.

PLAN NOTES

- PROVIDE 4-PIPE FAN COIL UNIT (FCU) ABOVE SECOND GYPSUM BOARD CEILING. ROUTE CHILLED AND HOT WATER PIPING TO UNIT AND PROVIDE MANUFACTURER RECOMMENDED CLEARANCES FOR SERVICE OF COILS AND VALVING. PROVIDE FCU WITH SECONDARY CONDENSATE DRAIN PAN. SEE FAN COIL DETAIL FOR MORE INFORMATION.
- PROVIDE WALL MOUNTED THERMOSTAT MOUNTED AT 54" AFF.



B1 FIRST FLOOR PLAN - WEST WING - MECHANICAL PIPING
3/16" = 1'-0"

A5 KEY PLAN - WEST WING
NTS



GRAPHIC SCALE: 3/16"=1'-0"
6' 0' 4' 10'

		MP104	
		DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND	
NAEFA NO. 2400 NO LICENSE #C-785 3015 South Street, Suite 300 Raleigh, North Carolina 27609 919-871-9270 Fax: 919-871-9880		MARINE CORPS BASE CAMP LEJEUNE, NORTH CAROLINA	
DES: LWM DR: PJR CHK: JDL SUBMITTED BY: DESIGN DIR: JENNI REED APPROVED: PW/O OR ICC DATE:		MECHANICAL REPAIRS BUILDING TT113	
SATISFACTORY TO: DATE:		FIRST FLOOR PLAN - WEST WING - MECHANICAL PIPING	
SIZE: E1 CODE IDENT. NO.: 80091		NAVIFAC DRAWING NO.: 60042077	
SCALE: AS NOTED		CONSTR. CONTR. NO.: N40085-24-F-5940	
SPEC:		SHEET 70 OF 110	


REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	

GENERAL NOTES:

1. SEE SHEET M-001 FOR GENERAL NOTES, LEGEND & ABBREVIATIONS
2. SEE CHILLED AND HOT WATER SYSTEM DIAGRAMS FOR PIPE SIZING AND MORE INFORMATION
3. FAN COIL UNITS AND ASSOCIATED PIPING SHOWN IS LOCATED IN ATTIC AND SHOWN ON FLOOR PLANS FOR COORDINATION PURPOSES ONLY. SEE SECTION VIEWS FOR ELEVATIONS AND LOCATIONS OF EQUIPMENT.



A1 ATTIC PLAN - OVERALL - MECHANICAL PIPING
1/8" = 1'-0"



DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND
MARINE CORPS BASE
CAMP LEJEUNE, NORTH CAROLINA

MP105

DES: LWM
DR: PJR
CHK: JDL
SUBMITTED BY:
DESIGN DIR: JENNI REED
APPROVED: PW/O OR OICC
SATISFACTORY TO:

MECHANICAL REPAIRS
BUILDING TT113
ATTIC PLAN - OVERALL - MECHANICAL PIPING
NAVIFAC DRAWING NO. **60042078**
CONSTR. CONTR. NO. N40085-24-F-5940
SCALE: AS NOTED SPEC: SHEET 71 OF 119

E1 80091



REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	

GENERAL NOTES:

1. SEE SHEET M-001 FOR GENERAL NOTES, LEGEND & ABBREVIATIONS
2. SEE CHILLED AND HOT WATER SYSTEM DIAGRAMS FOR PIPE SIZING AND MORE INFORMATION
3. FAN COIL UNITS AND ASSOCIATED PIPING SHOWN IS LOCATED IN ATTIC AND SHOWN ON FLOOR PLANS FOR COORDINATION PURPOSES ONLY. SEE SECTION VIEWS FOR ELEVATIONS AND LOCATIONS OF EQUIPMENT.

PLAN NOTES

1. PROVIDE DOAS MOUNTED ON EQUIPMENT PLATFORM IN ATTIC. ROUTE CHILLED AND HOT WATER PIPING TO UNIT AND PROVIDE MANUFACTURER RECOMMENDED CLEARANCES FOR SERVICE OF COILS AND VALVING.
2. PROVIDE 4-PIPE FAN COIL UNIT (FCU) ABOVE SECOND GYPSUM BOARD CEILING. UNIT TO BE INSTALLED AT ELEVATION AND ORIENTATION TO ALLOW FOR MAINTENANCE ACCESS FROM CATWALK. PROVIDE CHILLED AND HOT WATER PIPING TO 4-PIPE FAN COIL UNIT (FCU). INSTALL PER MANUFACTURER INSTALLATION INSTRUCTIONS AND PROVIDE RECOMMENDED CLEARANCES FOR SERVICE OF COILS AND VALVING. FCU TO BE PROVIDED WITH SECONDARY CONDENSATE DRAIN PAN. SEE FLOOR PLANS FOR CONTINUATION.
3. PROVIDE CHILLED AND HOT WATER PIPING UP FROM LEVEL BELOW AND ROUTE TO EQUIPMENT IN ATTIC AS SHOWN. COORDINATE EXACT ROUTING WITH OTHER EQUIPMENT, DUCTWORK AND STRUCTURE IN ATTIC.




A5 KEY PLAN - EAST WING
NTS

GRAPHIC SCALE: 3/16"=1'-0"
6' 0 4' 10'

B1 ATTIC PLAN - EAST WING - MECHANICAL PIPING
3/16" = 1'-0"

		MP106	
CRENSHAW CONSULTING ENGINEERS NO LICENSE #C-1765 205 East Street, Suite 200 Raleigh, North Carolina 27601 919-871-9270 Fax: 919-860-0000		DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND MARINE CORPS BASE CAMP LEJEUNE, NORTH CAROLINA	
DES: LWM DR: PJR CHK: JDL SUBMITTED BY: DESIGN DIR: JENNI REED APPROVED: PW/O OR OICC SATISFACTORY TO:		MECHANICAL REPAIRS BUILDING TT113 ATTIC PLAN - EAST WING - MECHANICAL PIPING NAVIFAC DRAWING NO. 60042079 CONSTR. CONTR. NO. N40085-24-F-5940	
SIZE: E1 CODE IDENT. NO.: 80091		SCALE: AS NOTED SPEC: SHEET 72 OF 110	



A2 ATTIC PLAN - SOUTH WING - MECHANICAL PIPING
3/16" = 1'-0"


REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	

GENERAL NOTES:


- SEE SHEET M-001 FOR GENERAL NOTES, LEGEND & ABBREVIATIONS
- SEE CHILLED AND HOT WATER SYSTEM DIAGRAMS FOR PIPE SIZING AND MORE INFORMATION
- FAN COIL UNITS AND ASSOCIATED PIPING SHOWN IS LOCATED IN ATTIC AND SHOWN ON FLOOR PLANS FOR COORDINATION PURPOSES ONLY. SEE SECTION VIEWS FOR ELEVATIONS AND LOCATIONS OF EQUIPMENT.

PLAN NOTES

- PROVIDE DOAS MOUNTED ON EQUIPMENT PLATFORM IN ATTIC. ROUTE CHILLED AND HOT WATER PIPING TO UNIT AND PROVIDE MANUFACTURER RECOMMENDED CLEARANCES FOR SERVICE OF COILS AND VALVING.
- PROVIDE 4-PIPE FAN COIL UNIT (FCU) ABOVE SECOND GYPSUM BOARD CEILING. UNIT TO BE INSTALLED AT ELEVATION AND ORIENTATION TO ALLOW FOR MAINTENANCE ACCESS FROM CATWALK. PROVIDE CHILLED AND HOT WATER PIPING TO 4-PIPE FAN COIL UNIT (FCU). INSTALL PER MANUFACTURER INSTALLATION INSTRUCTIONS AND PROVIDE RECOMMENDED CLEARANCES FOR SERVICE OF COILS AND VALVING. FCU TO BE PROVIDED WITH SECONDARY CONDENSATE DRAIN PAN. SEE FLOOR PLANS FOR CONTINUATION.



A5 KEY PLAN - SOUTH WING
NTS



03-01-20

CRENSHAW CONSULTING
engineers
NO LICENSE #C-785
205 East Street, Suite 200
Raleigh, North Carolina 27601
919-871-9270 Fax: 919-880-0000

DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND

MARINE CORPS BASE
CAMP LEJEUNE, NORTH CAROLINA

**MECHANICAL REPAIRS
BUILDING TT113**

ATTIC PLAN - SOUTH WING - MECHANICAL PIPING

DES: LWM	SIZE: E1	CODE IDENT. NO.: 80091	NAVIFAC DRAWING NO.: 60042080
DR: PJR	APPROVED: PWV OR OICC	DATE:	CONSTR. CONTR. NO.: N40085-24-F-5940
CHK: JDL	DESIGN DR: JENNI REED	DATE:	SHEET 73 OF 110
SUBMITTED BY:	SATISFACTORY TO:	DATE:	


REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	

GENERAL NOTES:

1. SEE SHEET M-001 FOR GENERAL NOTES, LEGEND & ABBREVIATIONS
2. SEE CHILLED AND HOT WATER SYSTEM DIAGRAMS FOR PIPE SIZING AND MORE INFORMATION
3. FAN COIL UNITS AND ASSOCIATED PIPING SHOWN IS LOCATED IN ATTIC AND SHOWN ON FLOOR PLANS FOR COORDINATION PURPOSES ONLY. SEE SECTION VIEWS FOR ELEVATIONS AND LOCATIONS OF EQUIPMENT.

PLAN NOTES


1. PROVIDE DOAS MOUNTED ON EQUIPMENT PLATFORM IN ATTIC. ROUTE CHILLED AND HOT WATER PIPING TO UNIT AND PROVIDE MANUFACTURER RECOMMENDED CLEARANCES FOR SERVICE OF COILS AND VALVING.
2. PROVIDE 4-PIPE FAN COIL UNIT (FCU) ABOVE SECOND GYPSUM BOARD CEILING. UNIT TO BE INSTALLED AT ELEVATION AND ORIENTATION TO ALLOW FOR MAINTENANCE ACCESS FROM CATWALK. PROVIDE CHILLED AND HOT WATER PIPING TO 4-PIPE FAN COIL UNIT (FCU). INSTALL PER MANUFACTURER INSTALLATION INSTRUCTIONS AND PROVIDE RECOMMENDED CLEARANCES FOR SERVICE OF COILS AND VALVING. FCU TO BE PROVIDED WITH SECONDARY CONDENSATE DRAIN PAN. SEE FLOOR PLANS FOR CONTINUATION.



B1 ATTIC PLAN - WEST WING - MECHANICAL PIPING
3/16" = 1'-0"



A5 KEY PLAN - WEST WING
NTS



CRENSHAW CONSULTING
Engineers
NO LICENSE #C-1765
205 East Street, Suite 200
Raleigh, North Carolina 27601
919-871-8270 Fax: 919-880-0000

DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND
MARINE CORPS BASE
CAMP LEJEUNE, NORTH CAROLINA

MP108

DES: LWM
DR: PJR
CHK: JDL
SUBMITTED BY:
DESIGN DIR: JENNI REED
APPROVED: PW/O OR OICC
SATISFACTORY TO:


MECHANICAL REPAIRS
BUILDING TT113
ATTIC PLAN - WEST WING - MECHANICAL PIPING
NAVIFAC DRAWING NO. 60042081
CONSTR. CONTR. NO. N40085-24-F-5940
SCALE: AS NOTED SPEC: SHEET 74 OF 110

E1 80091


REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	

GENERAL NOTES:

1. SEE SHEET M-001 FOR GENERAL NOTES, LEGEND & ABBREVIATIONS
2. PLAN DRAWINGS ARE DIAGRAMMATIC IN NATURE AND DO NOT ILLUSTRATE SPECIFIC DUCT TAKE-OFF CONFIGURATIONS OR TAPS.




C1 WEST SECTION VIEW AT DOAS-1
3/8" = 1'-0"



A1 SOUTH SECTION VIEW AT DOAS-1
1/4" = 1'-0"

GRAPHIC SCALE: 3/8"=1'-0"
3 0 2 6

GRAPHIC SCALE: 1/4"=1'-0"
4 0 2 4 8



CRENSHAW CONSULTING
ENGINEERS
NO LICENSE #C-105
305 East Street, Suite 300
Raleigh, North Carolina 27601
919-871-9270 Fax: 919-880-0000

DES: LWM
DR: PJR
CHK: JDL
SUBMITTED BY:
DESIGN DIR: JENNI REED
APPROVED: PWQ OR OICC
DATE:
SATISFACTORY TO:
DATE:

DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND
MARINE CORPS BASE
CAMP LEJEUNE, NORTH CAROLINA

MECHANICAL REPAIRS
BUILDING TT113
MECHANICAL SECTION VIEW
NAVIFAC DRAWING NO.
60042083
CONSTR. CONTR. NO. N40085-24-F-5940
SCALE: AS NOTED SPEC: SHEET 76 OF 110

M-301

REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	

DESIGN CONDITIONS

OUTDOOR DESIGN CONDITIONS					
SEASON		DBWB (°F)			
SUMMER		91/77 (1% ASHRAE)			
WINTER		22 (99.6% ASHRAE)			
DEHUMIDIFICATION CONDITIONS					
MCDB (°F)		W (grains H2O/lbm dry air)			
83.3 (1.0% ASHRAE)		140.62 (1.0% ASHRAE)			
INDOOR DESIGN CONDITIONS					
SPACE CLASSIFICATION	SEASON	OCCUPIED	UNOCCUPIED	ALARM	RELATIVE HUMIDITY
FIRE ALARMS/SPRINKLER	COOLING	120°F (MAX)	-	120°F (MAX)	0-85%
	HEATING	32°F (MIN)	-	32°F (MIN)	0-85%
NFPA 72 10.3.5. FOLLOW THIS OR MANUFACTURER'S REQUIREMENTS, WHICHEVER IS MORE STRINGENT.					
ELECTRICAL ROOM	COOLING	95°F (MAX)	-	95°F (MAX)	80% (MAX)
	HEATING	41°F (MIN)	-	41°F (MIN)	8% (MIN)
EXTERIOR OR PRIMARY ELECTRICAL EQUIPMENT ROOMS ONLY. OTHERWISE FOLLOW UFC 3-410-01.					
TELECOM ROOM	COOLING	68°F	-	95°F (MAX)	80% (MAX)
	HEATING	-	-	41°F (MIN)	8% (MIN)
ALL OTHER ROOMS	COOLING	75°F	80°F	85°F	50%
	HEATING	70°F	60°F	55°F	50%

DEDICATED OUTSIDE AIR SYSTEM (DOAS) SCHEDULE																																																																				
MARK	SUPPLY FAN			EXHAUST FAN			PREHEAT HEATING CAPACITY (HOT WATER)										COOLING CAPACITY (CHILLED WATER)										LWT	REHEAT HEATING CAPACITY (HOT WATER)										WATER PD MAX	MIN. NUM. OF ROWS	GPM	TOTAL CAP.	REHEAT HEATING CAPACITY (HOT WATER)										WATER PD MAX	ELECTRICAL					SINGLE POINT CONNECTION					VPH	UNIT WEIGHT	MAX DIMENSIONS			REMARKS
	SA CFM	ESP (IN.WG)	TSP (IN.WG)	EA CFM	ESP (IN.WG)	TSP (IN.WG)	TOTAL CAP.	EAT	LAT	FACE VEL	AIR PD MAX	EWT	LWT	WATER PD MAX	GPM	TOTAL CAP.	SENS. CAP.	SHR	EAT DB	EAT WB	LAT DB	LAT WB	FACE VEL	AIR PD MAX	EWT	LWT		WATER PD MAX	GPM	TOTAL CAP.	EAT	LAT	FACE VEL	AIR PD MAX	EWT	LWT	WATER PD MAX					GPM	QTY	BHP	KVA	HP	EAT BHP	QTY	BHP	KVA	MOP		480/3	3200	180"	55"	-	1-14										
DOAS-1	3915	1.50	5.20	3525	1.50	3.34	200.0	22.0	68.0	550	5.00	140.0	110.0	5.00	13.3	373.9	140.9	0.38	84.0	78.6	52.0	52.0	550	5.00	44.0	54.0	5.00	6	74.8	92.5	55.0	76.0	550	5.00	140.0	110.0	5.00	6.2	1.0	5.8	7.5	1.0	3.6	5.0	19.9	22.6	30.0	480/3	3200	180"	55"	-	1-14															
DOAS-2	3195	1.50	3.67	2900	1.50	2.79	159.2	22.0	68.0	550	5.00	140.0	110.0	5.00	10.6	297.5	112.1	0.38	84.0	78.6	52.0	52.0	550	5.00	44.0	54.0	5.00	6	59.5	73.6	55.0	76.0	550	5.00	140.0	110.0	5.00	4.9	1.0	4.0	5.0	1.0	2.9	5.0	17.1	19.1	25.0	480/3	3200	180"	55"	-	1-14															
DOAS-3	3505	1.50	2.98	3225	1.50	2.09	174.6	22.0	68.0	550	5.00	140.0	110.0	5.00	11.6	326.4	123.0	0.38	84.0	78.6	52.0	52.0	550	5.00	44.0	54.0	5.00	6	65.3	80.7	55.0	76.0	550	5.00	140.0	110.0	5.00	5.4	1.0	2.9	5.0	1.0	4.0	5.0	17.1	19.1	25.0	480/3	3200	180"	55"	-	1-14															
TOTALS:							533.8								35.6	997.8													199.6	246.8							16.5																															

- REMARKS:
- PROVIDE WITH 2" MERV 8 FILTERS ON THE EXHAUST AND 2" MERV 8 PREFILTERS & 2" MERV 13 FINAL FILTERS ON THE RETURN AND OUTSIDE AIR INTAKE. STATIC PRESSURE INCREASE FROM CLEAN FILTERS IS INCLUDED IN THE SCHEDULED TOTAL STATIC PRESSURE VALUE.
 - PROVIDE PREMIUM EFFICIENCY MOTORS FOR SUPPLY AND EXHAUST FANS. COMPATIBLE WITH VARIABLE FREQUENCY DRIVES.
 - PROVIDE WITH CLASS 1A LOW LEAKAGE DAMPERS ON THE EXHAUST DISCHARGE AND OUTSIDE AIR INTAKE UNIT CONNECTIONS.
 - PROVIDE UNIT WITH HORIZONTAL SUPPLY DISCHARGE, EXHAUST INLET AND OUTSIDE AIR INLET DUCT CONNECTION. UNIT MUST HAVE 2" DOUBLE WALL CONSTRUCTION.
 - VERIFY THAT UNIT CAN BE INSTALLED IN LOCATION SHOWN ON DRAWINGS PRIOR TO SUBMITTING FOR APPROVAL.
 - PROVIDE A 10,000 HR SALT SPRAY PROTECTIVE COATING ON THE COOLING AND REHEAT COILS.
 - UNIT MUST HAVE CROSSFLOW FIXED PLATE TOTAL ENTHALPY HEAT EXCHANGER, PLENUM SUPPLY/EXHAUST FANS, COOLING COIL, REHEAT COIL AND MARINE LIGHTS IN EACH FAN & ACCESS SECTIONS.
 - PROVIDE UNIT WITH SINGLE POINT CONNECTION.
 - REFER TO CV SCHEDULE FOR CONTROL VALVE REQUIREMENTS.
 - PROVIDE UNIT WITH RECIRCULATION PUMP AT PREHEAT COIL FOR FREEZE PROTECTION. ALSO PROVIDE 120/1 CIRCUIT FOR PUMP. PUMP IS SIZED FOR 110% OF PREHEAT COIL PRESSURE DROP AND DESIGN FLOW GPM. SEE HOT WATER PREHEAT COIL DETAIL AND CONTROLS FOR FURTHER INFORMATION.
 - MAXIMUM ALLOWABLE DISCHARGE OR RADIATED NOISE CRITERIA (NC) = 30.
 - AIR HANDLER DESIGNED WITH A FOULING FACTOR OF 0.00025 FT²-HR-°F/BTU FOR ALL COILS.
 - PROVIDE UNIT WITH A MINIMUM 8" INTEGRAL BASE FRAME. EQUIPMENT SUPPORTS TO HAVE VIBRATION ISOLATION. SEE DETAILS AND STRUCTURAL DRAWINGS FOR MORE INFORMATION.
 - PROVIDE VENTILATION SUPPLY DUCTWORK WITH SMOKE DETECTOR.

TOTAL ENERGY HEAT EXCHANGER															
SUMMER								WINTER							
OA	WB	DB	%RH	SA	WB	DB	%RH	OA	WB	DB	%RH	SA	WB	DB	%RH
83.3	76.5	76.0	50.0	81.2	77.0	26.8	22.4	70.0	35.0	48.8	35.9	35.4	63.7		
83.3	78.5	76.0	50.0	81.7	76.9	26.8	22.4	70.0	35.0	48.1	35.5	39	65.3		
83.3	78.5	76.0	50.0	80.1	76.9	26.8	22.4	70.0	35.0	51.7	37.5	58.8	76.7		

AIR DOOR (AD) SCHEDULE

MARK	AREA SERVED	MANUFACTURER	MODEL NO.	LENGTH	CFM	MOTOR HP	FLA	MCCP	VOLT/PH	WEIGHT	REMARKS
AD-1	KITCHEN DOOR ENTRY	MARS	STD242	42"	1418	0.5	5.1	15	120/1	70	1.2

- REMARKS:
- PROVIDE WITH MOTOR CONTROL PANEL AND WALL MOUNTING BRACKET.
 - PROVIDE WITH DOOR POSITION SWITCH OR MAGNETIC REED SWITCH, INTERLOCKED TO OPERATE IF DOOR IS OPEN.

AIR DISTRIBUTION SCHEDULE

MARK	DESCRIPTION	THROW	FACE SIZE	NECK SIZE	MOUNT	MINIMUM CFM	MAXIMUM CFM	MAX. NC	REMARKS
S1	SQUARE CONE DIFFUSER	4 WAY	12X12	6"ø	LAY-IN	0 CFM	75 CFM	30	1-4
S2	SQUARE CONE DIFFUSER	4 WAY	24x24	8"ø	LAY-IN	100 CFM	200 CFM	30	1-4
S3	SQUARE CONE DIFFUSER	4 WAY	24x24	10"ø	LAY-IN	225 CFM	275 CFM	30	1-4
S4	SQUARE CONE DIFFUSER	4 WAY	24x24	12"ø	LAY-IN	300 CFM	600 CFM	30	1-4
E1	PERFORATED EXHAUST DIFFUSER	NA	12X12	6"ø	LAY-IN	0 CFM	75 CFM	30	1-4
E2	PERFORATED EXHAUST DIFFUSER	NA	24x24	8"ø	LAY-IN	100 CFM	175 CFM	30	1-4
E3	PERFORATED EXHAUST DIFFUSER	NA	24x24	10"ø	LAY-IN	200 CFM	275 CFM	30	1-4
E4	PERFORATED EXHAUST DIFFUSER	NA	24x24	12"ø	LAY-IN	300 CFM	400 CFM	30	1-4
E5	LOUVERED, 3/4" SPACING GRILLE	NA	16X12	16X12	SURFACE	290 CFM	375 CFM	30	
R1	PERFORATED RETURN DIFFUSER	NA	12X12	6"ø	LAY-IN	0 CFM	75 CFM	30	1-4
R2	PERFORATED RETURN DIFFUSER	NA	24x24	8"ø	LAY-IN	100 CFM	175 CFM	30	1-4
R3	PERFORATED RETURN DIFFUSER	NA	24x24	10"ø	LAY-IN	200 CFM	275 CFM	30	1-4
R4	PERFORATED RETURN DIFFUSER	NA	24x24	12"ø	LAY-IN	300 CFM	400 CFM	30	1-4
R5	PERFORATED RETURN DIFFUSER	NA	24x24	14"ø	LAY-IN	425 CFM	700 CFM	30	1-4
R6	PERFORATED RETURN DIFFUSER	NA	24x24	16"ø	LAY-IN	725 CFM	950 CFM	30	1-4
R7	PERFORATED RETURN DIFFUSER	NA	24x24	16"ø	SURFACE	940	940	30	

- REMARKS:
- VERIFY CONSTRUCTION TYPES WITH ARCHITECTURAL PLANS TO DETERMINE MOUNTING DETAILS AND ACCESSORIES REQUIRED. COORDINATE COLOR W/ ARCHITECT.
 - PROVIDE WITH SQUARE TO ROUND TRANSITION.
 - ALL AIR DISTRIBUTION MUST BE 100% ALUMINUM CONSTRUCTION.
 - PROVIDE BLANKET INSULATION ON THE BACK OF ALL DIFFUSERS.

FAN COIL UNIT (FCU) SCHEDULE																																		
MARK	COOLING CAPACITY (CHW)															HEATING CAPACITY (HW)										ELECTRICAL				UNIT WEIGHT (LBS)	REMARKS			
	MAX CFM	MIN CFM	E.S.P. "WC	T.S.P. "WC	TOTAL MBH	SENSIBLE MBH	EAT (DB) °F	EAT (WB) °F	LAT (DB) °F	LAT (WB) °F	WATER TEMP. °F	WATER PD FT. MAX.	VELOCITY FPS. MAX	MIN. NUM. OF ROWS	GPM	HEATING					REHEAT (DEHUMIDIFICATION)					WATER PD FT. MAX.	VELOCITY FPS. MAX	ROWS	VPH			BHP	ECM HP	MCA/MOP
																TOTAL MBH	EAT/LAT °F	EWTL/LWT °F	GPM	TOTAL MBH	EAT/LAT °F	EWTL/LWT °F	GPM											
FCU1-01	300	250	0.50	0.86	9.1	7.0	76.2	67.0	57.0	57.0	44/54	5.0	3	4	1.8	8.1	65/95	140/110	0.70	4.6	55/72	140/110	0.35	5.0	4	2	277/1	0.085	0.645	4.7/15	120	12,3,4,5,6		
FCU1-02	500	250	0.50	1.15	12.1	9.3	76.2	67.0	57.0	57.0	44/54	5.0	3	4	2.4	8.1	65/95	140/110	0.70	4.6	55/72	140/110	0.35	5.0	4	2	277/1	0.145	0.693	4.7/15	120	12,3,4,5,6		
FCU1-03	400	400	0.50	1.15	12.1	9.3	76.2	67.0	57.0	57.0	44/54	5.0	3	4	2.4	13.0	65/95	140/110	1.05	7.3	55/72	140/110	0.70	5.0	4	2	277/1	0.145	0.693	4.7/15	120	12,3,4,5,6		
FCU1-04	500	375	0.50	1.44	15.1	11.6	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.0	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.242	0.723	4.7/15	120	12,3,4,5,6		
FCU1-05	400	250	0.50	1.15	12.1	9.3	76.2	67.0	57.0	57.0	44/54	5.0	3	4	2.4	8.1	65/95	140/110	0.70	4.6	55/72	140/110	0.35	5.0	4	2	277/1	0.145	0.693	4.7/15	120	12,3,4,5,6		
FCU1-06	500	375	0.50	1.44	15.1	11.6	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.0	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.242	0.723	4.7/15	120	12,3,4,5,6		
FCU1-07	500	375	0.50	1.44	15.1	11.6	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.0	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.242	0.723	4.7/15	120	12,3,4,5,6		
FCU1-08	500	375	0.50	1.44	15.1	11.6	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.0	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.242	0.723	4.7/15	120	12,3,4,5,6		
FCU1-09	500	375	0.50	1.44	15.1	11.6	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.0	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.242	0.723	4.7/15	120	12,3,4,5,6		
FCU1-10	500	375	0.50	1.44	15.1	11.6	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.0	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.242	0.723	4.7/15	120	12,3,4,5,6		
FCU1-11	1375	800	0.50	1.05	41.6	32.0	76.2	67.0	57.0	57.0	44/54	5.0	3	4	8.3	25.9	65/95	140/110	1.75	14.7	55/72	140/110	1.05	5.0	4	2	277/1	0.921	1.198	7.23/15	120	12,3,4,5,6		
FCU1-12	600	375	0.50	1.42	18.1	14.0	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.6	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.355	0.732	4.7/15	120	12,3,4,5,6		
FCU1-13	500	375	0.50	1.44	15.1	11.6	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.0	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.242	0.723	4.7/15	120	12,3,4,5,6		
FCU1-14	525	250	0.50	1.44	15.1	11.6	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.0	8.1	65/95	140/110	0.70	4.6	55/72	140/110	0.35	5.0	4	2	277/1	0.242	0.723	4.7/15	120	12,3,4,5,6		
FCU2-01	600	375	0.50	1.42	18.1	14.0	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.6	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.355	0.732	4.7/15	120	12,3,4,5,6		
FCU2-02	600	375	0.50	1.42	18.1	14.0	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.6	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.355	0.732	4.7/15	120	12,3,4,5,6		
FCU2-03	500	375	0.50	1.44	15.1	11.6	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.0	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.242	0.723	4.7/15	120	12,3,4,5,6		
FCU2-04	500	375	0.50	1.44	15.1	11.6	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.0	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.242	0.723	4.7/15	120	12,3,4,5,6		
FCU2-05	500	375	0.50	1.44	15.1	11.6	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.0	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.242	0.723	4.7/15	120	12,3,4,5,6		
FCU2-06	500	375	0.50	1.44	15.1	11.6	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.0	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.242	0.723	4.7/15	120	12,3,4,5,6		
FCU2-07	500	375	0.50	1.44	15.1	11.6	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.0	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.242	0.723	4.7/15	120	12,3,4,5,6		
FCU2-08	500	375	0.50	1.44	15.1	11.6	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.0	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.242	0.723	4.7/15	120	12,3,4,5,6		
FCU2-09	500	250	0.50	0.86	9.1	7.0	76.2	67.0	57.0	57.0	44/54	5.0	3	4	1.8	8.1	65/95	140/110	0.70	4.6	55/72	140/110	0.35	5.0	4	2	277/1	0.085	0.645	4.7/15	120	12,3,4,5,6		
FCU2-10	500	375	0.50	1.44	15.1	11.6	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.0	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.242	0.723	4.7/15	120	12,3,4,5,6		
FCU3-01	750	500	0.50	1.23	20.9	17.5	76.2	67.0	57.0	57.0	44/54	5.0	3	4	4.8	16.2	65/95	140/110	1.40	9.2	55/72	140/110	0.70	5.0	4	2	277/1	0.517	0.733	4.7/15	130	12,3,4,5,6		
FCU3-02	500	250	0.50	1.15	12.1	9.3	76.2	67.0	57.0	57.0	44/54	5.0	3	4	2.4	8.1	65/95	140/110	0.70	4.6	55/72	140/110	0.35	5.0	4	2	277/1	0.145	0.693	4.7/15	120	12,3,4,5,6		
FCU3-01	700	375	0.50	1.15	21.1	16.3	76.2	67.0	57.0	57.0	44/54	5.0	3	4	4.2	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.145	0.693	4.7/15	130	12,3,4,5,6		
FCU3-02	600	375	0.50	1.42	18.1	14.0	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.6	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.355	0.732	4.7/15	130	12,3,4,5,6		
FCU3-03	700	500	0.50	1.15	21.1	16.3	76.2	67.0	57.0	57.0	44/54	5.0	3	4	4.2	16.2	65/95	140/110	1.40	9.2	55/72	140/110	0.70	5.0	4	2	277/1	0.145	0.693	4.7/15	130	12,3,4,5,6		
FCU3-04	600	375	0.50	1.42	18.1	14.0	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.6	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.355	0.732	4.7/15	130	12,3,4,5,6		
FCU3-05	700	500	0.50	1.15	21.1	16.3	76.2	67.0	57.0	57.0	44/54	5.0	3	4	4.2	16.2	65/95	140/110	1.40	9.2	55/72	140/110	0.70	5.0	4	2	277/1	0.145	0.693	4.7/15	130	12,3,4,5,6		
FCU3-06	600	375	0.50	1.42	18.1	14.0	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.6	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.355	0.732	4.7/15	130	12,3,4,5,6		
FCU3-07	600	375	0.50	1.42	18.1	14.0	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.6	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.355	0.732	4.7/15	130	12,3,4,5,6		
FCU3-08	800	500	0.50	1.31	24.2	18.5	76.2	67.0	57.0	57.0	44/54	5.0	3	4	4.8	16.2	65/95	140/110	1.40	9.2	55/72	140/110	0.70	5.0	4	2	277/1	0.699	0.733	4.7/15	130	12,3,4,5,6		
FCU3-09	700	500	0.50	1.15	21.1	16.3	76.2	67.0	57.0	57.0	44/54	5.0	3	4	4.2	16.2	65/95	140/110	1.40	9.2	55/72	140/110	0.70	5.0	4	2	277/1	0.145	0.693	4.7/15	130	12,3,4,5,6		
FCU3-10	650	375	0.50	1.07	19.7	15.1	76.2	67.0	57.0	57.0	44/54	5.0	3	4	3.9	12.2	65/95	140/110	1.05	6.9	55/72	140/110	0.70	5.0	4	2	277/1	0.36	0.725	4.7/15	130	12,3,4,5,6		
TOTALS:					613.6										122.7	447.9			38.1				23.4											

REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	

EXPANSION TANK (ET) SCHEDULE														
MARK	FLUID	PIPING MATERIAL	SYSTEM VOLUME (GAL)	MIN. OPERATING TEMP. (F)	MAX. DESIGN TEMP. (F)	MAX. SYSTEM HEIGHT (FT.)	PRECHARGE PRESS. (PSI)	ASME PRESSURE RATING (PSI)	TANK VOLUME (GAL)	ACCEPTANCE VOLUME (GAL)	SERVICE	WEIGHT (LB)		REMARKS
												EMPTY	FULL	
ET-1	WATER	COPPER	475	50	140	21	18	125	10	10	HOT WATER	40	124	1
ET-2	WATER	COPPER	2258	42	90	28	18	125	13	13	CHILLED WATER	120	250	1

REMARKS:
1. PROVIDE PRE-CHARGED FULL ACCEPTANCE BLADDER TANK AS WELL AS SIGHT GLASS, ANCHOR CLIPS, AND STAINLESS STEEL CONNECTOR.

BUFFER TANK (BT) SCHEDULE						
MARK	GALLONS	DIMENSIONS	CONNECTION SIZE (IN)	WEIGHT (LBS)	SERVICE	REMARKS
BT-1	1500	5' DIA X 12' 4" LONG	6"	15250	CHILLED WATER	1

REMARKS
1. PROVIDE WITH INTERNAL BAFFLE, AIR VENT AT TOP OF TANK, DRAIN, FLANGED LOW CONNECTIONS AND
4 LEG STANDS FOR MOUNTING TO CONCRETE PAD.

AIR AND DIRT SEPERATOR (AS) SCHEDULE				
MARK	CONNECTION SIZE (IN)	MAX PD (FT. WG)	SERVICE	REMARKS
AS-1	3	5	HOT WATER	1,2
AS-2	4	5	CHILLED WATER	1,2

REMARKS
1. PROVIDE WITH REMOVABLE HEAD AND AUTOMATIC AIR RELIEF VALVE.
2. SEPARATOR MUST BE COALESCING AIR/DIRT TYPE.

HOT WATER UNIT HEATER (UH) SCHEDULE												
MARK	LOCATION	THROW	AIRFLOW (CFM)	HEATING CAPACITY (MBH)	EWI	LWT	FLOW (GPM)	PD (FT. HD)	FAN (HP)	VOLT/PH	WEIGHT	REMARKS
UH-1	109F MECH. BLDG.	HORIZONTAL	340	18.0	140	110	1.2	0.2	1/60	115/1	16	1,2,3
UH-2	138 MECHANICAL	HORIZONTAL	340	18.0	140	110	1.2	0.2	1/60	115/1	16	1,2,3
UH-3	141 SPRINKLER	HORIZONTAL	340	18.0	140	110	1.2	0.2	1/60	115/1	16	1,2,3

REMARKS
1. PROVIDE WITH WALL/CEILING MOUNTING BRACKET.
2. PROVIDE WITH WALL MOUNTED, LINE VOLTAGE THERMOSTAT. E.C. TO INSTALL AND WIRE.
3. SEE CONTROL VALVE SCHEDULE FOR CONTROL VALVE REQUIREMENTS.

CHEMICAL SHOT FEEDER (CF) SCHEDULE					
MARK	TANK VOLUME (GAL)	SERVICE	WEIGHT (LB)		REMARKS
CF-1	2	HOT WATER	20	40	1
CF-2	5	CHILLED WATER	40	80	1

REMARKS:
1. PROVIDE 200 PSIG PRESSURE RATED POT FEEDER.

AIR COOLED PACKAGE CHILLER (CH) SCHEDULE														
MARK	NOMINAL CAPACITY (TONS)	COOLING CAPACITY (TONS)	EWT (°F)	LWT (°F)	Δ P (FT)	GPM	FOULING FACTOR (°F FT2 H/BTU)	FULL LOAD EER	IPLV EER	VOLT/PH	MCA	MOCp	WEIGHT (LBS)	REMARKS
CH-1,2	90	85.9	54	44	12	213	0.0001	10.7	16.8	460/3	183	225	6000	1,2,3,4,5

REMARKS
1. PROVIDE MINIMUM 4 SCROLL COMPRESSORS, LOW AMBIENT OPERATION DOWN TO 0°F, HAIL GUARDS ON COIL AND COMPRESSOR SECTIONS, VIBRATION ISOLATION, FLOW SWITCH, BACNET MS/TP COMMUNICATIONS CARD FOR FULL INTERGRATION OF POINTS INTO BAS AND SINGLE POINT POWER CONNECTION.
2. SELECT UNIT AT 100° AMBIENT WITH R-454B OR R-32. CHILLER MUST HAVE TWO INDEPENDENT REFRIGERATION CIRCUITS.
3. PROVIDE FACTORY START-UP, 1 YEAR LABOR WARRANTY, 3 YEAR CONDENSER COIL WARRANTY AND 10 YEAR EXTENDED COMPRESSOR WARRANTY.
4. ENTIRE CHILLER MUST HAVE 10,000 HR SALTSPRAY PROTECTION IN ACCORDANCE WITH ASTM B117. COATINGS MUST NOT REDUCE COIL CAPACITIES BELOW SCHEDULED VALUES.
5. PROVIDE CORE FILTER DRYER ON SUCTION LINE AND LIQUID AND SUCTION LINE SERVICE VALVES.

BOILER (B) SCHEDULE																	
MARK	LOCATION	ORIENTATION	INPUT (MBH)	OUTPUT (MBH)	TURNDOWN	AFUE MIN EFF %	EWI (°F)	LWT (°F)	FLOW (GPM)	PD (FT. HD)	FLUE SIZE (IN)	INTAKE SIZE (IN)	ELECTRICAL			WEIGHT (LBS)	REMARKS
B-1	MECH ROOM	CONDENSING FLOOR MOUNTED	399	387	10:1	97.0	110	140	33	8	4	4	1201	3.0	3.8	400	1,2,3,4,5,6
B-2	MECH ROOM	CONDENSING FLOOR MOUNTED	399	387	10:1	97.0	110	140	33	8	4	4	1201	3.0	3.8	400	1,2,3,4,5,6
B-3	MECH ROOM	CONDENSING FLOOR MOUNTED	399	387	10:1	97.0	110	140	33	8	4	4	1201	3.0	3.8	400	1,2,3,4,5,6,7

REMARKS:
1. PROVIDE NATURAL GAS, LOW NOx BOILER, LOW CO MODULATING BOILER.
2. HOT WATER TEMPERATURES: 110°F EWI/140°F LWT.
3. PROVIDE NEUTRALIZATION TANK FOR BOILER CONDENSATE, PIPED TO FLOOR DRAIN.
4. PROVIDE BOILER MANAGEMENT PANEL. TO CONTROL INTERNAL BOILER FUNCTIONS. PROVIDE BACNET MS/TP CARD FOR EXTERNAL BACNET CONNECTION, ALARM, ENABLE/DISABLE AND PUMP CONTROL.
5. PROVIDE WITH POLYPROPYLENE (PP) 4" INTAKE AND 4" EXHAUST KITS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS FOR ROOF INSTALLATION.
6. MANUFACTURER OPTIONS TO INCLUDE: FLOW SWITCH, CONSTANT SPEED PRIMARY PUMP.
7. PROVIDE ONE (1) SPARE PUMP.


PUMP SCHEDULE										
MARK	SERVICE	TYPE	FLOW (GPM)	HEAD (FT. WG)	BHP	HP	VOLT/PH	RPM	REMARKS	
PCHWP-1	PRIMARY CHILLED WATER (CH-1)	INLINE	213	30	2.2	3.0	460/3	1800	1,2,5	
PCHWP-2	PRIMARY CHILLED WATER (CH-2)	INLINE	213	30	2.2	3.0	460/3	1800	1,2,5	
PCHWP-3	PRIMARY CHILLED WATER (STANDBY)	INLINE	213	30	2.2	3.0	460/3	1800	1,2,5	
SCHWP-1	SECONDARY CHILLED WATER	INLINE	322	77	7.6	10.0	460/3	1800	1,2,5	
SCHWP-2	SECONDARY CHILLED WATER (STANDBY)	INLINE	322	77	7.6	10.0	460/3	1800	1,2,5	
SHWP-1	SECONDARY HOT WATER SYSTEM	INLINE	77	40	1.2	1.5	460/3	1800	1,2,5	
SHWP-2	SECONDARY HOT WATER SYSTEM	INLINE	77	40	1.2	1.5	460/3	1800	1,2,5	
PHWP-1	PRIMARY HOT WATER SYSTEM (B-1)	INLINE	33	20	-	0.5	277/1	1800	3,4	
PHWP-2	PRIMARY HOT WATER SYSTEM (B-2)	INLINE	33	20	-	0.5	277/1	1800	3,4	
PHWP-3	PRIMARY HOT WATER SYSTEM (B-3)	INLINE	33	20	-	0.5	277/1	1800	3,4	

REMARKS:
1. PROVIDE WITH VFD AND BACNET MS/TP CARD.
2. PUMP IS SIZED FOR TOTAL SYSTEM CAPACITY WITH BACK-UP OR STANDBY PUMP FOR N+1 OPERATION, WITH LEAD/LAG CONTROLS.
3. PROVIDE WITH BACNET MS/TP CARD.
4. VERIFY FLOW AND HEAD REQUIREMENTS FOR SELECTED BOILER TO ENSURE PUMP IS SELECTED WITHIN 5% OF PEAK EFFICIENCY.
5. PROVIDE PUMP WITH SUCTION DIFFUSER AND FLEX CONNECTORS.

CONTROL VALVE SCHEDULE															
EQUIPMENT	FLOW RATE (gpm)	NOMINAL SIZE (in)	MIN. CV	MAX. PD (psi)	SERVICE	CONFIGURATION	ACTION	EQUIPMENT	FLOW RATE (gpm)	NOMINAL SIZE (in)	MIN. CV	MAX. PD (psi)	SERVICE	CONFIGURATION	ACTION
FCU-1-01	0.7	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-1-01	1.8	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-1-02	0.7	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-1-02	2.4	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-1-03	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-1-03	2.4	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-1-04	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-1-04	3.0	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-1-05	0.7	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-1-05	2.4	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-1-06	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-1-06	3.0	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-1-07	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-1-07	3.0	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-1-08	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-1-08	3.0	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-1-09	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-1-09	3.0	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-1-10	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-1-10	3.0	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-1-11	1.8	3/4	2.0	3.0	HW	2-WAY	MOD	FCU-1-11	8.3	1	2.0	3.0	CHW	2-WAY	MOD
FCU-1-12	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-1-12	3.6	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-1-13	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-1-13	3.0	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-1-14	0.7	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-1-14	3.0	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-2-01	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-2-01	3.6	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-2-02	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-2-02	3.6	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-2-03	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-2-03	3.0	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-2-04	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-2-04	3.0	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-2-05	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-2-05	3.0	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-2-06	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-2-06	3.0	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-2-07	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-2-07	3.0	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-2-08	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-2-08	3.0	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-2-09	0.7	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-2-09	1.8	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-2-10	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-2-10	3.0	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-2-11	1.4	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-2-11	4.8	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-2-12	0.7	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-2-12	2.4	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-3-01	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-3-01	4.2	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-3-02	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-3-02	3.6	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-3-03	1.4	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-3-03	4.2	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-3-04	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-3-04	3.6	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-3-05	1.4	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-3-05	4.2	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-3-06	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-3-06	3.6	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-3-07	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-3-07	3.6	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-3-08	1.4	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-3-08	4.8	3/4	2.0	3.0	CHW	2-WAY	MOD
FCU-3-09	1.4	1/2	2.0	3.0	HW	3-WAY	MOD	FCU-3-09	4.2	3/4	2.0	3.0	CHW	3-WAY	MOD
FCU-3-10	1.1	1/2	2.0	3.0	HW	2-WAY	MOD	FCU-3-10	3.9	3/4	2.0	3.0	CHW	3-WAY	MOD
DOAS-1 PREHEAT	13.3	1 1/4	2.0	3.0	HW	2-WAY	MOD	DOAS-1	74.8	3	2.0	3.0	CHW	2-WAY	MOD
DOAS-1 REHEAT	6.2	1	2.0	3.0	HW	2-WAY	MOD								
DOAS-2 PREHEAT	10.6	3/4	2.0	3.0	HW	3-WAY	MOD	DOAS-2	59.5	3	2.0	3.0	CHW	3-WAY	MOD
DOAS-2 REHEAT	4.9	3/4	2.0	3.0	HW	2-WAY	MOD								
DOAS-3 PREHEAT	11.6	1 1/4	2.0	3.0	HW	3-WAY	MOD	DOAS-3	65.3	3	2.0	3.0	CHW	3-WAY	MOD
DOAS-3 REHEAT	5.4	3/4	2.0	3.0	HW	2-WAY	MOD								
UH-1	1.2	1/2	2.0	3.0	HW	2-WAY	MOD								
UH-2	1.2	1/2	2.0	3.0	HW	2-WAY	MOD								
UH-3	1.2	1/2	2.0	3.0	HW	2-WAY	MOD								

 03-09-20	 CRENSHAW CONSULTING www.crenshawconsulting.com 205 South Street, Suite 200 Raleigh, North Carolina 27601 919-871-9270 Fax: 919-880-0001	DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND MARINE CORPS BASE CAMP LEJEUNE, NORTH CAROLINA	M-603
DES: LWM DR: PJR CHK: JDL SUBMITTED BY: DESIGN DIR: JENNI REED APPROVED: PWO OR OICC SATISFACTORY TO:	DATE: _____ DATE: _____ DATE: _____	SIZE: _____ CODE IDENT. NO.: _____ E1 80091 CONSTR. CONTR. NO.: N40085-24-F-5940 SCALE: AS NOTED SPEC: _____	NAVFAC DRAWING NO.: 60042095 MECHANICAL REPAIRS BUILDING TT113 MECHANICAL SCHEDULES SHEET 88 OF 110

REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	



A1 HOT WATER SYSTEM DIAGRAM
NTS



03-09-20

DES: LWM
DR: PJR
CHK: JDL
SUBMITTED BY:
DESIGN DR: JENNI REED
APPROVED: PWV OR OICC
SATISFACTORY TO:

2400

CRENSHAW CONSULTING
engineers
www.crenshawconsulting.com
NO LICENSE #C-785
303 East Street, Suite 300
Raleigh, North Carolina 27601
919-871-9270 Fax: 919-880-0

DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND

MARINE CORPS BASE
CAMP LEJEUNE, NORTH CAROLINA

**MECHANICAL REPAIRS
BUILDING TT113**

HOT WATER SYSTEM DIAGRAM

NAVIFAC DRAWING NO.
60042102

CONSTR. CONTR. NO. N40085-24-F-5940


SCALE: AS NOTED SPEC: SHEET 95 OF 110

M-801


NAVIFAC NO. 2400

DES: LWM
DR: PJR
CHK: JDL
SUBMITTED BY:
DESIGN DR: JENNI REED
APPROVED: PWV OR OICC
SATISFACTORY TO:


REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	



A1 CHILLED WATER SYSTEM DIAGRAM
NTS




- NOTE:
1. UTILIZE BALL VALVES UP THROUGH 3" PIPE SIZES FOR SHUT-OFF.
 2. UTILIZE BUTTERFLY VALVES FOR 3-1/2" PIPE SIZES AND LARGER FOR SHUT-OFF.
 3. SEE CONTROL VALVE SCHEDULE ON SHEET FOR 2-WAY & 3-WAY CONTROL VALVE REQUIREMENTS.




		M-802	
CRENSHAW CONSULTING 2400 NO LICENSE #C-1765 303 East Street, Suite 300 Raleigh, North Carolina 27601 919-871-9270 Fax: 919-8480		DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND MARINE CORPS BASE CAMP LEJEUNE, NORTH CAROLINA	
DES: LWM DR: PJR CHK: JDL SUBMITTED BY: DESIGN DIR: JENNI REED APPROVED: PWO OR OICC SATISFACTORY TO:		CHILLED WATER SYSTEM DIAGRAM NAVIFAC DRAWING NO. 60042103 CONSTR. CONTR. NO. N40085-24-F-5940 SCALE: AS NOTED SPEC: SHEET 96 OF 110	


REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	



B1 3D ISOMETRIC VIEW - DOAS-1




A1 3D ISOMETRIC VIEW - CHILLER YARD



A3 3D ISOMETRIC VIEW - MECHANICAL BUILDING

		M-901	
		CRENSHAW CONSULTING 2400 NO LICENSE #C-1765 3015 South Street, Suite 300 Raleigh, North Carolina 27609 919-871-9270 Fax: 919-880-0	
DES: LWM DR: PJR CHK: JDL SUBMITTED BY: DESIGN DIR: JENNI REED APPROVED: PW/O OR O/C SATISFACTORY TO:		DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND MARINE CORPS BASE CAMP LEJUNE, NORTH CAROLINA MECHANICAL REPAIRS BUILDING TT113 3D ISOMETRIC VIEW - DOAS-1 NAVIFAC DRAWING NO. 60042104 CONSTR. CONTR. NO. N40085-24-F-5940 SCALE: AS NOTED SPEC: SHEET 97 OF 119	
SIZE: E1 CODE IDENT. NO. 80091		DATE: DATE:	


REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	




A1 3D ISOMETRIC VIEW - DOAS-2

		M-902	
		DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND	
		MARINE CORPS BASE	
		CAMP LEJEUNE, NORTH CAROLINA	
DES: LWM DR: PJR CHK: JDL SUBMITTED BY: DESIGN DIR: JENNI REED APPROVED: PW/O OR OICC SATISFACTORY TO:		MECHANICAL REPAIRS BUILDING TT113	
SIZE: E1 CODE IDENT. NO.: 80091		NAVIFAC DRAWING NO.: 60042105	
DATE:		CONSTR. CONTR. NO.: N40085-24-F-5940	
SCALE: AS NOTED		SHEET 96 OF 119	

REVISIONS			
SYM.	DESCRIPTION	DATE	APP.
2	PPI REVISION 2	03.09.20	



A1 3D ISOMETRIC VIEW - DOAS-3



CRENSHAW CONSULTING
engineers
www.crenshawconsulting.com
NO LICENSE #C-785
205 South Street, Suite 200
Raleigh, North Carolina 27609
919-871-8270 Fax: 919-880-0000

DES: LWM
DR: PJR
CHK: JDL
SUBMITTED BY:
DESIGN DIR: JENNI REED
APPROVED: PW/O OR O/C DATE:
SATISFACTORY TO: DATE:

DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND
MARINE CORPS BASE
CAMP LEJEUNE, NORTH CAROLINA

**MECHANICAL REPAIRS
BUILDING TT113**
3D ISOMETRIC VIEW - DOAS-3
NAVIFAC DRAWING NO.
60042106
CONSTR. CONTR. NO. N40085-24-F-5940

SCALE: AS NOTED SPEC: SHEET 99 OF 119

M-903