

MACC# 24-0419
PROJECT# 24MO52CN
MAXIMO# 5422382

TITLE: MULTIPLE BUILDING FLOORING PROJECT

ATTACHMENTS: 1. Scope, Specs, and ACM Reports

SCOPE OF WORK: The contractor shall provide all material, labor, equipment, and supervision required to accomplish the following:

General Description: This scope of work is to be accomplished at Buildings 24, 1011, and 8 at Camp Lejeune, North Carolina. The contractor shall remove carpet in specified areas and replace along with any baseboard for those said areas.

General Specifications: The contractor shall follow the general specifications unless noted in the project area description section. All measurements are for reference use only. *THE CONTRACTOR SHALL TAKE THEIR OWN FIELD MEASUREMENTS IN DETERMINING REQUIRED MATERIAL AND COSTS. ALL WORK PERFORMED SHALL MEET OR EXCEED NC MACC GENERIC SPECIFICATIONS THAT ARE ATTACHED.*

Project Area Descriptions:

1. Building 24, Room 210

- a. The contractor shall demo approximately 288 sq ft of carpet 110 LF vinyl cove base. Prep floor and apply approximately 288 sq ft of floor sealer. Install approximately 288 SF of carpet and approximately 110 LF of vinyl cove base. Floor sealer to be Ardex Concrete Floor Sealer or equivalent. Carpet to be Tarkett Abrasive Action 19101 Midnight Blue carpet tiles or equivalent. Vinyl cove base to match existing cove base.

2. Building 1011, Rooms 202, 203, 206, 208, 209, 210

- a. The contractor shall demo approximately 2585 SF of carpet and 546 LF of vinyl cove base. Prep floor and apply approx. 2585 SF of floor sealer. Install approx. 2585 SF of carpet and 546 LF of vinyl cove base. Floor sealer to be Ardex Concrete Floor Sealer or equivalent. Carpet to be Tarkett Abrasive Action 19101 Midnight Blue carpet tiles or equivalent. Vinyl cove base to match existing cove base.

3. Building 8, Command Deck, Meeting Room, offices and S4 wing

- a. The contractor shall demo approximately 26,000 SF of carpet and 3,240 LF of vinyl cove base. Prep floor and apply approximately 26,000 SF of floor sealer. Install approximately 26,000 SF of carpet and 3,240 LF of vinyl cove base. Apply floor sealer to be Ardex Concrete Floor Sealer or equivalent. This shall be applied where all carpet was demoed. Carpet to be Tarkett Abrasive Action Winter Grey 19103 carpet tiles or equivalent. Vinyl Cove Base to match existing.

NOTE: All measurements are approximate and should be field verified by contractor.

PROCEDURE:

Preparation:

The contractor shall take the necessary precautions to prepare and protect personal property, government property, and work areas during the accomplishment of work for this scope.

Interior Floor Carpet, Wax, Buff and Repairs:

Contractor shall replace any threshold between carpet and VCT as needed.

Existing carpet should be removed and replaced to manufactures specifications.

Replace any vinyl wall base that is disturbed. Sealant shall be applied before carpet is installed.

SPECIAL CONDITIONS

1. Clean all over-spray, drips, splatters, and spills resulting from accomplishing work for this project.
2. Repair, refinish areas damaged or disturbed by new work to be provided under this contract.
3. Properly remove, haul, and dispose of all debris. The contractor shall not utilize the dumpster provided by Camp Lejeune for the occupants or the base landfill.

SCHEDULING AND ACCESS:

1. Building 24 - SSgt. Carlos Melchor 910-450-2113
2. Building 1011 - John Heffington 910-450-8422
3. Building 8 - Freddie McDonald Jr 910-451-4270
4. General
 - a. This schedule is event driven and may be deviated from if both the occupants and contractor agree. Once the work has been started this project shall be worked continuously during scheduling.
 - b. Working hours to ensure timely completion.
 - c. Working hours are from 0730 to 1800 Monday through Friday. Scheduling work for weekends and holidays can be arranged with the occupants upon request.

HAZARDOUS MATERIALS: See attached Asbestos Reports

ENVIRONMENTAL REQUIREMENTS: None Identified

SUBMITTALS:

The contractor shall submit to the contracting officer, the manufacturer's product specifications, complete with technical products data being used for this project. Submittal should be marked for PROJECT No.

MATERIAL SPECIFICATIONS (CARPET)

1. CARPET:

- a. Bldg. 24
 - i. Carpet to be Tarkett Abrasive Action 19101 Midnight Blue carpet tiles or equivalent. Vinyl cove base to match existing cove base.
- b. Bldg. 1011 Rooms 202, 203, 206, 208, 209, 210
 - i. Carpet to be Tarkett Abrasive Action 19101 Midnight Blue carpet tiles or equivalent. Vinyl cove base to match existing cove base.
- c. Bldg. 8 Command Deck, Meeting Room, S4 Wing
 - i. Carpet to be Tarkett Abrasive Action Winter Grey 19103 carpet tiles or equivalent. Vinyl Cove Base to match existing.

2. SEALANT:

- a. Ardex or equivalent sealant for moisture control.

WARRANTY

Flooring contractor shall provide per the attached Combined Division 01 Specifications.