

Enclosure (1) to Sources Sought Notice N00024-26-R-4443

General Information and Availability Work Package

A. General

- a. Rough Estimate:
 - i. Repair/Maintenance 320K hours
 - ii. Modernization: 1,000K hours
- b. Ship Particulars:
 - i. Length: 186m (610 ft)
 - ii. LBP: 182.9m (600 ft)
 - iii. Beam, max: 24.6m (80.7 ft)
 - iv. Draft, DWL: 7m (23.0 ft)
 - v. Draft, Navigation: 8.4m (27.6 ft)
 - vi. Depth, Fwd/Aft: 16.5m / 13.5m
(54.1 ft / 44.3 ft)
 - vii. Depth, top Deckhouse: 34.5m (113.2 ft)
 - viii. Depth, top Ltng Rod: 39.8m (130.6 ft)
- c. Facility Particulars:
 - i. Pier Length: > 610 ft
 - ii. Electrical: 800 amps, 4160 volts, 60 hz, 3 ph (UFC 4-150-02 table C-7)
 - iii. Potable Water: 10,000 GPD, 55 PSI (UFC 4-150-02 Table C-4)
 - iv. Firefighting Sea Water: 1250 GPM (UFC 4-150-02 Table C-3), 150 PSI measured at the most remote outlet (UFC 4-150-02, Para 3-3.2.1)
 - v. Sewage: Ability to accommodate and dispose of 10,000 GPD of effluent and 10,000 GPD of waste water
 - vi. Mean Pier Water depth draft: >33 ft
 - vii. Dry Dock to support DDG1000 Class Ship
- d. LMVLS Unit Module Dimensions
 - i. Length: 44'7"
 - ii. Width: 20'8"
 - iii. Height: 41'1"
 - iv. Weight: ~600 tons

- B. The Availability's modernization scope will largely be removal of the MT 61 Advanced Gun System (AGS) mount, installation of Conventional Prompt Strike capability, relocation of the Main Turbine Generator (MTG) intakes, and incorporation of changes to the Propulsion Seawater (PSW) system. The awarded contractor must be able to include and incorporate AIT integration, 3rd Party contractors, Government personnel, Long Lead Time Material (LLTM) procurement, etc. in their Integrated Production Schedule (IPS). Key trades & efforts include: Structural welding, cabling pulling, piping, electrical and ventilation work if needed. Both the MSR and AIT will execute the structural/Industrial work. A list of work specifications to be performed is provided in Enclosure (2).
- C. The Availability's maintenance package targets prioritized lifecycle and preventative maintenance activities outlined in Enclosure (2):

Enclosure (2)

CONVENTIONAL PROMPT STRIKE (CPS)			
ALTERATION	WORK SPEC #	TITLE	DESCRIPTION
SHIPALT-97881-	711-90-006	MT62 AGS UPPER GUN MOUNT REMOVAL	REMOVAL OF MT62 ADVANCED GUN SYSTEM (AGS). THIS INCLUDES REMOVING THE LOWER GUN MOUNT ASSEMBLY, ROTATING WEATHER SHIELD, AND CENTERLINE HOIST ASSEMBLY. STRENGTHENING THE MAIN DECK TO SUPPORT SLAMMING LOADS CAUSED BY REMOVAL OF MT62.
SHIPALT-97505-	721-90-001	AGS MT 61 REMOVAL AND LMVLS HM&E MODIFICATIONS	MODIFICATIONS NECESSARY TO SUPPORT INSTALLATION OF THE CONVENTION PROMPT STRIKE (CPS) WEAPON SYSTEM WITHIN THE 1400 STACK. INSTALLATION INCLUDES: THE LMVLS MAGAZINE, APM LAUNCH MODULES, SHOCK ISOLATION SYSTEM, WEATHER DECK HATCHES, AND ALL HM&E MODIFICATIONS NECESSARY TO SUPPORT CPS
SHIPALT-97869-	721-90-002	LMVLS WCS RIPOUT AND INSTALLATION	INTEGRATION OF (CPS) WEAPONS CONTROL SYSTEM COMPONENTS INCLUDE THE FOLLOWING: WEAPON CONSOLES, WEAPONS INTERFACE BOXES, REMOTE DISPLAYS, AND CS/C4I CABLING AND CONNECTIONS AS REQUIRED FOR CPS OPERATION AND CONTROL. IN ADDITION, THIS ALTERATION SUPPORTS RAYTHEON, LOCKHEED MARTIN, AND NAVWAR AIT WORK SCOPE.
SHIPALT-98380-	863-71-403	CPS TSCE ENTI CONVENTIONAL PROMPT STRIKE	BASELINE CONFIGURATION CHANGES ARE NEEDED IN SEVERAL TSCE HARDWARE CONFIGURATION ITEMS IN ORDER TO INTEGRATE WITH THE CONVENTIONAL PROMPT STRIKE WEAPON SYSTEM. PERIPHERALS AND CABLE CHANGES, CPS EEME CHANGES TO HOUSE CPS RACKS, CPS 1PPS EQUIPMENT ADDITION TO EME 1B
NON-CPS MODERNIZATION			
ALTERATION	WORK SPEC #	TITLE	DESCRIPTION
SHIPALT-96881-	202-90-001	FUEL ENDURANCE AND RANGE EXTENSION MODIFICATION	INCREASE THE NAUTICAL MILE RANGE OF THE DDG 1000 CLASS SHIPS. THIS IS ACCOMPLISHED BY INCREASING THE FUEL OIL STORAGE CAPACITY AS A RESULT OF CONVERTING EXISTING SALT WATER BALLAST (SWB) TANKS TO FUEL OIL (FO) STORAGE TANKS.
SHIPALT-97208-	251-90-001	MTG INTAKE RELOCATION	RELOCATION OF MAIN TURBINE GENERATOR INTAKE LOCATIONS FROM TOP TO SIDE OF DECKHOUSE TO AVOID EXHAUST INGESTION WHILE UNDERWAY.
SHIPALT-97209-	251-90-003	MTG INTAKE PRESSURE LOSS IMPROVEMENTS	THE EXISTING MTG 1 & MTG 2 INTAKE AND FOUNDATIONS, FROM THE TOP OF THE INTAKE BOOT THROUGH 2ND DECK, WILL BE REMOVED AND SCRAPPED. THE BERP PLATES AT 2ND DECK AROUND THE INTAKE WILL ALSO BE REMOVED AND SCRAPPED. A NEWLY FABRICATED INTAKE SECTION, WITH MODIFIED GEOMETRY, WILL BE INSTALLED. NEW BERP PLATES WILL BE INSTALLED AROUND THE NEW INTAKES.
SHIPALT-96942-	256-90-001	PROPULSION SEA WATER (PSW) REDESIGN	THIS MODIFICATION WILL ADD AUTOVENTS TO SEACHESTS IN THE PSW SYSTEMS THAT ARE CURRENTLY NON-VENTED.
SHIPALT-97760-	256-90-002	PROPULSION SEA WATER AND AUXILIARY PUMP SEA WATER CASING AUTOVENTS	THIS ALTERATION WILL ADD AUTOMATIC AIR RELEASE VALVES TO (5) MAIN PSW PUMP CASINGS, AND (4) ASW PUMP CASINGS TO PREVENT PUMP SEAL FAILURE, AND REMOVE AIR FROM THE PSW/ASW PUMP CASINGS DURING OPERATION.
SHIPALT-96880-	261-90-001	FUEL OIL STANDPIPE MODIFICATION	THIS ALTERATION WILL INCREASE THE REFUELING RATE OF DDG 1000 CLASS SHIPS WHILE ALONGSIDE, REFUELING AT SEA (RAS), BY INCREASING THE HEIGHT OF THE FWD AND AFT FUEL OIL OVERFLOW STANDPIPES.

SHIPALT-98337-	418-90-001	EO/IR SYSTEM IMPROVEMENTS	ADDITION OF TWO (2) FLIR 380HD CAMERAS, MOUNTED PORT AND STARBOARD ON THE HOUSE SIDES, ON SPONSONS SIMILAR TO EXISTING UHF, EHF, AND WHIP ANTENNAS. INSTALLATION OF WASH SYSTEM FOR CAMERAS AND CESV WINDOWS
SHIPALT-97994-	436-90-005	DDG 1000 CLASS ECS HARDPLC REFRESH	UPGRADING ENGINEERING CONTROL SYSTEM (ECS) SOFTPLC'S TO HARDPLCS TO AVOID OBSOLESENE AND CYBER VULNERABILITIES
SHIPALT-97995-	436-90-005	DDG 1000 CLASS ECS NETWORK REFRESH	UPGRADING ECS NETWORK SWITCHES WITH NEW MODELS TO ADDRESS CYBERSECURITY AND OBSOLESENE ISSUES
SHIPALT-98174-	536-90-001	PROPULSION FRESH WATER (PFW) SYSTEM HIGH POINT VENT	THIS ALTERATION WILL ADD HIGH POINT AUTO-VENTS THROUGHOUT THE PFW SYSTEM TO REMOVE ENTRAINED AIR AND IMPROVE PERFORMANCE OF THE PFW SYSTEM.
SHIPALT-97983-	583-90-006	BOAT HANDLING SYSTEM MODIFICATIONS V BUNK & LOCKING PIN	MODIFICATION OF EXISTING BOAT HANDLING SYSTEM (BHS) TO REMOVE EXISTING TRANSFER WHEELS, CAPTURE WHEELS, BRIDGE FENDERS AND KEEL ROLLERS IN ORDER TO INCOPROATE V-BUNK AND LOCKING MECHANISM
SHIPALT-96878-	643-90-001	CREW ACCOMMODATION AND BERTHING INCREASE	HABITIABILITY MODIFICATIONS (BERTHING, UNCLASS NETWORK DROPS) TO STATEROOMS TO SUPPORT INCREASE OR CREW SIZE FROM 200 TO 219. INSTALLATION OF ADDITIONAL LIFTAFT ATOP HANGAR.

MAINTENANCE WORK PACKAGE			
WORK ITEM	WORK SPEC #	TITLE	DESCRIPTION
AWI-1178-	897-11-001	PLANNED MAINTENANCE SYSTEM (PMS) ACCOMPLISHMENT	94K CHECKS/77K MRC MAN HOURS
AWI-1237-	980-11-001	LIGHT OFF DISCREPANCY CORRECTION ASSISTANCE	PROVIDE 500 MAN-DAYS OF LABOR AND 100,000 DOLLARS OF MATERIAL TOACCOMPLISH WORK NOT PREVIOUSLY IDENTIFIED IN THE WORK ITEM AS DIRECTED BY THE SUPERVISOR.
AWI-1239-	982-31-001	MACHINERY SPACE PRODUCTION COMPLETION AND REQUIREMENT FOR NON COMPLEX LIGHT OFF ASSESSMENT	PROVIDE 25 MAN-DAYS OF LABOR AND 50,000 DOLLARS OF MATERIAL TO CORRECT GOVERNMENT RESPONSIBLE DEFICIENCIES THAT ARE DISCOVERED DURING THE CONDUCT OF THE LOA, WHICH PREVENT SAFE LIGHT-OFF OF THE PLANT, AS DESIGNATED BY THE SUPERVISOR.
AWI-1241-	982-31-003	DOCK TRIAL, SEA TRIAL DISCREPANCY CORRECTION; ACCOMPLISH	PROVIDE 300 MANDAYS OF LABOR AND 100,000 DOLLARS OF MATERIAL FOR CORRECTION OF MINOR GOVERNMENT DISCREPANCIES ARISING FROM PRETRIAL MACHINERY OPERATIONAL TESTING, DOCK TRIAL, AND SEA TRIAL AS DIRECTED BY THE SUPERVISOR.
CNSP-0163	110-21-001	UNDERWATER HULL; INSPECT AND REPAIR	UNDERWATER HULL AND EACH APPENDAGE FROM FLAT KEEL TO 6IN ABOVE EACH UPPER LIMIT OF BOOT TOP, TO INCLUDE EACH ANCHOR BOLSTER, BILGE KEEL, SKEG, STERN FLAP, RUDDER STOOL, RUDDER, SUCTION AND DISCHARGE FROM SHELL INBOARD 24IN, EACH FAIRING, GRATING, ROPE GUARD, FAIRWATER, INTERIOR AND EXTERIOR OF EACH STERN TUBE BARREL, STRUT AND STRUT BARREL.
CNSP-0165	123-21-003	BALLAST TANK; PRESERVE	ACCOMPLISH BASE METAL WELD BUILD-UP OF A TOTAL OF 108 SQUARE INCHES OF PLATE DEFECTS IN THE TANK BOTTOM.
CNSP-0166	123-21-005	GRAY WATER TANK; INSPECT AND REPAIR	QUANTITY (6 EA), ANODE, CORROSION PREVENTIVE, ZEP-5 STYLE B, CIRCULAR SLAB, DISPOSAL
CNSP-0167	130-21-001	AIRCRAFT SECURING FITTING REPLACEMENT; ACCOMPLISH	ACCOMPLISH A VISUAL INSPECTION OF EACH AIRCRAFT SECURING FITTING

CNSP-0168	163-21-001	SEA CHEST; INSPECT AND REPAIR	ACCOMPLISH A VISUAL INSPECTION OF EACH SEA CHEST LOCATED INCLUDING EACH STRAINER PLATE, BUBBLE SHIELD, AND STRUCTURAL MEMBER FOR STRUCTURAL INTEGRITY, DETERIORATION, EACH PITTING, CRACK AND AREA OF DAMAGE OR DISTORTION
CNSP-0169	163-21-002	SEA VALVE WASTER SLEEVE INSPECT, REPAIR AND REPLACEMENT; ACCOMPLISH	REMOVE EACH PROTECTION SLEEVE, WASTER SLEEVE, WASTER RING, INCLUDING EACH ASSOCIATED FLANGE AND SPACER
CNSP-0170	235-21-001	PROPULSION MOTOR DRIVE (PMD) ENCLOSURE CLEANING	ACCOMPLISH AN IN-PLACE CLEANING OF QTY (4 EA) PMDS
CNSP-0171	235-21-002	ADVANCED INDUCTION MOTOR (AIM) WATER COOLERS; REPLACE	REMOVE EACH EXISTING EQUIPMENT, REMOVE EACH EXPANSION JOINT, QUANTITY (16 EA), INSTALL EACH NEW GENERATION WATER COOLER. INSTALL QUANTITY (16 EA) EXPANSION JOINTS
CNSP-0172	243-21-001	PORT AND STARBOARD PROPULSION SHAFT WATERBORNE BEARING CLEARANCE	ACCOMPLISH THE INSPECTION OF QTY (6 EA) WATERBORNE BEARINGS
CNSP-0173	243-21-002	PORT AND STARBOARD STERN TUBE SHAFT SEAL; OVERHAUL	ACCOMPLISH AN OVERHAUL OF THE PORT AND STBD STERN TUBE SAFT SEALS
CNSP-0174	243-21-003	POST DRY-DOCK PORT AND STARBOARD PROPULSION SHAFTING ALIGNMENT	ACCOMPLISH A WATERBORNE SHAFTING ALIGNMENT EVALUATION CHECK
CNSP-0175	243-21-004	WATERBORNE PROPULSION SHAFTING	ACCOMPLISH THE MEASURING AND RECORDING OF EACH AS-ARRIVED CLEARANCE BETWEEN THE EQUIPMENT
CNSP-0176	243-21-005	UNSHIP INSPECT AND REPAIR PROPULSION SHAFTING; ACCOMPLISH	ACCOMPLISH THE REMOVAL, INSPECTION AND REPAIR OF THE PORT AND STARBOARD MAIN PROPULSION WATERBORNE SHAFTING
CNSP-0177	256-21-001	HARMONIC FILTER GROOM, ACCOMPLISH	ACCOMPLISH A HARMONIC FILTER GROOM FOR EQUIPMENT
CNSP-0178	256-21-002	AUXILIARY SEAWATER (ASW) STRAINER REPLACEMENT; ACCOMPLISH	ACCOMPLISH THE REPLACEMENT OF QTY (8 EA) ASW STRAINER SCREEN ASSEMBLIES
CNSP-0179	256-21-003	PROPULSION SEAWATER (PSW) STRAINER SCREEN REPLACEMENT	ACCOMPLISH THE REPLACEMENT OF QTY (7 EA) PSW STRAINER SCREEN ASSEMBLIES
CNSP-0180	256-21-004	PROPULSION SEAWATER (PSW) COOLING PUMP; REPAIR	ACCOMPLISH PSW PUMP REPAIRS FOR EQUIPMENT
CNSP-0181	256-21-005	MIDEL TO SW COOLER	ACCOMPLISH CLEANING AND FLUSHING OF QTY (4 EA) AIR/SEAWATER COOLERS AND QTY (4 EA) MIDEL COOLERS
CNSP-0182	256-21-006	PROPULSION SEAWATER (PSW) PUMP REPAIR; ACCOMPLISH	ACCOMPLISH THE REQUIREMENTS OF 009-90 TO PROVIDE THE SERVICES OF AN AUTHORIZED ORIGINAL EQUIPMENT MANUFACTURER (OEM) SERVICE PROVIDER TO PROVIDE OVERSIGHT AND TECHNICAL GUIDANCE FOR THE DISASSEMBLY, INSPECTION, REPAIR, REASSEMBLY, INSTALLATION, CALIBRATION, ADJUSTMENT, AND TESTING FOR THE EQUIPMENT.
CNSP-0183	301-21-002	PERSONNEL SAFETY BARRIER (PSB) ACTUATORS; REPLACE	ACCOMPLISH THE REQUIREMENTS OF 009-90 FOR TECHNICAL DOCUMENTATION, OVERSIGHT, SPECIAL TOOLS, OPERATIONAL TESTING AND A TECHNICAL REPRESENTATIVE WHO WILL DIRECTLY ASSIST THE GOVERNMENT SUPERVISOR.
CNSP-0184	301-21-003	TELEROBOTIC FIREFIGHTING NOZZLE (TFN) DEPLOY/STOW SERVOMOTORS	ACCOMPLISH THE REPLACEMENT OF THE SERVOMOTORS FOR THE TELEROBOTIC FIRE NOZZLES
CNSP-0185	304-21-001	EXTENDABLE RAMP INCLINOMETERS; REPLACE	ACCOMPLISH THE INSTALLATION OF THE EXTENDABLE RAMP INCLINOMETERS

CNSP-0186	311-21-001	MAIN TURBINE GENERATOR; MAINTAIN	ACCOMPLISH THE REQUIREMENTS OF 009-90 FOR A TECHNICAL REPRESENTATIVE TO PROVIDE OVERSIGHT, TECHNICAL DOCUMENTATION, OPERATIONAL TESTING, SPECIAL TOOLS OR EQUIPMENT, AND DIRECT ASSISTANCE TO THE SUPERVISOR. TECHNICAL SERVICES OBTAINED BY THIS PARAGRAPH ARE NOT TO BE USED TO PERFORM PRODUCTION WORK.
CNSP-0187	312-21-002	EMERGENCY DIESEL ENGINE (EDG) TECHNICAL SUPPORT; PROVIDE	ACCOMPLISH THE REQUIREMENTS OF 009-90 TO PROVIDE THE SERVICES OF AN ORIGINAL EQUIPMENT MANUFACTURER (OEM) TO INSPECT AND ACCOMPLISH A TOP END OVERHAUL FOR THE EQUIPMENT
CNSP-0188	313-21-002	UNINTERRUPTIBLE POWER SUPPLY BATTERY REPLACEMENT: ACCOMPLISH	PROCURE EACH NEW UNINTERRUPTIBLE POWER SUPPLY PORTABLE BATTERY AND TURN OVER TO THE SUPERVISOR FOR STORAGE AND BATTERY HEALTH MAINTENANCE.
CNSP-0189	512-21-001	DRY ICE VENTILATION DUCTWORK CLEANING; ACCOMPLISH	ACCOMPLISH CLEANING OF EACH VENTILATION SYSTEM FROM EACH WEATHER OPENING TO TERMINAL END, INCLUDING IN-PLACE CLEANING OF EACH INSTALLED VENTILATION SYSTEM HEAT EXCHANGER, TO INCLUDE EACH AIR CONDITIONING CHILL WATER REFRIGERANT COIL, STEAM, AND ELECTRIC MAIN AND BOOSTER HEATER COIL
CNSP-0190	514-21-001	AUXILIARY SEAWATER (ASW) PUMP; INSPECT AND REPAIR	ACCOMPLISH THE REQUIREMENTS OF 009-90 TO PROVIDE THE SERVICES OF AN AUTHORIZED ORIGINAL EQUIPMENT MANUFACTURER (OEM) SERVICE PROVIDER TO PROVIDE OVERSIGHT AND TECHNICAL GUIDANCE FOR THE DISASSEMBLY, INSPECTION, REPAIR, REASSEMBLY, INSTALLATION, CALIBRATION, ADJUSTMENT, AND TESTING FOR THE EQUIPMENT.
CNSP-0191	520-21-001	SEA VALVE REPAIR AND REPLACEMENT; ACCOMPLISH	ACCOMPLISH A PRE-REPAIR OPERATIONAL TEST, BOTH LOCALLY AND REMOTELY, OF EACH VALVE OPERATOR AND VALVE PRIOR TO EACH REMOVAL TO DETERMINE ACTUAL OPERATING CONDITION BY FULLY OPENING AND CLOSING EACH VALVE THROUGH 4 COMPLETE CYCLES.
CNSP-0192	521-21-001	FIRE MAIN PUMP INSPECT AND REPAIR; ACCOMPLISH	REMOVE AND DISPOSE OF SYSTEM FLUIDS IN ACCORDANCE WITH FEDERAL, STATE AND LOCAL ENVIRONMENTAL REQUIREMENTS
CNSP-0193	523-21-001	DISTRIBUTIVE SEAWATER (DSW) PUMP REPAIR	ACCOMPLISH DSW PUMP REPAIRS FOR EQUIPMENT
CNSP-0194	532-21-001	AIR CONDITIONING (AC) PLANT CONDENSER MECHANICAL CLEAN AND SEAWATER STRAINER	ACCOMPLISH THE MECHANICAL CLEANING OF THE SEAWATER SIDE OF THE EQUIPMENT
CNSP-0195	532-21-002	PROPULSION HEAT EXCHANGER PLATE CLEANING: ACCOMPLISH	ACCOMPLISH THE CLEANING OF PROPULSION FRESH WATER HEAT EXCHANGERS PLATES
CNSP-0196	532-21-003	PROPULSION FRESHWATER (PFW) COOLING PUMP; REPAIR	ACCOMPLISH THE REQUIREMENTS OF 009-90 TO PROVIDE THE SERVICES OF AN AUTHORIZED ORIGINAL EQUIPMENT MANUFACTURER (OEM) SERVICE PROVIDER TO PROVIDE OVERSIGHT AND TECHNICAL GUIDANCE FOR THE DISASSEMBLY, INSPECTION, REPAIR, REASSEMBLY, INSTALLATION,
CNSP-0197	532-21-004	AIR CONDITIONING PLANT CONDENSER WATER CONTROL VALVE (CWCV); REPLACE	ACCOMPLISH THE REPLACEMENT OF THE AIR CONDITIONING WATER CONTROL VALVES (CWCV)

CNSP-0198	532-21-005	PROPULSION FRESHWATER (PFW) COOLING PUMP; REPAIR	ACCOMPLISH THE REQUIREMENTS OF 009-90 TO PROVIDE THE SERVICES OF AN AUTHORIZED ORIGINAL EQUIPMENT MANUFACTURER (OEM) SERVICE PROVIDER TO PROVIDE OVERSIGHT AND TECHNICAL GUIDANCE FOR THE DISASSEMBLY, INSPECTION, REPAIR, REASSEMBLY, INSTALLATION, CALIBRATION, ADJUSTMENT, AND TESTING FOR THE EQUIPMENT
CNSP-0199	551-21-001	LOW PRESSURE AIR COMPRESSOR (LPAC); OVERHAUL	ACCOMPLISH THE REQUIREMENTS OF 009-90 FOR TECHNICAL DOCUMENTATION, OVERSIGHT, TOOLS, OPERATIONAL TESTING AND A TECHNICAL REPRESENTATIVE WHO WILL DIRECTLY ASSIST THE GOVERNMENT SUPERVISOR
CNSP-0200	555-31-001	HIGH PRESSURE WATER MIST MECHANICALLY ATTACHED FITTINGS (MAF) AND PIPE; INSPECT	ACCOMPLISH THE REQUIREMENTS OF 009-71 FOR A HYDROSTATIC TEST OF EACH HIGH PRESSURE WATER MIST (HPWM) SYSTEM INSTALLED .
CNSP-0201	561-21-001	STEERING GEAR ACTUATION SYSTEM (SGAS) OIL INSPECTION	ACCOMPLISH THE REQUIREMENTS OF 009-90 TO PROVIDE THE SERVICES OF BUREAU VERITAS TO ACCOMPLISH TESTING OF THE GEARBOX OIL IN EACH SGAS GEARBOX
CNSP-0202	562-21-001	RUDDER BEARING SEAL AND RUDDERSTOCK SEAL; REPAIR	ACCOMPLISH PORT AND STBD RUDDER STOCK REPAIRS
CNSP-0203	581-21-001	ANCHOR AND ANCHOR CHAIN INSPECTION AND PRESERVATION; ACCOMPLISH	REMOVE THE EQUIPMENT, SEPARATE EACH ANCHOR, OUTBOARD SWIVEL SHOT, CHAIN STOPPER ASSEMBLY AND EACH SUCCEEDING 15 FATHOM SHOT, BY DISASSEMBLING THE DETACHABLE LINKS AND BITTER END SHACKLES
CNSP-0204	588-21-001	PVLS BERM PRESERVATION; ACCOMPLISH	ACCOMPLISH THE PREPARATION OF A SKETCH SHOWING EXISTING MARKINGS, LABEL PLATES AND PLACARDS OF EACH BERM COVER
CNSP-0205	593-21-001	VACUUM, COLLECTION, HOLDING AND TRANSFER (VCHT) SYSTEM; CHEMICAL CLEANING	ACCOMPLISH VCHT TANK AND PIPE CLEANING INSPECTION AND REPAIRS
CNSP-0206	624-21-001	CHILL AND FREEZE STOREROOM DOOR INSPECT AND REPAIR; ACCOMPLISH	ACCOMPLISH THE REQUIREMENTS OF 009-90 TO PROVIDE THE SERVICES OF A QUALIFIED OEM REPRESENTATIVE TO INSPECT AND REALIGN CHILL ROOM AND FREEZE ROOM DOORS
CNSP-0207	624-21-002	BALANCED JOINER DOOR	PROVIDE 25 MANDAYS OF LABOR AND 50,000 DOLLARS OF MATERIAL. INSPECT, TEST, REMOVE, CRATE, STORE, AND RE-INSTALL ALL BALANCED JOINER DOORS AND FRAMES.
CNSP-0208	631-21-001	UNDERWATER HULL PRESERVATION PAINT COMPANY ORIGINAL EQUIPMENT MANUFACTURERS'	ACCOMPLISH THE REQUIREMENTS OF DM 220-020 SURF, UNDERWATER HULL: PRESERVE UTILIZING OEM REPRESENTATIVE
CNSP-0209	631-21-002	FREEBOARD; PRESERVE	EXTERIOR HULL FROM UPPER LIMIT OF BOOT TOPPING TO TOP OF 01 LEVEL WATERWAY BAR, FROM BOW TO STERN, TO INCLUDE 12 INCHES INTO EACH PENETRATION AND PIPE AND WORK BOUNDARY, EXCLUDING RADAR ABSORBENT MATERIAL (RAM) TILE AREA/SURFACE, TO INCLUDE EACH DOOR
CNSP-0210	633-21-001	IMPRESSED CURRENT CATHODIC PROTECTION (ICCP) REFERENCE CELL	ACCOMPLISH THE REQUIREMENTS OF 009-90 TO PROVIDE THE SERVICES OF AN AUTHORIZED ORIGINAL EQUIPMENT MANUFACTURER (OEM) SERVICE PROVIDER TO ACCOMPLISH A PRE-DRYDOCK INSPECTION OF THE IMPRESSED CURRENT CATHODIC PROTECTION SYSTEM

CNSP-0211	634-21-003	FLIGHT DECK NONSKID REPLACEMENT	ACCOMPLISH FLIGHT DECK NONSKID REPLACEMENT UTILIZING SPRAYABLE DECK COATING, AND ACCOMPANYING TESTS OF DISTRIBUTED SEA WATER AND COUNTER MEASURE WASHDOWN SYSTEM, AND DECK DRAINS
CNSP-0212	639-21-001	PASSIVE COUNTERMEASURE SYSTEM (PCMS) REPAIR AND REPLACEMENT; ACCOMPLISH	ACCOMPLISH A JOINT VISUAL INSPECTION WITH THE SUPERVISOR OF EACH PCMS RAM TILE SHOWN TO DETERMINE LOCATIONS FOR DAMAGED TILE, MISSING TILE, CORROSION UNDER TILE, MISSING OR DETERIORATING CAULK, AND ENVIRONMENTAL LAYER PEELING. ACCOMPLISH REPAIR OF DAMAGED PCMS TILES USING MATERIALS PROVIDED
CNSP-0213	864-21-001	AN/SPY-3 ANTENNA PROTECTIVE COVERS	FABRICATE AND INSTALL PROTECTIVE COVERINGS FOR AN/SPY-3 ANTENNAS
CNSP-0214	865-21-001	STAGING AND SCAFFOLDING	PROVIDE 50 MAN-DAYS AND 50,000 DOLLARS OF STAGING AND SCAFFOLDING SERVICES
CNSP-0215	867-21-001	COMBAT SYSTEM TESTING SUPPORT; PROVIDE	PROVIDE 2,500 MANHOURS OF LABOR AND 25,000 DOLLARS OF MATERIAL, AS DESIGNATED BY THE SUPERVISOR, FOR SUPPORT OF COMBAT SYSTEMS WORK.
CNSP-0164-	123-21-001R1	TANK AND VOID CLEANING AND PUMPING; ACCOMPLISH	OPEN, VENTILATE, EMPTY, CLEAN, RENDER DRY, AND MAINTAIN EACH TANK
CNSP-0216-	123-21-006	TANK GAS FREE, REPAIR AND PRESERVE; ACCOMPLISH	OPEN, VENTILATE, EMPTY, CLEAN, RENDER DRY, AND MAINTAIN EACH TANK
CNSP-0217-	711-11-001	GUN WEAPON SYSTEM, 30MM, MK 46 MOD 1/2 RACE RING; INSTALL	PREPARE, REMOVE, INSPECT, INSTALL QTY 2 MK 46 GWS