

STATEMENT OF WORK (DRAFT)

ICE MACHINE CLEANING AND SANITIZATION

1. General

- 1.1. The contractor shall provide all tools, chemicals, expertise, equipment, cleaning supplies, labor and transportation required to perform quarterly cleaning and sanitizing of 17 ice machines. The covered ice machines consist primarily of units manufactured by Follett and Hoshizaki. Please refer to Table A for a complete list of manufacturers, models and locations.
- 1.2. In most cases, cleaning and sanitizing will consist of performance of the manufacturers' six month and monthly cleaning procedures. The intent of this contract is to assure each ice machine regardless of location or use status is thoroughly cleaned and sanitized on a quarterly basis. This includes ice machines that are classified as "spare" machines or machines that have been out of service.
 - 1.2.1. DO NOT USE Tap or ANY UNFILTERED WATER during cleaning/sanitization process.
 - 1.2.2. Cleaning/descaling and sanitizing procedure of supply lines between the filter and the ice machine to be included.
- 1.3. Contractor shall replace chutes, trays and similar plastic items that come into contact with ice and water when required or requested by the Contracting Officers Representative (COR). The Government will provide these items at Government expense upon request.
- 1.4. The contractor shall repair or replace with new parts for any ice machine damaged or broken during cleaning the ice machines while in the possession of the contractor. Examples include broken grills, dials, buttons, connections, or other parts that are part of the ice machine.
- 1.5. Cleaning will be performed "in place", work performed in place shall not interfere with the operation of the area in which the ice machine is located.
- 1.6. Cleaning / Sanitization will occur quarterly (every 90 calendar days) with no less than 80 calendar days and no more than 100 calendar days between cleanings on each machine.
- 1.7. Contractor shall use and provide all original equipment manufacturer's (OEM) or equivalent cleaning and sanitizing chemicals and supplies. Chemicals must be NSF approved for such use.
- 1.8. Contractor shall perform work between the hours of 7:00AM and 4:30PM, Monday through Friday; excluding machines in the Starbucks, Canteen, and Infusion Clinic locations. The Starbucks and Canteen locations must be serviced after 2pm. The Infusion Clinic location must be serviced after 3:30pm. Ice machine cleaning shall not be scheduled to occur on Federal Holidays or weekends without prior written authorization from the Government.
- 1.9. Contractor shall report any negative findings while cleaning the ice machines to the Government immediately upon discovery.
- 1.10. Upon completion of cleaning / sanitizing work, the contractor will notify the COR or approved facility representative that the service has been completed. The COR or a COR approved facility representative will inspect the ice machine. While inspection is being performed, the contractor may be asked to remove covers or similar items to aid in inspection.
- 1.11. The cost of damage of any water leak or other facility damage caused by improper removal or reinstallation before or after cleaning, will be the responsibility of the contractor. The contractor in most cases will be asked to return to the work site and make the corrections themselves.

- 1.12. Ice machines shall be returned to service by close of business (4:30 PM) on the same day they are removed from service for cleaning. If additional cleaning time is required to complete the cleaning, the contractor shall obtain authorization from the COR.
- 1.13. Contractor will provide a legible service report at the completion of each ice machine cleaning. The service report may be signed only by a tradesman from the air conditioning / refrigeration shop, an Engineering Supervisor or the Utility Systems Operator on duty. The service report will indicate the condition of the ice machine upon arrival, any unusual findings, concerns / recommendations, the date and time work started and date and time the work was completed.
- 1.14. A sticker will be placed on each ice machine after cleaning indicating the service (cleaning/sanitizing), the date the service was performed, and the contractor's information (name, and telephone number).
- 1.15. Occasionally ice machines may be removed from service, swapped with a different ice machine or relocated due to facility requirements by the government. The relocation of the devices covered under this contract does not preclude Contractors responsibilities regarding cleaning of the device.

Attachments:

SOP 138M-25-020 Ice Machine Preventive Maintenance Procedures

TABLE A

<u>Floor</u>	<u>Location</u>	<u>Room Number</u>	<u>Manufacturer</u>	<u>Model</u>	<u>Serial</u>	<u>VA PM Number</u>
Basement	Emergency Department	SOG19-OP	Folett	25CI425A-S	K63404	4110-41297
Basement	Basement Kitchen	Kit-A-1	Hoshizaki	DCM752BAH-OS	P00345A	4110-57014
1st Floor	Patriot Brew (Starbucks)	1A01B-1	TRUE	TCM-422-HA1-A-T-3	10876402	4110-58478
1st Floor	Patriot Café	1B20D-1	Hoshizaki	KM-660MAJ	Q13974E	4110-59565
2nd Floor	Infusion Clinic	2C06K-1	Folett	50C1425A-S	L42393	4110-44002
3rd Floor	PACU	3C17J.2-1	Folett	25CI425A-S	K63304	4110-41295
5th Floor East	Clean Supply	5A27-1	Folett	25CI425A-S	K62767	4110-41298
5th Floor East	Locker Room	5A14-1	Hoshizaki	DCM270BAH-OS	D08092E	4110-33620
5th Floor West	Nurse Station	W5U8-1	Folett	25CI425A-S	R40338	4110-56427
5th Floor West	Nurse Station	Nurse Station 2 - 1	Folett	DCM-300BAK-OS	Q00048K	4110-41296
6th Floor	Nurse Station	6A30-1	Folett	25CI424A-S	K62383	4110-41251
Bldg 34	Physical Therapy	108A-34	Scotsman	UN1520A-1A	23061320015400	4110-54247
CLC	Nourishment Kitchen	1C01-31	Folett	25CI45-S	K62392	4110-41250
CLC	Dining Room	1A10-31	Folett	25CI414A-S	S62375-061	4110-60489
CLC - DogWood	Dining Room	1B20D-C-28	Folett	50C1425A-S	K45893	4110-40435
CLC - Elm	Dining Room	1E3-28	Scotsman	HID312A-1	241013200107	4110-59583
Building 3	Grounds Shop	20-3	Hoshizaki	KML-325MAJ	N00459E	4110-53423