

Statement of Work (SOW)

1.0 General Information

- Title of Project: Heavy Repair and Tire Replacement for JLG 600S Boom Lift
- Equipment Identification:
 - Make/Model: JLG 600S Telescopic Boom Lift
 - Equipment ID: COE145825
 - Serial Number: 0300182454
- Background: The JLG 600S boom lift is non-operational. A diagnostic investigation revealed significant failures in its hydraulic and control systems, including multiple fluid leaks and drive/swing issues. Additionally, a separate inspection found that three of the machine's tires are worn beyond safe operational limits. This SOW outlines the consolidated tasks required to restore the boom lift to a safe and fully operational condition.
- Type of Contract: Firm-Fixed-Price.

2.0 Objective

The primary objective is for the contractor to provide all necessary personnel, supervision, parts, tools, materials, and equipment required to execute the complete repair of the JLG 600S boom lift, including the replacement of three tires. The goal is to return the equipment to a safe, reliable, and fully functional condition in accordance with the manufacturer's specifications.

3.0 Scope of Work

The contractor shall perform the following specific repair tasks on the JLG 600S Boom Lift (Serial #0300182454):

- 3.1 Hydraulic System Repair:
 - Replace the remanufactured hydraulic swivel.
 - Replace the main directional control valve for hydraulic functions.
 - Replace the swing gear box seal to correct the identified hydraulic fluid leak.
 - Replace the leaking hydraulic boom hoses.
- 3.2 Drive and Control System Repair:
 - Replace the swing drive hub assembly.
 - Replace the water-contaminated and corroded lift/swing controller.

- Replace the broken ignition switch.
- 3.3 Generator System Repair:
 - Replace the faulty 7500W onboard generator.
- 3.4 Tire Replacement:
 - Replace three (3) worn tires with new, OEM-specification tires suitable for the machine.
- 3.5 Final Assembly and Testing:
 - Install all associated hardware as required for the repairs.
 - Top off all necessary fluids (e.g., hydraulic fluid) to manufacturer-specified levels.
 - Conduct comprehensive functional and load testing of all repaired systems, including lift, swing, drive, and generator functions, to ensure they operate according to OEM specifications.
 - Clean the equipment and worksite upon completion of repairs.

4.0 Place of Performance

All work shall be performed at the contractor's designated repair facility.

5.0 Period of Performance

The work outlined in this SOW shall be completed within a reasonable timeframe, incorporating the labor for both the mechanical repairs and the tire replacement.

6.0 Acceptance Criteria

The repair work will be considered complete and acceptable upon:

- Government verification that all repairs and tasks outlined in Section 3.0 have been completed.
- Confirmation that three new tires have been installed.
- A successful joint inspection and functional test by Government personnel and the contractor's technician.
- Demonstration of fault-free operation of all machine functions (drive, lift, swing, extend, and generator) under a simulated load for a minimum of 30 minutes.
- Confirmation that all identified hydraulic leaks have been rectified.

