

STATEMENT OF WORK



STATEMENT OF WORK

Replacement of four HySecurity gate operators

at

U.S. Embassy Addis Ababa Ethiopia

April 2026

STATEMENT OF WORK

BACKGROUND

Scope of Work (SOW):

1. Project Summary

The Contractor shall provide all labor, tools, equipment, supervision, and necessary materials to remove four (4) old industrial sliding gate operators and replace them with four (4) new HySecurity sliding gate operators provided by the U.S. Embassy in Addis Ababa. The contractor is responsible for ensuring the system is fully functional, tested, and commissioned according to manufacturer standards and U.S. Embassy security requirements.

2. Scope of Services

- **Site Survey & Preparation:** The Contractor shall perform a site survey to familiarize themselves with the existing gate infrastructure, including tracks, wheels, and control systems.
- **Removal of Existing Equipment:** Safe removal and disposal of the four existing old HySecurity sliding gate operators. Existing/installed Model (SlideDriver 50VF2-EFO).
- **Installation of New Operators:** Installation of four new HySecurity operators, ensuring proper alignment with existing sliding gates, and integration with existing or new PLC (Programmable Logic Controller) systems. New Models consisting of three (SlideDriver 50VF2/3) and one (Slide Driver II SD50F).
- **Specification and drive type:** Continuous duty, Voltage: 220V 50Hz Single Phase, 2 hp Horsepower, Hydraulic Drive with VFD motor control.
- **Wiring & Components:** Inspection and installation of all associated control wiring, safety devices (photo eyes, edge sensors), and connection to the electrical power source.
- **Testing & Commissioning:** Upon completion of the work the contractor must perform functional tests to ensure the gates operate within designated safety standards (e.g., UL 325 and ASTM 2200). Work also must be verified by US embassy COR.

STATEMENT OF WORK

- **Site Cleanup:** The Contractor shall clean the work area daily, removing all construction debris, and ensure the site is returned to its original state.

3. Training

- The contractor is required to provide comprehensive training to local Embassy staff on the operation, daily troubleshooting, and preventative maintenance of the new HySecurity system.

4. Contractor Responsibilities

- **Tools & Equipment:** The contractor must specify and inform embassy well in advance on arrangement and provisions of all necessary tools, including but not limited to cranes, forklifts, rigging equipment, and safety gear.
- **Personnel:** Provide certified and experienced technicians familiar with high-security industrial gate systems.
- **Safety Compliance:** Strict adherence to safety guidelines, including, but not limited to, using certified operators for heavy equipment.
- **Security Clearance:** All personnel must be able to obtain security access to the U.S. Embassy compound.

5. Performance Period and schedule

The installation, testing, and training must be completed within **60 calendar days** from the Notice to Proceed (NTP). The work schedule shall be Monday through Saturday 8:00am-05:00pm.

6. Deliverables

- Installation and commissioning of 4x HySecurity operators.
- O & M training session completion report for local staff.
- As-built drawings/wiring diagrams.
- Operation and Maintenance manuals.
- Trip completion report, spare part and service contract recommendation.