

STATEMENT OF WORK (SOW) FOR USCG TRAINING CENTER CAPE MAY ANNUAL POWER WASHING

1.0 GENERAL

1.1 BACKGROUND

The United States Coast Guard Training Center Cape May (TCCM), located at 1 Munro Avenue, Cape May, NJ 08204, requires recurring pressure washing services for multiple facility structures. These buildings accumulate dirt, mold, mildew, and environmental debris, which pose safety hazards and negatively impact the installation's appearance. Maintaining clean and sanitary facilities is critical for the safety and professionalism of over 350 staff and approximately 5,000 Coast Guard recruits processed annually. This requirement encompasses pressure washing of building exteriors, including walls, windows, doors, facades, and associated exterior surfaces.

1.2 SCOPE

The Contractor shall provide all personnel, equipment, supplies, materials, transportation, tools, supervision, and other items necessary to perform comprehensive pressure washing and debris removal services for designated buildings at USCG Training Center Cape May. Services shall include cleaning building exteriors, removing debris (leaves, trash), and ensuring compliance with all applicable environmental, safety, and operational standards.

1.3 OBJECTIVE

The objective is to maintain designated building exteriors in a clean, safe, and professional condition by eliminating dirt, grime, mold, mildew, and other contaminants. This supports the base's operational standards, safety, and longevity of facilities..

1.4 APPLICABLE DOCUMENTS

The Contractor shall comply with the following documents and standards:

- Reference 1- TRACEN Cape May Stormwater Permit
- Reference 2- TRACEN Cape May Stormwater Pollution Prevention Plan
- Reference 3- USCG Stormwater Management Job Guide 2023
- Reference 4- TRACEN Cape May Map (for building locations)

2.0 SPECIFIC REQUIREMENTS/TASKS

2.1 TASK ONE. PRESSURE WASHING OF BUILDINGS.

All pressure washing and debris removal activities must comply with Section 4.4 Environmental Protection Requirements.

2.1.1 REQUIREMENTS

Pressure wash exteriors of designated buildings: walls, windows, doors, facades, and associated surfaces.

Utilize equipment and techniques appropriate for the integrity of building materials. Remove stains, dirt, grime, mold, mildew, spider webs, gum, and other contaminants.

PR #:
STATEMENT OF WORK

Clean and dispose of all refuse and trash daily in accordance with federal, state, and local regulations.

Contain and manage all wash water and debris to prevent discharge to storm drains or surface waters, per the facility's NJPDES permit and SWPPP.

Maintain job site, staging, and storage areas free from debris and safety hazards.

2.1.2 BUILDINGS TO BE PRESSURE WASHED

Building	Height	Exterior Sq Ft.
Munro Hall (Building 261)	40 ft	45,000
Healy Hall Barracks (Building 257)	40 ft	45,000
James Hall Barracks (Building 288)	40 ft	45,000
Sexton Hall Barracks (Building 303)	40 ft	25,000
Classroom-251 (Building 251)	20 ft	5,000
Classroom-252 (Building 252)	20 ft	5,000
Galley (Building 278)	20 ft	35,000
UPH (Buildings 254 and 255)	40 ft	40,000
Clinic (Building 270)	40 ft	40,000
Security (Building 297)	15 ft	6,000
Gymnasium – Fitness Center (Building 269)	35 ft	45,000
CGX (Building 22)	25 ft	15,000
MCPOCG Classrooms (Building 911)	15 ft	8,000
Mission Support Building (Building 262)	30 ft	20,000

2.1.3 QUALITY ASSURANCE

Contractor shall avoid peeling paint or damaging building surfaces during pressure washing.

Any damages caused by pressure washing shall be repaired at the Contractor's expense.

Contractor is responsible for restoring all site conditions to their pre-work state, including soils, grass, pavements, and utilities.

2.1.4 CONTRACTORS RESPONSIBILITIES

Provide all labor, equipment, supplies, parts, tools, chemicals, water, transportation, and supervision.

Comply with all local permitting requirements and stormwater discharge containment regulations.

Use bio-based cleaning agents that are environmentally safe and compatible with surfaces being cleaned.

Furnish and maintain all warning devices (barricades, cones, signs, lights, etc.) to protect the public, staff, and workers during operations.

PR #:
STATEMENT OF WORK

Pressure wash and clean all stucco, wood, concrete surfaces, roof drip edges, gutters, stoops, poles, walkways, and sidewalks throughout the property. Areas must be cleaned in their entirety; spot cleaning is not permitted.

Exercise special care around windows, doorways, outdoor receptacles, and equipment to prevent water intrusion. If water intrusion occurs, promptly remove accumulation and document the affected area for submission to the Supervisor or Foreman.

Clean doorways using low water pressure and brushes to prevent water intrusion.

Use pressure washer water brooms, ridge washers, hydro scrubbers, and scrub brushes to ensure thorough and even cleaning; rinse all surfaces to remove fine grit and grime.

Contractor is responsible for correcting any damage or swirl marks caused by improper pressure or methods.

Clean and dry glass surfaces to remove streaking resulting from cleaning operations.

Cover all vegetation; request removal of vehicles and closure of windows in areas scheduled for cleaning.

Clean out existing roof gutter systems and remove all debris from the property. Inspect gutters/expansion joints for damage and notify the maintenance supervisor of repairs beyond normal cleaning scope.

3.0 CONTRACTOR PERSONNEL

The contractor is responsible for providing all labor, materials, and equipment necessary to fulfill the tasks outlined in this SOW.

Additionally, the contractor must ensure compliance with safety regulations and environmental standards during all operations.

3.1 CONTINUITY OF SUPPORT

The contractor must ensure that the contractually required level of support for this requirement is maintained at all times. The contractor must ensure that all contract support personnel are present for all hours of the workday. If for any reason the contractor staffing levels are not maintained due to vacation, leave, appointments, etc., and replacement personnel will not be provided, the contractor must provide e-mail notification to the Contracting Officer's Representative (COR) prior to employee absence. Otherwise, the contractor must provide a fully qualified replacement.

3.2 EMPLOYEE IDENTIFICATION

Upon entry to TCCM, contractor employees must present a valid REALID or passport for valid entry into the facility. Contractor employees visiting Government facilities must wear an identification badge that, at a minimum, displays the contractor name, the employee's photo, name, clearance-level and badge expiration date. Visiting contractor employees must comply with

PR #:
STATEMENT OF WORK

all Government escort rules and requirements. All contractor employees must identify themselves as contractors when their status is not readily apparent and display all identification and visitor badges in plain view above the waist at all times.

Contractor employees working on-site at Government facilities must wear a Government issued identification badge. All contractor employees must identify themselves as contractors when their status is not readily apparent (in meetings, when answering Government telephones, in e-mail messages, etc.) and display the Government issued badge in plain view above the waist at all times.

3.3 EMPLOYEE CONDUCT

Contractor's employees must comply with all applicable Government regulations, policies and procedures (e.g., fire, safety, sanitation, environmental protection, security, "off limits" areas, wearing of parts of DHS uniforms, and possession of weapons) when visiting or working at Government facilities. The contractor must ensure contractor employees present a professional appearance at all times and that their conduct must not reflect discredit on the United States or the Department of Homeland Security. The Project Manager must ensure contractor employees understand and abide by Department of Homeland Security established rules, regulations and policies concerning safety and security.

Under no circumstances should the contractor's employees be on the "Confidence Course" or take pictures or videos of the recruits in training. Furthermore, when in restricted areas, the contractor's employees must not disturb recruit training.

3.4 REMOVING EMPLOYEES FOR MISCONDUCT OR SECURITY REASONS

The Government may, at its sole discretion (via the Contracting Officer), direct the contractor to remove any contractor employee from DHS facilities for misconduct or security reasons.

Removal does not relieve the contractor of the responsibility to continue providing the services required under the contract. The Contracting Officer will provide the contractor with a written explanation to support any request to remove an employee.

4.0 PERIOD OF PERFORMANCE

The period of performance for this contract: 15 July 2026 through 15 August 2026

4.1 PLACE OF PERFORMANCE

The primary place of performance will be:

USCG TRACEN Cape May
1 Munro Ave
Cape May, NJ, 08204

4.1.1 SECURITY

Contractor access to classified information is not currently required under this SOW.

Contractors must pass a background check and present a Real ID or valid driver's license with a secondary form of ID, along with valid vehicle registration and insurance. If a contractor cannot meet these requirements, they must be escorted by a CAC holder throughout their visit, which may cause delays or denial of access if no escort is available.

PR #:
STATEMENT OF WORK

For questions regarding visitor access, contact the designated Government POC.

4.2 HOURS OF OPERATION

Contractor employees must generally perform all work between the hours of 0800 and 1600 EST, Monday through Thursday (except Federal holidays).

It is solely the contractor's responsibility to ensure its employees do not work in hours in excess of what is allowed by the Fair Labor Standards Act for its employees.

The USCG will not pay for overtime under this anticipated contract unless it is negotiated as part of surge work and a modification is issued by the Contracting Officer.

The contractor shall assume the risk of any overtime worked that has not been authorized/funded by the Contracting Officer.

4.3 SAFETY REQUIREMENTS

All contractors engaged in operations at USCG TRACEN Cape May are mandated to adhere strictly to all federal safety regulations delineated by the Occupational Health and Safety Administration (OSHA).

4.4 ENVIRONMENTAL PROTECTION REQUIREMENTS

The Contractor shall provide all labor, materials, equipment, and expertise necessary to ensure full compliance with federal, state, and local environmental protection requirements related to stormwater management, wastewater and runoff control, spill and discharge notification, and debris and waste disposal. The Contractor's responsibilities shall include, but are not limited to, the following:

4.4.1 STORMWATER PERMIT AND STORMWATER POLLUTION PREVENTION PLAN (SWPPP) COMPLIANCE

The contractor shall ensure that all activities comply with the requirements of the facility's stormwater permit(s) and the associated Stormwater Pollution Prevention Plan (SWPPP). This includes maintaining up-to-date documentation, conducting regular inspections of stormwater control measures, and implementing corrective actions as needed to prevent unauthorized discharges. The Contractor shall prepare and submit all required reports, records, and documentation to demonstrate ongoing compliance with applicable stormwater regulations.

4.4.2 WASTEWATER AND RUNOFF MANAGEMENT

The Contractor shall manage all wastewater and site runoff in accordance with regulatory requirements. This includes the proper collection, treatment, and disposal of wastewater generated by facility operations. The Contractor shall implement measures to prevent the introduction of pollutants into stormwater or sanitary sewer systems, and shall ensure that all runoff is controlled to minimize environmental impact. The Contractor shall monitor discharge points as required, and maintain records of all wastewater management activities.

4.4.3 SPILL AND DISCHARGE NOTIFICATION

PR #:
STATEMENT OF WORK

The Contractor shall promptly identify, contain, and report any spills, leaks, or unauthorized discharges of hazardous or regulated materials in accordance with federal, state, and local notification requirements. The Contractor shall maintain and follow an established spill response protocol, including immediate notification to designated facility personnel and regulatory authorities, as required. The Contractor shall document all incidents, response actions taken, and outcomes, and submit incident reports as specified by applicable regulations.

4.4.5 DEBRIS AND WASTE DISPOSAL

The Contractor shall collect, handle, and dispose of all debris, solid waste, and hazardous materials generated by facility operations in accordance with all applicable laws and regulations. This includes the segregation of waste streams, use of approved containers, and coordination with licensed disposal facilities. The Contractor shall maintain accurate records of waste generation, storage, transport, and disposal, and shall provide documentation to demonstrate compliance with regulatory and permit requirements.

All work performed under this task shall be conducted in a manner that protects human health and the environment, and supports the facility's overall environmental compliance objectives.

4.5 GENERAL REPORT REQUIREMENTS

The contractor must provide all written reports in electronic format with read/write capability using applications that are compatible with DHS workstations (Microsoft Office Applications).

4.6 TRAVEL

Claims for travel or lodging except where otherwise noted herein will not be authorized or accepted. Unless otherwise noted, all travel and lodging associated with this contract is to be considered as part of the inspection, testing, and certification for all equipment inspected, and shall be included in the contractor's bid or proposal.

5.0 GOVERNMENT FURNISHED RESOURCES

The Government will provide the following resources to the Contractor for work required under this contract:

Access to water via building hose hookups or fire hydrants.

6.0 CONTRACTOR FURNISHED PROPERTY

The Contractor must furnish all facilities, PPE, materials, equipment and services necessary to fulfill the requirements of this contract, except for the Government Furnished Resources specified in SOW Section 5.0.

7.0 GOVERNMENT ACCEPTANCE PERIOD

The Government Technical Representative will review deliverables prior to acceptance and provide the contractor with an e-mail that provides documented reasons for non-acceptance. If the deliverable is acceptable, the Government Technical Representative will send an e-mail to the Contractor notifying it that the deliverable has been accepted.

7.1 The Government Technical Representative will have the right to reject or require correction

PR #:
STATEMENT OF WORK

of any deficiencies found in the deliverables that are contrary to the information contained in the Contractor's accepted proposal. In the event of a rejected deliverable, the Contractor will be notified in writing by the Government Technical Representative of the specific reasons for rejection. The Contractor may have an opportunity to correct the rejected deliverable and return it per delivery instructions.

7.2 The Government Technical Representative will have 10 business days to review deliverables and make comments. The Contractor must have 10 business days to make corrections and redeliver.

7.3 All other review times and schedules for deliverables must be agreed upon by the parties based on the final approved Project Plan. The Contractor must be responsible for timely delivery to Government personnel in the agreed upon review chain, at each stage of the review. The Contractor must work with personnel reviewing the deliverables to assure that the established schedule is maintained.