

STATEMENT OF NEED

FOR

(9CS Atrium Repair)

A. BACKGROUND:

The 9th Communications Squadron requires safe, functional, and mission-supportive outdoor spaces for personnel movement and daily operations. The existing atrium shade canopies have exceeded their service life and no longer meet structural, safety, or appearance standards. Exposure to weather and age-related degradation has resulted in material wear, reduced tension integrity, and diminished protective capability. Replacement is necessary to maintain a safe environment and ensure compliance with applicable Air Force, state, and federal standards.

B. SCOPE:

The contractor shall provide all labor, materials, equipment, supervision, and professional services required to remove the existing shade canopies and install new replacement canopies at the 9th Communications Squadron atrium. Work includes fabrication, delivery, installation, and any required hardware replacement. All work shall comply with applicable codes, Air Force standards, and Beale AFB requirements. The contractor shall coordinate access, work hours, and installation activities with the Government POC.

C. REQUIREMENT:

The 9th Communications Squadron requires the removal and replacement of five (5) exterior shade canopies, approximately 30 ft x 30 ft, fabricated using commercial-grade fire-resistant shade cloth in multiple colors. The contractor shall measure all canopy locations, fabricate the new canopies, and install them using existing cables and hardware, replacing components only as necessary to ensure proper fitness and structural integrity. All work must comply with applicable safety, structural, and installation standards, including UFC, AFOSH, NFPA, OSHA, CBC, and Beale AFB supplemental requirements.

Salient Characteristics / Purchase Description

- Five (5) replacement shade sails, approx. 30' x 30'
- Commercial-grade FR shade cloth (red, blue, yellow)
- Installation using existing cable/hardware; replace as needed
- Fabrication lead time approx. 8–10 weeks
- All canopies installed during the same installation period
- Minimum 1-year warranty on workmanship and materials
- Compliance with all applicable codes and Air Force standards

x. Delivery:

Contractor shall coordinate a delivery time with the Government Point of Contact (POC) identified in the inspect and accept information section of the contract at least two (2) weeks prior to anticipated delivery. (Contractor shall be responsible for the installation, assembly, and clean-up on the same day of delivery (this can be removed if installation is not applicable). Products shall be delivered within the hours listed below.

LOCATION & HOURS OF OPERATION.

The contractor shall coordinate delivery and installation with the Government POC at least **two (3) weeks prior** to anticipated delivery. Installation, assembly, and site cleanup shall occur the same day unless otherwise coordinated. Work shall be performed Monday–Friday between **0730–1630**.

Location: 9th Communications Squadron Beale AFB, CA 95903
6252 B St. Bldg. 2445, Beale AFB, CA 90903

Federal holidays are observed per installation policy.

New Year's Day	1 January
Martin Luther King's Birthday	Third Monday in January
President's Day	Third Monday in February
Memorial Day	Last Monday in May
Juneteenth	19 June
Independence Day	4 July
Labor Day	First Monday in September
Columbus Day	Second Monday in October
Veterans Day	11 November
Thanksgiving Day	Fourth Thursday in November
Christmas Day	25 December

ACCESS.

Contractor Manager or alternate shall complete an entry authorization list (EAL) for access to Beale Air Force Base. The request shall be submitted within two (2) weeks of delivery to Pass and Registration via the Government Point of Contact (POC) identified in the inspect and accept information section of the contract. All contractor vehicles must enter the base via the Wheatland Gate and shall be subject to inspection. All contractor personnel must obtain base passes or be listed on the Entry Access List (EAL) throughout duration of work performance. Any persons in the EAL are required to bring two (2) forms of identification or REAL ID to access the base.

TRAFFIC LAWS.

The contractor and their employees shall comply with all installation traffic regulations.

CELLULAR PHONE OPERATION POLICY.

The contractor shall comply with local base policies regarding cellular phone operation.