



1. PERFORM AS-FOUND TESTING OF EQUIPMENT OF AIRFLOW, FAN AND SYSTEM COMPONENTS. REBALANCE TO SCHEDULED AIRFLOW.
2. INSTALL NEW 800x800 DUCTWORK, REFER TO DETAIL K3/215-512.
3. DISCONNECT EXISTING 75 EXHAUST DOWN TO ACID STORAGE CABINET, RECONNECT TO NEW 400 EXHAUST AIR DUCT. BALANCE TO 30 L/S.
4. PERFORM AS-FOUND AIRFLOW AND FUNCTION TEST ON EXISTING TERMINAL UNIT. REPORT FINDINGS TO CORP AND ENGINEER. UNDER BASE BID, EXISTING TERMINAL UNIT CONTROLLER TO BE REPLACED WITH COMPATIBLE CONTROLLER FOR EXISTING NAILOR TERMINAL UNIT. EXISTING TERMINAL UNIT TO REMAIN AND CLEANED IN PLACE, INCLUDING AIRFLOW MEASUREMENT ELEMENTS. TEMPORARILY DISCONNECT DUCTWORK FROM TERMINAL UNIT AS REQUIRED TO COMPLETE CLEANING, AND RECONNECT AND SEAL DUCTWORK AFTER COMPLETION OF WORK. CONTROL TUBING SHALL BE REPLACED AND EXTENDED AS REQUIRED TO BE CONNECTED TO EXISTING BUILDING AUTOMATION SYSTEM. ALL NEW CONTROLS SHALL BE VERIFIED FOR ACCURACY AND RESPONSE. UNDER ALTERNATE 1, REPLACE EXISTING TERMINAL WITH A NEW SUPPLY AIR TERMINAL UNIT TO MATCH EXISTING. RECONNECT TO EXISTING DUCTWORK AND HVAC PIPING. CONTROL TUBING SHALL BE REPLACED AND NEW CONTROLS SHALL BE EXTENDED TO EXISTING BUILDING AUTOMATION SYSTEM. TYPICAL OF 25.
5. EXISTING TO REMAIN 300x150 BACKDRAFT DAMPER IN WALL ABOVE CEILING (100 L/S).
6. INSTALL NEW 800x800 RETURN AIR TRANSFER GRILLE IN WALL ABOVE CEILING. REFER TO DETAIL.
7. EXISTING TO REMAIN 350x200 TRANSFER AIR DUCT.
8. EXISTING TO REMAIN 300x150 TRANSFER AIR DUCT.
9. EXISTING TO REMAIN THERMOSTAT. RECONNECT TO NEW TERMINAL UNIT CONTROLLER.
10. EXISTING FAN COIL UNIT TO REMAIN. NOT IN SCOPE OF WORK.
11. 950x400 EXHAUST AIR DUCT UP TO EF-103.
12. 1550x400 EXHAUST AIR DUCT UP TO EF-104.
13. NEW 300 WELDED STAINLESS STEEL EXHAUST AIR DUCT. BALANCE TO 560 L/S.
14. NEW 400 WELDED STAINLESS STEEL EXHAUST AIR DUCT. REFER TO 215-490 FOR CONTINUATION.
15. 75 EXHAUST DOWN TO ACID STORAGE CABINET. BALANCE TO 30 L/S.

SHEET ID
215-467