

STATEMENT OF OBJECTIVES (SOO)

For

Replacement of Upper Roof on B3356

NAS JRB Fort Worth, TX

30 April 2026

STATEMENT OF OBJECTIVES (SOO)

For

Replacement of Upper Roof on B3356

NAS JRB Fort Worth, TX

1. INTRODUCTION

This Statement of Objectives (SOO) defines the requirements for the contractor to replace the B3356 Upper Roof. The damage occurred during high winds, elevating the current 60 mil TPO roof and separating the TPO on the roof from the TPO on the side parapet walls. Photograph of work area is attached to page 3, other photographs are not available due to site security restrictions.

2. REQUIREMENTS

Unless otherwise specifically noted herein, the contractor shall provide all equipment, tools, materials, supplies, transportation, labor, supervision, management, and other incidentals necessary to meet the requirements as stated in this SOO. All supplies and materials provided shall be new and not refurbished.

The site location is located on NAS JRB Fort Worth, TX. Contractor must be prepared to provide their own toilet facilities and water sources. Power connections for tools are available at the site. Refer to the attached photo for additional details.

- 2.1. Remove and save lightning protection for reinstallation.
- 2.2. Remove Parapet wall cap and termination bars on the upper roof.
- 2.2. Remove Existing Roof and Roofing System on the Upper Roof walls and roof.
- 2.3. Furnish and sheath roof and wall with 7/16" OSB using adhesive and drop anchors.
- 2.4. Furnish and install Single Ply TPO 60 Mil including t-joint covers over roof, up and over walls to be covered with new wall cap.
- 2.5. Install new parapet wall cap around perimeter, matching existing or Dark Bronze.
- 2.6. Install salvaged lightning protection.
- 2.7. Patch 10 spots and curb joints on the lower section of the roof that are failing.



No other images permitted because of Security Precautions