

Performance Work Statement (PWS)

Traffic and Crowd Control Support Services

2026 Warriors Over the Wasatch Airshow

Hill Air Force Base, Utah

26–28 June 2026

1.0 DESCRIPTION OF SERVICES

1.1 Scope

The contractor shall provide all personnel, equipment, tools, materials, supervision, transportation, delivery, installation, maintenance, and removal necessary to support traffic management and crowd-control operations for the 2026 Warriors Over the Wasatch Airshow at Hill Air Force Base (HAFB), Utah. All work shall comply with federal, state, local, and Department of Defense (DoD) regulations, including MUTCD standards.

1.2 Background

The Warriors Over the Wasatch Airshow is a large-scale public event attracting hundreds of thousands of attendees. Effective traffic and crowd-control measures are required to ensure safe pedestrian movement, efficient vehicle flow, and secure airfield operations.

2.0 REQUIREMENTS

2.1 General Requirements

The contractor shall:

- Deliver all required equipment to designated locations on HAFB.
- Install all traffic-control and crowd-control devices per government-provided layout diagrams.
- Maintain all equipment in serviceable condition throughout the event.
- Provide on-call support during event hours for adjustments, replacements, or emergency response.
- Remove all equipment and restore all areas to original condition following the event.

3.0 EQUIPMENT AND QUANTITIES

3.1 Airfield Requirements

The contractor shall provide the following items for airfield crowd-control and safety:

Item	Quantity
Crowd Barrier (Bicycle Fence)	860 EA
Drums	175 EA
Delineators	355 EA

3.2 Parking Lot Requirements

The contractor shall provide the following for public and staff parking areas:

Item	Quantity
Sign Stand Only	40 EA

3.3 Base Traffic Requirements

The contractor shall support on-installation traffic flow with:

Item	Quantity
Event Cones	600 EA

3.4 SR-193 Traffic Requirements

The contractor shall support off-base traffic operations in coordination with UDOT and local law enforcement:

Item	Quantity
4x4 Sign w/Stand	5 EA
Specialty Sign w/Stand	4 EA
Drums	60 EA
Arrow Boards	2 EA
Barricade w/o Light w/Paper Sign	15 EA
Traffic Control Plan – Full (Non-Engineered, Per Sheet)	As Required
Traffic Control Plan – Minimal (Non-Engineered, Per Sheet)	As Required

4.0 PERFORMANCE REQUIREMENTS

4.1 Delivery and Installation

- All equipment shall be delivered no later than **24 June 2026** unless otherwise coordinated.
- Installation shall follow government-provided maps and instructions.
- Equipment should be placed securely to withstand weather and high-traffic conditions.

4.2 Maintenance During Event

- The contractor shall provide personnel capable of responding to equipment failures, repositioning needs, or safety-related adjustments.
- Response time for critical issues shall not exceed **30 minutes** during event hours.

4.3 Removal and Site Restoration

- Removal shall begin immediately following event completion on **28 June 2026** or as directed.
- All equipment shall be removed no later than **29 June 2026**.
- All areas shall be restored to pre-event condition.

5.0 GOVERNMENT FURNISHED INFORMATION (GFI)

The government will provide:

- Event site maps and traffic-flow diagrams.
- Points of contact for daily coordination.
- Access to installation areas and escort support is required.
- Coordination with Security Forces, UDOT, and local agencies.

6.0 CONTRACTOR FURNISHED ITEMS

The contractor shall furnish:

- All equipment listed in Section 3.0.
- All labor, vehicles, tools, and materials required for installation and removal.
- All safety equipment is required for contractor personnel.
- Communication devices for coordination with event command.

7.0 PERFORMANCE STANDARDS

Requirement	Standard
Equipment Delivery	100% delivered by agreed-upon date
Installation Accuracy	100% installed per layout diagrams
Equipment Serviceability	100% functional during event
Response Time	≤ 30 minutes for critical issues

Requirement	Standard
Teardown Completion	100% removed by deadline

Failure to meet standards may result in corrective action or deductions as defined in contract terms.

8.0 PERIOD OF PERFORMANCE

- **Start Date:** 24 June 2026
- **End Date:** 29 June 2026
- Includes delivery, installation, event support, teardown, and site restoration.

9.0 QUALITY CONTROL

The contractor shall implement a Quality Control Plan (QCP) ensuring:

- Continuous monitoring of equipment condition.
- Immediate correction of deficiencies.
- Documentation of inspections and corrective actions.

10.0 QUALITY ASSURANCE

The government will conduct inspections to verify compliance with this PWS. Non-compliance will be documented, and corrective action may be required.

11.0 SAFETY

The contractor shall comply with:

- OSHA regulations
- MUTCD standards
- HAFB safety and security requirements
- All applicable federal, state, and local laws

Contractor personnel should always wear appropriate PPE.

12.0 SECURITY REQUIREMENTS

- Contractor personnel shall comply with HAFB access procedures.
- All vehicles and equipment are subject to inspection.
- Contractor personnel shall always display identification.