

WAR IN THE PACIFIC NATIONAL HISTORICAL PARK (WAPA) GUAM

**REPLACE 17.5-TON PACKAGE COOLING UNIT (PCU)
& APPURTENANCES AT THE VISITOR CENTER**

PMIS No. 350936

CONSTRUCTION SPECIFICATIONS



**NATIONAL PARK SERVICE
PACIFIC WEST REGION**

MARCH 2026

THIS PAGE INTENTIONALLY LEFT BLANK

TABLE OF CONTENTS

<u>DIVISION 01 - GENERAL REQUIREMENTS</u>	<u>NO. OF PAGES</u>
01 11 00	Summary of Work.....9
	NPS Hot Work Permit (Form HW-1)2
01 11 40	Work Restrictions (Resource Protection).....3
01 27 00	Definition of Contract Line Items (CLINs)1
01 31 00	Project Management & Coordination2
	Request for Information (RFI) Form.....1
01 32 16	Construction Schedule2
01 33 23	Submittal Procedures4
	CM-16 Transmittal Form.....1
	Statement & Acknowledgement (Form SF1413).....1
01 35 23	Safety Requirements.....3
01 40 00	Quality Requirements3
	Quality Control (QC) Daily Report Form.....1
01 50 00	Temporary Facilities & Controls4
01 57 23	Temporary Stormwater Pollution Prevention5
01 67 00	Product Requirements3
01 73 40	Execution4
01 74 19	Construction Waste Management.....4
01 77 00	Closeout Procedures3

THIS PAGE INTENTIONALLY LEFT BLANK

DIVISION 01

GENERAL REQUIREMENTS

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 00 00 – SUMMARY OF WORK

PART 1 – GENERAL

1.1 SUMMARY

A. Section includes the following:

1. Work Covered by Contract Documents
2. Work Phases / Sequence
3. Work Under Other Contracts
4. Government-Furnished Items
5. Government-Furnished Documents
6. Conduct of Operations
7. Contractor Use of the Site
8. Public Use of the Site
9. Government Use of the Site
10. Occupancy Requirements for Buildings & Areas
11. Codes
12. Permits
13. Professional Services
14. Utility Interruptions
15. Vehicles & Equipment

1.2 WORK COVERED BY CONTRACT DOCUMENTS

- A. Project Location: T. Stell Newman Visitor Center, War in the Pacific National Historical Park (WAPA), Guam. Refer to GFD #1 – Aerial Site Map.
- B. Project Background: In 2006, the T. Stell Newman Visitor Center at WAPA was renovated for national park visitor services. Refer to GFD #2 – Construction Dwg 474-80067.

At the time, three (3) new Package Cooling Units (PCU) were installed on the roof above the restrooms. Refer to Sheet M-4 of GFD #2 for the PCU equipment schedule.

During the government shutdown in October 2025, the Package Cooling Unit labeled as PCU #3 on Sheet M-4 of GFD #2 failed. The park attempted to service the unit in November 2025, but the service vendor (JWS Refrigeration & Air Conditioning Ltd.) noted that the unit was beyond repair / service and needed to be replaced. Refer to GFD #3 – Photos of PCU.

C. Project Scope of Work: The Work consists of the following:

1. Replace the existing PCU #3 and appurtenances on the roof of the T. Stell Newman Visitor Center at War in the Pacific National Historical Park, to include:
 - a. Remove and properly dispose of the existing PCU #3 and appurtenances.
 - b. Power wash the existing concrete pad (8' wide x 11'-4" long x 5.5" high) in preparation for the new PCU. Properly contain and dispose of debris and water from power washing.
 - c. Install a new 17.5-Ton Carrier Model PCU meant for rooftop applications in inclement weather on the existing 8' x 11'-4" concrete pad on the roof. The new PCU shall be

208V, 3-Phase, 60 HZ. The PCU must fit on the existing concrete pad, and the return / supply ducts must be positioned in the rear of the unit facing the wall.

- d. The new PCU shall be placed with a crane with adequate load capacity and operating permits, careful not to damage the existing building, grounds, grass, or surrounding area. Protect ground surfaces with plywood or other surface protections.
- e. The new PCU shall be anchored to the existing concrete pad per manufacturer's published installation instructions.
- f. The Contractor shall replace all PCU appurtenances as shown in Detail 1/Sheet M-4 of GFD #2 to include the exterior supply and return air ducts, condensate drains, outdoor air hood with manual damper package, and electrical power cable, panel, and controls.
- g. The Contractor shall also replace the thermostat controller to work with the new PCU.
- h. The new PCU and appurtenances shall be installed, connected, calibrated, and operable per the manufacturer's published recommendations. Complete troubleshooting and commissioning as needed.

- 2. Project will be constructed under a single prime contract. Refer also to Section 01 27 00 – Definition of Contract Line Items.

- D. Project Mitigations: The Contractor shall comply with Section 01 11 40 – Work Restrictions & Resource Protection.

1.3 WORK PHASES / SEQUENCE

- A. Work Phases: The Work will be completed in one (1) single work phase.

1.4 WORK UNDER OTHER CONTRACTS

- A. General: Cooperate with separate contractors so that all contracts may be carried out smoothly without interfering with or delaying Work under this or other contracts. If another contract is awarded that may have an impact on this contract, the Contractor will be promptly notified.

1.5 GOVERNMENT-FURNISHED ITEMS

- A. General: The Government may furnish items such as materials, equipment, facilities, services, or housing for Contractor use on this contract. The government may furnish these items to lower the overall project costs, make use of existing item(s), or out of necessity in a remote location. The Contractor can assume that all items offered below are at no direct cost to the Contractor.
- B. Government-Furnished Materials: NONE IDENTIFIED AT THE OUTSET OF THE CONTRACT.

In the event government-furnished materials are offered (at the outset or furnished later):

- a) The Government will arrange and pay for delivery of government-furnished materials to the project site or agreed upon location based on the contractor's approved construction schedule.
- b) The Government will inspect the delivered items for damage after delivery. The Contractor shall be present for, and assist in, the Government's inspection.
- c) The Government will arrange for the replacement of materials if the government-furnished materials are damaged, defective, or missing.
- d) The Contractor shall do their due diligence to protect government-furnished materials from damage during storage and handling, including damage from exposure to the elements.

- e) The Contractor shall install or otherwise incorporate government-furnished materials into the Work of this contract, as outlined in the contract documents.
- C. Government-Furnished Equipment / Transportation: NONE IDENTIFIED AT THE OUTSET OF THE CONTRACT.

In the event government-furnished equipment is offered (at the outset or furnished later):

- a) The Government will make the equipment available for Contractor use based on the Contractor's approved construction schedule.
 - b) The Government will inspect the equipment and document its condition prior to Contractor use. The Contractor shall be present for, and assist in, the Government's inspection.
 - c) The Contractor shall provide all licensed, certified equipment operators.
 - d) The Government will provide an orientation and training on the equipment prior to use.
 - e) The Contractor shall provide all fuels / oils to operate the equipment, unless stated otherwise.
 - f) The Government will arrange for the replacement or repair of equipment, or provide an alternative, if the government-furnished equipment breaks during use.
 - g) The Contractor shall do their due diligence to protect the government-furnished equipment from damage, including damage from exposure to the elements.
- D. Government-Furnished Facilities: The following facilities will be available to the Contractor for use on this contract. Refer also to Section 01 50 00 Temporary Facilities & Controls.
- 1. Restroom: Available onsite at the T. Stell Newman Visitor Center.
 - 2. Field Office: NOT AVAILABLE.
 - 3. Storage Space: NOT AVAILABLE.
- E. Government-Furnished Utilities: The following utilities will be available to the Contractor for use on this contract. Refer also to Section 01 50 00 Temporary Facilities & Controls.
- 1. Potable Water: Available onsite at the T. Stell Newman Visitor Center.
 - 2. Non-Potable Water: NOT AVAILABLE.
 - 3. Wastewater Disposal: NOT AVAILABLE.
 - 4. Hydrotesting & Disinfection Water Disposal: NOT AVAILABLE.
 - 5. Electrical Power: Available onsite at the T. Stell Newman Visitor Center.
- F. Government-Furnished Housing: NOT AVAILABLE ON THIS PROJECT.

1.6 GOVERNMENT-FURNISHED DOCUMENTS (GFD)

- A. General: The Government may furnish reports or other documents for informational purposes to supplement the contract documents (labeled as GFD). In cases of conflict between a GFD and the drawings and specifications, the drawings and specifications will govern.

1.7 CONDUCT OF OPERATIONS

- A. Park Regulations: The Contractor shall conduct their operations in conformance with the rules and regulations promulgated by the Secretary of the Interior for the National Park Service (NPS), and applicable park rules and regulations prescribed by the Park Superintendent. Law enforcement rangers will intervene if they perceive any unsafe or unlawful activity.

- B. **Work Hours:** Regular work hours shall be limited to daylight hours between **6:00 a.m. to 4:00 p.m.** Monday through Friday, unless stated otherwise. No work shall be performed on weekends, state or federal holidays. Work outside regular hours requires advance approval from the Contracting Officer to ensure key NPS personnel are present in the event of an emergency.
- C. **Advertisement:** No signs or advertisements shall be displayed on the construction site or within the park unless approved by the Contracting Officer.
- D. **COVID-19 (Coronavirus Disease 2019):** The Contractor shall comply with the latest guidance on Covid-19. The information provided below is not intended to provide a complete analysis of requirements for Contractor and is provided as a courtesy.
 - 1. Occupational Safety & Health Administration (United States Department of Labor). www.osha.gov/coronavirus.
 - 2. Center for Disease Control (CDC) - www.cdc.gov/coronavirus/2019-ncov/index.html
 - 3. Department of the Interior (DOI) - [Our Response to COVID-19 | U.S. Department of the Interior \(doi.gov\)](https://www.doi.gov/coronavirus).

1.8 CONTRACTOR USE OF THE SITE

- A. **Park Entry:** Vehicles associated with the contract shall be waived the entrance fee upon entering in marked company vehicles or by providing the full names, vehicle type, and the license plate numbers of employees entering in personal vehicles.
- B. **Site Access:** The Contractor shall access the site as outlined in the drawings or attached map.
- C. **Project Area Limits:** The Contractor will have limited use of the site for construction operations. Limit operations to the project area limits as outlined in the drawings or attached map. Do not disturb portions of the park or site beyond areas where Work is indicated.
- D. **Storage of Materials:** Confine storage of materials to the areas as outlined in the drawings or attached map. If no specific site is shown, assume storage of materials is allowed within the project area limits and arrange for storage of materials with the park facility manager so as not to disrupt normal operations. The park will attempt to provide a covered area, if available. The Contractor may also furnish conex storage containers for material / tool storage as long as they are placed on a hardened surface within the project area limits or other approved location, and as long as the Contractor protects all surfaces from damage. Damage to surfaces shall be restored to pre-construction conditions. The Contractor will also be responsible for the protection and security of all materials stored in the park.
- E. **Staging of Materials and Equipment:** Confine staging of materials and equipment to the areas as outlined in the drawings or attached map. If no specific site is shown, assume staging of materials and equipment is allowed within the project area limits and arrange for staging of materials and equipment with the park facility manager so as not to disrupt normal operations. Staging of heavy equipment at the jobsite overnight is permitted if the equipment remains within the designated locations within the project area limits, is checked for leaks and has the proper spill prevention measures (refer to PART 1.16.F), and has adequate surface protection to prevent permanent track marks, spalls, cracks, ruts, depressions, and other damage (refer to PART

1.16.K). The Contractor is responsible for the protection and security of all materials and equipment staged at the jobsite.

- F. Stockpiling: Confine stockpiling of excavated soils to the area immediately adjacent to the trench or excavation, and, remove stockpiled materials from the jobsite if the materials will not be reused as part of the project. Confine imported soils and/or aggregate to the area(s) outlined in the drawings or attached map. If no specific site is shown, assume imported soils or aggregate is allowed within the project limits; however, consult with the park facility manager for an optimal location so as not to disrupt normal park operations. Protect all surfaces from damage. Damage to surfaces shall be restored to pre-construction conditions.
- G. Rock Removal: When encountering large rock or a significant volume of rock during excavation, follow the guidance outlined in Section 1.8.F for initial stockpiling. If the contract documents involve rock work, use the excavated rocks before importing rock. If the contract documents do not specify instructions regarding rock removal, relocation, or disposal, please submit a Request for Information (RFI) to the NPS for further instructions (with an estimated quantity of rock). All rock excavated at project sites on Molokai, Maui, and the Big Island of Hawai'i will remain within the project area limits or be relocated to a different location within the park.
- H. Field Office: Establishment of a construction camp within the park will not be permitted. The park will make every attempt to furnish the contractor with indoor office space for up to two (2) contractor personnel; however, if the park cannot accommodate the Contractor with office space, the Contractor will be allowed to setup a temporary field office within the project area limits (final location to be approved by the park facility manager). Note that connection to NPS internet or computer networks is prohibited for security purposes. Refer also to Section 01 50 00.
- I. Property Damage: The Contractor is required to report missing, lost, stolen, or damaged property occurring within the park. This report must be made to a Law Enforcement Ranger or NPS Dispatch at the first available opportunity at: **(808) 985-6170**.
- J. No Smoking Policy: Smoking is prohibited inside or outside within 25 feet of any buildings in the park. This applies to existing buildings and buildings under construction or renovation. Discarding of tobacco products or debris anywhere other than into designated tobacco receptacles is considered littering and subject to fines.

1.9 PUBLIC USE OF THE SITE

- A. General: Cooperate with NPS and partner staff so that the Work may be carried out smoothly without interfering with or delaying the Work under this or other contracts.
- B. Park Visitation: The project site will be OPEN to park visitors during construction. Partial and/or temporary closures in select areas may be permitted upon specific written approval by the Contracting Officer. The Contractor shall conduct their operations to minimize the inconvenience to the public.
- C. Park Events: The following park events are anticipated during the Work: NONE SCHEDULED.

1.10 GOVERNMENT USE OF THE SITE

- A. General: Cooperate with NPS and partner staff so that the Work may be carried out smoothly without interfering with or delaying the Work under this or other contracts.

1.11 OCCUPANCY REQUIREMENTS FOR BUILDINGS & AREAS

- A. Government Occupancy: The Government will OCCUPY the building(s) or area(s) under construction until the construction phase is complete and final acceptance has been issued. Cooperate with the Government during construction activities to minimize conflicts. Perform the Work so as not to interfere with the Government's day-to-day operations. Maintain existing building ingress, egress, doorways, corridors, access walkways, access roads, and public space unless the Contractor obtains written permission from the Contracting Officer to close, partially close, or temporarily close specific areas.
- B. Government Occupancy of Completed Areas: The Government reserves the right to occupy portions of buildings or areas and resume operations where the Work has been completed, provided such occupancy does not interfere with the completion of the remaining Work.
 - 1. The Contractor shall ensure all Work is completed; all systems are operational; all testing, balancing, and inspections have been performed; and all final cleaning is completed prior to Government occupancy.
 - 2. The Contracting Officer will prepare a Letter of Beneficial Use / Occupancy for the portion(s) of the building or areas to be re-occupied by the Government.
 - 3. Upon Government occupancy, the Government will assume responsibility for the maintenance and custodial services for occupied portions of the building or areas.

1.12 CODES

- A. General: The Contractor shall complete all Work in accordance with the latest versions of applicable federal, state, and local codes, standards, and regulations. Per Policy Memorandum 23-01 approved on May 9, 2023, the National Park Services (NPS) has adopted the International Code Council's (ICC) suite of codes and standards effective January 1, 2024. Additionally, the latest NFPA 70 (National Electric Code) is also adopted effective January 1, 2024. All work shall comply with the ICC suite of codes and standards and NFPA 70, where applicable. Additional codes, standards, and regulations may also apply. In the event of a conflict between codes, standards, regulations, and the contract documents, submit a Request for Information (RFI) with code references / citations to the Contracting Officer for a determination.

1.13 PERMITS

- A. General: The Contractor shall comply with all permit conditions, whether they are from permits furnished by the government (PART 1.13.D) or permits obtained as part of this contract (PART 1.13.E). Identify the start dates and durations to obtain all permits in the construction schedule. Note: A general building permit is not required for work on NPS land; however, the Contractor must still comply with all state and local building code provisions.
- B. Hot Work Permit: Hot work is defined as work activities (such as welding, cutting, blazing, and related work) that can be a source of ignition when flammable materials are present. All hot work operations shall be conducted in accordance with the procedures contained in RM-58, NPS policy on Hot Work Permits (see Appendix 35.8), and 29 CFR 1910.252(a). If the project requires any activities considered "hot work," submit a NPS Hot Work Permit (Form HW-1) application to the

Contracting Officer at least 48 hours prior to the scheduled hot work. The NPS will then review and complete Form HW-1 and return a copy to the Contractor with the required conditions or precautions. No hot work shall occur without a completed and signed Form HW-1 and all the required precautions in place. See attached Form HW-1.

- C. Confined Space Entry Permit: The Contractor and/or Employer shall adhere to, and implement, the permit-required confined space requirements of the Authority Having jurisdiction. Before each entry into a permit-required confined space, a permit must be completed, hazards must be assessed and controlled, proper ventilation and air-monitoring ensured, and personnel trained and equipped, with an attendant(s) stationed outside the space for constant communication and rescue readiness. A copy of the permit shall be furnished to the NPS for situational awareness.
- D. Government-Furnished Permits: NONE.
- E. Other Required Permits: The Contractor shall apply for and obtain the following permits. Comply with all permit conditions.
 - 1. Permit #1: Crane operating permit from the Authority Having Jurisdiction (AHJ), if applicable.

1.14 PROFESSIONAL SERVICES

- A. General: Professional services include any business, department, or individual whose core output is a service or expertise rather than a manufactured product.
- B. Shop Drawings: Shop Drawings are NOT REQUIRED for this project.
- C. Professional Land Surveyor (PLS): A professional land surveyor is NOT REQUIRED for this project.
- D. Professional Engineer (P.E.): A professional engineer is NOT REQUIRED for this project.

1.15 UTILITY INTERRUPTIONS

- A. General: Utilities include a connection or service to or between facilities involving Potable Water, Non-Potable Water, Fire Protection, Wastewater, Electrical Power, HVAC, Security, Alarms & Notifications, Internet and Telecommunications.
- B. Existing Utilities: Notify the Contracting Officer (and all applicable utility companies) of the Work being performed on a utility prior to excavation or disruption. The Contractor shall be responsible for locating and preventing damage to known utilities. If damage occurs to a known utility, repair the utility at no additional expense to the Government. If damage occurs to an unknown utility: 1) submit a Request for Information (RFI) to the NPS for further instructions, or, if time is of essence, 2) repair the utility / restore service and an equitable adjustment will be made in accordance with the Changes Clause of the contract.

- C. Utility Disruptions: Do not disrupt utility service to Government or NPS partner buildings or facilities unless required under the contract documents. If utility disruptions are required:
1. All Work shall be performed during normal business hours. If it is advantageous to perform the utility disruption after normal business hours, submit an RFI requesting allowance.
 2. Notify the Contracting Officer (and all applicable utility companies) not less than seven (7) calendar days in advance of the proposed utility disruption.
 3. Identify the affected services, location(s), start date, and duration of the disruption.
 4. For disruptions or outages lasting more than four (4) hours, or, for systems that cannot be disrupted due to critical security or public health requirements, install temporary utility services. Refer to Section 01 50 00 (Temporary Facilities & Controls) for more information.
 5. For disruptions or outages lasting more than four (4) hours that cannot be mitigated with temporary utility services, notify the Contracting Officer (and all applicable utility companies) not less than fourteen (14) calendar days in advance of the utility disruption(s).
 6. Do not proceed with utility disruptions without written permission from the Contracting Officer and the local utility service provider (where applicable).

1.16 VEHICLES & HEAVY EQUIPMENT

- A. General: The Contractor shall comply with the following work restrictions for vehicles and heavy equipment.
- B. Rules of the Road: Vehicles and heavy equipment shall comply with posted traffic regulations, including speed limits and double-yellow center lane markings. Vehicles and heavy equipment shall take every safe opportunity to use paved pullouts to allow faster-moving traffic to pass. Failure to comply with traffic regulations will result in a citation being issued to the driver.
- C. Vehicle Parking: Confine parking of Contractor vehicles to the areas as outlined in the drawings or attached map. Vehicles are not permitted to park along park roads or in overlooks / pullouts. Vehicles are not permitted to park overnight in the park.
- D. Driveways and Entrances: Keep driveways and entrances serving the premises clear and available to Government employees, vendor deliveries, and emergency vehicles at all times.
- E. Vehicle Exhaust: Vehicles shall be properly maintained to ensure the exhaust produced is within legal limits. The effects of excessive vehicle exhaust may be subject to enforcement of State and Federal laws regarding emissions as well as those regarding threatened and endangered species.
- F. Spills: The Contractor shall be responsible for prevention of spills and/or cleanup efforts required in accordance with 40 CFR and all applicable state environmental quality laws regarding disposal and cleanup of hazardous / industrial wastes. The Contractor must immediately notify a Law Enforcement Ranger or NPS Dispatch of any spills at: **(808) 985-6170**.
- G. DOT Compliance: Vehicles and heavy equipment shall be compliant with all DOT requirements including but not limited to drivers with appropriate license class, possessing a medical examiner card with license class as appropriate, carrying three (3) triangles or three (3) flares, carrying a mounted fire extinguisher, and possessing a valid DOT safety sticker, as applicable.
- H. Hauling & Load Restrictions: All vehicle load, weight, and size limitations, as established by State law, apply to vehicles operated on the park road (36 CFR § 4.11). No loads heavier than the

current load rating for park roads and bridges will be permitted. Load restrictions on park roads are identical to state load restrictions with such additional regulations as may be imposed by the Park Superintendent. Information regarding rules and regulations for vehicular traffic on park roads may be obtained from the Office of the Park Superintendent.

- I. **Oversized Vehicles:** Oversized vehicles are defined as vehicles where the width of the vehicle or load exceeds one lane (i.e., beyond the center line of the paved road). Oversized vehicles must not exceed the clearances along the park road corridor. Oversized vehicles will require an escort, and drivers must avoid driving on the shoulder of the road. Contractor shall notify the Contracting Officer of oversized vehicles, scheduled arrival dates & times at the park entrance, and the identity of who is escorting the vehicle (e.g., police, contractor, etc.). The Contractor shall avoid transporting loads using oversized vehicles during peak visitation periods in the park. These peak visitation periods may vary between parks and seasons. Submit an RFI at least seven (7) days prior to entering the park with an oversized vehicle to obtain the optimal travel times.
- J. **Slow Vehicles:** The Contractor is to notify the Contracting Officer of slow vehicles that may cause traffic delays or extended traffic lines.
- K. **Tracked Equipment:** Heavy equipment with rubber tires is preferred on projects within the national park. Heavy equipment with metal tracks may be allowed on paved asphalt surfaces, concrete surfaces, or ceremonial lawn areas only with adequate surface protection to prevent permanent track marks, spalls, cracks, ruts, depressions, and other damage. The means and methods of surface protection (such as plywood sheets or steel plates) shall also not damage surfaces. The exceptions listed below may apply. If the Contractor anticipates one of these exceptions, submit a Request for Information (RFI) to the NPS for further instructions.
 - 1. Tracked equipment may be allowed on paved asphalt or concrete surfaces in lieu of surface protection if the Contractor repairs all the affected surfaces to pre-construction condition or replaces the surface with new asphalt or new concrete, as applicable.
 - 2. Tracked equipment may be allowed on older paved asphalt surfaces if the asphalt surface is scheduled for pavement preservation (by others) within one (1) year of contract completion.
 - 3. Tracked equipment may be allowed on un-paved gravel roads if the tracked equipment stays on the road and does not create ruts, damage, or impacts the surface water flow. If damage occurs, the Contractor shall re-grade / restore the terrain to pre-construction conditions.
 - 4. Tracked equipment may be allowed on grass surfaces within the project area limits with adequate surface protection or the terrain is re-graded / restored to preconstruction conditions. Reseeding of re-graded / restored areas is not required unless otherwise specified.

PART 2 – PRODUCTS (Not Used)

PART 3 – EXECUTION (Not Used)

END OF SECTION 01 11 00

Hot Work Permit (Form HW-1)



Hot Work Permitting

Hot work shall only be performed in **designated** or **permit-required** areas. Before hot work operations begin in a non-designated location, a signed Hot Work Permit, issued by the Permit Authorizing Individual or his/her designee, shall be issued.

Designated Area

A designated area shall be a specific area designed for, or approved by the Permit Authorizing Individual or his/her designee for, such work. A designated area can be a maintenance shop or a detached outside location that is of noncombustible or fire-resistive construction, essentially free of combustible and flammable contents, and suitably segregated from adjacent areas. All designated areas shall have been inspected and approved by the Permit Authorizing Individual or his/her designee.

Permit-Required Area

A permit-required area shall be an area that is made fire safe and authorized by the issuance of a signed NPS Hot Work Permit. The Hot Work Permit shall be signed by Permit Authorizing Individual or his/her designee.

Non-permissible Areas

Hot work **shall not be allowed** in the following areas:

- (a) In areas not authorized by the Permit Authorizing Individual or his/her designee
- (b) In sprinklered buildings while such protection is impaired
- (c) In the presence of explosive atmospheres (that is, where mixtures of flammable gases, vapors, liquids, or dusts with air exist)
- (d) In explosive atmospheres that can develop inside unclean or improperly prepared drums, tanks, or other containers and equipment that have previously contained such materials
- (e) In explosive atmospheres that can develop in areas with an accumulation of combustible dusts

GENERAL

Park: _____ District: _____ Building: _____ Floor: _____

Work to be done: _____

Special precautions: _____

PERSON PERFORMING WORK

Contractor Business Name: _____

Contractor Representative: _____

Contractor Contact Number: _____

NPS Employee's Name: _____

NPS Office: _____

NPS Employee's Contact Number: _____

CHECK

Work area and all adjacent areas to which sparks and heat might have spread (including floors above and below and on opposite side of wall(s) were inspected every 20 minutes for 1 hour after the work was completed and were found fire safe.

ATTENTION

Before approving any hot work permit, the Permit Authorizing Individual or his/her designee shall inspect the work area and confirm that the proper precautions have been taken to prevent fire, in accordance with the NPS Hot Work Permit Form (Form HW-1) and the NPS Hot Work Policy.

PRECAUTIONS

- ☐ Sprinklers in service
- ☐ Hot work equipment in good repair

WITHIN 35 FEET OF HOT WORK AREA

- ☐ Floors swept, clean of combustibles
- ☐ Combustible floors wetted down, covered w/ damp sand or other shields in place
- ☐ All wall and floor openings covered

WORK ON WALLS OR CEILINGS

- ☐ Combustibles moved away from opposite side of wall

WORK ON ENCLOSED EQUIPMENT (tanks, containers, ducts, dust collectors etc.)

- ☐ Equipment cleaned of all combustibles
- ☐ Containers purged of all flammable vapors

FIRE WATCH

- ☐ To be provided during and 60 minutes after operation
- ☐ Supplied with a fully charged and operable fire extinguisher
- ☐ Trained in use of equipment and activating fire alarm system

FINAL CHECK

- ☐ To be made every 20 minutes for 60 minutes after completion of any operation unless fire watch is provided

Is a fire watch required? Yes ☐ No ☐

The location where the work is to be done has been examined, necessary precautions taken, and permission is granted for this work.

Permit Issue Date: _____ Permit Expires: _____

Permit Authorizing Individual or Designee: _____

Signature: _____ Date: _____

SECTION 01 11 40 – WORK RESTRICTIONS & RESOURCE PROTECTION

PART 1 – GENERAL

1.1 SUMMARY

- A. General: The NPS is the steward of unique resources found within the national parks. The NPS is committed to protecting natural, cultural, historical, archaeological, and other resources found within the parks and the adjacent lands.
- B. Section includes work restrictions for protecting resources in the national parks including, but not limited to the following:
 - 1. Preservation of Natural Features
 - 2. Invasive Species Prevention
 - 3. Invasive Species Inspections
 - 4. Threatened & Endangered Species (T&E Species)
 - 5. Archaeological Resources
 - 6. Soundscape / Noise
 - 7. Air Quality (Indoor & Outdoor)

PART 2 – PRODUCTS (Not Used)

PART 3 – EXECUTION

3.1 PRESERVATION OF NATURAL FEATURES

- A. General: The Contractor shall comply with the following work restrictions:
 - 1. Prevent damage to natural surroundings.
 - 2. Provide temporary barriers to protect existing trees, tree roots, plants, grass areas and lawns that are directly impacted by construction operations. Temporary barriers should be free-standing orange traffic delineator posts with grabber / looper tops and plastic rails.
 - 3. Do not fasten ropes, cables, or guys to existing trees, rock outcrops, or other natural features.
 - 4. Do not remove, injure, or destroy existing trees, tree roots, or plants without approval by the Contracting Officer or unless it's explicitly required in the contract documents.
 - 5. If a tree, tree branch, root, or mass of vegetation is preventing the Contractor from completing the work, notify the Contracting Officer immediately for a determination. Trees may need to be surveyed by park staff for bird nests prior to removal. Tree removal / trimming may be subject to additional restrictions if project is in Hawaiian hoary bat habitat.
 - 6. Carefully supervise the excavation, grading, filling, equipment movement, and other construction operations near trees and tree branches to prevent damage.

3.2 INVASIVE SPECIES PREVENTION – NOT APPLICABLE

3.3 INVASIVE SPECIES INSPECTIONS – NOT APPLICABLE

3.4 THREATENED & ENDANGERED SPECIES (T&E SPECIES)

- A. General: Threatened & Endangered Plant and Animal Species are protected by Federal law. Workers must obey all park regulations and drivers must obey all traffic laws and watch for

animals on or alongside roads or within the project area. Contact NPS Dispatch at: **(808) 985-6170** immediately if an animal is hit or injured or will not move off the road.

- B. General Mitigations: Within the project area, the following mitigation measures are required to minimize disturbance to T&E species:
1. The project area shall be cleaned-up at the end of each work shift so that tools, materials, debris, and trash are not left out in a manner that could be a hazard to T&E species.
 2. Noise and vibrations from tools and equipment shall be kept to a minimum when working in the vicinity of a listed T&E species.
 3. Hazmat spill prevention protocols shall be employed when using gas-powered equipment.
 4. Tarps shall be used to contain all paint chips and building debris from exterior surfaces as these can be hazards to listed T&E species.
 5. Ensure no standing water on tarps or other construction surfaces as it may be a breeding ground for mosquitoes which may carry Dengue fever, avian malaria / flu, and other diseases.
 6. Ensure loose nails, screws, and fasteners do not fall on the ground when working on exterior surfaces as these can be a hazard to T&E species. If they do land on the ground, pick them up immediately and dispose of them properly.

3.5 ARCHAEOLOGICAL RESOURCES

- A. General: Archaeological resources are physical evidence of past human activity, including evidence of the effects of that activity on the environment. Archaeological resources are found above and below ground and underwater. Known archeological resources will be marked and flagged by the park. Do not disrupt known archaeological resources or flagged areas during construction activities. If required in Section 01 11 00, PART 1.2.D, the Contractor shall erect temporary barriers around the archaeological resource to help ensure avoidance. Temporary barriers shall be free-standing orange traffic delineator posts with grabber / looper tops and plastic rails (or a comparable barrier that does not involve digging but is an effective barrier). Submit a CM-16 with the proposed temporary barrier product for NPS approval.

The Contractor does not need to provide an Archaeological Monitor; however, the Contractor, or Contractor's designee, will observe all ground-disturbing activities during earthwork and other construction operations. If the Contractor discovers archaeological resources, the Contractor shall stop work, notify the Contracting Officer immediately, and relocate to a non-sensitive area. The park may have an Archaeological Monitor present at the jobsite who is authorized to stop work upon discovery of archaeological resources. Archaeological resources typically found in the park or at the project site will be discussed at the preconstruction meeting.

3.6 SOUNDSCAPE / NOISE

- A. General: The Contractor shall minimize noise levels at the project site to protect the soundscape of the park and minimize noise to staff, visitors, neighbors, and habitat. Perform operations to minimize noise. Perform noise-producing work in less sensitive hours of the day or week or as directed by the Contracting Officer. Repetitive and/or intermittent, high-level noise is permitted only during daytime hours. If the Contractor exceeds the thresholds below, the Contractor may be required to stop work, temporarily relocate to a non-sensitive area, or adjust the construction means and methods at no additional expense to the Government.

1. Maximum permissible construction equipment noise at 50 feet:

<u>EARTHMOVING</u>	<u>dB(A)</u>	<u>MATERIALS HANDLING</u>	<u>dB(A)</u>
Front Loaders	75	Concrete Mixers	75
Backhoes	75	Concrete Pumps	75
Dozers	75	Cranes	75
Tractors	75	Derricks Impact	75
Scrapers	80	Pile Drivers	95
Graders	75	Jack Hammers	75
Trucks	75	Rock Drills	80
Pavers, Stationary	80	Pneumatic Tools	80
Pumps	75	Saws	75
Generators	75	Vibrators	75
Compressors	75		

2. Do not exceed the following dB(A) limitations at 50 feet:

<u>TIME DURATION OF IMPACT NOISE</u>	<u>dB(A)</u>
More than 12 minutes in any hour	70
More than 3 minutes in any hour	80

3.7 AIR QUALITY (INDOOR & OUTDOOR)

- A. General: The Contractor shall minimize the negative impacts to indoor and outdoor air quality as a result of their operations. This may include:
 1. Control of emissions from vehicles or heavy equipment.
 2. Control of fumes, vapors, or gases from products or packaging.
 3. Control of particulates and dust from indoor operations such as cutting and sanding.
 4. Control of particulates and dust from outdoor operations.
 5. Control of moisture during operations that may lead to damage, fumes, or mold.
- B. Mitigations: The Contractor shall mitigate for negative impacts to indoor and outdoor air quality as a result of their operations. This may include:
 1. Ensure vehicles and heavy equipment do not idle when not in use.
 2. Ensure proper ventilation and air movement of indoor spaces.
 3. Install temporary mechanical ventilation where appropriate.
 4. Ensure tools are equipped with the proper guards or particulate catchment devices.
 5. Ensure particulates and debris are collected and disposed of on a regular basis.
 6. Consider water trucks or temporary irrigation devices for dust control on unpaved surfaces.
 7. Ensure products are properly dried or cured prior to advancing the work.
 8. Ensure materials are stored in a dry location.
 9. Ensure wet / damp materials are not installed or covered.

END OF SECTION 01 11 40

SECTION 01 27 00 – DEFINITION OF CONTRACT LINE ITEMS (CLIN)

PART 1 – GENERAL

1.1 SUMMARY

- A. This section explains, in general, what is and is not included in a contract line item and defines where one item ends and another begins.
- B. If no contract line item exists for a portion of work, include costs in a related item.

PART 2 – PRODUCTS (Not Used)

PART 3 – EXECUTION

3.1 LIST OF CONTRACT LINE ITEMS

- A. Contract Line Item (CLIN) 00010
 - 1. This item consists of replacing the existing Package Cooling Unit (PCU) and appurtenances on the roof of the T. Stell Newman Visitor Center. Refer to Section 011100, PART 1.2.C.
 - 2. Payment will be made at the contract lump sum price.

END OF SECTION 01 27 00

SECTION 01 31 00 – PROJECT MANAGEMENT & COORDINATION

PART 1 – GENERAL

1.1 SUMMARY

- A. This section includes administrative provisions for coordinating construction operations on the Project including, but not limited to, the following:
 - 1. Construction Coordination
 - 2. Requests for Information (RFI)
 - 3. Project Meetings

1.2 CONSTRUCTION COORDINATION

- A. Contractor Coordination: Coordinate construction operations included in different drawing sheets and/or specification sections to ensure efficient and orderly installation of each part of the Work.
 - 1. Schedule construction operations in the sequence required to obtain the best results where installation of one part of the Work depends on installation of other components.
 - 2. Coordinate installation of different components with other Contractors to ensure maximum access for required maintenance, service, and repair.
 - 3. Plan and coordinate construction operations to incorporate applicable permit requirements.
- B. Administrative Procedures: Coordinate scheduling of administrative procedures with other construction activities to avoid conflicts and ensure orderly progress of the Work.

1.3 REQUEST FOR INFORMATION (RFI)

- A. General: Upon discovery of the need for additional information or an interpretation of the contract documents, the Contractor shall prepare and submit an RFI. The Contracting Officer will only respond to RFIs submitted by the prime Contractor. Coordinate and submit RFIs in a prompt manner to avoid delays in the work.
- B. RFI Form: Include a detailed, legible description of the subject or item needing more information or interpretation on the NPS RFI Form with the information below. Submit the RFI form in MS Word format to allow the NPS to provide a response.
 - 1. RFI number, numbered sequentially.
 - 2. Date of RFI.
 - 3. RFI subject.
 - 4. Specification Section, section title, and related paragraphs, if applicable.
 - 5. Drawing number and detail references, if applicable.
 - 6. Description of the issue or question.
 - 7. Photographs or sketches, if applicable.
 - 8. Contractor's suggested resolution. State whether the suggested resolution results in "no additional time / cost" to the contract or if it will result in "additional time / cost." Do not provide a detailed price proposal unless requested to do so by a Contracting Officer.
- C. RFI Response: The Contracting Officer, or authorized representative, will review each RFI, determine the action required, and respond accordingly.

1.4 PROJECT MEETINGS

- A. Preconstruction Meeting: Before the start of construction, the Contracting Officer will arrange for a preconstruction meeting (typically by MS Teams or teleconference). A meeting agenda will be forwarded to the group prior to the meeting. During the meeting, the agenda will be updated by the Contracting Officer or designee and distributed to the group as the meeting minutes.
- B. Progress Meetings: The NPS may schedule periodic meetings to discuss the progress of the Work with the Contractor, subcontractor(s), and key NPS staff. The need for and frequency of these meetings will be discussed at the preconstruction meeting. Progress meetings are typically held once per week via teleconference and last no more than 30 minutes. These weekly meetings are mainly to discuss progress for team situational awareness. Meeting minutes are not required.

PART 2 – PRODUCTS (Not Used)

PART 3 – EXECUTION (Not Used)

END OF SECTION 01 31 00

REQUEST FOR INFORMATION (RFI)

CONTRACTOR SECTION					
Park Name & Project Title:					
NPS Solicitation / Contract No:					
Contractor Name:					
Subject of RFI:					
RFI Number:		Date Submitted:		Response Required By:	
<i>Please provide additional information or clarifications to the questions below:</i>					
<i>Contractor Recommendation, if applicable</i>					
NPS SECTION					
Name of NPS Respondent:				Date of Response:	
<i>Below is additional information or clarifications in response to the Contractor RFI:</i>					

SECTION 01 32 16 – CONSTRUCTION SCHEDULE

PART 1 – GENERAL

1.1 SUMMARY

- A. This section consists of Construction Schedule requirements including:
 - 1. Schedule of Values
 - 2. Construction Baseline Schedule
 - 3. Construction Schedule Updates
 - 4. Look-Ahead Schedule
- B. Purpose: The construction schedule ensures adequate planning, coordination, scheduling, and reporting during execution of the Work by the Contractor. The construction schedule will assist the NPS and the Contractor in the monitoring the progress of the work, evaluating the proposed changes, and the processing the Contractor's progress payments.

1.2 DEFINITIONS

- A. Schedule of Values (SOV): A document that helps define the payment process on contracts. The SOV allocates the entire awarded contract sum to various portions or activities of the Contractor's work. The value for each portion of work in the SOV shall generally coincide with the value(s) outlined in the accepted price proposal (where applicable).
- B. Activity: A discrete part of a project identified for planning, scheduling, monitoring, and controlling the construction project. Activities included in a construction schedule consume time and resources. Critical activities are activities on the critical path. They start and finish on the planned early start and finish times. Predecessor activities are activities that precede another activity in the schedule network. Successor activities are activities that follow another activity in the schedule network.
- C. Critical Path: Longest connected chain of interdependent activities through the schedule network that establishes the minimum overall project duration and contains no float.
- D. Float: Measure of leeway in starting and completing an activity.

1.3 SUBMITTALS

- A. Schedule of Values (SOV): Submit a schedule of values (SOV) with a breakdown of all major work activities for which progress payments will be requested. The SOV should identify the park, project title, contract number, and Contractor name. In addition, the SOV must also include the following columns (at a minimum): Item #, Activity Description, Total Contract Value (\$), Previous Pay Applications (\$), Work this Period (\$), % Complete (%), and Balance to Complete (\$). The SOV must also have a total value for all (\$) columns.

Ensure each portion of work or activity is assigned to the appropriate Contract Line Item (CLIN), Bid Option, or Contract Modification. Ensure an updated SOV is submitted with each invoice.

Ensure the SOV is updated with each contract modification. Failure to submit an accurate SOV reflecting the work completed at the time of invoice submission may delay invoice approval.

B. Construction Baseline Schedule: Submit a construction baseline schedule with all major work activities. At a minimum, the schedule must have the following information:

- Milestone: Contract Award (actual date)
- Activity: Permit Applications & Approvals, if applicable
- Activity: Division 01 Plan Preparation & Review
- Milestone: Preconstruction Meeting & Notice to Proceed (anticipated)
- Activity: Material Submittal Preparation & Review
- Activity: Material Purchasing & Delivery
- Activity: Initial Invasive Species Inspections & Field Mobilization
- Activities: All Major Work Activities (with start and end dates) with critical path identified
- All Federal and State Holidays.
- Activities: Testing and Service Interruptions
- Milestone: Pre-Final Inspection (at Substantial Completion)
- Activity: Punchlist Completion (within 30 days after Substantial Completion)
- Milestone: Final Inspection (within 30 days after Substantial Completion)
- Activity: Field Demobilization (after all field work is complete and accepted)
- Activity: Preparation of Final Closeout Documents
- Milestone: End Contract Period of Performance

MS Project is the preferred computer software for developing a construction schedule; however, the NPS will accept any format that relays the requested information and can be easily updated and understood. No work shall be performed or shown on weekends, state, and federal holidays. Ensure coordination of the work with subcontractors and vendors in the development of the construction schedule and schedule updates.

C. Construction Schedule Updates: Submit updates to the construction baseline schedule: 1) when requested, 2) when there is a change to the critical path, 3) when the previously approved schedule is no longer accurate, or 4) when there is a change to the contract such as a modification. Construction schedule updates must be approved in advance of the Work.

D. Look-Ahead Schedule (Optional): The Contractor may submit a 1-3 week look-ahead schedule at the beginning of each week to notify the NPS of planned work and potential disruption to park operations. The look-ahead schedule typically shows proposed work planned for each day of the week. The look-ahead schedule does not need to be approved, but it must be consistent with the approved schedule. If the look-ahead schedule is not consistent with the approved schedule, submit a construction schedule update for approval. The look-ahead schedule can be submitted in any format, but weekly / monthly calendar view seems to work well.

PART 2 – PRODUCTS (Not Used)

PART 3 – EXECUTION (Not Used)

END OF SECTION 01 32 16

SECTION 01 33 23 – SUBMITTAL PROCEDURES

PART 1 – GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for submittals including:
 - 1. Submittal Procedures
 - 2. Submittals
 - 3. Submittal Review

1.2 DEFINITIONS

- A. Action Submittals: Written, graphic information, and physical samples that require the Government's approval.
- B. Informational Submittals: Written information that does not require the Government's approval. Submittals may be rejected for not complying with the requirements.
- C. Portable Document Format (PDF): An open standard file format licensed by Adobe Systems used for representing documents in a fixed-layout document format.
- D. File Transfer Protocol (FTP): Communications protocol that enables transfer of files to and from another computer over a network and that serves as the basis for standard Internet protocols. An FTP site is a portion of a network located outside of network firewalls within which internal and external users are able to access the files.

1.3 SUBMITTAL PROCEDURES

- A. General: Prepare and submit all submittals required by individual specification section, contract clause, or as requested in the drawings. The Contracting Officer reserves the right to require submittals in addition to those called for in individual specification sections. Review submittals for legibility, accuracy, completeness, and compliance with the contract documents prior to submittal to the Contracting Officer.
- B. Submittal Format: All submittals shall be transmitted using the NPS CM-16 form via email (or approved FTP / Sharepoint Site). Each submittal item shall have its own CM-16 form. Complete all applicable fields of the CM-16 form; provide a submittal number not previously used; and attach all supporting documentation. Resubmittals shall retain the original submittal number followed by a letter starting with "a, b, and so forth. The completed submittal may be submitted in PDF format (or optimized PDF format if file size is > 10 mb). Ensure all pages of the submittal are positioned upright (rotate page if needed), and all blank pages removed. No action will be taken on a submittal item unless it is accompanied by a properly formatted CM-16 form.
- C. File Transfer: For attachments with file size < 10 mb, transmit file(s) via email. For attachments with file size > 10 mb, transmit file(s) via FTP or secure Sharepoint Site. Note that Dropbox and similar commercial file share services are not secure and not allowed on the NPS network.

1.4 SUBMITTALS

- A. General: At a minimum, prepare and submit the following submittals for the project:
- B. Submittal Log (Optional): The Contractor may submit and update a submittal log to help keep track of the progress of all action and informational submittals.
- C. Contract Submittals: The following contract submittals shall be submitted within 7 days after contract award. Failure to submit these submittals may delay the notice to proceed. Note that the Contracting Officer (CO) will typically review and approve these submittals.
 - 1. Satisfactory evidence of Liability Insurance Coverage and Workers Compensation for the Contractor and all Subcontractors (per contract clause).
 - 2. Performance and Payment Bonds.
- D. Division 01 Informational Submittals: The following Division 01 informational submittals shall be received within 14 calendar days after contract award and at least 7 calendar days prior to the preconstruction meeting. If any of these documents have not been received within 7 calendar days of the preconstruction meeting, the meeting may be cancelled and the Notice to Proceed (NTP) may be delayed. Work shall not commence until written NTP has been issued by the Contracting Officer. Submit each document separately with its own CM-16 form for acceptance. Refer to applicable specification sections for the required content of each submittal. Note that the Contracting Officer's Representative (COR) will typically review and accept these submittals.
 - 1. Letter designating the Job Superintendent (comply with Section 01 73 40, PART 1.2.A).
 - 2. List of Subcontractors / Written Statement & Acknowledgement (SF1413 Form) for all Subcontractors certifying compliance with applicable labor clauses (per contract clause).
 - 3. Construction Schedule (comply with Section 01 32 16, PART 1.3.B).
 - 4. A comprehensive Schedule of Values (comply with Section 01 32 16, PART 1.3.A).
 - 5. Accident Prevention Plan (comply with Section 01 35 23, PART 1.2.A).
 - 6. Quality Control Plan (comply with Section 01 40 00, PART 1.4.A).
 - 7. Under-an-Acre Pollution Prevention Plan (UPPP) (comply with Section 01 57 23, PART 1.4).
 - 8. Construction Waste Management Plan (comply with Section 01 74 19, PART 1.4.A).
- E. Division 01-49 Action Submittals: All Division 01-49 action submittals shall be received and approved prior to construction start (i.e. field mobilization). If any of the required documents have not been received and approved prior to construction start, the start date could be delayed. Items shall not be purchased by the Contractor until written NTP has been issued by the Contracting Officer and the applicable Division 01-49 action submittals have been approved. Submit each submittal separately with its own CM-16 form for approval. Refer to applicable specification sections for the required content of each submittal. Note that the Contracting Officer's Representative (COR) will typically review and approve these submittals with assistance from key park personnel regarding colors, styles, or substitutions.
 - 1. Product Data - Submit product cut sheets / data on all materials & products to be used on the project or as required in the Division 01-49 specification sections. Highlight the size, model, or type of each required or recommended product. Ensure all products meet the Buy American Act provisions and are commercially available in the United States.

2. Samples – If applicable, submit a physical sample of a product and/or an array of color choices for approval.
- F. Shop Drawings – A shop drawing is a drawing or set of drawings produced by the Contractor, supplier, manufacturer, subcontractor, or fabricator. Shop drawings are typically required for prefabricated components or to illustrate the coordination work between trades. The shop drawing's primary emphasis is on the particular product or installation. Note that the Contracting Officer's Representative (COR) will typically review and approve these submittals.
1. Shop Drawings shall be developed in AutoCAD or similar drafting software.
 2. Shop Drawings shall include details, dimensions, notational information and other data to ensure the Contractor has a complete understanding of the work.
 3. Shop Drawings shall be submitted in DRAFT to the Contracting Officer along with a CM-16 form. Allow 7 calendar days for the drawings to be reviewed by the NPS. The Contractor shall correct any issues with the shop drawings as identified in the review comments and resubmit on a CM-16 form for final approval.
 4. Update shop drawings during and after installation if changes are necessary, and submit the final as-built shop drawings as part of the Closeout Documents.
- G. Permit Applications & Permit Approvals: All applicable permit applications and permit approvals shall be received prior to construction start (comply with Sections 011100, PART 1.13; Section 015723, PART 1.4; and Section 017340, PART 3.2.A). Note that the Contracting Officer's Representative (COR) will typically review and approve these submittals.
- H. Submittals (During Construction):
1. Construction Schedule Updates (comply with Section 01 32 16).
 2. Quality Control (QC) Daily Reports (comply with Section 01 40 00, PART 1.4.B).
 3. Testing & Inspection Data, if applicable (comply with Section 01 40 00, PART 1.4.C).
 4. Field Surveying Data, if applicable (comply with Section 01 73 40, PART 1.2.B).
 5. Field Engineering Data, if applicable (comply with Section 01 73 40, PART 1.2.C).
 6. Product Data for Newly Introduced Products (comply with Section 01 33 23, PART 1.4.D).
- I. Closeout Submittals: All closeout submittals shall be received and accepted prior to contract final acceptance. If any of these documents have not been received within 30 days after issuance of the Letter of Substantial Completion, final acceptance may not be issued. Note that the Contracting Officer's Representative (COR) will typically review and approve these submittals.
1. Project Record Drawings (comply with Section 017700, PART 1.2.B).
 2. Warranties (comply with Section 017700, PART 1.2.C)
 3. Operation & Maintenance (O&M) Manual (comply with Section 017700, PART 1.2.D).
 4. Project Photos (comply with Section 017700, PART 1.2.E)
 5. Project Closeout Binders (comply with Section 017700, PART 1.2.F).

1.5 SUBMITTAL REVIEW

- A. General: All submittals will be reviewed by the Contracting Officer, or authorized representative, to ensure compliance with the contract documents. Acceptance or approval of a Contractor's submittal does not relieve a Contractor from complying with the contract requirements.

- B. Informational Submittals: The Contracting Officer, or authorized representative, will review the informational submittal or resubmittal and indicate the appropriate action on the CM-16 Form as follows:
1. ACCEPT: Acceptable with no corrections.
 2. REJECT: Rejected as not in accordance with the contract or requiring major corrections, clarifications, or missing information. Contractor shall revise and resubmit the submittal.
- C. Action Submittals: The Contracting Officer, or authorized representative, will review the action submittal or resubmittal and indicate the appropriate action on the CM-16 Form as follows:
1. APPROVED: Acceptable with no corrections.
 2. APPROVED WITH NOTATIONS: Minor corrections or clarifications required. Comments are clear and no further review of resubmittal is required. Contractor shall address the review and comply with the comments when proceeding with the work.
 3. DISAPPROVED – RESUBMIT: Rejected as not in accordance with the contract or requiring major corrections, clarifications, or missing information. Contractor shall revise and resubmit the submittal with changes clearly identified.
- D. Brand Name or Equal: In accordance with Federal Acquisition Regulation Clause 52.211-6, items in this solicitation identified as “Brand Name or Equal,” include salient characteristics required to satisfy the Government’s needs. When proposing “equal” products, the Contractor [in addition to the requirements identified in Section L] shall submit evidence that “equal” products meet the salient physical, functional, or performance characteristics specified with their proposal for technical evaluation purposes. For each item proposed as an “approved equal” submit supporting data to include the following:
1. Name, address, and telephone number of the product vendor.
 2. Manufacturer’s literature / product cut sheets.
 3. Comparison of the salient characteristics between the proposed item and the item specified.
 4. Compliance with the Buy American Act / Commercially available in the United States.
 5. Difference in cost between the proposed item and the item specified.
- E. Partial or Incomplete Submittals: The Contracting Officer, or authorized representative, will review all submittals. If it appears the submittal is incomplete, it will be considered non-responsive and returned without further review.
- F. Processing Time: Allow at least 7 calendar days for the Contracting Officer, or authorized representative, to review a submittal and 3 calendar days to review a resubmittal.

PART 2 – PRODUCTS

PART 3 – EXECUTION

END OF SECTION 01 33 23

CM-16 TRANSMITTAL FORM - NATIONAL PARK SERVICE (NPS)

CONTRACT INFORMATION													
Park:		Contract No.:		Project Title:			Date:		Contractor Name:			Submittal No.	
CONTRACTOR ACTION								NPS ACTION					
								Action			Informational		
Item No.	Action Submittal	Informational Submittal	Specification Section	PART, Paragraph	Drawing No. (if applicable)	Description of Item (Attach Supporting Documentation)	Meets Buy American Act?	Alternative Material Proposed?	Approved	Approved with Notations	Disapproved - resubmit	Accepted	Rejected
NPS SUBMITTAL REVIEW COMMENTS							SIGNATURES						
							Contractor's Project Manager:					Date:	
							I certify that this submittal has been reviewed for accuracy, completeness, and compliance with contract requirements.						
							NPS CO / COR:					Date:	
							Approval of this submittal is subject to the contract terms and conditions, drawings and specifications. Review of submittals will be general and shall not be construed as permitting any departure from contract requirements.						

STATEMENT AND ACKNOWLEDGMENT

OMB Control Number: 9000-0066

Expiration Date: 4/30/2022

Paperwork Reduction Act Statement - This information collection meets the requirements of 44 U.S.C. § 3507, as amended by section 2 of the Paperwork Reduction Act of 1995. You do not need to answer these questions unless we display a valid Office of Management and Budget (OMB) control number. The OMB control number for this collection is 9000-0066. We estimate that it will take .05 hours to read the instructions, gather the facts, and answer the questions. Send only comments relating to our time estimate, including suggestions for reducing this burden, or any other aspects of this collection of information to: U.S. General Services Administration, Regulatory Secretariat Division (M1V1CB), 1800 F Street, NW, Washington, DC 20405.

PART I - STATEMENT OF PRIME CONTRACTOR

1. PRIME CONTRACT NUMBER		2. DATE SUBCONTRACT AWARDED		3. SUBCONTRACT NUMBER	
4. PRIME CONTRACTOR				5. SUBCONTRACTOR	
a. NAME				a. NAME	
b. STREET ADDRESS				b. STREET ADDRESS	
c. CITY		d. STATE	e. ZIP CODE	c. CITY	
				d. STATE	
				e. ZIP CODE	
6. The prime contract ☐ does, ☐ does not contain the clause entitled "Contract Work Hours and Safety Standards Act -- Overtime Compensation."					
7. The prime contractor states that under the contract shown in Item 1, a subcontract was awarded on the date shown in Item 2 to the subcontractor identified in item 5 by the following firm:					
a. NAME OF AWARING FIRM					
b. DESCRIPTION OF WORK BY SUBCONTRACTOR					

8. PROJECT		9. LOCATION		
10a. NAME OF PERSON SIGNING		11. BY (Signature)		12. DATE SIGNED
10b. TITLE OF PERSON SIGNING				

PART II - ACKNOWLEDGMENT OF SUBCONTRACTOR

13. The subcontractor acknowledges that the following clauses of the contract shown in Item 1 are included in this subcontract:

Contract Work Hours and Safety Standards Act - Overtime Compensation (If included in prime contract see Block 6)	Construction Wage Rate Requirements
Payrolls and Basic Records	Apprentices and Trainees
Withholding of Funds	Compliance with Copeland Act Requirements
Disputes Concerning Labor Standards	Subcontracts (Labor Standards)
Compliance with Construction Wage Rate Requirements and Related Regulations	Contract Termination - Debarment
	Certification of Eligibility

14. NAME(S) OF ANY INTERMEDIATE SUBCONTRACTORS, IF ANY

A		C		
B		D		
15a. NAME OF PERSON SIGNING		16. BY (Signature)		17. DATE SIGNED
15b. TITLE OF PERSON SIGNING				

SECTION 01 35 23 – SAFETY REQUIREMENTS

PART 1 – GENERAL

1.1 SUMMARY

- A. This section includes establishing an effective accident prevention program and providing a safe working environment for Contractor personnel, NPS staff, and park visitors.

1.2 SUBMITTALS

- A. Accident Prevention Plan (APP) – After contract award and before the Pre-Construction Meeting, submit a “site specific” accident prevention plan with the following information (at a minimum).
 - 1. Name of the onsite manager responsible for implementing the accident prevention plan.
 - 2. Emergency contact phone numbers (include NPS dispatch at: **808-985-6170**).
 - 3. Map of the local area emergency medical facilities relative to the jobsite.
 - 4. Contractor’s general company safety plan & protocol.
 - 5. Contractor’s first aid and emergency medical procedures & accident reporting forms.
 - 6. Contractor’s COVID-19 (Coronavirus) disease prevention protocols.
 - 7. Completed activity hazard analysis (AHA) completed for each major work activity.

1.3 QUALITY ASSURANCE

- A. General: Comply with the contract documents and contract clauses related to safety and health. In case of conflicts between Federal, State, and local safety and health requirements, the most stringent shall apply. Failure to comply with safety and health requirements may result in suspension of work. In the event of a perceived safety violation, NPS staff may stop work until the safety violation is addressed. In the event that NPS staff requests that Contractor personnel stop work due to a safety violation, contact the Contracting Officer immediately for a resolution.
- B. Onsite Safety Manager: Designate an authorized representative responsible for the following work. The authorized representative responsible for safety may also perform other duties.
 - 1. Implementing the accident prevention plan.
 - 2. Conducting daily safety meetings.
 - 3. Conducting safety inspections and reviews.
 - 4. Compiling and reviewing product safety data sheets (SDS) with personnel.
 - 5. Ensuring personnel are equipped with and wear proper personal protective equipment (PPE).
 - 6. Ensuring personnel comply with safety and health requirements.
 - 7. Ensuring personnel comply with the latest COVID-19 protocols.
 - 8. Investigation, reporting, and tracking accidents, injuries, or safety violations.
- C. Qualifications of Employees: Ensure the following for all Contractor personnel:
 - 1. Ensure personnel are physically able to perform their assigned duties in a safe manner.
 - 2. Do not allow personnel whose ability or alertness is impaired because of prescription or illegal drug use, fatigue, illness, intoxication, or other conditions that may expose themselves or others to injury to perform work.

3. Ensure operators of vehicles, hoisting equipment, and hazardous equipment shall be able to understand signs, signals, operating instructions, and be fully capable of operating such equipment. Retain copies of operator licenses and certifications onsite.
4. Provide adequate training to personnel to ensure prompt and efficient application of first aid.

PART 2 – PRODUCTS

2.1 FIRST AID

- A. General: Provide adequate first aid equipment for all contract employees for the hazards associated with the types of ongoing construction work at the site. NPS approval of first aid equipment is not required.

2.2 PERSONAL PROTECTIVE EQUIPMENT (PPE)

- A. General: Provide personal protective equipment (PPE) that meets applicable OSHA and ANSI standards for all contract employees. NPS approval of PPE is not required.

PART 3 – EXECUTION

3.1 DAILY SAFETY INSPECTIONS

- A. General: Conduct daily safety inspections and maintain safety reports.

3.2 EMERGENCY INSTRUCTIONS

- A. General: Display telephone numbers and reporting instructions for ambulance, physician, hospital, fire department, and police in conspicuous locations at work site.

3.3 FIRE & LIFE SAFETY

- A. General: Comply with requirements of the National Fire Protection Association (NFPA) 241 (Standards for Safeguarding Construction, Alteration, and Demolition Operations).

3.4 HAZARDOUS MATERIALS

- A. Hazardous Materials: Explosive, flammable, poisonous, corrosive, oxidizing, irritating, or otherwise harmful substances that could cause death or injury.
- B. Store hazardous materials in accordance with manufacturer's and OSHA Subpart D requirements. Display Material Safety Data Sheets (MSDS) in conspicuous locations at work site.
 1. Immediately report spills of hazardous materials to NPS Dispatch at: **808-985-6170**.
 2. Maintain a spill emergency response kit.
 3. Train employees how to respond to a spill and use emergency response kit.

3.5 PROTECTIVE EQUIPMENT

- A. General: Inspect personal protective equipment (PPE) daily and maintain in a serviceable condition. Clean, sanitize, and repair personal items as appropriate before issuing.
- B. Hard Hats: A hard hat use area shall be designated by the Contractor, as applicable. Hard hats shall be worn by all personnel in hard hat use areas. It is a Contractor's responsibility to require persons working at or visiting the jobsite to wear hard hats at all times.

3.6 SAFETY MEETINGS

- A. General: At a minimum, conduct weekly, if not daily, 15-minute "toolbox" safety meetings. These meetings shall be conducted by the Job Superintendent or a crew leader and be attended by all construction personnel at the worksite. Topics to coincide with work scheduled for the week. Document all safety meetings in the Quality Control (QC) Daily Report Form.

3.7 EMERGENCY MEDICAL & ACCIDENT REPORTING

- A. Emergency Medical & Accident Reporting: In the event of an emergency / medical incident, the Contractor shall **Dial 911** as needed. The Contractor shall also contact NPS Dispatch at: **808-985-6170** for any medical emergency, traffic accident, or personal injury occurring within the Park. NPS Dispatch is called so that the entrance station will be prepared should any emergency vehicles need to enter the park and so that any available Emergency Medical Services personnel in the park might respond until such time as the ambulance arrives.

END OF SECTION 01 35 23

SECTION 01 40 00 – QUALITY REQUIREMENTS

PART 1 – GENERAL

1.1 SUMMARY

- A. This section includes administrative and procedural requirements for quality assurance and quality control. The Contractor is responsible for all quality assurance and quality control to guard against defects and deficiencies of the work.

1.2 DEFINITIONS

- A. Quality Assurance: Activities, actions, and procedures performed before and during execution of the work to guard against defects and deficiencies and to substantiate that the proposed construction will comply with the requirements.
- B. Quality Control: Tests, inspections, procedures, and related actions during and after execution of the work to evaluate the actual products incorporated into the Work and to ensure that the completed construction complies with the requirements.
- C. Product Testing: Tests and inspections performed by 1) a Nationally Recognized Testing Laboratory (NRTL), 2) a National Voluntary Laboratory Accreditation Program (NVLAP), 3) a testing agency qualified to conduct product testing, or 4) a Contractor qualified to conduct product testing to establish product performance and compliance with industry standards.

1.3 CONFLICTING REQUIREMENTS

- A. Reference Standards: If compliance with two or more standards is specified, and those standards establish different or conflicting requirements, refer the conflicting requirements or uncertainties to the Contracting Officer for a determination before proceeding with the Work.
- B. Minimum Quality Level: Quality level shown or specified shall be the minimum provided or performed. Actual installation may comply exactly with the minimum quality specified, or it may exceed minimum quality within reasonable limits. Refer all uncertainties to the Contracting Officer for a determination before proceeding with the Work.

1.4 SUBMITTALS

- A. Quality Control Plan (QCP) – After contract award and before the Pre-Construction Meeting, submit a “site specific” quality control plan with the following information (at a minimum).
 - 1. Name of the onsite manager responsible for implementing the plan and ensuring quality.
 - 2. Organizational flow chart showing key contractor / subcontractor personnel.
 - 3. Qualifications of key staff with applicable training certificates and licenses.
 - 4. Contractor communications and reporting procedures / forms (to also include the NPS daily report form, RFI form, and CM-16 form).
 - 5. A list of project specific testing and inspection procedures at all phases of the work (i.e. preparatory, initial, follow-up) to ensure quality, with steps for correction of work / re-work.
 - 6. Qualifications of laboratory, agency, or Contractor performing product testing.

- B. Quality Control (QC) Daily Reports: Submit quality control daily reports documenting daily progress and the quality of work. The daily report shall be typed, legible, and complete and include representative and legible photos of that day's work. The daily report shall be submitted daily no later than the business day after the work was performed. The NPS prefers that the Contractor use the NPS daily report form. If the Contractor prefers to use their own form, it will be allowed if it contains all major sections / information from the NPS form.
- C. Testing and Inspection Data / Reports: Submit all completed testing and inspection data / reports for approval prior to advancing the Work on subsequent phases. If a testing or inspection report indicates the Work does not meet the requirements, submit remedial actions for approval within one (1) calendar day from receiving the results, and do not advance the Work until this issue is resolved in writing.

1.5 QUALITY ASSURANCE

- A. General: Comply with the contract documents and contract clauses related to quality. In cases of conflicts between Federal, State, and local quality requirements, the most stringent shall apply. Failure to comply with quality requirements may result in suspension of work.
- B. Onsite Quality Manager: Designate an authorized representative responsible for the following work. The authorized representative responsible for quality may also perform other duties.
 - 1. Implementing the quality control plan.
 - 2. Conducting quality inspections and reviews.
 - 3. Compiling and reviewing product testing and inspections with quality personnel.
 - 4. Ensuring all personnel comply with quality requirements.
 - 5. Completing and submitting QC Daily Reports in a timely manner.
 - 6. Completing and submitting all other submittals in a timely manner.

1.6 QUALITY CONTROL

- A. General: The Contractor is responsible for testing and inspections as identified in the contract documents. Test and inspect the work as needed to ensure that the quality of materials, workmanship, construction, finish, and functional performance comply with applicable specifications, drawings, permit requirements, and as required by the local Building Code.

PART 2 – PRODUCTS (Not Used)

PART 3 – EXECUTION

3.1 OFF-SITE CONTROL

- A. General: Items fabricated off-site shall be inspected for quality control at place of fabrication.

3.2 ON-SITE CONTROL

- A. Preparatory Phase: Prior to beginning each feature of the work:
 - 1. Review submittal requirements with personnel directly responsible for quality assurance and quality control of the work.

2. Review applicable specification sections and drawings related to the featured work.
3. Ensure copies of referenced standards related to testing and inspections are available onsite.
4. Ensure provisions have been made for field control testing.
5. Examine work area to ensure preliminary work has been completed.
6. Verify field dimensions and advise the Contracting Officer of any uncertainties or discrepancies with the contract documents.
7. Ensure necessary equipment and materials are at the project site and they comply with the approved material submittals and shop drawings (if applicable).
8. Document preparatory phase activities in the Quality Control (QC) Daily Report.

B. Initial Phase: As soon as work begins:

1. Test and inspect representative portions of a particular feature of work for quality of workmanship. Document type and locations of all tests and inspections.
2. Review control testing procedures to ensure compliance with the contract requirements.
3. Document initial phase activities in the Quality Control (QC) Daily Report.

C. Follow-Up Phase: As work progresses:

1. Ensure compliance with contract requirements until completion and acceptance of work.

3.3 ENFORCEMENT

- A. The Contractor shall stop work on any item or feature pending the satisfactory correction of the deficiency noted by the Contracting Officer.

3.4 REPAIR AND PROTECTION

- A. General: Upon completion of field testing or sampling, repair damaged construction and restore substrates and finishes. Protect construction exposed by or for quality control activities.

END OF SECTION 01 40 00

QC DAILY REPORT FORM - NATIONAL PARK SERVICE (NPS)

Date of Report: Day, Date

Report Submitted By: Name of Person

CONTRACT INFORMATION						
Park:		Contract No.		Project Title:		
Prime Contractor:		Onsite Job Superintendent:		Subcontractor(s) Onsite:		Vendor Deliveries:
NPS Contracting Officer:		Contracting Officer's Rep (COR):		NPS Inspector(s) / Monitor(s):		Official Visitor(s) to Site:
WEATHER REPORT						
Conditions (AM)	Conditions (PM)	Min. Temp	Max. Temp	Rainfall (in.)	Weather Delays or Disruptions:	
SITE CONDITIONS						
Jobsite / Housekeeping:		Conflict(s) with NPS Operations:		Utility Disruptions:		Subsurface Conditions / Digging:
LABOR POOL / PERSONNEL				HEAVY EQUIPMENT		
Employees by Job Category or by Crew:	Prime	Sub.	Hours	Heavy Equipment by Type:	Hours Operating	Hours Idle
Total Labor Hours:				Total Equipment Hours:		
SUMMARY of DAILY WORK (Attach Representative Photos of the Daily Work Progress)						
INSPECTIONS / TESTING						
PLANNED WORK / UPCOMING MILESTONES						
URGENT ITEMS for DISCUSSION						

SECTION 01 50 00 – TEMPORARY FACILITIES & CONTROLS

PART 1 – GENERAL

1.1 SUMMARY

- A. This section includes requirements for temporary facilities & controls.

1.2 QUALITY ASSURANCE / REGULATORY

- A. General: Comply with the latest edition of applicable codes, regulations, and standards when installing temporary facilities & controls.
- B. Temporary Water & Wastewater Services: Comply with:
 - 1. Hawaii: State of Hawaii, Department of Health (DOH), Hawaii Administrative Rules (HAR).
 - 2. Pacific Island Territories (Guam, Saipan, American Samoa): EPA Region 9.
- C. Temporary Potable Water Services: All materials in contact with potable water must be NSF/ANSI-61 certified.
- D. Hydrotesting & Disinfection Water: For hydrotesting and disinfection of potable water systems, comply with applicable sections from the American Water Works Association (AWWA) Standards as well as the Authority Having Jurisdiction (AHJ) regarding pollution prevention.
- E. Temporary Erosion and Sediment Control: Refer to Section 01 57 23.
- F. Temporary Electrical Service: Install service to comply with the International Electric Code.
- G. Temporary Fire Protection Services: Install service to comply with the National Fire Protection Association (NFPA) Code.
- H. Telecommunications: Install service to comply with regulations from the local service provider.
- I. Pedestrian Access Routes: Install temporary routes to comply with the Architectural Barriers Act Accessibility Standards (ABAAS) if the affected pedestrian access route is currently accessible.
- J. Temporary Traffic Control Devices: Install temporary traffic control devices to comply with the Manual on Uniform Traffic Control Devices (MUTCD).

1.3 SUBMITTALS

- A. Specified / Proposed Products: All products specified or proposed by the Contractor for use as temporary facilities & controls shall be submitted for approval per Section 01 33 23.

PART 2 – PRODUCTS

2.1 TEMPORARY MATERIALS

- A. General: Temporary materials may be new or used but they must be adequate for the usage; they must not create an unsafe condition; and they must not violate the requirements of applicable codes, regulations, and standards. Submit temporary materials for approval per Section 01 33 22.
- B. Temporary Utilities (Potable Water, Non-Potable Water, Fire Protection, Wastewater, Electrical Power, HVAC, Security, Alarms, Notifications, Internet and Telecommunications): Varies depending on utility type. Comply with PART 1.2 Quality Assurance / Regulatory. Refer also to Divisions 03-48, where applicable.
- C. Telecommunications: Varies depending on local service provider.
- D. Temporary Erosion and Sediment Control Devices: Refer to Section 01 57 23.
- E. Temporary Safety Barrier Fence: Orange plastic fence, 4-feet height minimum, secured to self-supporting posts or steel posts driven into the ground no greater than 6-feet apart. If posts are driven into the ground, comply with Section 01 11 40, PART 3.4 (Archaeological Resources).
- F. Temporary Barrier Tape: Yellow tape imprinted with "CAUTION: CONSTRUCTION AREA," manufactured by Reef Industries, Inc. Houston, Texas, or approved equal.
- G. Temporary Site Enclosure Fence: Chain link, galvanized steel, 6-feet height minimum, secured to top and bottom rails and self-supporting posts with concrete bases.
- H. Temporary Barrier or Partition: Plywood secured to lumber with nails, screws, or fasteners.
- I. Temporary Traffic Control Devices: Varies depending on project scope and site. Comply with PART 1.2 Quality Assurance / Regulatory.
- J. Lumber and Plywood: Refer to Division 06.
- K. Concrete: Refer to Division 03.
- L. Asphaltic Concrete (AC) Pavement: Refer to Division 32.

2.2 TEMPORARY EQUIPMENT

- A. General: Temporary equipment may be new or used but it must be adequate for the usage; it must not create an unsafe condition; and it must not violate the requirements of applicable codes, regulations, and standards. Submit temporary equipment for approval per Section 01 33 22.
- B. Fire Extinguishers: Portable, UL rated, with class and extinguishing agent as required by locations and classes of fire exposures.

2.3 TEMPORARY FACILITIES

- A. General: Temporary facilities may be new or used but they must be adequate for the usage; they must not create an unsafe condition; and they must not violate the requirements of applicable codes, regulations, and standards. Submit temporary materials for approval per Section 01 33 22.

- B. Temporary Toilets: Sufficiently lighted, ventilated, weatherproof, ADA-accessible toilet facilities with sturdy enclosures, privacy locks, and anti-bacterial hand sanitizer.

2.4 TEMPORARY ITEMS (GOVERNMENT-FURNISHED)

- A. General: Refer to Summary of Work Section 01 11 00, PART 1.5 for a list of government-furnished items.

PART 3 – EXECUTION

3.1 INSTALLATIONS

- A. General: Install temporary facilities & controls as noted in the contract documents, per regulatory guidance, or as instructed by the Contracting Officer.
- B. Temporary Utilities (Potable Water, Non-Potable Water, Fire Protection, Wastewater, Electrical Power, HVAC, Security, Alarms, Notifications, Internet and Telecommunications): Install temporary utility service in compliance with applicable codes, regulations, and standards.
- C. Temporary Erosion and Sediment Control Devices: Refer to Section 01 57 23.
- D. Temporary Toilets: Provide a sufficient number of toilets for Contractor personnel, NPS staff, and park visitors, as applicable. If toilets are to be used by NPS staff and/or park visitors, provide separate toilet facilities for men and women. The Contractor shall pump the toilets frequently and keep the toilets clean so as not to attract insects or animals.
- E. Temporary Field Offices: Establishment of a construction camp within the park will not be permitted. The park will make every attempt to furnish the contractor with indoor office space for up to two (2) contractor personnel; however, if the park cannot accommodate the Contractor with office space, the Contractor will be allowed to setup a temporary field office within the project area limits (final location to be approved by the park facility manager).
- F. Temporary Storage Space: The construction of storage sheds will not be allowed at the project site. If interior storage or covered space is required to protect materials and equipment, the park will attempt to provide a space for temporary use. The use of Contractor-furnished shipping containers may be allowed at the project site at the discretion of the Contracting Officer.
- G. Temporary Safety Barriers: For controlled sites, the Contractor shall construct and maintain a safety barrier fence marked with barrier tape to discourage people from entering the project site. Note that the Contractor is responsible for safety and accident prevention at the jobsite.
- H. Temporary Site Enclosures: For uncontrolled sites, the Contractor shall construct and maintain a site enclosure fence, barrier, or partition to prevent people and animals from entering the project site except by locked gates or doors. Note that the Contractor is responsible for safety and accident prevention at the jobsite.
- I. Pedestrian Access Routes: Construct and maintain temporary pedestrian access routes as outlined in the contract documents while the primary pedestrian access routes are under construction.

- J. Vehicle Traffic Access Routes: Construct and maintain temporary roads and paved areas as outlined in the contract documents while the primary vehicle access routes are under construction.
- K. Temporary Traffic Controls: The Contractor shall erect and maintain barricades, danger signals, and warning signs in compliance with applicable codes and standards. The Contractor shall provide adequate traffic control, including flaggers on either side of any work performed in the road. Any workers on or near the road must wear highly visible, bright clothing.
- L. Construction Waste Management: Refer to Section 01 74 19.

END OF SECTION 01 50 00

SECTION 01 57 23 – TEMPORARY STORMWATER POLLUTION PREVENTION

PART 1 – GENERAL

1.1 SUMMARY

- A. This section includes requirements for temporary stormwater pollution prevention and implementing measures to prevent the discharge of pollutants during construction activities.

1.2 REGULATIONS

- A. The Clean Water Act prohibits anybody from discharging “pollutants” through a “point source” into a “water of the United States” unless they have a NPDES permit. The permit will contain limits on what you can discharge, monitoring and reporting requirements, and other provisions to ensure that the discharge does not hurt water quality or people’s health.
- B. The National Park Service (NPS) standards and guidelines requires that water quality be protected at all times to ensure compliance with the Organic Act.

1.3 DEFINITIONS

- A. Pollutant - The term pollutant is defined very broadly in the Clean Water Act. It includes any type of industrial, municipal, and agricultural waste discharged into water. Some examples include dredged soil, solid waste, incinerator residue, sewage, garbage, sewage sludge, munitions, chemical wastes, biological materials, radioactive materials, heat, wrecked or discarded equipment, rock, sand, cellar dirt, and industrial, municipal, and agricultural waste.
- B. Point Source – The term point source is also defined very broadly in the Clean Water Act. It means any discernible, confined and discrete conveyance, such as a pipe, ditch, channel, tunnel, conduit, discrete fissure, or container. It also includes vessels or other floating craft from which pollutants are or may be discharged.
- C. National Pollution Discharge Elimination System (NPDES) – A permit program that addresses water pollution by regulating point sources that discharge pollutants to waters of the United States. Created in 1972 by the Clean Water Act, the NPDES permit program is authorized to state governments by EPA to perform many permitting, administrative, and enforcement aspects of the program.
- D. Under-Acre Pollution Prevention Plan (UPPP) - A stormwater management plan that is developed and implemented to protect waters of the United States from pollutants during construction activities that disturb less than one (1) acre of total land area.
- E. Stormwater Pollution Prevention Plan (SWPPP) – A stormwater management plan that is developed and implemented to protect waters of the United States from pollutants during construction activities that disturb one (1) acre or more of total land area.

1.4 AUTHORIT(IES) HAVING JURISTITION

- A. General: Comply with the standards and regulations of the Authority Having Jurisdiction (AHJ).
- B. Authority Having Jurisdiction: The following are the AHJ for the Pacific Island National Parks:
 - 1. Hawaii: State of Hawaii, Department of Health (DOH), Clean Water Branch (CWB).
<https://health.hawaii.gov/cwb/general-permits/>
 - 2. Pacific Island Territories (Guam, Saipan, American Samoa): EPA Region 9
<https://www.epa.gov/npdes-permits>

1.5 NPDES GENERAL PERMITS OVERVIEW (STATE OF HAWAII)

- A. General Permits are NPDES permits issued by the State of Hawaii, Department of Health, Clean Water Branch for a specific type of activity or discharge. General permits can only cover the types of activities or discharges specified in that specific general permit. If a facility or project has multiple types of discharges, an applicant may separately request coverage under multiple general permits for their facility or project (e.g., applicant may request coverage for construction storm water and dewatering discharges). If a discharge or activity does not have a general permit that covers the discharge, the applicant must apply for an individual NPDES permit.
- B. List of NPDES General Permits – Below is a list of NPDES general permits in the State of Hawaii applicable to work in NPS units with a brief description of their authorized discharges:
 - 1. Discharges of Storm Water Associated with Construction Activities - NPDES permit coverage is required for activities that disturb one (1) acre or more of total land area. Land disturbance includes, but is not limited to, clearing, grubbing, grading, excavation, demolition (even if leaving foundation), uprooting of vegetation, equipment staging on grassed areas or bare ground, equipment staging on paved roadway (only if area blocked off from public usage), storage areas, and roadway work that touches the base course.
 - 2. Discharges of Hydrotesting Waters – NPDES permit coverage is required for the release or discharge of hydrotesting waters to State waters. “Hydrotesting Waters” means water used to test the integrity of a tank or pipeline, pipeline disinfection, and/or pipeline flushing.
 - 3. Discharges Associated with Construction Activity Dewatering – NPDES permit coverage is required for discharges to State waters of construction activity dewatering effluent. “Dewatering Effluent” is any type of water (e.g. ground water, storm water, stream water, ocean water, etc.) pumped from a construction area.
 - 4. Discharges of Treated Process Wastewater Associated with Well Drilling Activities – NPDES permit coverage is required for discharges to State waters of treated process wastewater associated with well drilling activities. Treated process wastewater includes well drilling slurries, lubricating fluids wastewaters, and well purge wastewaters.

1.6 SUBMITTALS / REQUIREMENTS

- A. General: Complete and submit the applicable submittals or complete the applicable requirements after contract award and prior to contract Notice to Proceed (NTP).
- B. Projects with No Land Disturbance (Indoors) – NO SUBMITTALS REQUIRED.
- C. Projects with Land Disturbance of less than one (1) acre: Complete and submit the following submittals to NPS (only) for review and acceptance.

- 1. Under-Acre Pollution Prevention Plan (UPPP). The NPS UPPP Template can be found at: https://www.nps.gov/dscw/precon_act113.htm

- D. Projects with Land Disturbance of one (1) acre or more in the State of Hawaii with an existing and valid NPDES general permit (Refer to Section 1.5 above), complete the following:

To be eligible for NPDES general permit coverage, an activity / discharge must be able to:

- 1. Meet any eligibility requirements (such as restrictions / prohibitions on coverage);
 - 2. Comply with all terms / requirements of the specific general permit;
 - 3. Comply with any pre-request requirements in the specific general permit such as the creation and completion of any required pollution plans (e.g. Storm Water Pollution Prevention Plan as required by Appendix C).
 - 4. Comply with the standard general permit conditions contained in Hawaii Administrative Rules (HAR) Chapter 11-55 Appendix A; and
 - 5. Report any unpermitted / unauthorized discharges to the Clean Water Branch and complete compliance with any enforcement action as a result, prior to seeking general permit coverage.

To request coverage under a general permit, the Contractor must complete / submit the following to the State of Hawaii, Department of Health (DOH), Clean Water Branch (CWB):

- 1. Notice of Intent (NOI) to the CWB e-Permitting Portal, and;
 - 2. Other as requested by the CWB.

- E. Projects with Land Disturbance of one (1) acre or more in the Pacific Island Territories (Guam, Saipan / Commonwealth of the Northern Marianas Islands, American Samoa), or, in the State of Hawaii (for an activity or discharge not covered by a NPDES general permit), secure a NPDES individual permit with the Authority Having Jurisdiction (AHJ). The NPS contract Period of Performance will be adjusted to reflect the additional time needed to secure a NPDES permit. A NPDES individual permit typically involves submittal of the following:

- 1. Notice of Intent (NOI).
 - 2. NPDES Individual Permit Application.
 - 3. Storm Water Pollution Prevention Plan (SWPPP).
 - 4. Notice of Termination (NOT).

1.7 QUALITY ASSURANCE

- A. General: Comply with the applicable pollution prevention plan and the requirements of the AHJ.

- B. Onsite Manager: Designate an authorized representative responsible for pollution prevention including the duties outlined below. The authorized representative may perform other duties.
 - 1. Implementing the applicable pollution prevention plan.
 - 2. Ensuring all stormwater, erosion control, and pollution prevention devices and measures, aka Best Management Practices (BMP), comply with Work Restrictions Section 01 11 40.
 - 3. Properly installing BMP devices and measures.
 - 4. Conducting daily checks on BMP devices and measures and adjusting BMPs as needed.
 - 5. Ensuring all personnel comply with the applicable pollution prevention plan and are familiar with the BMP devices and measures.
 - 6. Removing all BMP devices and measures after final inspection / acceptance.

PART 2 – PRODUCTS

2.1 BEST MANAGEMENT PRACTICES (BMP) DEVICES & MEASURES

- A. General: Furnish and install the required stormwater, erosion control, and pollution prevention devices and measures, aka Best Management Practices (BMP), as outlined in the pollution prevention plan or as required by the AHJ. All devices shall comply with Section 01 11 40. Submit BMP devices for approval per Section 01 33 23.

PART 3 – EXECUTION

3.1 REGULATORY REQUIREMENTS

- A. General: Comply with the requirements of the Authority Having Jurisdiction (AHJ) and associated permit conditions.

3.2 PROTECT PARK RESOURCES

- A. General: Comply with the Work Restrictions Section 01 11 40 for all stormwater, erosion control, and pollution prevention BMP devices. If the recommended BMP devices or measures have the potential to damage the park's natural, cultural, historical, or archaeological resources, the NPS will suggest strategies to mitigate or prevent damage to these resources. The Contractor shall include these mitigation strategies in the applicable pollution prevention plan.

3.3 POLLUTION PREVENTION

- A. General: The Contractor shall execute the following:
 - 1. Implement the applicable pollution prevention plan.
 - 2. Ensure all stormwater, erosion control, and pollution prevention devices and measures, aka Best Management Practices (BMP), comply with Work Restrictions Section 01 11 40.
 - 3. Implement mitigation strategies to prevent resource damage from BMP devices or measures.
 - 4. Properly install BMP devices and measures. The park's archaeological monitor may wish to be present for BMP installation involving ground disturbance.
 - 5. Conduct daily checks on BMP devices and measures and adjust BMPs as needed, especially after storm events.

6. Conduct daily checks on BMP devices and measures to ensure compliance with Safety Requirements Section 01 57 23.
7. Ensure all personnel comply with the applicable pollution prevention plan and are familiar with the BMP devices and measures.
8. Ensure all construction operations remain within the Project Area Limits.
9. Complete all work within the dry season or dry periods when possible.
10. If a discharge occurs or if the project receives a written notice or order from a regulatory agency, the Contractor shall immediately notify the Contracting Officer and shall file a written report to the AHJ within 7 days of the discharge event, notice, or order. Corrective measures shall be implemented immediately following the discharge, notice, or order.
11. Properly dispose of any entrapped sediment from within or behind BMP devices or measures.
12. Manage hazardous waste in accordance with Federal, State, and local regulations.
13. Remove all BMP devices and measures after final inspection.

END OF SECTION 01 57 23

SECTION 01 67 00 – PRODUCT REQUIREMENTS

PART 1 – GENERAL

1.1 SUMMARY

- A. This section includes administrative, procedural, and regulatory requirements for the selection of products for use on the project; product delivery, storage, handling, packaging; and manufacturer's standard warranties on products.

1.2 DEFINITIONS

- A. Products: Items purchased for incorporating into the Work, whether purchased for the project or taken from previously purchased stock. The term "product" includes "material," "equipment," "system," and terms of similar intent.
- B. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature.
- C. New Products: Items that have not previously been incorporated into another project or facility.
- D. Comparable Product: Product demonstrated and approved through the submittal process, or where indicated as a product substitution to have indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other salient characteristics that equal or exceed those of the specified or named product.
- E. Chain-of-Custody: Process whereby a product is maintained under physical possession or control during its entire life cycle.
- F. Government-Furnished Materials: Refer to Section 01 11 00, PART 1.5.

1.3 REGULATORY

- A. Buy American Products: Comply with contract clause 52.225-1.
[52.225-1 Buy American-Supplies | Acquisition.GOV](#)
- B. Environmentally Preferable Purchasing: Comply with the USEPA, Final Guidance on Environmentally Preferable Purchasing.
[Final Guidance on Environmentally Preferable Purchasing | US EPA](#)

1.4 SUBMITTALS

- A. Specified Products: All products specified in the contract documents or as a result of the Request for Information (RFI) process shall be submitted for approval per Section 01 33 23.
- B. Material Safety Data Sheets (MSDS): For each product required by OSHA to have MSDS, ensure MSDS are posted during the Work.

- C. Installed Products: All approved products furnished and installed on the project shall be submitted per Section 01 77 00.
- D. Manufacturer's Warranties: All manufacturer's warranties for products furnished and installed on the project shall be submitted per Section 01 77 00.

1.5 QUALITY ASSURANCE

- A. Compatibility: If the Contractor is given the option of selecting between two or more products for use on the project, the product selected shall be the most compatible with the existing conditions or systems. Refer all conflicting requirements or uncertainties to the Contracting Officer for a determination before proceeding with the Work.

1.6 PRODUCT DELIVERY, HANDLING, AND STORAGE

- A. General: Deliver, handle, and store products using means and methods that prevent damage, deterioration, loss, and theft during the entire chain-of-custody period.
- B. Delivery and Handling:
 - 1. Comply with manufacture's written instructions on delivery and handling of products.
 - 2. Schedule delivery of products to minimize long-term storage at the project site.
 - 3. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or vulnerable to deterioration, loss, or theft.
 - 4. Comply with Section 01 11 40 for inspection of products for invasive species.
 - 5. Deliver products to the project site in an undamaged condition; in the manufacturer's original sealed container or other packaging system; complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
 - 6. Inspect products upon delivery to ensure compliance with the Contract Documents. Ensure products are undamaged and properly protected.
- C. Storage:
 - 1. Comply with manufacture's written instructions on the storage of products.
 - 2. Store products vulnerable to deterioration, loss, or theft in secure, weather tight enclosures above ground with ventilation adequate to prevent condensation.
 - 3. Store products vulnerable to damage from insects and vermin in insect-proof enclosures.
 - 4. Store cementitious products on protected and elevated platforms away from moisture.
 - 5. Comply with manufacture's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage of products.
 - 6. Store loose granular products in well-drained areas on solid surfaces to prevent mixing with foreign matter and debris.

1.7 PRODUCT PACKAGING

- A. General: Minimize packaging as defined in ASTM D5834. Maximize recycling procedures as outlined in ASTM D5834. Comply with Section 01 74 19.

PART 2 – PRODUCTS

2.1 SPECIFIED PRODUCTS:

- A. General: Furnish and install all products specified in the contract documents or as a result of the Request for Information (RFI) process. All products shall be new unless otherwise specified.

2.2 COMPARABLE PRODUCTS:

- A. General: The Contracting Officer will consider a Contractor's request for comparable products if the following conditions are satisfied.
 - 1. The comparable product does not require revisions to the contract documents.
 - 2. The comparable product is similar or better in quality to the specified product.
 - 3. The comparable product is compatible with other portions of the Work.
 - 4. The comparable product meets the Buy American Act provisions.
 - 5. The comparable product provides a manufacturer's warranty.
 - 6. The comparable product is new.

2.3 GOVERNMENT-FURNISHED MATERIALS

- A. General: Refer to Summary of Work Section 01 11 00, PART 1.5.

PART 3 – EXECUTION

3.1 INSTALLATION:

- A. General: Install all products and materials per the contract documents and the manufacturer's recommendations. Refer all conflicting requirements or uncertainties to the Contracting Officer for a determination before proceeding with the Work.

3.2 PROTECTION:

- A. General: Provide adequate coverings and accommodations as necessary to protect installed products and materials from damage by natural elements, traffic, and subsequent construction. Remove coverings when no longer needed.

END OF SECTION 01 67 00

SECTION 01 73 40 – EXECUTION

PART 1 – GENERAL

1.1 SUMMARY

- A. This section includes general procedural requirements governing execution of the Work including:
 - 1. Examination.
 - 2. Coordination with Local Utility Service Providers.
 - 3. Preparation.
 - 4. Construction Layout and Documentation.
 - 5. Field Engineering.
 - 6. Installation.
 - 7. Starting and Adjusting.
 - 8. Protection of Installed Construction.
 - 9. Correction of the Work.
 - 10. Progress Cleaning.

1.2 SUBMITTALS

- A. Job Superintendent: The Contractor shall submit the names, duties, and responsibilities of the primary and backup Job Superintendent for approval per Section 01 33 23.
- B. Field Surveying Data: For field surveys conducted to confirm compliance with the contract documents, submit field surveying data per Section 01 33 23.
- C. Field Engineering Data: For field engineering conducted to confirm compliance with the contract documents, submit field engineering data per Section 01 33 23.

1.3 QUALITY ASSURANCE

- A. Job Superintendent: The Contractor shall appoint a Job Superintendent responsible for the overall project execution. The Job Superintendent shall be always present at the jobsite during the Work. The Contractor may appoint a backup Job Superintendent to fill in for the primary Job Superintendent during emergencies or temporary offsite duties and responsibilities.
- B. Land Surveyor Qualifications: Where applicable, the Contractor shall hire a professional land surveyor legally qualified to practice in jurisdiction where project is located for all Work.
- C. Engineer Qualifications: Where applicable, the Contractor shall hire a professional engineer legally qualified to practice in jurisdiction where project is located for all Work.

PART 2 – PRODUCTS (Not Used)

PART 3 – EXECUTION

3.1 EXAMINATION:

- A. Existing Conditions: Before beginning the Work, examine and verify that the existing conditions from the contract documents are correct.
- B. Existing Utilities: Before beginning the sitework, examine and verify the existence and location of all utilities to be impacted by the Work (including water, wastewater, stormwater, fire protection, electrical power, and telecommunications).
- C. Existing Facilities: Before beginning any work to facilities, verify condition of substrates, components, and systems for dimensions, tolerances, and other conditions affecting performance.
- D. Cutting & Patching: Before performing cutting and patching operations, examine surfaces to be cut and patched and conditions under which cutting and patching are to be performed.
- E. Acceptance of Conditions: Proceed with the Work only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates Contractor acceptance of existing conditions.

3.2 COORDINATION WITH LOCAL UTILITY PROVIDERS:

- A. General: If the contract documents specify work to, or affecting, a utility that is owned and/or managed by a local utility service provider, contact the local utility service provider sufficiently in advance of the Work to arrange any necessary permits, notification, or coordination.

3.3 PREPARATION:

- A. Field Measurements: Take field measurements as required to fit Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
- B. Space Requirements: Verify space requirements and dimensions of items shown on the drawings.
- C. Cutting & Patching: Protect in-place construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portion of the project that might be exposed during cutting and patching operations.
- D. Differing Site Conditions: Refer all conflicting requirements or uncertainties from differing site conditions to the Contracting Officer for a determination before proceeding with the Work.

3.4 CONSTRUCTION LAYOUT & DOCUMENTATION:

- A. Verification: Verify layout information shown on drawings before proceeding with the Work. Refer all discrepancies to the Contracting Officer for a determination.
- B. Construction Layout: Where precision and accuracy are vital to project execution, engage a professional land surveyor licensed to practice in the project area to layout the construction. Establish benchmarks and control points in less conspicuous locations without damaging resources. The park's archaeological monitor may wish to be present for any ground disturbance.

- C. Construction Documentation: Where precision and accuracy are vital to project documentation, engage a professional land surveyor licensed to practice in the project area to complete the as-constructed surveying and mapping required in Section 01 77 00.

3.5 FIELD ENGINEERING:

- A. Verification: Verify the technical requirements shown on the drawings before proceeding with the Work. Refer all discrepancies to the Contracting Officer for a determination.
- B. Field Engineering: Where confirmation of the requirements is vital to project execution, engage a professional engineer licensed to practice in the project area to confirm the requirements.

3.6 INSTALLATION:

- A. General: The Contractor is responsible for the correct installation of the Work.
- B. Location: Locate Work and components of Work accurately in correct alignment and elevation.
 - 1. Make vertical work plumb and make horizontal work level unless otherwise specified.
 - 2. Where space is limited, install components to maximize space available for future operation, maintenance, and component replacement.
 - 3. Conceal pipes, ducts, and wiring in finished areas, unless otherwise indicated.
- C. Instructions: Comply with the manufacturer's written instructions for installing products.
- D. Scheduling: Install products at the time, and under conditions, for the best possible results. Maintain conditions required for product performance until final acceptance.
- E. Loading: Conduct construction operations so that no part of the Work is subjected to loading in excess of that expected during normal conditions of occupancy.
- F. Tool & Equipment: Do not use tools and equipment that produce harmful noise or air quality.
- G. Anchors & Fasteners: Provide anchors and fasteners as required to anchor each component securely in place.
- H. Cutting & Patching: Employ skilled workers to perform cutting and patching. Cut using methods least likely to damage elements retained or adjoining construction. Patch as required to restore surfaces to original condition. Clean areas and spaces where cutting and patching was performed and remove all excess paint, mortar, oils, putty, and similar patching materials.
- I. Joints: Make joints a uniform width. Where joint locations in exposed areas are not indicated, arrange joints for best visual effect. Fit exposed connections together to form hairline joints.
- J. Hazardous Materials: Use products, cleaners, and installation materials not considered hazardous.

3.7 STARTING & ADJUSTING:

- A. Starting: Start equipment and operating components to confirm proper operation. Remove malfunctioning units; troubleshoot if necessary; replace with new units; and retest.
- B. Adjusting: Adjust operating components and equipment for proper operation.
- C. Testing: Test each piece of equipment to verify proper operation. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- D. Manufacturer's Field Service: If components or equipment fail to operate correctly, or if specified in the contract documents, employ a factory-authorized service representative to inspect, troubleshoot, start, adjust, test, and repair field-assembled components and equipment.

3.8 PROTECTION OF INSTALLED CONSTRUCTION:

- A. Protection: Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at the time of final acceptance.
- B. Instructions: Comply with the manufacturer's written instructions for temperature and relative humidity.

3.9 CORRECTION OF THE WORK:

- A. Defects: Repair or remove and replace the defective construction. Restore damaged substrates and finishes.
- B. Restorations: Restore permanent facilities used during construction to the specified condition.
- C. Damaged Surfaces: Remove and replace the damaged surfaces exposed to view if surfaces cannot be repaired without visible evidence of repair.
- D. Damaged Components: Repair components that do not operate properly. Remove and replace operating components that cannot be repaired.
- E. Damaged Glass: Remove and replace chipped, scratched, and broken glass or reflective surfaces.

3.10 PROGRESS CLEANING:

- A. General: Keep project site, work areas, and common areas clean and free from waste, debris, excess materials, tools and equipment, which can negatively impact project execution. Clean work areas multiple times daily. Dispose of waste properly and regularly.

END OF SECTION 01 73 40

SECTION 01 74 19 – CONSTRUCTION WASTE MANAGEMENT & DISPOSAL

PART 1 – GENERAL

1.1 SUMMARY

- A. This section includes administrative and procedural requirements for managing, salvaging, recycling, and disposing nonhazardous waste and debris from demolition and construction operations.

1.2 DEFINITIONS

- A. Demolition Waste: Building and site improvement materials resulting from demolition or selective demolition operations.
- B. Construction Waste: Building and site improvement materials, packaging, and other solid waste resulting from construction, remodeling, renovation, or repair operations.
- C. Green Waste: Vegetative and organic matter such as grass, sod, roots, branches, and trees resulting from grubbing, clearing, cutting, and trimming operations.
- D. Garbage: Refuse and food scraps resulting from preparation, cooking, dispensing, and consumption of food.
- E. Solid Waste: Garbage, sludge, or other solid discharged material (except hazardous waste) resulting from domestic, industrial, or commercial operations.
- F. Debris: Nonhazardous waste generated during demolition or construction operations. Debris can also result from building materials and natural materials such as rock, sediment, trees, etc. dispersed on a landscape by natural processes such as floods, storms, typhoons, hurricanes, etc.
- A. Hazardous Materials: Explosive, flammable, poisonous, corrosive, oxidizing, irritating, or otherwise harmful substances that could cause death or injury. Materials regulated as a hazardous material in accordance with 49 CFR 173 (Code of Federal Regulations), requires a Material Safety Data Sheet (MSDS) in accordance with 29 CFR 1910.1200, or which during end use, treatment, handling, storage, transportation or disposal meets, has components which meet, or have the potential to meet the definition of Hazardous Waste in accordance with 40 CFR 261.
- G. Salvaging: Recovery of intact demolition or construction waste for subsequent processing in preparation for reuse, either on the subject project or a future project.
- H. Recycling: Recovery of demolition or construction waste materials or components for subsequent processing in preparation for reuse, either on the subject project or a future project.
- I. Disposal: Removal of demolition and construction waste, green waste, garbage, solid waste, and debris to an off-site landfill or waste hauling facility acceptable to authorities having jurisdiction.

1.3 PERFORMANCE REQUIREMENTS

- A. General: The Contractor shall minimize the creation of waste from the project. Factors contributing to the waste stream include over packaging, improper storage, ordering errors, poor planning, breakage, mishandling, and contamination. Minimize waste disposal in landfills.
- B. Hazardous Materials: If waste materials encountered during demolition or construction are found to contain lead, asbestos, polychlorinated biphenyls (PCBs) such as fluorescent lamp ballasts, or other harmful substances, they are to be handled and removed in accordance with local, state, and federal laws and requirements concerning hazardous waste.

1.4 SUBMITTALS

- A. Construction Waste Management Plan – After contract award and before the Pre-Construction Meeting, submit a “site specific” construction waste management plan that addresses the onsite storage, handling, salvaging, recycling, and disposal of demolition waste, construction waste, green waste, garbage, solid waste, debris, and hazardous materials generated on the project, as applicable. If the Contractor proposes to salvage existing materials and reuse on the current project, the salvageable materials and the proposed treatment to make them fit for reuse must be outlined in the construction waste management plan for consideration. For disposal items, identify the landfill or waste hauling facility where the waste items will be disposed.

1.5 QUALITY ASSURANCE

- A. Onsite Waste Manager: Designate an authorized representative responsible for the following work. The authorized representative responsible for waste may also perform other duties.
 - 1. Implementing the construction waste management plan.
 - 2. Ensuring adequate onsite storage containers protected from the weather and animals.
 - 3. Ensuring personnel are keeping the jobsite clean at all times.
 - 4. Ensuring personnel are regularly disposing of waste and debris.
 - 5. Ensuring onsite waste storage containers are regularly emptied at the waste hauling facility.
 - 6. Ensuring the proper handling of items identified for salvaging and recycling.
 - 7. Ensuring personnel are familiar with the MSDS of hazardous materials.
 - 8. Ensuring the proper storage, handling, and disposal of hazardous waste.

PART 2 – PRODUCTS

2.1 ONSITE WASTE STORAGE CONTAINERS

- A. General: Provide separate containers for the storage and handling of items to be salvaged, recycled, disposed, and composted (green waste). Storage containers shall be protected from the weather and animals. Storage containers for solid waste shall not leak. Provide containers for the storage and handling of hazardous waste in accordance with the Authority Having Jurisdiction (AHJ). Storage containers shall be located near the project site to encourage use and for equipment access, but preferably hidden from view of the park visitor where possible.

2.2 HAZARDOUS MATERIALS SPILL EMERGENCY RESPONSE KIT

- B. General: Furnish and maintain a hazardous materials spill emergency response kit at the project site at all times for known or suspected hazardous materials. NPS approval of hazardous materials spill response kit is not required.

PART 3 – EXECUTION

3.1 TRAINING

- A. General: Provide adequate training to contractor and subcontractor personnel, vendors, and suppliers on proper packaging and waste management procedures.

3.2 COORDINATION

- A. General: Coordinate the salvaging, recycling, and disposal of waste with contractor and subcontractor personnel, product suppliers, and waste disposal vendors.

3.3 IMPLEMENTATION

- A. General: Implement the waste management plan as outlined.

3.4 PACKAGING

- A. General: Minimize packaging as defined in ASTM D5834.

3.5 DEMOLITION & CONSTRUCTION WASTE

- A. General: Except for items identified to be salvaged, recycled, or otherwise reused, remove all demolition and construction waste materials, garbage, and solid waste from the project site and legally dispose in landfill or waste hauling facility acceptable to the authorities having jurisdiction. Do not burn waste on government property. Do not allow waste to accumulate at the project site. Dispose of waste in a manner that prevents spillage or tracking of waste and debris on government property or outside of government property.

3.6 SALVEGABLE OR RECYCLABLE ITEMS

- A. General: For demolition or construction waste that can be reuse, either on the subject project or a future project, salvage or recycle the items as outlined in the waste management plan.

3.7 GREEN WASTE

- A. General: For green waste constituting of vegetative and organic matter generated from construction operations, without any deleterious content (causing harm or damage to the environment), the green waste may remain onsite under the following conditions:
 1. Lawn clippings and sod may be spread out in designated areas as approved by the Contracting Officer as long as there's no negative impacts to park resources.
 2. Trees, branches, limbs and stems may be spread out in designated areas as approved by the Contracting Officer as long as there's no negative impacts to park resources or wildland fire management.

3. At sites where scattering green waste is not a viable option due to the volume or density of the green waste, a chipper may be used to compact the green waste. The chips generated may then be disposed in designated areas as approved by the Contracting Officer.
4. At sites where scattering green waste or using a chipper is not a viable or acceptable option, the green waste shall be removed and properly disposed of from the project site.
5. All storage, handling, and disposal of green waste shall comply with Section 01 11 40.

3.8 HAZARDOUS MATERIALS

- A. General: Treat, handle, store, transport, and disposal hazardous materials in accordance with manufacturer's and OSHA Subpart D requirements. Display Material Safety Data Sheets (MSDS) in conspicuous locations at work site.
 1. Immediately report spills of hazardous materials to NPS Dispatch at: **808-985-6170**.
 2. Maintain a spill emergency response kit.
 3. Train employees how to respond to a spill and use emergency response kit.

END OF SECTION 01 74 19

SECTION 01 77 00 – CLOSEOUT PROCEDURES

PART 1 – GENERAL

1.1 SUMMARY

A. This section includes administrative and procedural requirements for closeout including:

1. Closeout Submittals
2. Closeout Inspections & Acceptance of Work
3. Demonstration & Training
4. Demobilization & Final Cleaning

1.2 CLOSEOUT SUBMITTALS

- A. General – Submit final closeout submittals after project substantial completion. Contract final acceptance is contingent on timely submittal and NPS acceptance of final closeout submittals.
- B. As-Built Drawings – During the execution of the project, maintain a full-sized (22" x 34") hard copy of the construction drawings and/or shop drawings at the jobsite with clearly marked changes including deletions, additions, and special instructions or notes. Mark the changes on a regular if not daily basis to ensure the as-built markups are current and thorough. Make the As-Built Drawings available to the Contracting Officer or authorized representative for review at any time during construction to confirm progress. Upon completion of all fieldwork including the punchlist, transpose the red-lined markups / notes from the hardcopy As-Built Drawings to an electronic PDF copy of the drawings. Submit the PDF copy of the As-Built Drawings to the COR for review and approval. Then, update the full-sized (22" x 34") hard copy of the As-Built Drawings, as needed, and deliver / mail to the onsite Point of Contact (POC).
- C. Warranties - Submit all manufacturer's warranties for products furnished and installed on the project. These are usually found on the product cut sheets. In addition, submit a letter with a Contractor-issued warranty on all workmanship for a period of one (1) year starting from the date of final acceptance. The Contractor-issued warranty on workmanship is covered under the contract terms; however, inclusion of this letter in the closeout documents will permit the park to track the warranty period. Submit all warranties in PDF format to the COR.
- D. Operation & Maintenance (O&M) Manual: Submit an Operation & Maintenance (O&M) manual in PDF format to the COR with the following information:
1. Preventative Maintenance Schedule – Include a preventative maintenance schedule for all recommended work on all major products, components, systems, or facilities to maximize their lifespan. The preventative maintenance schedule is typically a one-page summary or table of all preventative maintenance recommended by the vendor or contractor. The preventative maintenance schedule shall include the item, the maintenance recommendation, and the frequency (i.e. every quarter, 5 years, etc.). The preventative maintenance schedule should be located on the first page of the O&M Manual for quick reference.

2. Product Information – Include all products approved and used on the project. Please ensure only approved products are submitted. Do not include products that were not approved. Referencing CM-16's that were submitted prior to the construction start is not acceptable.
 3. Operating Instructions – Include operating instructions for all major equipment, components, systems, or facilities.
 4. Testing & Inspection Reports – Include any testing and inspection reports completed.
- E. Project Photos – Submit clear, representative photos of the project BEFORE, DURING, and AFTER construction in PDF or JPG format to the COR. Photos shall be labeled with subject, location, and date. If photos are copied to a MS Word file, photos shall not exceed four (4) photos to a page. Referencing photos attached to daily reports is not acceptable.
- F. Project Closeout Binders – Submit two (2) D-ring binders containing hard copies of the final approved closeout submittals from Section 01 77 00, PART 1.2 (B thru E above). These binders shall include: As-Built Drawings (11x17), Warranties, Preventative Maintenance Schedule, Product Information, Operating Instructions, Testing & Inspection Reports, and Project Photos. Label the outside of each project closeout binder with the project title, contract number, contractor name, and completion month and year. Upon approval of the closeout submittals, the Project Closeout Binders shall be delivered / mailed to the onsite POC.
- G. Accessibility Inspection Report: If the project requires compliance with ABAAS for accessibility under Section 01 11 00, PART 1.12.B, fill out applicable sections of the Accessibility Inspection Form to document compliance with the Architectural Barriers Act Accessibility Standards (ABBAS). Inspect the work at various stages of construction to ensure the finished product meets the contract requirements. Failure to comply with ABAAS may result in rework. Complete the Accessibility Inspection Form in PDF format and submit to the COR for review and approval.

1.3 CLOSEOUT INSPECTIONS & ACCEPTANCE

- A. Pre-Final Inspection & Substantial Completion:
1. When the project, or a designated portion of the project, is substantially complete, the Contractor shall request a pre-final inspection in writing (via email) at least seven (7) calendar days in advance of the inspection date. The Work will be considered substantially complete when all major work elements are complete, and all components are operable.
 2. During the pre-final inspection, the Contractor and the NPS will develop a "punchlist" of remaining work or deficiencies to satisfy the contract requirements. The punchlist will be reviewed onsite with the Contractor to ensure all parties have a clear understanding of the remaining work. The basis for what may be included in a punchlist includes:
 - a. Items required as outlined in the construction documents (i.e. plans and specifications).
 - b. Items required as outlined from the responses to RFI questions.
 - c. Mitigation of a potential hazard generated from the work performed.
 - d. Correction of a workmanship issue (per industry standards, manufacturer's recommendations, or as outlined in Section 01 73 40 Execution).
 - e. Items associated with final cleanup.
 3. If the NPS confirms that the work is substantially complete at the time of the pre-final inspection, the Contracting Officer will issue a Letter of Substantial Completion with the punchlist of remaining work to be completed or corrected prior to final acceptance. The

original contract period of performance will end, and the Contractor will have thirty (30) calendar days to complete the punchlist, as weather permits.

4. If the NPS determines that the work is NOT substantially complete at the time of the pre-final inspection, the Contracting Officer will notify the Contractor in writing. The Contractor may request a new pre-final inspection; however, all re-inspection costs may be charged against the Contractor in accordance with the Inspection of Construction clause of the contract.
5. If all or a portion of the Work is determined to be substantially complete, and the Government wishes to occupy or begin using the area, the Contracting Officer may issue a Letter of Beneficial Use / Occupancy to the Contractor outlining the terms of occupancy.
6. If there are no field punchlist items identified during the pre-final inspection, and only administrative closeout submittals remain, the Contracting Officer may issue a Letter of Beneficial Use / Occupancy to the Contractor.

B. Final Inspection & Final Acceptance:

1. When all field punchlist items are completed, the Contractor shall request a final inspection in writing at least three (3) calendar days in advance of the inspection date. During the final inspection, the NPS will confirm punchlist completion. After all field punchlist items are completed, and all closeout submittals have been received and accepted, the Contracting Officer will issue a Letter of Final Acceptance.
2. If the Contractor fails to complete the field punchlist items and/or submit the closeout submittals in the allotted thirty (30) day timeframe, the Contracting Officer may either replace the work with an appropriate reduction in contract price or negotiate other considerations. In addition, re-inspection costs may be charged against the Contractor in accordance with the Inspection of Construction clause of the contract.
3. If there are no field punchlist items, a final inspection is not required.
4. Once the Letter of Final Acceptance is issued and the Contracting Officer receives the Release of Claims, the Contractor may submit final invoice.

PART 2 – PRODUCTS (Not Used)

PART 3 – EXECUTION

3.1 LABEL SWITCHES & POST OPERATING INSTRUCTIONS

- A. General: After completion of the work, label all switches and controls and post operating instructions, as applicable. All labels and posts shall be printed, clear, secure, and protected.

3.2 SPECIALTY TOOLS, SPARE PARTS, EXCESS MATERIALS

- A. General: After completion of the work, deliver specialty tools required to operate new equipment, components, systems, or facilities to the onsite POC. If the Contractor wishes to transfer spare parts or excess materials to the park, and the park is amenable, the Contractor shall document the items to transferred.

3.3 DEMONSTRATION & TRAINING

- A. General: Provide onsite demonstration and training to NPS operators and personnel on the proper and safe operation of all new systems and components. This demonstration & training can occur at the time of the pre-final or final inspections, or it can be arranged as a separate event to accommodate either park personnel or the training vendors, if applicable. However, in either case

the Contractor shall notify the NPS at least seven (7) days in advance of the proposed demonstration & training so the park can arrange for key or interested staff to attend.

3.4 REMOVAL OF TEMPORARY FACILITIES & CONTROLS

- A. General: After completion of the work, remove all temporary facilities and controls such as portable toilets, surface protections, fencing, traffic and erosion / sediment control devices.

3.5 DEMOBILIATION

- A. General: After completion of the work, remove all equipment and machinery from the site.

3.6 FINAL CLEANING

- A. General: After completion of the work, clean all surfaces and remove all waste materials. Properly dispose of all waste and debris offsite. Dispose of all food refuse in proper containers so as not to attract wildlife, vermin, or pests.

END OF SECTION 01 77 00