

**STATEMENT OF WORK
FOR CLEANING
EMPTYING OF OIL/WATER SEPARATORS,
GREASE TRAPS, SEPTIC TANKS, LIFT
STATIONS AND DEICER TANKS**

Kaiserslautern Military Community
Ramstein Air Base, Germany

DRAFT

A large, light gray diagonal watermark reading "DRAFT" is visible across the page. Below the title, there is a black rectangular redaction box covering a signature or stamp.

18 Feb 2026

Table of Contents

<u>SUBJECT</u>	<u>Page Number</u>
1.0. Description of Services	2
2.0. General Information	5
3.0. Services Summary	8
4.0. Government Furnished Property and Services	9
5.0. Appendices	
Appendix A - Estimated Workload Data	
Appendix B – Equipment List	
Appendix C – Desired Pick-up Frequency List	
Appendix D – Service Deliverables	

**PERFORMANCE WORK STATEMENT
FOR
CLEANING AND EMPTYING OF SEPTIC TANKS, DEICER TANKS, GREASE TRAPS
AND OIL/WATER SEPARATORS IN THE KMC**

1. BASIC SERVICES.

This is a non-personal services contract; the Government shall not exercise any supervision or control over the contract service providers performing the services herein. The contractor shall provide all management, tools, supplies, equipment and labor necessary to empty, dispose and clean oil/water separators, grease traps, de-icer and septic tanks located in the Kaiserslautern Military Community (KMC), Ramstein Air Base, Landstuhl-Kirchberg, Kaiserslautern-Vogelweh, Kaiserslautern-Kapaun, Kaiserslautern-Einsiedlerhof Kaiserslautern-Rod&Gun Club and Husterhoeh Pirmasens. Work shall comply with commercial, government and foreign governing standards (FGS).

1.1. APPLICABLE SPECIFICATIONS AND REGULATIONS.

The following list is an overview of applicable regulations pertaining to liquid waste; and is not all-inclusive. Whatever is more stringent shall be followed and latest guidance be adhered to by the contractor.

- Wasserhaushaltsgesetz (WHG)
- Landeswassergesetz Rheinland-Pfalz (LWGRh-Pf)
- Abfallverzeichnis-Verordnung (AVV)
- Kreislaufwirtschaftsgesetz (KrWG)
- Nachweisverordnung (Nachw-W) Abfall
- Gefahrgutverordnung Strasse (GGVS)
- ADR (Accord européen relatif au transport international des marchandises dangereuses par route)
- European Agreement concerning the carriage of dangerous goods on public roads (ADR)
- Oil Pollution Act of 1990, Section 1001.
- The Federal Water Pollution Act
- DIN 1999-100, DIN 4040
- Die technischen Normen für Ölabscheider sind die EN 858-1 und EN 858-2

1.2. DISPOSAL OF HAZARDOUS WASTE.

The contractor shall comply with the Kreislaufwirtschafts-und Abfallgesetz and the Ordinance on Waste Recovery and Disposal Records (Nachweisverordnung-NachwV). The contractor shall be responsible for all administrative duties and fees in relation to the German Government agency Sonderabfall Management GmbH (SAM). Any costs resulting thereof shall be included in the price per Cubic Meter (CbM).

1.2.1. OIL/WATER SEPARATORS. The OWS will be monitored through the wastewater management team of 786 CES/CEOA.(monthly) The contractor is responsible to pump all oil, oil residue, and other waste from separators. Drain separator completely. Inspect all parts for

problems. Wash and drain the separator and fill it with clear water as required for the unique configuration of the separator. Transport all materials from oil/water separators to an approved off-base oil recovery and storage facility.

1.2.2. GREASE TRAPS. Pump out all grease and residues from trap; remove waste built up from trap or pit walls and all associated equipment within the pit. Flush down with water and pump out remaining residue as required by the unique configuration of the grease trap. Residual or recharged water must be higher than lower inlets. Clear obstructions in inlet/outlet pipes to ensure unrestricted flow. Transport all materials from grease traps to an approved off-base dump facility.(every 4 weeks)

1.2.3. SEPTIC TANKS, LIFT STATIONS AND DEICER TANKS. Empty all contents including sludge on the bottom of tank/lift stations and backflow sewage and drain completely. Pump all waste to include deicer fluid, sludge on the bottom of septic tanks/lift stations and backflow sewage. Drain tanks/lift stations completely. Tank walls, bottoms and coverings shall be hosed off to remove all loose particles. All liquid waste shall be pumped out, close septic/deicer tank in accordance with requirements of state health department and dispose at an approved off-base dump facility. Ensure exterior grounds are cleared from any soil caused through the emptying of tank.

1.2.4. EMPTYING FREQUENCY/WORK SCHEDULE.

The contractor shall follow the cleaning requirements as shown in appendix A. Contractor should follow the below guidelines/ minimum pickup frequencies:

Sewage and Septic – weekly/bi-weekly/monthly/annual

Lift stations – as directed by the COR

De icer - as directed by the COR

OWS/ Grease Traps including cyclic General Inspections– as directed by the COR

Work schedule must at least contain the type of asset to be served, the location and date. Within fourteen (14) workdays after inception of contract the schedule must be provided to the COR. It is the contractor's responsibility to schedule this service as deemed necessary, but under all circumstances to avoid overfilled/overflowing OWS, grease traps and septic tanks that pollute the environment and would lead to emergency response procedures. See appendix.

1.3. EMERGENCY SERVICE CALLS. Normally, all work will be in accordance with the contractor's work schedule. Unexpected services may be required in the event of natural disasters and/or other unscheduled repairs to pipes or other infrastructure involving oil/water separators, grease traps, septic tanks and lift stations. In the event that servicing is required outside the contractor's schedule, the contractor shall begin the service within 4 hours after notification. Emergency calls may not be utilized for unfulfilled commitments of the contractor such as negligence to follow a proper cleaning schedule, mismanagement or other foreseeable circumstances. On-call service shall be priced separately as negotiated in the contract.

1.4. GENERAL INSPECTIONS

For all Oil Water Separators and Grease traps the contractor shall perform General Inspections IAW DIN 1999-100 and DIN 4040. The contractor will be informed through the COR on a monthly/annual basis which assets are due for testing and re-certification. The contractor should schedule service accordingly within fourteen (14) business days. The schedule shall include the estimated date, times and the locations. The contractor shall provide any schedule changes to the COR no later than eight (8) business days prior to the start of the service. After completion of the general inspection the contractor shall submit a written compliance inspection report, video recordings and pictures or any additional supporting documentation within eight (8) business days after completed service. The report shall include: date and time of the service, location of the oil water separator, overall condition (including discrepancies cited and repairs needed), service performed and name of the technician performing the service.

1.5. REQUIRED DOCUMENTATION.

A copy of the waste disposal documentation (sample form attached) shall be submitted to the COR upon completion of work on a weekly basis (first working day of the week for the prior week). Further documents and reports shall be stored at the contractor's location for the duration of the contract. They shall be provided in English and only sent electronically (Adobe PDF) upon the request from the COR. Original documentation referring from weight stations and dump sites in conjunction with Waste Recovery and Disposal Records/ Nachweisverordnung-NachwV for each asset can be submitted in German, electronically (Adobe PDF). All documents and records shall be sent to the 786 CES/CEOES organization [REDACTED]

1.6. SAFETY AND HEALTH STANDARDS. The contractor shall initiate and maintain programs to comply with the provisions of the Occupational Safety and Health Standards Act concerning entry requirements in confined spaces and handling potential hazardous substances. Contractor vehicles and vehicle operators must comply with applicable road ordinances when transporting hazardous waste.

2. QUALITY CONTROL.

The contractor shall have and maintain a written quality control plan to ensure services are performed IAW this PWS. The contractor shall have procedures to identify and prevent services that do not meet the standards.

2.1. QUALITY ASSURANCE.

The government will inspect and evaluate the contractor's performance to ensure services are IAW the requirements set forth in this contract. The COR will use the contractor's work schedule or modified version thereof, to record validation results. Results of the validation then become the official Air Force record of the contractor's performance. When a performance threshold has not been met or contractor performance has not been accomplished as required, the COR will initiate and provide the CO with a Corrective Action Report (CAR) for issuance to the contractor. The contractor shall respond to the CAR IAW the instructions provided and return it to the CO within five (5) calendar days of receipt. The CO will forward the contractor's response to the COR once received. The COR will perform re-inspection within one (1) business day of receipt of contractor's response.

2.2. UNACCEPTABLE PERFORMANCE.

The contractor shall report to the site location within two (4) hours after notification to correct unacceptable performance. The contractor shall re-perform at no cost to the Government. Any re-performance and/or unacceptable performance will be documented by the COR and may result in the Government seeking equitable price reduction or adequate consideration IAW FAR52.212-4, Contract Terms and Conditions – Commercial Items.

2.3. CONTRACT MANAGER.

The contractor shall provide the name of a contract manager (primary and alternate) who shall be responsible for the performance of work and have full authority to act on behalf of the contractor on all contract matters relating to the daily operations of this contract. The contract manager shall be available during normal duty hours (0700-1600). The Contractor shall be able to meet with the COR to resolve any contract issues. The contract manager and alternate shall be able to understand, read, speak, and write basic and technical English (to speak English with sufficient structural accuracy and vocabulary to participate in formal and informal conversations on practical, social, and professional topics). The contractor shall provide to the CO and COR, five (5) business days after award, a list with the names, addresses, and cell phone numbers of the contract manager's supervisor, contract manager, and an alternate with authority to act on behalf of the contractor if the contract manager cannot be contacted prior to starting performance. Any required changes to this list shall be submitted in writing to the CO and COR, ten (10) business days prior to the change taking effect.

2.4. CONTRACTOR PERSONNEL.

Contractor personnel shall present a neat appearance. Contractor personnel shall be easily recognizable while on the installation in conjunction with this contract. This shall be accomplished by the wearing of distinctive clothing, overcoats, or hats, bearing the company name or logo. The color or design of the selected apparel shall ensure easy and quick identification of contractor personnel for reasons of safety and personal protection. The contractor shall provide all safety equipment for contractor personnel working.

2.5. HOURS OF OPERATION.

The contractor shall coordinate all work to be accomplished IAW this PWS with the COR for oil/water separators, grease traps, deicer, septic tanks and lift stations to be emptied and disposed. Regular business hours are 0700-1600, Monday through Saturday. Emergency services may be required during non-business or off-hours (early AM or late PM), Monday through Saturday.

2.6. PERFORMANCE OF SERVICES DURING MILITARY EXERCISES OR OPERATIONS.

Work stoppages may occur during the execution of this contract due to military exercises or operations. During these times, access to areas supporting the exercise or operation may be curtailed or denied. During scheduled and unscheduled exercises or operations, the contractor must be prepared to postpone performance in coordination with the COR until immediately after completion of the military exercise or operation. No additional cost will be incurred to the Government for the waiting time until the exercise or operation is over.

2.7. SECURITY REQUIREMENTS.

The contractor personnel shall comply with all requirements and procedures IAW AFFARS 5352.242-9000, Contractor Access to Air Force Installations.

2.7.1. CONTRACTOR/EMPLOYEE BASE PASS AND IDENTIFICATION, SPECIAL CLEARANCES AND VEHICLE PASSES.

Contractor personnel shall obtain an Installation Common Access Card (ICAC) not later than fourteen (14) days prior to the Period of Performance (PoP). To obtain the ICAC, the contractor is required to submit to the COR following.

- AEA Form 190-16A (Request for ICAC)
- AEA Form 190-16E (Data Protection Statement)
- AE 190-16K (Acknowledgement of Responsibility)
- AE 604-1 (Security Questionnaire for a Simple Security Check)
- Copy of Passport
- Police Good Conduct Certificate (Polizeiliches Führungszeugnis)

AE Form 190-16A, AEA 1290-16E, AE 190-16K and the Security Questionnaire will be provided by the COR, 786 CES/CEOES. Contractor personnel shall present completed documentation to Security Forces personnel at bldg. 800, Ramstein Air Base, to obtain their ICAC. Contractor personnel can only gain access to the KMC after the security check has been passed with a positive result. It is the responsibility of the contractor to collect and return the ICAC of personnel that is no longer employed within one (1) week, in case contract is terminated and/or after end of the PoP.

2.7.2. ACCESS TO RESTRICTED AREAS.

Access to secure areas must be coordinated with the COR. Restricted areas require notification through the COR to the FM/alternate at least one (1) week prior to the date of the service to allow time for coordination.

2.7.3. ESCORT.

For any restricted/secure area access in conjunction with (ICW) the scope of work, the COR will arrange for an escort and entry authorization at the designated place of performance.

2.7.4 SPECIAL QUALIFICATIONS.

Contractor employees performing services shall be able to speak English sufficiently well to communicate on a basic level with on-site personnel.

2.8. CONFORMANCE WITH ENVIRONMENTAL MANAGEMENT SYSTEMS.

The contractor shall perform work under this contract consistent with the relevant environmental policy and objectives identified in the installation environmental management system (EMS) applicable for your contract. The contractor shall perform work in a manner that conserves water, energy, and other resources to the maximum extent feasible and ensure minimum production of waste as possible, giving preference to recycling and reutilization opportunities. Furthermore, the contractor shall give preference to less toxic materials whenever available and still reliable for

their work. In the event an environmental nonconformance or noncompliance of host nation and USAF environmental laws and regulations associated with the contracted services is identified, the contractor shall take corrective and/or preventative actions. In the case of noncompliance, the contractor shall respond and take corrective action immediately. In the case of nonconformance, the contractor shall respond and take corrective action based on the time schedule established by the EMS Coordinator. In addition, the contractor shall ensure that their employees are aware of the environmental management system on base and how these requirements affect their work performed under this contract. All on-site contractor personnel shall receive the installation EMS awareness level information.

2.8.1. CONFORMANCE WITH ENVIRONMENTAL REQUIREMENTS.

The contractor shall perform all work in accordance with applicable German and US Air Force environmental laws, regulations and operating standards, including but not limited to, the Final Governing Standards (FGS) for Germany. The contractor shall be immediately capable of understanding and addressing environmental laws and regulations as they pertain to work performed under this contract. The FGS for Germany and other important environmental laws and requirements applicable to all contractors working on base will be made available upon request.

2.8.2. NOTIFICATION OF ENVIRONMENTAL SPILLS.

If a spillage of disposal material does occur, the contractor shall thoroughly clean up the area of the spill. If the spill is greater than 5 gallons (19 liters), the contractor shall immediately report the incident to the COR (786 CES) and the Environmental Management Office (86 CES). The contractor shall be liable for containment and environmental cleanup of their spill or release of such substance if necessary. If the contractor discovers an overflow of disposal material, the contractor shall immediately report the incident to the COR.

2.9. DOD MISSION ESSENTIAL SERVICES DURING CRISIS.

IAW DODI 1100.22, Policy and Procedure for Determining Work Force Mix, paragraph 5b, it is determined that none of the services as stated in this PWS are mission essential.

3. SERVICE DELIVERY SUMMARY.

The Service Summary provides information on contract requirements and the expected level of the contractor's performance. The contract service requirements are summarized in performance objectives. The performance threshold briefly describes the acceptable levels of service required for each requirement. These thresholds are critical to mission success. During the first 30 days of the contract, two (2) errors for each performance objective will be allowed in an effort to overcome normal phase-in problems (this applies when there is a change of contractor only).

Performance Objective	Para	Performance Threshold	Method of Assessment
<u>PO-1</u> <u>Basic Services</u> Pump all waste including sludge on the bottom of septic tanks/Lift stations and backflow sewage and drain completely. Remove and properly dispose of wastewater, deicer fluid, non-hazardous oil, grease, and sludge. Clean all systems and fill with clean water as required.	1.1. - 1.2.3..	No more than 1 valid complaint per month	Re-perform within two (4) hours
<u>PO-2</u> <u>Emptying Frequency</u> The contractor shall follow the cleaning requirements as shown in appendix A. Contractor should follow the guidelines/ minimum pickup frequencies.	- - 1.2.4.	No more than 1 valid complaint per month	Re-perform within two (4) hours
<u>PO-3</u> <u>Emergency Service Calls.</u> Service calls handled promptly and all work completed as specified.	1.3.	No more than 0 valid complaint per month	Re-perform within two (2) hours
<u>PO-4</u> <u>Disposal of Hazardous Waste</u> The contractor shall comply with the Kreislaufwirtschafts-und Abfallgesetz and the Ordinance on Waste Recovery and Disposal Records (Nachweisverordnung-NachwV). The contractor shall be responsible for all administrative duties and fees in relation to the German Government agency Sonderabfall Management GmbH (SAM). Any costs resulting thereof shall be included in the price per Cubic Meter (cbm).	1.2.	No deficiencies permitted	Periodic inspections
<u>PO-5</u> <u>General Inspections</u> The contractor shall perform general inspection of all systems IAW DIN 1999-100 and DIN 4040 listed in appendix A	1.4.	No deficiencies permitted	Periodic inspections
<u>PO-6</u> <u>Required Documentation</u> Copy of waste disposal slip shall be stored at the contractor's location for the duration of the contract and only be submitted upon the request of the COR. Waste disposal slips Certified disposal slips from landfill sites	1.5.	Upon request, within 5 business days.	Periodic inspection
<u>PO-7</u> <u>Safety and Health Standards</u> The contractor shall initiate and maintain programs to comply with the provisions of the Occupational Safety and Health Standards Act concerning entry requirements in confined spaces and handling potential hazardous substances. Contractor vehicles and vehicle operators must comply with applicable road ordinances when transporting hazardous waste.	1.6.	Contractor Quality Control Program (CQCP)	Submitted with proposal / quotation
<u>PO-8</u> Contractor Work Schedule/ Pick up frequency schedule OWS	1.2.4	Within 14 workdays after inception of contract	Periodic inspection
<u>PO-9</u> Maintenance and General Inspections Reports OWS	1.5	Within 8 business days after service	Periodic inspection

4. GOVERNMENT FURNISHED PROPERTY AND SERVICES.

Water for cleanup operations is available to the contractor upon request in coordination with designated shops from 786/CES. The water connection shall be provided by the contractor.

4.1. DAMAGE TO GOVERNMENT PROPERTY.

The contractor shall report all damages to U.S. Government property within one (1) hour after occurrence to the COR

4.2. CONTRACT MODIFICATIONS

Unforeseen circumstances might lead to contract modifications on an as needed basis. At least Appendix B "Equipment List" will be updated annually while assets get replaced, upgraded and decommissioned during the lifetime of this contract. For the scope of this contract any upward or downward adjustment to Appendix B, Equipment List, of up to 3%, is considered in-scope and will not require modification. The contractor shall consider this with their initial pricing.

5. APPENDICES.

A. Estimated Workload Data

B. Equipment List

Oil Water Separators

Grease Traps

Sewage & Septic/Deicer Tanks/Lift Station

C. Desired pick up Frequency List

Oil Water Separators

Grease Traps

Sewage & Septic/Deicer Tanks/Lift Station

D Service Deliverable

D.1. Proof of status of “Entsorgungsfachbetrieb”

D.2. ADR Certified Vehicles

D.3. ADR Certified Licenses

D.4. Contractor Equipment List

D.5. Contractor Employee List

APPENDIX A

ESTIMATED ANNUAL WORKLOAD DATA

ITEM	NAME	ESTIMATED QUANTITY	
1	Dispose and Clean oil/water separators	1063	Cubic Meter (CBM)
2	Dispose and Clean grease traps	408	Cubic Meter (CBM)
3	Dispose and Clean septic tanks	5525	Cubic Meter (CBM)
4	Dispose and Clean deicer fluid tanks	30	Cubic Meter (CBM)
5	Dispose and Clean lift stations	63	HOURS (HRS)
6	Dispose and Clean emergency call tanks/lift stations	30	HOURS (HRS)
7	Dispose and Clean emergency call ows separators	10	EACH

DRAFT