

WA FWS LPO MULTI(1) Little Pend Oreille NWR Culvert Improvements

Little Pend Oreille National Wildlife Refuge

Pend Oreille, Washington

This Work consists of replacement of 6 Aquatic Organism Passage (AOP) culverts within the Wildlife refuge

Project Location: approximately 75 Miles North of Spokane, Washington (city).

Project Length: 0.23 Miles

Estimated Price Range: between \$2,000,000 and \$5,000,000

Tentative Solicitation Date: Spring/ Summer 2026

Contract Type: Sealed Bid; Firm-Fixed-Price

Tentative Fixed Completion Date: this project has multiple schedules

Schedule A, fixed completion date: Fall 2027

Schedule B, fixed completion date: Fall 2028

Schedule C, fixed completion date: Fall 2028

Project Description

Project name and Number: WA FWS LPO MULTI(1) Little Pend Oreille NWR Culvert Improvements

**DESCRIPTION OF WORK in US CUSTOMARY UNITS
USING FP-14 SPECS**

	One Schedule Sch Name _Base_	Additional Sch Sch Name Option X	Additional Sch Sch Name Option Y
DIVISION 150 – Project Requirements			
152 Construction Survey & Staking (yes/no)	Yes	Yes	Yes
153 Contractor Quality Control and Assurance (yes/no)	Yes	Yes	Yes
154 Contractor Sampling & Testing (yes/no)	Yes	Yes	Yes
155 Schedules for Construction Contracts (construction schedules) (yes/no)	Yes	Yes	Yes
157 Soil Erosion & Sediment Control (erosion control devices)	Fiber Roll/ Temp Stream Diversion	Fiber Roll/Temp Stream Diversion	Fiber Roll/temp Stream Diversion
158 Watering for Dust Control	Yes	Yes	Yes
DIVISION 200 – Earthwork			
201 Clearing & Grubbing	1 acre	1.2 acre	1.5 acre
203 Removal of Cattle Guard	2 each	2 each	2 each
204 Excavation & Embankment	380 CUYD	499 CUYD	590 CUYD
251 Place Riprap	650 CUYD	740 CUYD	830 CUYD
DIVISION 300 – Aggregate and Base Courses			
302 Roadway Aggregate	523 CUYD	649 CUYD	776 CUYD
DIVISION 600 – Incidental Construction			
602 Concrete Box Culverts	109 LNFT	109 LNFT	148 LNFT

Project Description

Project name and Number: WA FWS LPO MULTI(1) Little Pend Oreille NWR Culvert Improvements

	One Schedule Sch Name _Base_	Additional Sch Sch Name Option X	Additional Sch Sch Name Option Y
603 Structural Plate Structures (<i>culverts & drains</i>)		76 LNFT	
619 Remove and Reset Gate	1	1	1
622 Rental Equipment (<i>yes/no</i>)	Yes	Yes	Yes
623 General Labor (<i>yes/no</i>)	Yes	Yes	Yes
625 Seeding	2129 SQYD	2935 SQYD	3428 SQYD
625 Fertilizer	0.5 Acre	0.7 Acre	0.8 Acre
626 Cuttings, Willow Pole	1100 Each	1100 each	1100 each
629 Rolled Erosion Control Products	715 sqyd	715 sqyd	715 sqyd
633 Permanent Traffic Control – sign systems	24 each	30 each	36 each
635 Temporary Traffic Control - Barricade	10 each	14 each	14 each
635 Temporary Traffic Control – <u>Construction Signs</u>	14 each	22 each	22 each
635 Temporary Traffic Control – <u>TCS</u>	64 day	127 day	154 day
647 Mitigation, Rock weir	4 each	10 each	15 each
647 Mitigation, Log Barrier	2 each	2 each	2 each
647 Mitigation, Root Wad	6 each	8 each	8 each
647 Mitigation, Fish Passage Boulder	38 each	51 each	60 each
647 Mitigation, Streambed Material	490 CUYD	655 CUYD	725 CUYD
647 Mitigation, Streambed Channel Realignment	237 CUYD	237 CUYD	237 CUYD

Project Description

Project name and Number: WA FWS LPO MULTI(1) Little Pend Oreille NWR Culvert Improvements