



eProjects No.: 1624308

ExSOW

**SP-312
Chiller Replacement**

at the

Naval Station, Norfolk, Virginia

DESIGNED BY:

NAVFAC MIDLANT; PWD NORFOLK; FACILITIES ENGINEERING
9742 MARYLAND AVENUE
NORFOLK, VIRGINIA 23511-3095

COST PREPARED BY:

Electrical: Dave Burnette
Mechanical: Robert Kreie

COST APPROVED BY:

Design Director: James M Smith, RA
Engineering Director: J.C. Miller, P.E.

For Commander, NAVFAC MID-ATLANTIC:

Date: 2-6-20

Executable Scope

eProjects Work Order Number: 1624308
Building: SP-312
Project Title: SP-312 Chiller Replacement
Customer: Peter Klaus
Scope By: Robert Kreie, Dave Burnette
Date: July 31, 2024
General Notes:

Building SP-312 was constructed in phases from 1968 through 1983 and is a 53,250 SF one-story structure. The building was originally designed as avionic shops, equipment storage, training areas and offices.

The purpose of the executable scope is to replace the existing 50 ton Trane air cooled chiller with like in kind.

Contractor Requirements:

- A. Contractor must perform a thorough site visit before preparing the bid for any work associated with this project.
- B. All material must be new and provided by the Contractor unless specifically noted as existing, or as provided by the Government.
- C. Contractor must verify existing conditions prior to ordering or installing any materials or equipment.
- D. Contractor will be responsible for disposal of all unused and demolished materials to an offsite location.
- E. Any potential issues observed during the Pre-Award walk-through that may conflict with these documents must be brought to the attention of the Contracting Officer.
- F. Minimize damage to existing work to remain. The Contractor is responsible for the repair, patching, repainting or replacing of any work in areas affected, damaged or modified by this work. New material must match adjacent material, texture and color.
- G. Construction will be accomplished in and around areas which will remain operational. Avoid interference with the operational work routine.
- H. Refer to reference drawings, photographs, and attachments for clarification.
- I. Notify the Contracting Officer when the work is complete for an inspection to be performed. Contract must not be considered complete until a satisfactory record of inspection is granted.
- J. Contractor must observe and maintain building and compound security requirements. This building is a secured facility.
- K. Contractor must provide and install all required materials in accordance with manufacturer's written instructions.
- L. Adhere to all EM-385 & OSHA safety regulations.

Work shall be completed as listed below:

Mechanical:

- A. Provide chiller replacement as shown on attached drawings.

Electrical:

- A. Demolition
 - 1. Demolish existing chiller disconnect switch, conduit, and wiring.
 - 2. Demolish existing chiller heat trace disconnect switch, conduit, and wiring.
- B. New Work
 - 1. Provide new disconnect switch, wiring, and conduit for chiller.
 - 2. Provide new disconnect switch, wiring, and conduit for heat tape.

Required submittals from the contractor for government review and approval:

Contractor must not proceed with construction until Government approval is provided for required submittals. Submittals must be electronic – paper copies will not be approved.

- Air Cooled Chiller.
- Chilled water piping.
- Electrical disconnect switch, conduit, and wiring.
- Panelboard circuit breaker.

List of Attachments:

Drawings:

12,911,894	G-001 Cover Sheet, List of Sheets & General Data
12,911,895	M-001 Legend, Abbreviations and General Notes
12,911,896	MD101 Demolition Plan
12,911,897	M-101 New Work Plan
12,911,898	M-501 Details and Schedules
12,911,899	M-701 Controls
12,911,900	E-001 Electrical Symbols, Legend, Abbreviations, and Notes
12,911,901	ED101 Partial Electrical Floor Plan – Demolition
12,911,902	ED701 Panelboard Schedules – Demolition
12,911,903	EP101 Partial Electrical Floor Plan
12,911,904	EP701 Panelboard Schedules