

**Sacramento VA Medical Center – VA Northern California Health Care System  
(VANCHCS)  
10535 Hospital Road  
Mather, CA 95655**

## **SCOPE OF WORK**

### **1.0 Introduction**

This Statement of Work (SOW) defines the requirements of the Veterans Health Administration (VHA) in establishing a fixed-price **Brand name or equal** purchase order for Shelving Units.

### **1.1 Background**

VA Stockton Engineering & Logistics Building requires Shelving Units to outfit the new facility to provide member services for the Veterans Health Administration (VHA).

### **1.2 Scope**

The scope of this purchase order is to provide VA Stockton products that meet or exceed the specifications laid out in these sections. Each item is for delivery to the VA Stockton Engineering & Logistics Building location. Contractors shall furnish the Shelving Units. Estimated delivery dates are **May 31, 2026 to Aug 31, 2026.**

The delivery schedule is based upon the current construction schedule, which is subject to change. The vendor shall not increase prices for a change in delivery date due to construction delays. The awardees actual delivery dates will be confirmed by VA upon award.

## **2.0 General Requirement**

All equipment to be supplied under the specifications shall be the newest and the most current model of a standard product of a manufacturer of record. A manufacturer of record is defined as a company whose main occupation is the manufacture for sale of the items of equipment and which:

- a. Maintains a factory production line.
- b. Maintains a stock of replacement parts for the item.
- c. Maintains engineering drawings, specifications, operating manuals and maintenance manuals.
- d. Has published and distributed descriptive literature and equipment specifications on the equipment.

## Key Features:

### **M2055A - Shelving, Wire, Chrome (72x24)**

Wire shelving unit. Unit has fully adjustable shelves constructed of stainless steel.

For use in general purpose storage areas.

Shelving is provided in various sizes and configurations.

Price provided is for a unit approximately 72"H x 24"D x 72"W with four shelves.

Must Include: (1) PLASTIC SHELF LINER - 72 X 24", CLEAR per Lower Shelf on each Unit, (6) WIRE SHELF LEDGE - 24 X 4", CHROME per Unit, (3) WIRE SHELF LEDGE - 72 X 4", CHROME per Unit, (1) ADDITIONAL CHROME WIRE SHELVES - 72 X 24" 2/BOX per Unit, (3) SHELF DIVIDERS - 24 X 8", CHROME per Unit, and POLYURETHANE CASTERS FOR WIRE SHELVING UNITS - SET OF 4, BLACK 4/SET

### **M2055B - Shelving, Wire, Chrome (48x72)**

Wire shelving unit. Unit has fully adjustable shelves constructed of stainless steel.

For use in general purpose storage areas.

Shelving is provided in various sizes and configurations.

Price provided is for a unit approximately 72"H x 24"D x 72"W with four shelves.

Additional items required for this JSN: (1) Shelf Liner for lower Shelf, (1) Basket Divider for each Shelf, and Polyurethane Casters - set of (4) Black

### **M2070A - Shelving, Storage, 77hx36wx18d**

Heavy Duty Adjustable storage shelving unit

Corrosion resistant

Steel frame open unit with adjustable shelves

Weight Capacity: up to 2500 lb when weight is evenly distributed

Instructions included for easy assembly

Heavy-duty steel construction with black powder-coated finish for lasting durability

Four wire shelves provide ample storage for heavy or bulky items such as paint cans, tools, work equipment and more

Shelves adjust in 3 in. increments to fit any storage needs

#### Contents include:

- Uprights (2) • Cross Beams (8) • Beam Strap (12)
- Welded Wire Mesh (4) • Lock Pin (16) • M6 Allen Button Bolt (24)
- Pan Philip Self-Taping Screw (2) • Plastic Dry Wall Anchor (2) • Flat Washer M5

#### Dimensions

Assembled Depth (in inches): 24.0

Assembled Height (in inches): 78.0

Assembled Weight (in lbs): 130.0  
Assembled Width (in inches): 77.0  
Packaged Depth (in inches): 79.13  
Packaged Height (in inches): 9.45  
Packaged Weight (In lbs): 150.5  
Packaged Width (in inches): 25.59  
Number of Shelves: 4  
Shelf Material: Wire/Metal  
Swatch Color: Black  
Total Weight Capacity: 10,000  
Warranty / Certifications: 1 Year

### **M2080 - Shelving, Storage (36W x 24D x 84H)**

Store and unload heavy, bulky items with convenient four-way access to shelves. Quick, easy assembly. Shelves snap into place and adjust at 1 1/2" increments. 3 Shelves hold up to 1800lbs each Add on (2) H-2189-ADD extra shelves per unit for a total of (5) shelves per unit Smooth solid 5/8"board eliminates item fall-through. Includes shelf support and particle boards.

### **M2085 - Shelving,Storage,Pallet, Starter Section**

Pallet storage shelving starter section. This unit is of heavy-duty construction and has channel type bracing in between columns, heavy duty foot plate with 3-point security. The size will be determined by weight load. It is designed for easy forklift access in storage areas and warehouses. Provide easy forklift access to palletized boxes, crates and containers

- Boltless assembly. Beams lock into place and adjust in 2" increments
- Welded 14-gauge steel frame. 16-gauge steel beams
- Includes 2 upright frames and 4 beams
- Fits 3 standard GMA 48 x 40 pallets on 1 level
- Outside Width: Add 6" to 96" Beam Width = 104" Outside Width
- 96" Wide Pallet can hold:

--- (2) 48 x 40" Standard GMA

Possible Add on items:

- Pallet Rack Wire Decking (46"W x 48"D): H-5725
- Additional Beams for Pallet Racks - 96": H-5953
- Add On Units: H-6196-ADD

### **M2085M - Shelving, Pallet / Bulk**

Pallet storage shelving starter section. This unit is of heavy-duty construction and has channel type bracing in between columns, heavy duty foot plate with 3-point security. The size will be determined by weight load. It is designed for easy forklift access in storage areas and warehouses.

- Provide easy forklift access to palletized boxes, crates and containers
- Boltless assembly. Beams lock into place and adjust in 2" increments

- Welded 14-gauge steel frame. 16-gauge steel beams
- Includes 2 upright frames and 4 beams
- Fits 3 standard GMA 48 x 40 pallets on 1 level
- Outside Width: Add 6" to 144" Beam Width = 150" Outside Width
- 144" Wide Pallet can hold:
  - (3) 48 x 40" Standard GMA (or)
  - (2) 48 x 40" Standard GMA & (1) 48 x 48" Drum Pallet (or)
  - (1) 48 x 40" Standard GMA & (1) 96" Long Pallet (or)
  - (1) 120" Long Pallet

Possible Add on items:

- Pallet Rack Wire Decking (46"W x 48"D): H-5725
- Additional Beams for Pallet Racks - 144": H-6804
- Add On Units: H-6810-ADD

\*\*\*Secured/Bolted to floor (concrete pad). Include Installation costs to anchor.

### **3.0 Work Hours:**

Normal business hours are 8:00AM to 4:30PM Monday thru Friday excluding Federal Holidays. Work completed outside this time shall be requested through the Point of Contact.

The Government recognized US holidays are: New Year's Day, Martin Luther King, Jr. Day, Presidents Day, Juneteenth, Memorial Day, Independence Day, Labor Day, Columbus Day, Veterans Day, Thanksgiving Day, and Christmas Day. If the holiday falls on Sunday, it is observed on Monday.

### **4.0 Delivery and Receiving:**

Delivery and receipt of the proposed items is anticipated to be directed to the location identified below. Confirmation of delivery location will be provided by the VA POC post-award. Any item that has not been coordinated will be turned away and any additional charges will be the responsibility of the sender/transportation company.

Delivery shall be freight on board (FOB) – Destination.

#### **Delivery Address:**

Richard A. Pittman Stockton VA Community Based Outpatient Clinic  
6505 S. Manthey Rd  
French Camp, CA 95231

### **5.0 Period of Performance:**

Period of performance will be from **May 31, 2026 to Aug 31, 2026**, giving the vendor 120 days to deliver the product, to each listed location, after award.

## **6.0 Warranty and Support:**

The contractor shall provide a manufacture's one-year, free replacement warranty on units with normal wear and tear, including free return shipping, from date of delivery.

## **7.0 Use of Premises**

If during the performance of this contract, work will be carried out on VA Stockton Engineering & Logistics Building premises, the vendor shall perform all work in such a manner that will cause a minimum interference with operations and the operations of other contractors on the premises.

The vendor shall communicate through the VA POC any required coordination requirements with the General Construction contractor prior to and during delivery and installation activities.

The project may be an active construction site during delivery and installation. The vendor shall take all necessary precautions to protect the premises and all persons and property therein from damage or injury. The vendor shall assume responsibility for taking precautions for the vendor's (and associated subcontractors') employees, agents, licensees, and permittees. The vendor shall abide by any safety requirements imposed by the GC (e.g. hard hats, safety vests).

## **8.0 GOVERNMENT AND CONTRACTOR RESPONSIBILITIES**

VA shall provide the contractor with copies of documents that the VA is required to provide.

The contractor shall request other VA documentation deemed pertinent to the work accomplishment directly from the COR (i.e., Sharay Brandon.) The contractor is expected to use common knowledge and resourcefulness in securing all other reference materials, standard industry publications, and related materials that are pertinent to the work.

The contractor shall maintain frequent communications with the Program Office and the COR to conduct work in progress reviews if necessary. Progress reports shall be delivered electronically to the COR, with an electronic courtesy copy to the Program Office AUS.

The contractor assumes full responsibility for the delivery of the goods and shall assume all the duties, responsibilities and obligations associated with the prime contractor.

The contractor assumes liability for its subcontractors and shall ensure that its subcontractors shall comply in all respect with the relevant terms of this agreement to the extent that it or they are retained by the Contractor.