

DPW, CONSTRUCTION, ESTIMATING & CONTRACT SERVICES BRANCH
4th Floor Bldg. 667A
West Point N.Y. 10996

Subject: Performance Work Statement

Contract name: Temporary Chillers - Summer 2026

IJO: UF-25313-5J

Project Location: Bldgs. 601, 655, & 752.

Scope:

Contractor to provide all labor, material, equipment, and supervision in accordance with all applicable codes and specifications to the following locations at USMA West Point, NY 10996:

- 1) Supply, install, and test operate one 500-ton trailer mounted air-cooled chiller with pumps at Bldg. 601, Thayer Hall – **one-month rental – May 22nd to June 21st, 2026.**
- 2) Supply, install, and test operate one 500-ton trailer mounted air-cooled chiller with pumps at Bldg. 655, Eisenhower Hall – **six-month rental – April 15th to October 15th, 2026.**
- 3) Supply, install, and test operate one 500-ton trailer mounted air-cooled chiller with pumps at Bldg. 752, Mahan Hall – **one month rental – May 22nd to June 21st, 2026.**

***Bldg. 655 temp chiller shall be delivered and installed and fully operational from April 15th to October 15, 2026.**

***Bldgs. 601 & 752 temp chiller shall be delivered and installed and fully operational for one month from May 22nd to June 21st, 2026.**

Description of Work:

Contractor shall mobilize, install, inspect, and test operation of the trailer mounted chillers no later than April 15th for start of full operational service. On October 15th, the contractor will disconnect mechanically, electrically, and demobilize the temporary chillers and all associated material and equipment.

- 1) Supply and install one 500-ton chiller with pumps at Bldg. 601, Thayer Hall and have all associated work needed for installation completed and the chiller ready and in operation by May 22nd. The existing building power and disconnect is 230/480 VAC, 800 amps. Supply a 750-1250 KVA transformer to supply power to the chiller unit from electrical vault. The contractor will be responsible to install approximately 250' ft. of 3" to 6" in. rubber hose with connection ends to attach chiller to building 681 chill water supply and return piping risers. Supply and install all pipe fittings as necessary for a complete installation. Supply and install all temporary electrical cables and appurtenances needed to connect chiller to the supplied building power electrical

disconnect. The proposed site location and attachment locations (electrical disconnect, piping, etc.) to existing building systems will be shown at site visit. The contractor shall have a qualified HVAC subcontractor at the site visit to review this location and determine the exact details (specific location, attachment details, piping / cable length etc.). The government PM will be notified when new cabling is ready to be connected, and PM will then notify Electric shop for termination.

2) Supply and install one 500-ton chiller with pumps at Bldg. 655, Eisenhower Hall and have all associated work needed for installation completed and the chiller ready and in operation by April 15th. The existing building power and disconnect is 230/480 VAC, 1000 amps. Supply a transformer to supply power to the chiller unit (if necessary). The contractor will be responsible to install approximately 200' ft. of 6" in. rubber hose with connection ends to attach chiller to building 655 chill water supply and return piping. Supply and install all pipe fittings as necessary for a complete installation. Supply and install all temporary electrical cables and appurtenances needed to connect chiller to the supplied building power electrical disconnect. The proposed site location and attachment locations (electrical disconnect, piping, etc.) to existing building systems will be shown at site visit. The contractor shall have a qualified HVAC subcontractor at the site visit to review this location and determine the exact details (specific location, attachment details, piping / cable length etc.). The government PM will be notified when new cabling is ready to be connected, and PM will then notify Electric shop for termination.

3) Supply and install one 500-ton chiller with pumps at Bldg. 752, Mahan Hall and have all associated work needed for installation completed and the chiller ready and in operation by May 22nd. The existing building power and disconnect is 230/480 VAC, 1000 amps. Supply a transformer to supply power to the chiller unit (if necessary). The contractor will be responsible to install approximately 250' ft. of 6" in. rubber hose with connection ends to attach chiller to building 752 chill water supply and return piping. Supply and install all pipe fittings as necessary for a complete installation. Supply and install all temporary electrical cables and appurtenances needed to connect chiller to the supplied building power electrical disconnect. The proposed site location and attachment locations (electrical disconnect, piping, etc.) to existing building systems will be shown at site visit. The contractor shall have a qualified HVAC subcontractor at the site visit to review this location and determine the exact details (specific location, attachment details, piping / cable length etc.). The government PM will be notified when new cabling is ready to be connected, and PM will then notify Electric shop for termination.

Supply all labor and materials required to disconnect existing building piping for temporary chiller hook-up. Supply all labor and materials required to reconnect all piping after temporary chillers are removed. All existing system components, electrical connections, structures, roadways, etc. shall be returned to their original existing conditions upon completion of this work for acceptable closing.

*****Contractor will supply / install all material/supplies and return piping risers with Victaulic blank solid flanges upon completion of demobilization. ****

Specific Requirements:

a) All work shall be performed in accordance with applicable federal, state, local, and USMA requirements laws and regulations.

b) Supply material needed to support temporary chillers at site locations. Plywood, boards, chinks, etc. shall be installed under and chalked around tires and front trailer supports to protect the surface underneath chiller trailer.

c) Remove building louvers as necessary to run piping and electrical cables into building. Install temporary enclosures around temporary piping to cover the opening where louvers were removed.

d) Use hard rubber piping to connect chiller to building connections.

e) Supply all supervision, labor, equipment, and materials needed for installation and removal of temporary chillers.

f) Supply and install the automatic “red” high-capacity air bleeder for normal operations on each chiller unit. Supply the following brand: Bell & Gossett - High-Capacity Air Vent, Model 107A.

g) In addition to the work described above, the contractor shall also provide on-call maintenance and repair service for their supplied equipment during the periods of operation as described above. Contractor shall respond within two hours of placed call. After normal work hours, the contractor shall respond within four hours of placed call. The COR will initiate these on-call maintenance and repair services. There will be no additional payment for repairing parts or materials needed as these are to be included in the cost of operational chiller units provided.

Submittals:

The contractor shall provide the following submittals as a minimum for review and approval. The government shall have 14 calendar days to review each delivery:

1) Contractor bid/proposal:

Work plan for the execution of the design, procurement, installation, and testing of the work. This plan shall describe how they will be executed and how it will be accomplished so as to not interfere with the ongoing operations of the affected buildings and facilities.

Coordination / Schedule:

Contractor shall attend a site visit/existing conditions survey as scheduled by the COR. The contractor shall:

- 1) Coordinate the date and time of the work with COR within 5 days of Notice to Proceed.
- 2) Complete material, equipment, delivery, and installation by no later than May 15th.

Quality Control:

The contractor shall develop a Quality Control Plan to ensure that the requirements of the contract are provided as specified. This plan shall be submitted for review and approval prior to executing any design or construction work. The plan shall contain the minimum of the following:

- 1) An inspection program covering all the services to be performed under this contract.
- 2) A description of the process to be used for verifying compliance with the contract requirements including non-destructive examinations of welds.
- 3) The methodology to be used for identifying deficiencies in the quality of services performed before the level of performance has an adverse impact on the execution of the project.
- 4) A description of the daily quality control reports to be generated during the performance of the work including photographs of the work.
- 5) Qualifications of the QA/QC representative.

Health, Safety and Environmental Protection:

The contractor shall develop and submit for review and approval their Health and Safety Plan along with their Environmental Protection Plan for this work. These plans shall cover the being performed including fall protection. These plans shall comply with all federal, state, local, and USMA requirements, laws, and regulations.

Reports / Records:

Within 10 days of completion of construction, the contractor shall submit all records of the work including but not limited to quality inspection reports (including photographs), test reports, and manufacturer's documentation.