

STATEMENT OF WORK

5 March 2026

Project #: 18016548

Title: Replace Doors Multi Facilities

Project Manager: Mr. Charles Shoemaker

Facilities: 198, 211, 512, 1126, 1361, 1613, 1784, 2316

Period of Performance: 180 Days

Liquidated Damages: Does not apply to this task order

Submittals: Door, frame, glass, and hardware specifications

Government Furnished Material: None

Attachments:

- A. General Requirements**
- B. Door Pictures**
- C. Floor Plans with Door Locations**

The following is a list of requirements pertaining to this task order:

1. Purchase and install (Kawneer Trifab VersaGlaze), (Oldcastle 3000) or equal aluminum/glass doors for replacement of existing storefront systems and hollow metal doors for remainder of personnel doors. Doors need to be fabricated to specifications listed below.
2. Contractor will provide and verify field measurements.
3. Exterior storefronts are Aluminum Bronze Frame with 1" insulated Bronze tinted Low-e glass installed to full height and width of doors.
4. Doors should have a minimum of a 10" bottom rail.
5. Exterior doors will have keyed locks that will accept "BEST" cores with panic hardware.
6. Interior doors will have push/pull hardware with no locks.
7. Install Bronze surface mount closers on all doors.
8. Include thresholds, door sweeps, and weather strip on exterior doors.
9. Ensure proper seal around all door frames.
10. Support MHAFB's recycling policy in accordance with Executive Order 13101. Remove and deliver old doors, hardware, and material to building 1800 Recycle Center.

11. Building 198

- a. Remove existing hollow metal door assembly and install exterior hollow metal door and frame with 4" x 2' lite, mounted in CMU. Install new threshold, closer, panic bar with lever trim. Door lock assembly shall be compatible for Best lock

system. Paint door and jamb to match existing scheme. . Building 198 is located on the airfield and will require an EAL.

b.

12. Building 211

- a. Remove existing hollow metal door assembly and install exterior hollow metal door and frame with 6" x 3' lite, mounted in metal building. Install new threshold, closer, lever handles & trim. Door lock assembly shall be compatible for Best lock system. Paint door and jamb to match existing scheme.
- b. Remove existing hollow metal double door assembly and install exterior hollow metal double doors with no lite, mounted in metal building. Install new threshold, closer, lever handles & trim. Door lock assembly shall be compatible for Best lock system. Paint door and jamb to match existing scheme.

13. Building 512

- a. Remove and replace existing wooden door with side lite assembly to match the Wing CC Suite entrance scheme with a set of double doors. The rough opening is approximately 6' 2" W x 7' 1 3/4" H. Install new threshold, closers, panic bars with lever trim. Door lock assembly shall be compatible for Best lock system.

14. Building 1126

- a. Remove existing hollow metal door assembly and install exterior hollow metal door and frame with 2' x 2' lite, mounted in CMU. Install new threshold, closer, panic bar with lever trim. Door lock assembly shall be compatible for Best lock system. Paint door and jamb to match existing scheme.
- b.

15. Building 1361

- a. Remove existing hollow metal double door assembly and install exterior hollow metal double doors with no lite, mounted in metal building. Install new threshold, panic hardware on both doors, keyed center mullion, closers, lever handles & trim. Door lock assembly shall be compatible for Best lock system. Paint door and jamb to match existing scheme. Building 1361 is located on the airfield and will require an EAL.

16. Building 1613

- a. Remove and replace the existing store front assembly with a new set of aluminum storefront double doors with insulated glass & side lites. Install new threshold, closers, 2 panic hardware bars to cylinders & handles. The rough opening is approximately 11' 8" W x 7' 2" H.

- b. Remove and replace the existing set of aluminum and glass set of double doors with new set of double doors, threshold, closers, 2 panic hardware bars to cylinders & handles. The existing doors are 2' 6" W each x 7' 0" H.
- c. Remove existing hollow metal double door assembly and install exterior hollow metal double doors and jamb, mounted in CMU. Install new threshold, panic hardware, & closers. Paint door and jamb to match existing scheme.
- d. Remove and replace hollow metal door and jamb assembly. Install new hollow metal door and jamb with panic hardware and lever handle trim. Door is 3' 0" x 7' 0". Paint door and jamb to match existing scheme.
- e. Remove and replace hollow metal door and jamb assembly. Install new hollow metal door and jamb with panic hardware and lever handle trim. Door is 3' 0" x 7' 0". Paint door and jamb to match existing scheme.
- f. Remove and replace hollow metal door and jamb assembly. Install new hollow metal door and jamb with a Best 9K series entrance handle. Door is 3' 0" x 7' 2". Paint door and jamb to match existing scheme.
- g. Remove and replace hollow metal door and jamb assembly. Install new hollow metal door and jamb with a Best 9K series storeroom handle. Door is 3' 0" x 7' 2". This door requires a 2' x 2' bottom vent installed and non-removable hinge pins. Paint door and jamb to match existing scheme.
- h. Remove and replace hollow metal door and jamb assembly. Install new hollow metal door and jamb with closer, panic hardware, and lever handle trim. Door is 3' 0" x 7' 2". Paint door and jamb to match existing scheme.

17. Building 1784

- a. Remove and replace hollow metal door and jamb assembly. Install new hollow metal door and jamb with panic hardware and Simplex cipher lock with Best core. Door is 3' 0" x 7' 0". Door also requires a 2' W x 2' 8" Lite. Paint door and jamb to match existing scheme.

18. Building 2316

- a. Remove and replace 7/8" thick stainless steel swinging double doors and jamb. Install new double action swinging doors with 2' x 2' lites, & head and foot bolts. The rough opening is approximately 6' W x 7' ½" H. Paint the jamb to match existing scheme.

- b. Remove and replace 7/8" thick stainless steel swinging double doors and jamb. Install new double action swinging doors with 2' x 2' lites. The rough opening is approximately 5' W x 7' H. Paint the jamb to match existing scheme.
- c. Remove and replace 7/8" thick stainless steel swinging door and jamb. Install new double action swinging door with 2' x 2' lites. The rough opening is approximately 3' W x 7' H. Paint the jamb to match existing scheme.
- d. Remove and replace existing 3' 8" W x 7' 2" H hollow metal door assembly and install exterior hollow metal door and frame with 4" x 30" lite, mounted in CMU. Install new threshold, closer, panic bar to Trilogy electric combination lock. Door lock assembly shall be compatible for Best lock system. Paint door and jamb to match existing scheme.
- e. Remove and replace hollow metal door and jamb assembly. Install new hollow metal door and jamb with a Best 9K series storeroom handle and closer. Door is 3' 0" x 7' 2". Paint door and jamb to match existing scheme. Door/jamb are mounted to CMU.
- f. Remove and replace hollow metal double door and jamb assembly. Install new hollow metal door and jamb with a Best 9K series entrance handle and closer. Both doors are 3' 0" x 7' 2". Paint door and jamb to match existing scheme. Door/jamb are mounted to CMU.

19. Building 2610

- a. Remove and replace an interior double door with side lites and transom storefront assembly. The rough opening is approximately 9' W x 9' H. The new storefront system requires threshold, panic hardware with lever handle trims and automatic openers. Door lock assembly shall be compatible for Best lock system. Paint door and jamb to match existing scheme.

DON'T START CONSTRUCTION UNTIL DOORS ARE ON SITE AND READY FOR INSTALLATION.

END STATEMENT OF WORK

