

**PERFORMANCE WORK STATEMENT
FOR
MAINTENANCE OF OIL/WATER SEPARATORS,
GREASE TRAPS, SEPTIC TANKS, AND SAND
INTERCEPTORS**

DRAFT

**Buckley SFB, Colorado
17 February 2026**

TABLE OF CONTENTS

	Page
1. BASIC SERVICE	3
1.1. SPECIFICATIONS AND DESCRIPTION OF WORK	3
1.1.2. SAFETY AND HEALTH STANDARDS	3
1.1.2.1. CONFINED SPACE ENTRY TRAINING	3
1.1.2.2. WRITTEN CONFINED SPACE PLAN	4
1.1.3. TESTING	4
1.1.3.1. QUARTERLY, SEMI ANNUAL AND ANNUAL REQUIREMENTS	4
1.1.4. SERVICE	4
1.1.4.1. SCHEDULING SERVICE	4
1.4.1. EMERGENCY SERVICE	4
1.2. OIL/WATER SEPARATORS	4
1.3. GREASE TRAPS	5
1.4. SEPTIC TANKS	5
1.5. SAND INTERCEPTORS	5
1.6. SERVICE TICKETS	5
16.1 EMERGENCY SERVICE CALLS	5
1.7. WASTE HANDLING	5
1.7.1 SAFETY AND HEALTH STANDARDS	5
1.8.. LICENSES AND PERMITS	6
1.9.. PARTS AND REPAIR	6
2. SERVICES SUMMARY	6
2.1. QUALITY CONTROL	6
2.2. QUALITY ASSURANCE	6
2.3. PERFORMAMNCE ASSESSMENT	7
2.3.1. PERIODIC VALIDATION	7
2.3.2. UNSATISFACTORY PERFORMANCE	7
2.4. PERIODIC PROGRESS MEETINGS	7
2.4.1. MEETINGS	7
2.4.2. MEETING MINUTES	7
3. GOVERNMENT FURNISHED PROPERTY AND SERVICES	7
3.1. GOVERNMENT FURNISHED PROPERTY AND SERVICES	8
3.2. GOVERNMENT FURNISHED SUPPLIES AND EQUIPMENT	8
3.3. SECURITY, FIRE AND MEDICAL SERVICES	8
4. GENERAL INFORMATION	8
4.1. HOURS OF OPERATION	8
4.2. HOLIDAYS AND CLOSURES	8
4.2.1. RECOGNIZED FEDERAL HOLIDAYS	8
4.2.2. OTHER BASE CLOSURES	9
4.3. PERFORMANCE OF SERVICE DURING CRSIS OR HEIGHTENED SECURITY	9
4.4. CONTRACTOR WORK SCHEDULE	9
4.4.1. SCHEDULE SUBMISSION AND APPROVAL	9

4.4.2. SCHEUDLE CHANGE	9
4.5 CONTRACT PERSONNEL	9
4.5.1 CONTRACT MANAGER	9
4.5.2. PERSONNEL	9
4.5.3. EMPLPYEE RESTRICTIONS	9
4.6. CONTRACTOR MANPOWER REPORTING	10
4.7. OPSEC	10
4.8. SECURITY REQUIREMENTS	10
4.8.1 BASE ACCESS	10
4.8.2. MAIN BASE ACCESS	10
4.8.3 SECURITY MANAGER	10
4.8.3.1. SECURITY TRAINING	11
4.8.3.2. SECURITY AUTHORITY	11
4.8.4. RESTRICTED/CONTROLLED AREAS	11
4.8.4.1. ACCESS COORDINATION	11
4.8.4.2. ESCORTS	11
4.8.4.3 RESTRICTED AREA (RA) BADGES	11
4.8.4.4. LOST BADGES	11
4.8.5. EMPLOYEE BACKGROUND CHECKS	12
4.8.5.1. PRE-APPROVAL COORDINATION	12
4.8.5.2. BADGE ISSUANCE	12
4.8.5.3. ACCESS REVOCATION	12
4.8.5.4. BADGE VALIDITY	12
4.8.5.5. CONTRACT PERSONNEL REQUIREMENTS	12
4.8.6. CONTRACTOR VEHICLES	13
4.8.7. FOR OFFICIAL USE ONLY (FOUO)	13
4.8.8. REPORTING REQUIREMENTS	13
4.8.9 PHYSICAL SECURITY	13
4.8.10. KEY CONTROL	13
4.8.11. HEIGHTEN SECURITY AND FPCONS	13
4.8.12. SECURITY REQUIEMENT COSTS	13
4.9. SAFETY REQUIREMENT AND REPORTS	14
4.10. CONTRACTING OFFICER AND CONTRACTING OFFICER REPRESENTATIVE	14
4.11. MULTI-FUNCTIONAL TEAM	14
4.12. DAMAGES TO GOVERNMENT BUILDING, EQUIPMENT OR VEGETATIONS	14
4.13. HAZARDOUS WASTE	14
APPENDIX A - TABLE A: ESTIMATED WORKLOAD DATA	15

**PERFORMANCE WORK STATEMENT
FOR
MAINTENANCE OF OIL/WATER SEPARATORS,
GREASE TRAPS, AND SEPTIC TANKS**

1. BASIC SERVICES. The Contractor shall provide all management, tools, supplies, equipment and labor necessary to maintain oil/water separators, grease traps, and septic tanks located at Buckley Space Force Base (SFB), CO. Work shall comply with government and commercial standards. Drainage lines shall be clear of grease, oil, sand, dirt, and sludge to ensure they are kept free flowing for a distance of 50 ft from any tank, trap, and separator. The Contractor shall ensure all grates, covers, grills, locks, safety bars, etc., are repositioned on the tanks, traps, and barrels. Contractor shall ensure the surrounding work area is cleaned and disinfected to prevent odors from any spillage before departing the area. Contractor shall re-perform pumping, cleaning, and clearing of clogged lines and traps/tanks when work requirements have not been adequately performed. Re-performance shall be at no additional cost to the Government. See attached map for location, size, and frequency of cleaning of oil/water separators, grease traps, septic tanks, and sand interceptors.

1.1. SPECIFICATIONS AND DESCRIPTION OF WORK. The following list of federal regulations pertaining to liquid wastes is not all-inclusive.

- Resource Conservation and Recovery Act (as amended by the Hazardous and Solid Waste amendments of 1984), subtitle C, "Hazardous Waste Management."
- Oil Pollution Act of 1990, Section 1001.
- The Clean Water Act, Title 3, "Standards and Enforcement", and Title 4, "Permits and Licenses".
- Title 40 CFR 260-282, "Hazardous Waste"
- Title 40 CFR Parts 104-149 "Water Programs".
- Title 40 CFR Part 110, "Discharge of Oil".
- Title 40 CFR Part 112, "Oil Pollution Prevention".
- Title 40 CFR Part 401-471, "Effluent Guidelines and Standards".
- Title 40 CFR Subpart F, "Releases from Solid Waste Management Units".

1.1.2. SAFETY AND HEALTH STANDARDS. The Contractor shall initiate and maintain and document the programs to comply with the provisions of the Occupational Safety and Health Standards Act concerning entry requirements in confined spaces and handling potential hazardous substances.

1.1.2.1. CONFINED SPACE ENTRY TRAINING. All OWSs are accessible from ground level however, some OWSs on Buckley SFB are below the grounds surface. Many of the OWSs are considered a permit-required confined space IAW CFR 1910.146. In the event that the Contractor deems it necessary to break the surface and/or plane and enter the confined space, they shall notify the Contracting Officer's Representative (COR) to coordinate with [REDACTED]

[REDACTED] Service must be coordinated to ensure fire

department rescue availability.

1.1.2.2. WRITTEN CONFINED SPACE PLAN. The Contractor performing confined space entries must have a written confined space plan IAW CFR 1910.146 (c)(4) and will provide a copy of the written confined space plan to be used for entries into confined spaces at Buckley SFB to the COR. The Contractor shall provide proof of closed entry permits for confined space entries at Buckley SFB upon request of the Air Force.

1.1.3. TESTING

1.1.3.1. SEMI ANNUAL AND ANNUAL REQUIREMENTS Before solid and liquid materials can be removed, the Contractor shall perform appropriate tests of the contents (floating materials, liquid and sludge) to determine the materials present inside the oil/water separators, grease traps, septic tanks and sand interceptors. Information from the test results shall be used to determine appropriate handling, transporting and reclamation/disposal of oil/water separator material. The Government shall be notified if test results exceed any parameters outlined in the 40 CFR 279.11 prior to maintenance scheduling or servicing. If serviceable features listed in appendix A shall be subject to analytical testing that demonstrates compliance with Metro Water Recovery's specific discharge limitations listed in section 6.18.1 of the Metro Water Recovery Rules and Regulations prior to disposal, analytical results shall be shared with the government for review.

1.1.4. SERVICE

1.1.4.1. SCHEDULING SERVICE. The Contractor shall initiate scheduling all services IAW Appendix A "Estimated Workload Data" and with COR in Service Contracts at [REDACTED] prior to servicing OWS, Grease Traps, Septic Tanks, and Sand Interceptors listed on Appendix A. At least 14 Days prior to the proposed scheduled service date falling in each month, the Contractor must contact the COR who will coordinate the date(s) and time(s) with the using agencies and provide confirmation of approval of schedule to the Contractor. Contractor should state which disposal facilities will be used. Contractor shall comply with disposal facility rules and regulations. Contractor shall not discharge deleterious waste as defined by Metro Water Recovery section 6.13 of the Metro Water Recovery rules and regulations.

1.1.4.2. EMERGENCY SERVICE. Normally, all work will be in accordance with the Contractor's work schedule. Unexpected services may be required in the event of natural disasters or other unscheduled repairs to pipes or other infrastructure involving oil/water separators, grease traps, septic tanks, and sand interceptors. In the event that servicing is required outside the Contractor's schedule, the Contractor shall begin the service within 24 hours after notification. On-call service shall be priced separately as negotiated in the contract.

1.2. OIL/WATER SEPARATORS. The contractor must be a permitted waste hauler, approved by the applicable regulatory authority. The contractor is also responsible for the waste they process from Buckley SFB at their service location. The contractor shall pump all oil, oil residue, and other wastewater from separators and catch tanks: draining separator and catch tanks completely. All filters shall be removed, cleaned of all sludge and debris, and reinstalled. All oil, oil residue, and other wastewater from tanks shall be properly recycled or disposed of in

accordance with federal state and local regulation. After cleaning, contractor shall inspect entire system for proper performance. Contractor shall wash and drain the separator and fill with clean water as required for the unique configuration of the separator. Contractor shall transport all materials from oil/water separators to an approved off-base reclamation/disposal facility.

1.3. GREASE TRAPS. The contractor must be a permitted waste hauler, approved by the applicable regulatory authority. The contractor is also responsible for the waste they process from Buckley SFB at their service location. Services shall be performed to all grease traps listed in Appendix A. The Contractor shall furnish one five (5) gallon pail of powered ENZYME DIGESTANT for each grease trap listed in Appendix A at the beginning of the contractual year and treat grease traps when service is performed. The Contractor shall pump out all grease and residues from trap and remove waste build up from trap or pit walls and all associated equipment within the pit. Flush down with water and pump out remaining residue as required by the unique configuration of the grease trap. Residual or recharge water must be higher than lower inlets. The Contractor shall ensure covers, walls, floor of trap and inlet and outlet pipes/connections are free from solidified grease buildup and free flowing. Transport all materials from grease traps to an approved off-base storage facility.

1.4. SEPTIC TANKS. The contractor must be a permitted waste hauler, approved by the applicable regulatory authority. The contractor is also responsible for the waste they process from Buckley SFB at their service location. Prior to cleaning and pumping operations, the contractor shall contact the Base Environmental Office 460 CES/Civil, Environmental and Infrastructure Engineering (CEIE) at [REDACTED] Environmental Elements Chief to ensure how and what is being tested and perform appropriate tests of the contents (floating materials, liquid and sludge) to determine if the materials are hazardous waste. If such tests indicate the cleaning service will generate hazardous waste, the servicing of the septic tank shall be terminated and the contractor shall contact the COR, who will contact the installation environmental office. The environmental office shall be responsible for disposal of hazardous contents. If non-hazardous, services shall be performed annually for septic tanks listed in Appendix A. Contractor shall pump and dispose all waste in accordance with the federal, state, local, and environmental laws. Contractor shall ensure all tanks are drained completely and inspect all parts for problems. Cleaning shall include all surfaces of walls, baffles, inlet connection, and outlet connection. The Contractor will not be responsible for tank replacements. Chlorine tablets will be added by the Contractor to the septic holding tanks in order to maintain a chlorine residue. The job sites shall be kept neat and clean at all times, any spillage or leakage shall be washed down and disinfected. Analytical testing shall be performed on Building 1145 in accordance with section 1.1.3. of this PWS. Notify 460 CEIE (Environmental) of analytical results prior to disposing the septic tank contents.

1.5. SAND INTERCEPTOR. The contractor must be a permitted waste hauler, approved by the applicable regulatory authority. The contractor is also responsible for the waste they process from Buckley SFB at their service location. Contractor shall remove all material in the interceptors (single compartment or double compartment) to within three inches from the bottom of the tank or less. Sides shall be scraped or washed down with water and the scrapings or material washed down from the walls shall be removed. Inlet and outlet pipes shall be cleaned of any buildup. Lids, and covers shall be replaced to prevent persons from accidentally falling into

the interceptor. Appropriate control measures must be selected, designed, installed, implemented, and maintained to minimize all potential pollutants, such as but not limited to sediment, waste, trash, chemicals, sanitary waste, and contaminated soils in discharges to the sanitary or stormwater drains. Any material accidentally spilled on the ground during cleaning, transporting equipment or removing material shall be cleaned up prior to departure from the site. Recovered sediment shall be collected and disposed of at an approved facility in accordance with local, state, and federal laws and regulations if applicable. In some cases, environmental sampling may be required for hazardous substances. Contractor shall notify 460 CES/CEIE (Environmental) prior to any sediment cleanout and disposal and identify the disposal location. Sampling shall be accomplished prior to transporting waste to any Treatment Storage or Disposal Facility. For questions/concerns, please contact the Toxics Program Manager, [REDACTED]

1.6. SERVICE TICKETS. Service tickets shall be provided by the Contractor for each of the areas listed in this agreement. As a minimum, the tickets shall reflect the date, time, and type of service (approx. number of gallons removed) that was performed with a comments section that allows for description of services provided and notation of any repairs that the unit being serviced may require. A copy of the tickets shall be sent the COR.

1.6.1 EMERGENCY SERVICE CALLS. Normally, all work will be in accordance with the Contractor's work schedule. Unexpected services may be required in the event of natural disasters or other unscheduled repairs to pipes or other infrastructure involving oil/water separators, grease traps, and septic tanks. In the event that servicing is required outside the Contractor's schedule, the Contractor shall begin the service within 24 hours after notification. On-call service shall be priced separately as negotiated in the contract.

1.7. WASTE HANDLING. All liquids and semi-solid waste removed from Buckley SFB shall be disposed of off Air Force/Space Force property in accordance with all applicable federal, state, and local environmental regulations. Do not discharge to the sanitary sewer wastewater which differ significantly in quantity or quality from discharges under normal conditions without permission from Metro Water Recovery (Metro), Buckley's wastewater regulator. To obtain permission to discharge to sanitary sewer, analytical sampling will be required that shows the discharge meets Metro regulatory limits. Allow a minimum of six weeks and contact Buckley SFB Water Quality PM, [REDACTED] to coordinate permission or to report an accidental discharge to sanitary sewer.

1.7.1 SAFETY AND HEALTH STANDARDS. The Contractor shall perform work in a safe manner as required by OSHA Safety and Health Requirements. Provide a verbal report to the Contracting Officer (CO) as soon as possible of each occurrence of damage to government property or an accident resulting in death, injury, occupational disease, or adverse environmental impact. Provide a completed copy of required Accident Investigation Reports to the CO with five calendar days of each occurrence.

1.8. LICENSES AND PERMITS. The Contractor shall be responsible for obtaining all federal, state, and local required permits in order to perform the work and transport of hazardous and non-hazardous materials as described in this performance work statement (PWS) and in

accordance with Our Base Policies and Environmental Engineering Office; To the extent of: Hazardous materials to be used must be reported prior to use. Quantities used need to be reported ideally when received or at least monthly. AFMAN32-7002 S.3.3.1 requires that all hazardous materials (HM) be submitted to 460 CES/CEIE for review and authorization prior to bringing on Buckley AFB. Manufacturer-specific part numbers and Safety Data Sheets (SDS) are required to be provided to 460 CES/CEIE along with container sizes to ensure correct usage tracking. All HM usage is required to be tracked once approved for use and reported to the Environmental Element each month. Types of HM can include adhesives, paints, sealants, solvents, and similar products. Please contact 460 CES/CEIE for further information and assistance.

In addition, contractor must comply with Commercial Vehicle Safety Act of 1986, WASTE GREASE TRANSPORTERS, FACILITIES, AND PERSONAL USERS OF WASTE GREASE, HB 10-1125 and for complying with any federal, state, and municipal laws, codes, and regulations applicable to the performance of work. The Contractor shall provide proof of such applicable licenses and permits upon request of the Air Force/Space Force.

1.9. PARTS AND REPAIRS: All replacement parts provided shall be factory new or factory used approved parts, with the exception of general hardware items. Individually needed parts or combined parts for one specific work order with a unit cost of less than \$100.00 shall be included in the maintenance cost. If an individual replacement/repair part is needed that exceeds \$100.00, the Contractor shall provide 3 itemized quotes showing materials and parts, to include the total cost of repairs, to the COR. All repairs will be negotiated prior to the start of any work. The CO is the only person authorized to contractually obligate the Government.

2. SERVICE SUMMARY.

Performance Objective	PWS Para	Performance Threshold	Assessment Method
Clean and Maintain Oil/Water Separators, Sand Interceptors, Grease Traps, and Septic Tanks. Initial check documented. Document all safety hazards on all separators, traps, and tanks during inspections. Remove and properly dispose of non-hazardous oil, grease, and sludge. Clean all systems and fill with clean water as required. Ensure septic tanks are in good working order.	1.1. - 1.5.	Provides preventative maintenance and inspections on all systems per industry standards. No more than 1 customer complaint per service month.	COR inspection during contractor preventative maintenance and inspection visits. COR site visits to ensure systems are fully operational. Review of reports.
Emergency Service Calls. Service calls handled promptly, and all work completed as specified.	1.6.1	If required outside the Contractor's schedule, the Contractor shall begin the service within	Periodic COR inspection during emergency service to ensure contractor's

		24 hours after notification. No deficiencies permitted.	timely response and repair.
--	--	---	-----------------------------

2.1. QUALITY CONTROL. The Contractor shall develop and maintain a quality program to ensure liquids and semi-solid waste removal is performed in accordance with commonly accepted commercial practices; and with the NFPA Standards 11 through 17, 72, and the manufacturer's instructions. The Contractor shall develop and implement procedures to identify, prevent, and ensure non-recurrence of defective services. At a minimum, the Contractor shall develop quality control procedures addressing the areas identified in paragraph 2, Service Delivery Summary.

2.2. QUALITY ASSURANCE. The Government shall inspect and evaluate the Contractor's performance to ensure services are received in accordance with requirements set forth in this PWS. The Contractor shall provide work schedules to the COR in accordance with paragraph 4.3 of this PWS. The COR shall inspect by validating actual work performance, physically checking an attribute of the completed task, checking a management information report, investigating customer complaints, conferring with facility managers, or otherwise inspecting the task or its results to determine whether or not performance meets the standards contained in this PWS. The COR will use the Contractor's work schedule or modified version thereof, to record validation results. Results of the validation then become the official Air Force/Space Force record of the Contractor's performance. When a performance threshold has not been met or Contractor performance has not been accomplished, the COR will initiate and provide the CO a Corrective Action Report for issuance to the Contractor. The Contractor shall respond to the CAR IAW instructions provided and return it to the CO within 5 calendar days of receipt.

2.3. PERFORMANCE ASSESSMENT

2.3.1. PERIODIC VALIDATIONS. This method requires the COR to employ a "spot check" style of evaluation based on the Contractor's schedule. Periodic validations will be conducted on a scheduled basis (daily, weekly, monthly, quarterly, semi-annual or annually) and may be adjusted, based on quality trends.

2.3.2. UNSATISFACTORY PERFORMANCE. Any unsatisfactory inspection (defect) result shall be recorded and the Contractor shall re-perform the service after notification by the COR. Failing to meet the performance threshold as outlined in the SS for any of these performance objectives in any one month period shall result in a warning or letter of concern from the CO. Failing to meet the performance threshold as outlined in the SS of these performance objectives in any combination for any two or more consecutive or non-consecutive months during a contract period shall constitute an immediate Progress Meeting with the Multi-functional Team. All remedies shall be in accordance with the FAR 52.212-4 (a), Contract Terms and Conditions - Commercial Items, Inspection/Acceptance.

2.4. PERIODIC PROGRESS MEETINGS

2.4.1. MEETINGS. The CO, Functional Commander, COR, QRPM and/or Environmental Manager, other Government personnel as appropriate, and the Contractor shall periodically meet to discuss the Contractor's performance. The following issues shall be discussed: opportunities to improve the contract, required contract modification(s), unsatisfactory inspections and trends against each performance objective observed, positive performance, and steps taken by the Contractor to prevent unsatisfactory occurrences in the future. The Contractor shall provide a summation of unsatisfactory inspections and customer complaints and provide insight into any identified trends.

2.4.2. MEETING MINUTES. The minutes of these meetings will be reduced to writing, signed by the CO, and any other signatures as deemed appropriate, and distributed to the functional area and the Contractor. Should the Contractor not concur with the minutes, the Contractor shall provide a written notification to the CO identifying areas of non-concurrence for resolution.

3. GOVERNMENT FURNISHED PROPERTY AND SERVICES.

3.1. GOVERNMENT FURNISHED PROPERTY AND SERVICES. The Government will provide all water and electricity as may be required by the Contractor to perform the service. Contractor should be prepared to supply materials to access provided utilities. Contractor shall provide all extensions (hoses/electrical cords) to utilities and compatible hook ups to water source or hydrants where applicable. Contractor shall provide long distance hoses of at least two hundred (200) feet or more. Contractor shall protect water sources by use of back flow prevention supplied by the Contractor. Available electrical connections can be utilized by Contractor or Contractor must provide a generator.

3.2. GOVERNMENT FURNISHED SUPPLIES AND EQUIPMENT. None.

3.3 SECURITY, FIRE AND MEDICAL SERVICES.

The Government will provide police and fire protection. In the event of a medical emergency, base ambulance service for transporting an injured employee to a local hospital is available but the contractor will provide cost reimbursement to the Medical Emergency Provider. From a Government land line, dial 911 for emergencies; or dial [REDACTED] for Buckley SFB Security Forces and dial [REDACTED] for Buckley SFB Fire Department and Medical Services.

NOTE: Dialing 911 from a cellular phone on Buckley SFB will connect to off base authorities and response time may be delayed. If calling 911, report your location at Buckley Space Force Base.

4. GENERAL INFORMATION.

4.1. HOURS OF OPERATION.

Perform OWS, grease traps, septic tanks, and sand interceptor's services during normal duty hours and be available (by phone, cell phone, text message, or email) during the Government Program Office's hours (7:00 a.m. to 3:30 p.m. Mountain Time, Monday through Friday) and for after-hours response to problems or emergencies. This excludes federal holidays, unless otherwise required in the contract or approved by the CO. There may be situations that require

the Contractor to work at times other than normal duty hours. When the Contractor's work schedule conflicts with an Air Force/Space Force mission requirement, advise the CO and reschedule the work to minimize disruption.

4.2. HOLIDAYS & CLOSURES

4.2.1. RECOGNIZED FEDERAL HOLIDAYS. There may be federal holidays when the Contractor is not required to perform service, except in emergency situations or to support specific mission needs. The holidays are:

New Year's Day - 1 January
Martin Luther King Day - 3rd Monday in January
President's Day - 3rd Monday in February
Memorial Day - last Monday in May
Juneteenth - 19 June
Independence Day - 4 July
Labor Day - 1st Monday in September
Columbus Day - 2nd Monday in October
Veteran's Day - 11 November
Thanksgiving Day - 4th Thursday in November
Christmas Day - 25 December

If a holiday falls on a Saturday, the preceding Friday will be observed. If a holiday falls on Sunday, the following Monday will be observed. If a holiday falls on a scheduled service day, the Contractor will be responsible for rescheduling services for the first day after the holiday observance.

4.2.2. OTHER BASE CLOSURES. Work scheduled but not accomplished because of base closure due to exercises or real-world events will be accomplished as soon as possible after base reopening. The Government will not incur cost for these delays or rescheduled services.

4.3. PERFORMANCE OF SERVICE DURING CRISIS OR HEIGHTENED SECURITY

The services under this contract are not essential for performance during crisis or FPCON DELTA. The CO will determine circumstances which constitute a crisis based on direction from Security Forces and base leadership.

4.4. CONTRACTOR WORK SCHEDULE

4.4.1. SCHEDULE SUBMISSION AND APPROVAL. The Contractor shall submit a schedule for all services described in this PWS and Appendices to the COR for approval at the post-award conference. Changes to the schedule must be submitted 5 days before implementation and receive CO approval before the Government will allow the proposed changes. The schedule must be submitted electronically using a file format compatible with government software.

4.4.2. SCHEDULE CHANGES. Occurrence based (non-permanent) schedule changes due to customer requests or base exercises shall be submitted to the COR and do not require CO approval.

4.5. CONTRACT PERSONNEL

4.5.1. CONTRACT MANAGER. The Contractor shall establish and maintain an office through which the contract manager or alternate(s) can be contacted during work hours. The contract manager or alternate shall be available during normal duty hours to discuss problem areas with the government personnel designated by the CO (or designated COR). The Contractor shall provide the COR with telephone number(s) where validation results and complaints can be reported. The Contractor shall also provide to the COR the names and phone numbers of Contractor POCs for after business hours including nights, weekends, and holidays. This information will be kept updated by the Contractor whenever personnel changes occur. The contract manager or alternate shall have full authority to act for the Contractor on all contract matters relating to the daily operation of this contract.

4.5.2. PERSONNEL. Contractor personnel shall present a neat appearance. Contractor personnel shall be easily recognizable while on the installation in conjunction with this contract. This shall be accomplished through the wear of distinctive clothing, overcoats, or hats, bearing the company name or logo. The coloring or design of the items selected should be such that identifies personnel easily and quickly for reasons of safety and personal protection.

4.5.3. EMPLOYEE RESTRICTIONS. The Government is authorized to restrict employment under the contract of any Contractor employee or prospective Contractor employee who is identified as a potential threat to the health, safety, security, general well-being, or operational mission of the installation and its population.

4.6. CONTRACTOR MANPOWER REPORTING. The Contractor shall report all Contractor labor hours (including subContractor labor hours) required for performance of services provided under this contract for "U.S. Air Force" via a secure data collection site. The Contractor is required to completely fill in all required data fields using the following web address [https://beta.SAM.gov \(betaSAM\)](https://beta.SAM.gov (betaSAM)). Reporting inputs will be for the labor executed during the period of performance during each government fiscal year (FY), which runs October 1 through September 30. While inputs may be reported any time during the FY, all data shall be reported no later than October 31 of each calendar year. Contractors may direct questions to the electronic Contractor Manpower Reporting Application help desk in betaSAM.

4.7. OPSEC. The Contractor (including subContractors) executing the oil/water separators, grease traps, and septic tanks, will not have access to any form of critical information or activities in performance of the contract. The Contractor (including subContractors) will return all building plans, diagrams, blueprints, maps and other infrastructure information provided by 460 CES. 460 CES will account for materials and ensure destruction is consistent with OPSEC measures as needed.

4.8. SECURITY REQUIREMENTS. Contractor employees shall comply with Buckley SFB security requirements imposed by the Installation Commander at all times while on Buckley SFB premises. The Contractor shall obtain all necessary passes, decals, badges, or other items required for access to perform contract services at Buckley SFB. The Contractor is responsible for accountability of all such media, which shall be surrendered to the Security Forces Squadron Pass and Registration Section upon completion or termination of the contract or upon termination of an individual's employment for the Contractor. The Contractor shall comply with all Buckley SFB policies regarding entry to the installation, rules of the road, contingency operations compliance, and photography prohibitions. Contractor employees are authorized entry to the installation for the purpose of work under this contract only and are not authorized in other facilities or areas without prior government authorization. Due to safety/security requirements, Contractor personnel shall be required to *fluently* speak, comprehend, read, and write English.

4.8.1. BASE ACCESS. *The Contractor must be aware that entry requirements are subject to change due to installation and world situations. All employees may be subject to a background check through the FBI for base access.* To gain unescorted access on to Buckley SFB, the Contractor will obtain a Defense Biometric Identification System (DBIDS) card. The DBIDS paperwork must be submitted to the CO for Security Forces approval before the card can be issued to the Contractor. The Government will assist the Contractor to coordinate security matters with the 460th Security Forces Squadron (SFS) and other base agencies, as needed.

4.8.2. MAIN BASE ACCESS. Current security access restrictions at Mississippi Gate require all Contractor vehicles to enter through the Mississippi Gate only. All personnel and vehicles entering the installation are subject to search prior to entry. All personnel operating vehicles on the installation must have a valid driver's license, current registration and current insurance on the vehicle they are operating. Proof of these items must be presented if requested by Security Forces personnel. The Contractor should plan and allow for delays as a result of increased and ever-changing security procedures.

4.8.3. SECURITY MANAGER. Upon contract award, the Contractor shall designate, in writing to the CO, a Security Manager who shall be the Contractor's point of contact for all security matters. Within 5 working days of contract award, the Contractor's Security Manager shall contact the Civil Engineer Squadron (CES) Security Manager for assistance on accomplishing Contractor personnel security requirements.

4.8.3.1. SECURITY TRAINING. Contractor personnel are required to attend security and OPSEC orientation under Homeland Security Presidential Directive (HSPD) Title 12. The Contractor shall schedule initial and annual refresher training (for all assigned Contractor personnel) through the CES Security Manager. All Contractor personnel shall be thoroughly briefed by the CES Security Manager on established security requirements and procedures as stipulated in Air Force Policy Directive (AFPD 31-1, Integrated Defense).

4.8.3.2. SECURITY AUTHORITY. The Contractor shall brief all employees that they shall *immediately leave any area* upon notification by the CO, COR, constituted authority, Security Forces, or when directed as occasional operational requirements, real world activities, or emergencies dictate.

4.8.4. RESTRICTED/CONTROLLED AREAS. Contractor performance within restricted/controlled areas shall require Contractor compliance with various levels of security and established personnel security entry control procedures. The Contractor shall ensure all Contractor employees performing services in secured areas are processed for a controlled area, limited access, or visitor badge by the Entry Controller of the restricted/controlled area.

4.8.4.1. ACCESS COORDINATION. The facility manager/user/occupant/requester will be responsible for *providing* access, escorts, or temporary visitor access badges for Contractor personnel while performing contract duties. The Contractor shall be responsible for *scheduling* access/escorts/badges by contacting the facility manager/requester at the Entry Control Point of the restricted/controlled area.

4.8.4.2. ESCORTS. At all times while in restricted/controlled areas, Contractor employees shall be under direct surveillance of a person from that facility who is cleared to wear a controlled area badge and perform escort duties. Visitor badges shall be returned to the Entry Controller each time the employee completes the duties and leaves the area. This requirement is waived for Contractor personnel who have unescorted access privileges and display a controlled area badge for the restricted/controlled areas.

4.8.4.3. RESTRICTED AREA (RA) BADGES. When inside the RA, Contractor personnel shall, at all times, display restricted/controlled area badges on their outer garments above the waist. Incidents of a person not properly displaying badges or violating escort procedures (e.g. working out of view of escort) shall be treated as a breach of security and that person shall be susceptible to apprehension, search and detainment. Any person inside a restricted area without a restricted/controlled area badge will be detained or apprehended, searched, removed, and turned over to appropriate authorities for disposition.

4.8.4.3.1. LOST BADGES. The Contractor shall immediately report the occurrence of lost badge(s) to the COR, who will in turn report to Security Forces Squadron (SFS). If the COR is not available, the loss shall be reported directly to 460th SFS within one duty day of loss. Replacement badge(s) will not be issued until reporting procedures are satisfactorily completed.

4.8.5. EMPLOYEE BACKGROUND CHECKS. All Contractor employees who do not have a current security investigation acceptable to the Security Forces, and who require a National Agency Check (NAC) for the performance of their duties, shall complete an Electronic Personnel Security Questionnaire (EPSQ), SF 85P, Questionnaire for Public Trust Positions, in three copies (original and two photocopies); and an AF Form 2583, Request for Personnel Security Action. For all employees requiring local area network (LAN) access (if applicable), the Contractor shall submit the following information: full name, date and place of birth, social security account number, affirmation of United States citizenship, and any current security investigation data. Information shall be in writing, on company letterhead, and submitted to Security Forces through the CES Security Manager.

4.8.5.1. PRE-APPROVAL COORDINATION. The CES Security Manager is the source for the necessary forms and will provide instructions for receiving, preparing, and processing these

forms. The Contractor shall coordinate with all required facilities to process all necessary paperwork. After forms have been properly completed, the CES Security Manager will make an appointment for Contractor employee(s) to go to the Security Forces for submittal of paperwork and fingerprinting. Appointments will be scheduled within two weeks of request.

4.8.5.2. BADGE ISSUANCE. A minimum of 180 days is required to process Contractor employee NACs. Additional time will be required if the NAC is unfavorable and may result in denial of entry to restricted/controlled areas or denial of base LAN access. The CES Security Manager will notify the Contractor of any NAC results. After completion of a favorable NAC, each eligible employee shall report to the CES Security Manager for processing of AF Form 2586, Unescorted Entry Authorization Certificate. The CES Security Manager will schedule appointments for issuance of badges.

4.8.5.3. ACCESS REVOCATION. The Buckley SFB Installation Commander reserves the right to deny restricted area entry to any Contractor employee who's NAC is unfavorable, and the right to terminate the entry of any employee upon disclosure of information indicating the individual's continued entry to a secure area is not in the best interest of national security.

4.7.5.4. BADGE VALIDITY. Controlled area badges will be valid only for the actual period of employment or the term of the contract, whichever occurs first. Contractor employees must display the controlled area badge on their outer garment above waist level, and must, upon request, surrender the badge to any DOD member for identification verification. Violations or deviations from established security procedures by Contractor employees may result in confiscation of controlled area badges and denial of future entry to restricted areas.

4.8.5.5. CONTRACT PERSONNEL REQUIREMENTS. The Contractor shall not employ persons for work on this contract who are identified to the Contractor by the CO as a potential threat to the health, safety, security, general well-being, or operational mission of the installation and its population.

4.8.6. CONTRACTOR VEHICLES. Contractor vehicles must be maintained in a safe and operational condition at all times while on Buckley SFB. All trucks will be searched prior to gaining access to Buckley SFB. All vehicles/drivers must process through the Large Vehicle Inspection Point (LVIP) located adjacent to the Mississippi (South) Gate.

4.8.7. FOR OFFICIAL USE ONLY (FOUO). The Contractor shall comply with DOD 5400-7-R, DoD Freedom of Information Act (FOIA) Program requirements. This regulation sets policy and procedures for the disclosure of records to the public and for marking, handling, transmitting, and safeguarding FOUO material.

4.8.8. REPORTING REQUIREMENTS. Contractor personnel shall report to the COR and CO any information or circumstances of which they are aware may pose a threat to the security or well-being of DOD personnel, Contractor personnel, resources, and classified or unclassified defense information.

4.8.9. PHYSICAL SECURITY. The Contractor shall be responsible for safeguarding all government property and controlled forms provided for Contractor use. At the end of each work period, all government facilities, equipment, and materials shall be secured.

4.8.10. KEY CONTROL. The Contractor shall establish and implement methods of making sure all keys/combinations issued to the Contractor by the Government are not lost or misplaced and are not used by unauthorized persons. The Contractor shall not duplicate any keys issued by the Government. The Contractor shall immediately report to the COR or CO any occurrences of lost or duplicated keys. In the event keys other than master keys are lost or duplicated, the Contractor may be required, upon written direction of the CO, to re-key or replace the affected lock or locks without cost to the Government. The Government may, however, at its option, replace the affected lock or locks or perform re-keying and deduct the cost of such from the monthly payment due the Contractor. In the event a master key is lost or duplicated, the Government shall replace all locks and keys for that system, and the total cost will be deducted from the monthly payment due the Contractor.

4.8.11. HEIGHTENED SECURITY AND FPCONS. During periods of heightened security and Force Protection Conditions (FPCONS), the Contractor shall be responsible for maintaining the same contractual collection schedule unless notified by the Government that refuse service has been temporarily suspended or restricted. During times of heightened security, entry onto and around the base will be significantly restricted. The Contractor shall make concessions for potential delays caused by security measures and will ensure that timely and successful completion of the collection schedule is accomplished. The services under this contract are not essential for performance during crisis or FPCON DELTA. The CO will determine circumstances which constitute a crisis based on direction from Security Forces and base leadership. The COR will ensure that Level I Antiterrorism IAW DoDI 2000.16_AF Sup 10-245 is conducted either through CBT (Force Protection Awareness Training in ADLS) or in person.

4.8.12. SECURITY REQUIREMENT COSTS. All costs incurred by the Contractor associated with security requirements, including submission of necessary security investigation paperwork, routine entry/exit delays, and operational delays due to contingencies or exercises, are to be anticipated by the Contractor and shall be included in the price of the contract. Exercises are estimated to occur approximately 30 workdays per year.

4.9. SAFETY REQUIREMENTS AND REPORTS.

The Contractor shall perform work in a safe manner as required by OSHA Safety and Health Requirements. Provide a verbal report to the CO as soon as possible of each occurrence of damage to government property or an accident resulting in death, injury, occupational disease, or adverse environmental impact. Provide a completed copy of required Accident Investigation Reports to the CO within five calendar days of each occurrence.

4.10. CONTRACTING OFFICER AND CONTRACTING OFFICER REPRESENTATIVE. (QUALITY ASSURANCE PERSONNEL).

The Contracting Officer will appoint a primary and alternate representative for management of the day to day activities of the contract. The identity, title, and authority of this representative will be provided in writing to the Contractor after contract award.

4.11. MULTI-FUNCTIONAL TEAM. The Senior Leadership may require a multi-functional team be established between the Government and the Contractor to ensure joint cooperation and a sound customer focus of all parties involved in the execution of this contract.

4.12. DAMAGES TO GOVERNMENT BUILDINGS, EQUIPMENT, OR VEGETATION Damages to government buildings, equipment, or vegetation are addressed in FAR 52.237-2, Protection of government Buildings, Equipment, and Vegetation.

4.13. HAZARDOUS WASTE. The Contractor shall report any instances of spills, leaks, and inadvertent release of hazardous materials to the CO or COR immediately. The contractor is responsible for the management and disposal of their own hazardous waste off-site. The contractor shall ensure that all personnel involved in handling and packaging the hazardous waste be trained for the level of expertise required for the proper performance of the task and, in particular, in the areas of chemical incompatibility, general first aid procedures and spills. The contractor shall provide handling and personnel protective equipment to ensure safe handling of the HW. For questions/concerns, please contact the Toxics Program Manager at 460 CES/CEIE.

5. APPENDICES.

A. Estimated Workload Data

APPENDIX A

ESTIMATED WORKLOAD DATA

FAC #/TRAP	LOCATION	FREQUENCY	TOTAL GALLON CAPACITY	Service per year
Oil Water Separators				
340				
433	2SWS Generator Bldg.	Annually	150	1
439	2 SWS Parking Storage	Annually	150	1
728	Potable Water Pump House-Southside	Annually	100	1
1006	CE Wash Rack-SW Corner	Annually	1100	1

FAC #/TRAP	LOCATION	FREQUENCY	TOTAL GALLON CAPACITY	Service per year
Grease Traps				
		Semi-Annual		
316	Chapel	Semi-Annual	1600	2
351	CDC #2 S/E corner	Semi-Annual	2000	2
630	Panther Den-west side	Semi-Annual	2000	2
725	CDC – Located outside building	Semi-Annual	2000	2
806	Fire Department	Semi-Annual	570	2
1005	Joint Army and Air Building - South Side (Adjacent Drill Hall)	Semi-Annual	1600	2
1032	LDC-N/E side	Semi-Annual	1500	2

FAC #/TRAP	LOCATION	FREQUENCY	TOTAL GALLON CAPACITY	Service per year
Septic Tanks				
1110	Princess Closet	Annually	1,000	1
1145	CATM	Annually	15,500	1

FAC #/TRAP	LOCATION	FREQUENCY	TOTAL GALLON CAPACITY	Service per year
Sand Interceptors				
806	FD Sand/Grit-Northside – Escort Required	Semi-Annual	90	2
1006	CE Wash Rack-SW Corner	Semi-Annual	80	2
1022-1	Outdoor Rec Sand/Grit – Maintenance Bay	Semi-Annual	25	2
1022-2	Outdoor Rec Sand/Grit for Wash Rack	Semi-Annual	25	2
1028	Security Forces	Semi-Annual	120	2