

MT DAR MALM 2026(1), Defense Access Roads FY 2026
Malmstrom Airforce Base, Judith Basin County, Montana

The work consists of roadway reconditioning, aggregate surfacing, aggregate stabilization, subexcavation, and drainage improvements.

There are six (6) schedules; only one schedule will be awarded.

Project length: Schedule A = 18.05 miles
 Schedule B = 23.00 miles
 Schedule C = 32.49 miles
 Schedule D = 37.38 miles
 Schedule E = 41.77 miles
 Schedule F = 52.12 miles

Tentative Solicitation Date: Summer 2026

Tentative Fixed Completion Date: Fall 2027
 (Once solicitation is issued, see SF1442, Block 11 for exact date.)

Estimated Price Range: \$5 million to \$10 million

Location: 50 miles SE of Great Falls, Montana

DESCRIPTION OF WORK in US CUSTOMARY UNITS
FP-24

	Schedule A	Schedule B	Schedule C	Schedule D	Schedule E	Schedule F
DIVISION 150 – Project Requirements						
152 Construction Survey & Staking (yes/no)	Yes	Yes	Yes	Yes	Yes	Yes
153 Contractor Quality Control and Assurance (yes/no)	Yes	Yes	Yes	Yes	Yes	Yes
154 Contractor Sampling & Testing (yes/no)	Yes	Yes	Yes	Yes	Yes	Yes
155 Schedules for Construction Contracts (<i>construction schedules</i>) (yes/no)	Yes	Yes	Yes	Yes	Yes	Yes

	Schedule A	Schedule B	Schedule C	Schedule D	Schedule E	Schedule F
157 Soil Erosion & Sediment Control (<i>erosion control devices</i>)	Fiber Rolls 700 LNFT	Fiber Rolls 880 LNFT Filter Rock 41 EACH	Fiber Rolls 980 LNFT Filter Rock 41 EACH	Fiber Rolls 1160 LNFT Filter Rock 41 EACH	Fiber Rolls 1220 LNFT Filter Rock 41 EACH	Fiber Rolls 1420 LNFT Filter Rock 41 EACH
158 Watering for Dust Control	Yes	Yes	Yes	Yes	Yes	Yes
DIVISION 200 – Earthwork						
203 Removal of Structures and Obstructions	1 EACH	1 EACH	1 EACH	1 EACH	1 EACH	1 EACH
204 Excavation and Embankment (<i>unclassified borrow</i>)	60 CUYD	60 CUYD	60 CUYD	60 CUYD	60 CUYD	60 CUYD
DIVISION 250 – Earth Retaining Systems and Slopes						
251 Riprap	Class 2 5 CUYD	Class 2 5 CUYD	Class 2 5 CUYD	Class 2 5 CUYD	Class 2 5 CUYD	Class 2 5 CUYD
DIVISION 300 – Aggregate and Base Courses						
302 Crushed Aggregate (<i>Roadway Aggregate, Method 2</i>)	1235 TON	1515 TON	1515 TON	1515 TON	1515 TON	1515 TON
303 Road Reconditioning	18.05 MILE	23.00 MILE	32.49 MILE	37.38 MILE	41.77 MILE	52.12 MILE
311 Stabilized Aggregate Surface Course	Aggregate 50792 TON Calcium Chloride 880 TON	Aggregate 63599 TON Calcium Chloride 1102 TON	Aggregate 77580 TON Calcium Chloride 1592 TON	Aggregate 84358 TON Calcium Chloride 1829 TON	Aggregate 90983 TON Calcium Chloride 2061 TON	Aggregate 105328 TON Calcium Chloride 2564 TON
DIVISION 600 – Incidental Construction						
602 Culverts & Drains (<i>indicate one or both</i>)	24-inch Culvert 78 LNFT 36-inch Culvert 46 LNFT	24-inch Culvert 78 LNFT 36-inch Culvert 46 LNFT	24-inch Culvert 78 LNFT 36-inch Culvert 46 LNFT	24-inch Culvert 78 LNFT 36-inch Culvert 46 LNFT	24-inch Culvert 78 LNFT 36-inch Culvert 46 LNFT	24-inch Culvert 78 LNFT 36-inch Culvert 46 LNFT
607 Cleaning, Relaying, & Repairing Existing Drainage Structures	Cleaning 2 EACH	Cleaning 4 EACH	Cleaning 4 EACH Repairing 1 EACH	Cleaning 5 EACH Repairing 4 EACH	Cleaning 5 EACH Repairing 4 EACH	Cleaning 8 EACH Repairing 4 EACH
622 Rental Equipment (<i>yes/no</i>)	Yes	Yes	Yes	Yes	Yes	Yes

	Schedule A	Schedule B	Schedule C	Schedule D	Schedule E	Schedule F
623 General Labor (yes/no)	Yes	Yes	Yes	Yes	Yes	Yes
624 Topsoil (<i>landscaping & related items</i>)	4-inch depth 270 SQYD	4-inch depth 270 SQYD	4-inch depth 315 SQYD	4-inch depth 450 SQYD	4-inch depth 450 SQYD	4-inch depth 450 SQYD
625 Turf Establishment (<i>indicate seeding or mulching separately</i>)	667 SQYD	1500 SQYD	1545 SQYD	1680 SQYD	1680 SQYD	1680 SQYD
629 Rolled Erosion Control Products and Cellular Confinement Systems (<i>rolled erosion control product, type 2.D</i>)	n/a	833 SQYD	833 SQYD	833 SQYD	833 SQYD	833 SQYD
635 Temporary Traffic Control	Yes	Yes	Yes	Yes	Yes	Yes
635 Temporary Traffic Control – <u>Flagger</u>	1020 HOUR	1300 HOUR	1780 HOUR	2080 HOUR	2320 HOUR	2720 HOUR
635 Temporary Traffic Control – <u>TCS</u>	71 DAY	90 DAY	124 DAY	144 DAY	161 DAY	186 DAY