

## STATEMENT OF WORK (SOW) FOR

Providing Graded Crushed Aggregate Base Course [REDACTED]

PROJECT: ASPR – 234870

24 FEB 26

The Contractor shall provide all, plant, labor, material, design, and supervision to provide and deliver approximately 16,410 tons of Graded Crushed Aggregate Base Course (GCA). [REDACTED]

[REDACTED] The Taxiway is Type A traffic area [REDACTED] must support a Modified Heavy Aircraft as per UFC 3-206-2. The Contractor shall not commence work without prior coordination with the Contracting Officer, Project Inspector and Using Agency.

### **One (1) Design:**

GCA will conform to the Uniform Guide Specifications (UFGS) 32.11.23 and the equivalent American Association of State Highway Transportation Officials (ASSHTO) #57

#### General Design Notes:

- Design shall be in strict accordance with Unified Facilities Criteria (UFC) and the Avon Park Air Force Range Design Standards. The information provided in this SOW, the specifications provided and the requirements of the AVPAFR Design Standards shall be determined to be the minimum standards required in this project. Where the information provided and/or AVPAFR Design Standards conflict, then the most stringent shall be used. This includes all standards, codes, regulations and requirements provided by reference.
- If any submittal doesn't, in the opinion of the Contracting Officer, meet or exceed the requirements contained within this SOW, in the AVPAFR Design Standards or in any referenced design guidance or nationally recognized code, then it shall be unacceptable and returned to the Contractor for correction and resubmission. The Contracting Officer has the option, in lieu of disapproval, to provide acceptance of a submittal with required corrections identified if it is determined the submittal is substantially

### **Two (2) Submittals:**

Contractor shall submit the following information to the Contracting Officer, for approval. If the contractor cannot provide such tests, they can provide equivalent engineering tests that display similar geotechnical properties of the GCA stock.

- L.A Abrasion Test: ASTM C131/C121M (Toughness and Hardness of Rock)
- Gradation Analysis: ASTM C11 (Size of aggregates by weight)
- Degree of Compaction: ASTM D1557 (Optimum Moisture Content, Method C)
- Liquid Limit and Plasticity Index: ASTM D4318 (Soil Classification)
- Clay Lumps and Friable Particles: ASTM C142 (Cleanliness)
- Flat and Elongated Particles: ASTM D4791 (remove undesirable rocks)

### **Three (3) Bid:**

The Contractor shall provide all plant, labor, material, design and supervision to provide and deliver approximately 16,410 tons of GCA. Contractors shall also provide field and laboratory quality control testing, as required by the Government. Work will consist of the following:

- Provide 16,410 Tons of GCA conforming to UGGS 32.11.23 and ASSSHTO #57
- Delivery 16,410 tons of GCA in pre coordinated intervals agreed upon by the customer between May 2026 and July 2026 in the vicinity of APR, FL 33825, 45 South BLVD, Avon Park, FL 33825. The project plans will dictate the location of the stockpile area on the jobsite.
- Test every 2,500 tons of GCA, provide a Quality Assurance test consisting of a Gradation Analysis, Liquid Limit and Plasticity Index, Moisture Density Relationship, Wear, Flat and Elongated Pieces. As stated in section two (2) submittals, if the contractor cannot provide this information, they will provide the corresponding engineering tests describing similar geotechnical properties of the GCA stock.

### **Four (4) Performance:**

Before Final payment is allowed, all waybills and certified delivery tickets must be complied by the customer and contractor. Contractors will provide waybills and receipts for every vehicle moving GCA to the jobsite.

Contractor shall be able to produce a minimum sub-lot of 1,500 tons in an eight-hour period.

Contractors are responsible for the safety and wellbeing of their employees.

- Drivers must be properly licensed, capable of operating heavy machinery, and capable of communicating in English.
- Drivers must be legally allowed to enter and operate a motor vehicle on a military installation and must always carry proper identification
- Drivers must be able to contact business leadership during all hours of operation via cell phone.

All mud, dirt, debris, foreign objects, trash, or spills caused by the contractor (including Sub-Contractors) on a street or parking lot, used as access to the work site or staging area shall be cleaned off the same day or as soon as practicable or requested by the CO.