

MACC No. 25-0455

PROJECT No. 25M013MZ

MAXIMO No. 5484607

TITLE: Building RR631, RR633, RR635 Flooring Repair Project

ATTACHMENTS: 1. Drawings, Scope and Specs.

SCOPE OF WORK: The contractor shall provide all material, labor, equipment, and supervision required to accomplish the following:

GENERAL DESCRIPTION: This scope of work is to be accomplished at Building RR631, RR633, RR635 located on Everett Creek Road at Camp Lejeune, North Carolina.

GENERAL SPECIFICATIONS: The contractor shall follow the general specifications unless noted in the project area description section. All measurements on the attached sketches are for reference use only. The contractor shall take their own field measurements in determining required material and costs. All work performed shall meet or exceed SPECIFICATIONS THAT ARE ATTACHED.

PROJECT AREA DESCRIPTIONS: See attached Work Area Sketches for additional details.

1. RR631, RR633, RR635 Remove all LVP flooring in thru out buildings.
2. Seal floors with Ardex floor sealer or comparable product that meets or exceeds manufacturers specifications.
3. Install Tarkett Provence 2131 6"x 48" LVT or comparable product that meets or exceeds manufacturers specifications.
4. Install Johnsonite Medium Gray wall base or comparable product that meets or exceeds manufacturers specifications.

PREPARATION:

1. The contractor shall take the necessary precautions to prepare and protect personal property, government property, and work areas during the accomplishment of work for this scope.

INTERIOR FLOOR CARPET, WAX, BUFF AND REPAIRS:

1. Contractor shall replace any threshold between carpet and other flooring as needed.
2. Existing flooring should be removed and replaced to manufactures specifications.
3. Replace any vinyl wall base that is disturbed.
4. Sealant shall be applied before flooring is installed.

SPECIAL CONDITIONS

1. Clean all over-spray, drips, splatters, and spills resulting from accomplishing work for this project.
2. Repair, refinish areas damaged or disturbed by new work to be provided under this contract.

3. Properly remove, haul, and dispose of all debris. The contractor shall not utilize the dumpster provided by Camp Lejeune for the occupants.

SCHEDULING AND ACCESS:

- The Primary Point of Contact for the buildings are as follows: Zachory Melchisky at 910-440-0558

ENVIRONMENTAL REQUIREMENTS: None Identified

SUBMITTALS:

1. The contractor shall submit to the contracting officer, the manufacturer's product specifications, complete with technical products data being used for this project.
2. Submittal should be marked for project number.

MATERIAL SPECIFICATIONS:

1. RESILIENT FLOORING
 - a. See attached specifications.
2. SEALANT
 - a. See attached specifications.

WARRANTY:

- 1) Flooring contractor shall provide a 5- year warranty for defects in materials and workmanship and provide a 25-year non-prorated limited warranty against excessive surface wear and static, delamination, edge ravel, zippering, and backing resilient.